JULY · 1950

electronics

A McGRAW-HILL PUBLICATION



PRINTED-CIRCUIT TV TUNER

PERMALLOY DUST TOROIDS FOR MAXIMUM STABILITY...

The UTC type HQ permalloy dust toroids are ideal for all audio, carrier and supersonic applications. HQA coils have Q over 100 at 5,000 cycles... HQB coils, Q over 200 at 4,000 cycles... HQC coils, Q over 200 at 30 KC... HQD coils, Q over 200 at 60 KC... HQE (miniature) coils, Q over 120 at 10 KC. The toroid dust core provides very low hum pickup... excellent stability with voltage change... negligible inductance change with temperature, etc. Precision adjusted to 1% tolerance. Hermetically sealed.



HQA, HQC, HQD CASE
1 13/16" Dia. x 1 3/16" High

HQB CASE
1 5/8" x 2 5/8" x 2 1/2" High

HQE CASE
1/2" x 1 5/16" x 1 3/16" High



Type No.	Inductance Value	Net Price	Type No.	Inductance Value	Net Price	Type No.	Inductance Value	Net Price
HQA-1	5 mhy.	$7.00	HQA-16	7.5 hy.	$15.00	HQC-1	1 mhy.	$13.00
HQA-2	12.5 mhy.	7.00	HQA-17	10. hy.	16.00	HQC-2	2.5 mhy.	13.00
HQA-3	20 mhy.	7.50	HQA-18	15. hy.	17.00	HQC-3	5 mhy.	13.00
HQA-4	30 mhy.	7.50	HQB-1	10 mhy.	16.00	HQC-4	10 mhy.	13.00
HQA-5	50 mhy.	8.00	HQB-2	30 mhy.	16.00	HQC-5	20 mhy.	13.00
HQA-6	80 mhy.	8.00	HQB-3	70 mhy.	16.00	HQD-1	4 mhy.	15.00
HQA-7	125 mhy.	9.00	HQB-4	120 mhy.	17.00	HQD-2	1 mhy.	15.00
HQA-8	200 mhy.	9.00	HQB-5	.5 hy.	17.00	HQD-3	2.5 mhy.	15.00
HQA-9	300 mhy.	10.00	HQB-6	1. hy.	18.00	HQD-4	5 mhy.	15.00
HQA-10	.5 hy.	10.00	HQB-7	2. hy.	19.00	HQD-5	15 mhy.	15.00
HQA-11	.75 hy.	10.00	HQB-8	3.5 hy.	20.00	HQE-1	5 mhy.	6.00
HQA-12	1.25 hy.	11.00	HQB-9	7.5 hy.	21.00	HQE-2	10 mhy.	6.00
HQA-13	2. hy.	11.00	HQB-10	12. hy.	22.00	HQE-3	50 mhy.	7.00
HQA-14	3. hy.	13.00	HQB-11	18. hy.	23.00	HQE-4	100 mhy.	7.50
HQA-15	5. hy.	14.00	HQB-12	25. hy.	24.00	HQE-5	200 mhy.	8.00

UTC INTERSTAGE AND LINE FILTERS

FILTER CASE M
1 3/16" x 1 11/16"
1 5/8" - 2 1/2" High



These U.T.C. stock units take care of most common filter applications. The interstage filters, BMI (band pass), HMI (high pass), and LMI (low pass), have a nominal impedance at 10,000 ohms. The line filters, BML (band pass), HML (high pass), and LML (low pass), are intended for use in 500/600 ohm circuits. All units are shielded for low pickup (150 mv/gauss) and are hermetically sealed.

STOCK FREQUENCIES
(Number after letters is frequency)
Net Price $25.00

BMI-60	BMI-1500	LMI-200	BML-400
BMI-100	BMI-3000	LMI-500	BML-1000
BMI-120	BMI-10000	LMI-1000	HML-200
BMI-400	HMI-200	LMI-2000	HML-500
BMI-500	HMI-500	LMI-3000	LML-1000
BMI-750	HMI-1000	LMI-5000	LML-2500
BMI-1000	HMI-3000	LMI-10000	LML-4000
			LML-12500

United Transformer Co.
150 VARICK STREET NEW YORK 13, N. Y.
EXPORT DIVISION: 13 EAST 40th STREET, NEW YORK 16, N. Y. CABLES "ARLAB"

electronics

A McGRAW-HILL PUBLICATION

JULY • 1950

PRINTED CIRCUIT TV TUNER ..... Cover
Removable metallized coil strips of RCA turret contains input pi-network, m-derived bandpass filter and high-band oscillator coils. See p 118

WHY TELEVISION RECEIVERS FAIL IN SERVICE 66
Field experience reveals 15 major reasons for service calls, many preventable at design and production stages

ENGINEERING TRENDS IN SPOT WELDER CONTROLS, by Stuart C. Rockefellow 70
Quick-replacement features meet automobile assembly-line requirements

TELEVISION ANTENNA DIPLEXERS, by W. H. Sayer and J. M. De Bell, Jr. 74
Antenna-matching device permits feeding two or three different carriers to one transmitting antenna

TESTING TURNTABLES FOR WOW, RUMBLE AND SPEED, by R. O. Maze 78
Equipment requires only a standard record for direct indication of record-player characteristics

HIGH-FREQUENCY OPERATION OF TRANSISTORS, by C. B. Brown 81
Describes 23-megacycle amplifier with gain of 8

MODULATED LIGHT DENSITOMETER, by Henry P. Kalmus and Milton Sanders 84
Phototube amplifier rejects 120-cps signals caused by room illumination

CLOSED-CIRCUIT INDUSTRIAL TELEVISION, by R. W. Sanders 88
Simplified wired system for remote viewing of industrial processes

THE DIOTRON, AN AID TO RMS INSTRUMENTATION, by R. D. Campbell 93
Circuit uses temperature-limited diode in conjunction with d-c amplifier and feedback loop

KILOMEGACYCLE BUZZER TEST OSCILLATOR, by G. L. Davies, C. B. Pear, Jr., P. E. P. White 96
Output between 3 and 11 kilomegacycles from an 800-cycle buzzer with 200 microvolts into 50 ohms

CASTING RESIN TECHNIQUES, by Jack Bayha 100
Instructions for preparing, mixing, applying and curing NBS resin for potted electronic units

NINE-TOWER BROADCAST ARRAY, by C. W. Winkler and M. Brasseur 102
Suppresses a total of 247 degrees of radiation and employs four phase monitors

GEIGER COUNTER FOR LECTURES, by Ronald L. Ives 105
Rugged portable unit delivers 50 watts audio output for cosmic ray and radioactivity demonstrations

SYNC SEPARATOR CIRCUIT ANALYSIS, by W. Heiser 108
Equations are given for design and calculated values compared with measured values

ESTIMATING VHF FIELD INTENSITY (Reference Sheet), by E. A. Slusser 112
Nomograph relates transmitter power, antenna height, and effect of obstructions in the path to received field strength

BUSINESS BRIEFS	60	ELECTRON ART	120	NEW BOOKS	122
CROSSTALK	65	NEW PRODUCTS	124	BACKTALK	132
TUBES AT WORK	118	NEWS OF THE INDUSTRY	128	INDEX TO ADVERTISERS	(Last Page)

DONALD G. FINK, *Editor*; **W. W. MacDONALD**, *Managing Editor*; John Markus, Vin Zeluff, A. A. McKenzie, *Associate Editors*; William P. O'Brien, James D. Fahnestock, *Assistant Editors*; Ann Mastropolo, Marilyn Wood, *Editorial Assistants*; Gladys T. Montgomery, *Washington Editor*; Harry Phillips, *Art Director*; Eleanor Luke, *Art Assistant*

KEITH HENNEY, *Consulting Editor*

H. W. MATEER, *Publisher*; **WALLACE B. BLOOD**, *Manager*; R. S. Quint, *Buyers' Guide Manager*; D. H. Miller, James Girdwood, *New York*; Wm. S. Hodgkinson, *New England*; Warren W. Shew, *Philadelphia*; C. D. Wardner, *Chicago*; J. L. Phillips, *Cleveland*; J. W. Otterson, *San Francisco*; Carl W. Dysinger, *Los Angeles*; Ralph C. Maultsby, *Atlanta*; Bernard H. Butler, *London, England*

Contents Copyright 1950, by McGraw-Hill Publishing Company, Inc. All Rights Reserved. McGRAW-HILL PUBLISHING COMPANY, INCORPORATED. JAMES H. McGRAW (1860–1948), Founder • PUBLICATION OFFICE, 99-129 North Broadway, Albany 1, N. Y., U. S. A. EDITORIAL AND EXECUTIVE OFFICES, 330 West 42nd St., New York 18, N. Y., U. S. A.—Member A. B. P., Member A. B. C.

Curtis W. McGraw, President; Willard Chevalier, Executive Vice President; Joseph A. Gerardi, Vice-President and Treasurer; John J. Cooke, Secretary; Paul Montgomery, Senior Vice-President, Publications Division; Nelson Bond, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Director of Circulation; Dexter Keezer, Director of Economics Department; Russell F. Anderson, Editor, World News.

ELECTRONICS: July, 1950, Vol. 23, No. 7. Published monthly with an additional issue in June, price 75¢ a copy for U. S. and possessions, and Canada; $1.50 for Latin America; $2.00 for all other foreign countries. Buyers' Guide issue $2.00. Allow at least ten days for change of address. All communications about subscriptions should be addressed to the Director of Circulation. Subscription rates—United States and possessions, $6.00 a year, $9.00 for two years, $12.00 for three years. Canada (Canadian funds accepted): $10.00 a year, $18.00 for two years, $20.00 for three years. Latin American countries $15.00 for one year, $25.00 for two years, $30.00 for three years. All other countries $20.00 for one year, $30.00 for two years, $40.00 for three years. Please indicate position and company connections on all subscription orders. Entered as Second Class matter August 29, 1936, at Post Office, Albany, New York, under the act of March 3, 1879. BRANCH OFFICES: 520 North Michigan Avenue, Chicago 11, Ill.; 68 Post Street, San Francisco 4; Aldwych House, Aldwych, London, W.C. 2; Washington, D. C. 4; Philadelphia 3; Cleveland 15; Detroit 26; St. Louis 8; Boston 16; Atlanta 3, Ga.; 1111 Wilshire Blvd., Los Angeles 17; 738-9 Oliver Building, Pittsburgh 22. ELECTRONICS is indexed regularly in The Engineering Index.



EL-MENCO CAPACITOR - CM-15

Miniature



CM 15 MINIATURE CAPACITOR

Actual Size 9/32" x ½" x 3/16"
For Television, Radio and other Electronic Applications
2 — 420 mmf. cap. at 500v DCw
2 — 525 mmf. cap. at 300v DCw
Temp. Co-efficient ±50 parts per million per degree C for most capacity values.
6-dot color coded.

This small-sized, high-capacity fixed mica condenser meets and beats strict Army-Navy standards. Like all El-Menco capacitors, the CM-15 must pass severe tests before leaving the factory. It is tested for dielectric strength at *double* working voltage; for insulation resistance and capacity value. You can always depend on the tiny CM-15 to give positive product performance under the most critical climate and operating conditions.

MANUFACTURERS WHO MAINTAIN REPUTATIONS for high-quality electrical equipment, demand and get high-quality El-Menco capacitors.

THE ELECTRO MOTIVE MFG. CO., Inc.
WILLIMANTIC CONNECTICUT

El-Menco

Write on your firm letterhead for Catalog and Samples

MOLDED MICA CAPACITORS **MICA TRIMMER**

FOREIGN RADIO AND ELECTRONIC MANUFACTURERS COMMUNICATE DIRECT WITH OUR EXPORT DEPT. AT WILLIMANTIC, CONN. FOR INFORMATION.
ARCO ELECTRONICS, INC. 135 Liberty St., New York, N. Y. - Sole Agent for Jobbers and Distributors in U.S. and Canada



Designed for use at frequencies from 50 c/s - 2000 c/s. Phonic Motors of this type form the nucleus around which are built the timing devices illustrated on this page.



The Timing Device Type D-199-A provides an impulse of 1/10 second duration once every second, when the motor is supplied with power at a frequency of 1000 c/s.

The Timing Device Type D-193-A provides an impulse of 1/10 second duration 61 times per minute and, in addition, an impulse of ½ second duration once per minute. A worm and wheel adjustment allows phasing correction.



Phonic Motors and Timing Devices

IN many branches of scientific work the need arises for a motor capable of a very high standard of constancy of speed. The frequency of the mains electricity supply is not normally controlled to better than one or two per cent., so that a mains-operated synchronous motor may be inadequate, and centrifugal governors, as used on gramophone motors, may not provide a sufficiently precise control. In such cases a phonic motor driven by an alternating current supply of high frequency stability may be employed. It is not perhaps generally realized that in their modern form such motors may be used to give quite a large torque, and are able to maintain synchronism despite the sudden imposition of relatively large inertia loads. Under steady-state conditions, "hunting" is almost entirely eliminated, and the constancy of rotational speed is almost entirely dependent on the frequency stability of the alternating current supply.

A precision quartz crystal controlled frequency of 100 kc/s may attain a frequency stability of the order of one part in 10^8. This frequency is then divided electronically to 1,000 c/s by means of regenerative dividers or locked multivibrators. In order to facilitate comparisons with time signals, or to use the frequency standard as a clock, it is necessary to derive a still lower frequency—preferably one cycle per second. Electronic division in the range 1,000 to 1 cycle per second, with high phase stability, is difficult, and the simplest and most reliable method is to drive a phonic motor from the 1,000 c/s source, and to fit mechanical contacts to suitably geared driven shafts. An added advantage is that by employing further gearing, more widely spaced signals may be obtained. Thus signals spaced at intervals of one sidereal second, or any other specified interval, may be obtained from an oscillator with a fundamental frequency of 100 kilocycles per mean time second. By means of a simple mechanical device, controlled changes in phase of the timing of the contacts are also possible.

MOTOR TORQUE

Are You

ON OUR MAILING LIST for TECHNIQUE

A JOURNAL OF INSTRUMENT ENGINEERING

IF NOT MAIL COUPON NOW

MUIRHEAD & CO. LTD · BECKENHAM · KENT · ENGLAND

Please mail me, free of charge, your quarterly journal "TECHNIQUE"

NAME

POSITION

COMPANY

ADDRESS

MUIRHEAD & Co. Ltd.

PRECISION ELECTRICAL INSTRUMENT MAKERS

BECKENHAM · KENT · ENGLAND

Telegrams and Cables: MUIRHEADS ELMERS-END

PRECISION MUIRHEAD ELECTRICAL INSTRUMENTS

MU.26



Logistics

for resistors too!

For *adequate* supplies of resistors in an ever-widening market, depend on IRC *logistics*. Already the largest manufacturer of resistors in the world, IRC has increased its output tremendously to meet your requirements. And in addition, IRC capacity is now being supplemented by licensees in Canada and Denmark—while English, Australian and Italian licensees provide resistors for other world markets formerly supplied from the United States. IRC *availability* extends even to your urgent, small-order requirements for standard resistors. Through our Industrial Service Plan, your IRC Distributor can supply these promptly from full stocks of the most popular types and sizes.



Stock-piling of advanced BT's

has been proved practical by IRC's study of resistor-use patterns. A recently completed three-year profile shows that 80% of the BT resistors used in TV and radio equipment include only 30 values. This holds true despite design changes and shifts in the industry's emphasis on sets. And these facts prove that you can now simplify purchasing, stocking and expediting practices by placing long-term orders covering your basic, recurring needs for BT's. Engineered to meet JAN-R-11 specifications for fixed composition resistors, IRC BT's have established their superiority in all important characteristics. Bulletin B-1 brings you full details of IRC BT's, and a copy of our study is yours for the asking.

is important



Chokes

The right Resistors . . .

for precision applications often require a combination of characteristics. IRC Deposited Carbon PRECISTORS combine accuracy and economy in:—Circuits in which the characteristics of carbon composition resistors are unsuitable and wire-wound resistors too expensive — Metering and voltage divider circuits requiring high stability and close tolerance of the resistance values — High-frequency applications. The two sizes of IRC PRECISTORS are manufactured to customers' specifications, rather than to standard RMA values (subject, of course, to minimum and maximum values for each type). For complete data on characteristics and values, mail coupon for Bulletin B-4.

Modern mass production equipment . . .

plus exclusive manufacturing techniques, make IRC Insulated Chokes relatively inexpensive — and offer considerable savings over ordinary types. Available in two sizes, IRC chokes are insulated in molded phenolic housings for full protection against high humidity, abrasion, damage during assembly, and danger of shorting to chassis. "Q" improves with rise in frequency and is sufficiently high for broad-band tuning in FM and TV regions. Resistance is low enough to permit use as filament chokes for moderately high power tubes. Coupon brings you full information in Bulletin H-1.



Dependable source of small-size controls . . .

IRC meets your requirements with the new 1½" Type Q. Mechanization of production and testing assures increased supplies of these miniature controls. And elimination of hand operations provides complete uniformity of construction and performance. New IRC Type Q Controls are rugged and compact. Resistance element is the best IRC has ever produced. Increased arc of rotation permits the same resistance ratios used in larger IRC Controls. IRC Type Q's are characterized by low noise level, negligible changes in resistance even after long exposure to humidity, unusual durability and efficiency, and adaptability to a wide variety of small-space applications. Bulletin A-1 gives full information.

IRC

Wherever the Circuit Says ~~~

Power Resistors • Voltmeter Multipliers • Insulated Composition Resistors • Low Wattage Wire Wounds • Controls • Rheostats • Voltage Dividers • Precisions • Deposited Carbon Precistors • High Frequency and High Voltage Resistors • Insulated Chokes

INTERNATIONAL RESISTANCE COMPANY

401 N. Broad Street, Philadelphia 8, Pa.

In Canada: International Resistance Co., Ltd., Toronto, Licensee

INTERNATIONAL RESISTANCE CO.
403 N. BROAD ST., PHILADELPHIA 8, PA.

Please send me complete information on the items checked below:

- ☐ Advanced BT Resistors (B-1)
- ☐ PRECISTORS (B-4)
- ☐ IRC Study of Resistor Use
- ☐ New Q Controls (A-1)
- ☐ Insulated Chokes (H-1)
- ☐ Name and Address of local IRC Distributor

NAME .....

TITLE .....

COMPANY .....

ADDRESS .....

CITY ..... STATE .....

J. P. ARNDT & CO., ADV. AGENCY

3 TYPES OF VICKERS Standard MAGNETIC AMPLIFIERS

...designed to give you better control—at lower cost

Whatever your specific control operation needs in power . . . performance . . . and economy . . . you'll find a Vickers Standard Magnetic Amplifier that is tailored to give your control requirements these benefits:

- **NO MAINTENANCE**
- **HIGH PERFORMANCE**
- **RUGGED CONSTRUCTION**
  No Moving Parts
- **NO WARM-UP TIME**
- **A-C OR D-C CONTROL**
  A-C or D-C Output
- **RESPONDS TO SUM OR DIFFERENCE OF SEVERAL SIGNALS**
- **ALLOWS ELECTRICAL ISOLATION BETWEEN CIRCUITS**



HIGH PERFORMANCE

For 60 cps power sources — 28 styles — maximum output powers from milliwatts to 108 watts.
For 400 cps power sources — 20 styles — maximum output powers from 30 watts to 585 watts.



HIGH GAIN

For 60 cps power sources — 22 styles — maximum output powers from ½ watt to 1200 watts.



HIGH POWER

For 60 cps power sources — 20 styles — maximum output powers from 65 watts to 3660 watts.

TYPICAL APPLICATIONS

Servo Mechanisms • Line-to-line Voltage Regulators • Hydraulic Transmission Controls • A-C and D-C Generator Voltage Regulators • Speed and Frequency Regulators • Lamp and Furnace Controls
Temperature Regulators
Time Delay Devices

NOW AVAILABLE

BULLETIN 20-A, which lists condensed characteristics of the complete line of Vickers Standard Magnetic Amplifiers. Write for your copy today! Please make request on your letterhead.

VICKERS ELECTRIC DIVISION

VICKERS INC.
1400 LOCUST STREET • ST. LOUIS 3, MISSOURI

EXACTITUDE

Precise impedance and wavelength measurements in the range of **60** to **1000** megacycles per second.

1000 to 2000 Mc range covered with slightly reduced accuracy.



The large demand has enabled us to make production savings, and the famed FTL-30A Slotted Line is now available at a greatly reduced price.

Write for complete FTL-30A brochure.

INTERNATIONAL TELEPHONE AND TELEGRAPH — FTL

Federal Telecommunication Laboratories, Inc.

500 Washington Avenue Nutley 10, New Jersey

For Tough Machining Jobs, Get REVERE FREE-CUTTING BRASS







Above, Model CS, smallest condenser, air space .009". Below, Model B, largest, air space .013". Rotor shafts, shown in top illustration, are Revere Free-Cutting Brass, plates aluminum. Made by The American Steel Package Co., Defiance, Ohio, an important supplier to the electronics industry.

HERE are several examples of the fact that Revere Free-Cutting Brass is really good. These rotor shafts for variable condensers are cut on automatic machines at 3600 r.p.m. Circular tools are used to cut the concentric slots which are .050" deep. Only one cut has to be taken. Approximately 425 pieces are produced per hour on a 6-second cycle. The American Steel Package Company, Defiance, Ohio, produces a number of different condenser models, with air spacing ranging from .009" up to .042". The slots in the shaft of Revere Free-Cutting Brass are all of the same width, regardless of air spacing, namely .014" plus or minus .0002". It takes good machines, good tools, good men, and good metal to work that closely. A report from a Revere Technical Advisor who had collaborated with the company states: "Customer is outstanding in his praise of Revere Rod." . . . If you have a problem in the machining of brass, why not give Revere an opportunity to work with you? The Revere Technical Advisory Service is at your command.

REVERE

COPPER AND BRASS INCORPORATED

Founded by Paul Revere in 1801

230 Park Avenue, New York 17, New York

Mills: Baltimore, Md.; Chicago, Ill.; Detroit, Mich.; Los Angeles and Riverside, Calif.; New Bedford, Mass.; Rome, N. Y.
Sales Offices in Principal Cities, Distributors Everywhere.

YOU ASKED FOR IT...

here it is!



MODEL TR—New deluxe rim drive, 2 pole phonomotor for 78, 33⅓ and 45 R.P.M. records. Ingenious turret-type speed change mechanism results in unsurpassed performance and dependability. Uses standard narrow flange turntable.

General Industries' *New* Deluxe 3-SPEED PHONOMOTOR

Now . . . in answer to the tremendous demand for a manual version of the popular GI turret model 3-speed record changer motor, General Industries presents the *new* Model TR. Truly the last word in compact 3-speed phonomotors, the Model TR is designed for use in the finest phonographs and radio-combinations.

In addition to the Model TR, General Industries will continue to offer the ever-popular Model TS, 3-speed neoprene belt-driven model for both manual and record-changer use.

Today, as always, General Industries leads the field with the *only* complete line of phonomotors for every record-playing requirement. Write, wire or phone for the latest General Industries catalog containing specifications and description of the full GI *Smooth Power* lineup.

The GENERAL INDUSTRIES Co.

DEPARTMENT B • ELYRIA, OHIO

The New ML-2C39A*...



Proving once again that MACHLETT ..makes the Difference

1. Design of cathode lead for positive adjustment and control of transconductance; limits are 20,000-23,000 umhos or only 25% of permissible specified range.

2. High temperature ceramic in hot cathode end eliminates danger of gas evolution from glass at high temperatures. Assures better protection under overload conditions.

3. Uniquely processed mesh grid assures greater frequency stability with variation in grid dissipation.

4. Gold over silver plating to maintain optimum surface conductivity even in corrosive atmospheres.

5. Machlett's high vacuum processing for good cathode activation and freedom from gasiness.

6. Stronger glass-metal seals. Less breakage inserting and removing tubes.

** Conforms with recently issued JAN specifications.*

ML-2C39A GENERAL CHARACTERISTICS

Electrical

Cathode: Coated Unipotential	
Heater Voltage	6.3 volts
Heater Current	1.0 amperes
Amplification Factor (Average)	100
Direct Interelectrode Capacitances (Average)	
Grid Plate	1.95 μμfd.
Grid Cathode	6.50 μμfd.
Plate Cathode	0.035 μμfd.
Transconductance (I_b = 70 ma., E_b = 600 v.) (Average)	23,000 μmhos

Radio Frequency Power Amplifier
Class-C FM Telephony or Telegraphy
(key down conditions, 1 tube)

Maximum Ratings	
D-C Plate Voltage	1000 max. volts
D-C Cathode Current	125 max. ma.
D-C Grid Voltage	−150 max. volts
Peak Positive R-F Grid Voltage	30 max. volts
Peak Negative R-F Grid Voltage	−400 max. volts
Plate Dissipation	100 max. watts
Grid Dissipation	2 max. watts

ML-381 FOR PULSED APPLICATIONS

Maximum Ratings (Tentative)

e_p, peak	3500 volts
i_p, peak	4.5 amps
i_g, peak	2.0 amps
I_p, ave	30 MA
I_g, ave	15 MA
T, pulse length	5 μ sec.
duty	1%
E_f	5.5 volts ± 5%

In all other respects the ML-381 is electrically and mechanically interchangeable with the 2C39A.

"Look to the Tube Specialist"

Long experience in the development and manufacture of the 2C39A electron tube has given Machlett Laboratories a comprehensive understanding of the operating problems encountered in a wide variety of applications of this tube type.

For assistance on your specific problem, write to Machlett Laboratories or contact your local Graybar office.

Distributed by GRAYBAR

MACHLETT OVER 50 YEARS OF ELECTRON TUBE EXPERIENCE

ADVENTURES IN ELECTRONIC DESIGN

THE BEST CHEFS IN THE WORLD ARE MEN.

Each one of these renowned chefs has his pet dishes for which he is famous. In making up these dishes, from Shish Kabob to Crepes Suzettes, these chefs carefully select each ingredient and carefully blend them in exact proportions to impart the distinct flavor body and texture that make these dishes glamorous good eating. And ceramic capacitors are just like foods that are good eating. For example Centralab has actually experimented with over 20,000 different ceramic compounds and discarded all but 250 of them. With these 250, they've developed a wide variety of formulas or recipes. Each one makes a ceramic capacitor of distinct electrical and physical properties. That's why CRL ceramic capacitors are better — the exact ceramic formula to meet exact electrical and physical needs is individually compounded to meet them. CRL has spent hundreds of thousands of laboratory and manufacturing hours . . . over the past 20 years to perfect its ceramic parts. New experiments with new ingredients are constantly going on. So as each chef has his own secrets of food success — so Centralab engineers develop the perfect ceramic body to solve each of your capacitor problems.

Centralab – DEVELOPMENTS THAT HELP YOU

Division of GLOBE-UNION INC., Milwaukee

THE SPOTLIGHT'S
The Most Permanent-

RESULTS prove Centralab Hi-Vo-Kaps Best for TV

YES, CRL Ceramic High Voltage Capacitors — the kind that high voltage requirements of TV need (10-20-30 KV, 500 mmf capacity) — have become the accepted standard for the TV industry. This is no accident! For these units were specifically designed for the TV job. Behind them stands more years of engineering know how—more extensive production know-how than offered by any similar units. If you have high voltage capacitor problems — it will pay you to call in CENTRALAB — to investigate CRL Hi-Vo-Kaps today.

ON CERAMICS
Type Capacitors





Centralab offers the widest line of ceramic capacitors in the entire industry — By-pass, Coupling, Temperature Compensating — tubulars, discs, plates. *Remember* — it's ceramics for longest life under high humidity and high temperature conditions.

Top — tubular trimmers especially designed for TV tuners. Bottom — ceramic trimmer-capacitors — with unusually stable characteristics. Stability due to *optically ground* uniformly flat surfaces. Rotor and stator plates of metallic silver — fired to ceramic rotor and stator bodies.

Printed Electronic Circuits — the pinnacle of their development — Centralab Ampec.... 3 full audio stages of a speech amplifier — all components complete in one miniature unit — 1¼" x 1⅛" x .340" over tube sockets.

Looking for savings? *At left* — Vertical Integrator — widely used in TV vertical integrator circuits — vastly reduces assembly costs. *At right* — a CRL Pentode Couplate — easily replaces screen, grid and plate resistors; screen by-pass, plate r.f. by-pass and coupling capacitors.





IMPORTANT BULLETINS FOR YOUR TECHNICAL LIBRARY!

They're factual!

THEY'RE FREE!

Choose From This List!

Centralab Printed Electronic Circuits

973 — AMPEC — three-tube P. E. C. amplifier.
42-6 — COUPLATE — P. E. C. interstage coupling plate.
42-22 — VERTICAL INTEGRATOR — for TV application.
42-24 — CERAMIC PLATE COMPONENTS — for use in low-power miniature electronic equipment.
42-27 — MODEL 2 COUPLATE — for small or portable set applications.
999 — PENTODE COUPLATE — specialized P. E. C. coupling plate.
42-9 — FILPEC — Printed Electronic Circuit filter.

Centralab Capacitors

42-3 — BC TUBULAR HI-KAPS — capacitors for use where temperature compensation is unimportant.
42-4R — BC DISC HI-KAPS — miniature ceramic BC capacitors.
42-10 — HI-VO-KAPS — high voltage capacitors for TV application.
42-59 — CERAMIC TUBULAR TRIMMERS — designed for TV and VHF application.
695 — CERAMIC TRIMMERS — CRL trimmer catalog.
981 — HI-VO-KAPS — capacitors for TV application. For jobbers.
42-18 — TC CAPACITORS — temperature compensating capacitors.
814 — CAPACITORS — high-voltage capacitors.
975 — FT HI-KAPS — feed-thru capacitors.

Centralab Switches

953 — SLIDE SWITCH — applies to AM and FM switching circuits.
970 — LEVER SWITCH — shows indexing combinations.
995 — ROTARY SWITCH — schematic application diagrams.
722 — SWITCH CATALOG — facts on CRL'S complete line of switches.

Centralab Controls

42-19 — MODEL "1" RADIOHM — world's smallest commercially produced control.

Centralab Ceramics

967 — CERAMIC CAPACITOR DIELECTRIC MATERIALS.
720 — CERAMIC CATALOG — CRL steatite, ceramic products.

Look to CENTRALAB in 1950! First in component research that means lower costs for the electronic industry. If you're planning new equipment, let Centralab's sales and engineering service work with you. For complete information on all CRL products, get in touch with your Centralab Representative. Or write direct.

CENTRALAB
Division of Globe-Union Inc.
900 East Keefe Avenue, Milwaukee, Wisconsin

Yes—I would like to have the CRL bulletins checked below for my technical library!

☐ 973	☐ 42-24	☐ 42-9	☐ 42-10	☐ 981	☐ 975	☐ 722
☐ 42-6	☐ 42-27	☐ 42-3	☐ 42-59	☐ 42-18	☐ 953	☐ 42-19
☐ 42-22	☐ 999	☐ 42-4R	☐ 695	☐ 814	☐ 970	☐ 967
					☐ 995	☐ 720

Name _____

Address _____

City _____ State _____

TEAR OUT COUPON
for the Bulletins you want

Centralab
CRL
Division of GLOBE-UNION INC. • Milwaukee

SPECIFY *Federal* HF CABLES

to get the cable that is *Precisely Right* for your application

IT PAYS TO SPECIFY FEDERAL...

- **America's most complete selection of solid dielectric cable types.**
- **Quality and performance proved by years of outstanding operation.**
- **Competitively priced . . . prompt delivery—most types available for shipment from stock.**

There is no need to compromise when you specify Federal cable. Federal is your assurance of obtaining precisely the cable you require—whether it is one of the scores of Army-Navy approved types or one of the exclusive Federal-developed special purpose cables.

Nor is there any compromise with quality and dependability when you insist on Federal. Millions of feet of Federal cable, serving in countless applications, are continuing proof of Federal's superiority.

Does Your New Design Require Unusual Cable Characteristics?

These three types are typical of the special purpose cables developed by Federal to meet specific requirements and manufactured exclusively by Federal:

Federal No.	TYPE	Characteristic Impedance — Ohms	Capacitance mmf/foot
KT-107	Shielded, balanced, twisted pair (Twinax)	72	22
K-109	Ultra-low-capacitance coaxial cable	160	8.3
K-113	Low impedance coaxial cable	34	39

For data on other Federal special types, as well as specifications on Federal's complete line of JAN-Approved cables, write today for your free copy of Federal's Cable Data Booklet. Address Department D-313.

Federal Telephone and Radio Corporation

A unit of IT&T

SELENIUM and INTELIN DIVISION, 100 Kingsland Road, Clifton, New Jersey

In Canada: Federal Electric Manufacturing Company, Ltd., Montreal, P. Q.
Export Distributors: International Standard Electric Corp., 67 Broad St., N. Y.

MIRAGLAS TUBINGS and SLEEVINGS

NOW COST NO MORE THAN COTTON TUBINGS AND SLEEVINGS

. . . and PROVIDE PREMIUM PROTECTION . . . at NO EXTRA COST



MIRAGLAS TUBINGS and SLEEVINGS, woven of fiberglas yarn, provide the ultimate protection against overloading, extreme high or low temperatures, moisture, corrosive acids, fumes, vapors, oils, general dust and dirt . . . they won't rot, have high tensile and dielectric strength and great flexibility . . . and they cost no more than cotton sleevings and tubings.

MIRAGLAS VARNISHED TUBINGS are made in 4 grades:

STANDARD *for maximum flexibility and high temperature applications where dielectric strength is not a factor*

DOUBLE SATURATED *is similar to Standard but with a dielectric rating up to 1500 volts*

TRIPLE STRENGTH *is especially flexible, resists rough handling and has a dielectric rating to 2500 volts*

IMPREGNATED *is the superior grade, has a dielectric rating beyond 7000 volts, is high gloss, non-hydroscopic, and unequalled for long life under most severe conditions*

MIRAGLAS BRAIDED SLEEVINGS, **of continuous filament fiberglas yarn, are available untreated or impregnated to prevent ends from fraying, in two average wall thicknesses: .008" and .006" with inside diameters from 1/16" to 1/2" in 1/16" increments (there is no 7/16" I.D. sleeving).**

Take note of the name MIRAGLAS . . . it stands for the ultimate in fiberglas electrical insulations . . . TAPES, TUBINGS, SLEEVINGS, CORDS, CLOTHS, ETC. Write today for details and characteristics.

MITCHELL-RAND INSULATION CO. Inc.

51 MURRAY STREET · COrtlandt 7-9264 · NEW YORK 7, N. Y.

M-R THE ELECTRICAL INSULATION HEADQUARTERS FOR 61 YEARS.

A PARTIAL LIST OF M-R PRODUCTS: FIBERGLAS VARNISHED TUBING, TAPE AND CLOTH · INSULATING PAPERS AND TWINES · CABLE FILLING AND POTHEAD COMPOUNDS · FRICTION TAPE AND SPLICE · TRANSFORMER COMPOUNDS · FIBERGLAS SATURATED SLEEVING · ASBESTOS SLEEVING AND TAPE · VARNISHED CAMBRIC-CLOTH AND TAPE · MICA PLATE, TAPE, PAPER, CLOTH, TUBING · FIBERGLAS BRAIDED SLEEVING · COTTON TAPES, WEBBINGS AND SLEEVINGS · IMPREGNATED VARNISH TUBING · INSULATED VARNISHES OF ALL TYPES · EXTRUDED PLASTIC TUBING

I-T-E's

NEW ADJUSTABLE

SHUNT PM-EM FOCUS COIL

Gives You Proper Focus Under a Wider Range of Conditions

With the I-T-E Adjustable Shunt PM-EM Focus Coil you can adjust PM strength over a wide range, compensating for most tube and set variations. This feature virtually eliminates assembly line rejects caused by out-of-tolerance PM strength. Flexibility of the adjustable shunt makes it possible for you to use one focus coil design to focus several types and sizes of tubes.

Design features greatly reduce magnetic interference with ion magnet on new short neck tubes. Among the many other advantages of I-T-E Adjustable Shunt PM-EM Focus Coils is their low operating temperature — gained through lower focus current requirements. I-T-E Adjustable Shunt PM-EM Focus Coils retain proper focusing over a wide range of line voltage variations.

I-T-E makes Adjustable Shunt PM-EM Focus Coils for use with 10", 12", 14", 16" and 19" picture tubes. They are available in a variety of standard or special mountings, and any special mounting can be furnished upon request. Information needed to manufacture: Type of tube; second anode voltage; focusing current desired; special considerations for mountings and leads.

I-T-E's design engineers will be glad to work with you on your applications or requirements — consult them without obligation. For complete information of I-T-E Adjustable Shunt PM-EM Focus Coils — or any other I-T-E wire-wound products — write, wire, or call, specifying your needs.

FOCUS COILS

RESISTOR DIVISION, I-T-E CIRCUIT BREAKER COMPANY

19th & Hamilton Streets, Philadelphia 30, Pa.

I-T-E Wire-Wound Products: FOCUS COILS · DEFLECTION YOKES · RESISTORS

extreme precision, instant response in remote indication and control



GEARED MOTOR-DRIVEN INDUCTION GENERATORS: Small 2-phase servo motor in combination with a compact gear-reducer and a low residual induction generator. Motor has high torque/inertia ratio and develops maximum torque at stall. Gear-reducer permits a maximum torque output of 25 oz. in. and is available in ratios from 5:1 to 75,000:1.

INDUCTION MOTORS: miniature 2-phase motors of the squirrel cage type. Designed specifically to provide fast response to applied control signals and maximum torque at zero r.p.m. Unit shown weighs 6.1 oz. and has stalled torque of 2.5 oz. in.

CIRCUTROL UNITS: rotary electromagnetic devices for use as control components in electronic circuits and related equipment. Single and polyphase rotor and stator windings are available in several frame sizes. Deviation from sine accuracy of resolver shown is ±0.5% of maximum output.



SYNCHRONOUS MOTORS: for instrumentation and other applications where variable loads must be kept in exact synchronism with a constant or variable frequency source. Synchronous power output up to 1/100 H.P.



SYNCHRONOUS DIFFERENTIAL UNITS: electro-mechanical error detectors with mechanical output for use in position or speed control servo systems. These torque-producing half-speed synchroscopes are composed of two variable frequency synchronous motors and a smoothly operating system of differential gearing.

Output: Speed $= \frac{N_1 - N_2}{2}$; Torque up to 1.0 oz. in.



TELETORQUE UNITS: precision synchros for transmitting angular movements to remote points. Accurate within ±1°. May be actuated by mechanisms that produce only 4 gm. cm. (.056 oz. in.) of torque.



ADDITIONAL SPECIAL PURPOSE AC UNITS BY KOLLSMAN

With the recent addition of new units to Kollsman's already widely diversified line, the electronics engineer will find the solution to an even greater variety of instrumentation and control problems. These lightweight, compact units offer the high degree of accuracy and positive action essential in dealing with exact quantities. They are the product of Kollsman's long experience in precision instrumentation and aircraft control — and of considerable work done in this field by Kollsman for special naval and military application. Most units are available at various voltages and frequencies. For complete information, address: Kollsman Instrument Division, Square D Company, 80-64 45th Avenue, Elmhurst, N. Y.

KOLLSMAN INSTRUMENT DIVISION

SQUARE D COMPANY

ELMHURST, NEW YORK · GLENDALE, CALIFORNIA

NEW

DRIVER-HARRIS ELECTRONIC TESTING

Obsoletes Previous Methods of Testing Enameled Wire Insulation



This revolutionary Dielectric Continuity Tester at Driver-Harris checks the quality of coating on 19 strands of wire simultaneously—as the wire leaves enameling furnaces. Tap switches on the test units are calibrated in impulses per minute required to operate an alarm. With the speed of the wire known, and also the maximum number of faults per 100 feet permitted by specification, each test unit is readily set to operate in conformance with the terms of the test imposed.

In order to guarantee the quality of a spool of enameled wire, *every inch* of the wire should be checked for dielectric faults, not just a few feet. In general practice, however, only a short sample of wire is examined. This is passed through a mercury cup held at a fixed potential, and shorts through the insulation are indicated on a voltmeter. If faults do not exceed a specified maximum for a given length of wire, insulation throughout the *entire* spool is assumed to be satisfactory.

This inefficient, compromise method has two important disadvantages: (1) the small portion of wire tested may not truly represent the condition of insulation throughout the spool; (2) insulation failures are not discovered until long after the enameling process is completed.

By checking insulation *continuously*, as wire leaves the enameling furnaces—the only 100% dependable way—Driver-Harris' new test equipment obsoletes such ineffectual and wasteful procedure.

So long as specifications are met, the new Driver-Harris electronic tester permits the enameling process to continue uninterrupted. When the *rate* at which faults occur approaches the maximum number of faults permitted by specifications, the test mechanism sounds an alarm and a record is made on a moving chart.

In this way, enamel coating is not only tested for continuity throughout the entire length of spooled wire, but sub-standard enameling is detected—and can be corrected —as soon as it occurs.

Thus makers of wire-wound resistors—particularly in finer sized wire, where shorts are more likely to occur—are enabled to eliminate time-waste and material-waste in their production, and obtain superior, more dependable products.

Makers of world-famous Nichrome and over 80 alloys for the electrical, electronic and heat-treating fields*

Driver-Harris Company

HARRISON, NEW JERSEY

BRANCHES: Chicago, Detroit, Cleveland, Los Angeles, San Francisco

Manufactured and sold in Canada by
The B. GREENING WIRE COMPANY, LTD., Hamilton, Ontario, Canada

FIFTIETH ANNIVERSARY

*T. M. Reg. U. S. Pat. Off.

COPPER ALLOY BULLETIN

PRODUCT IMPROVEMENT EDITION

REPORTING NEWS AND TECHNICAL DEVELOPMENTS OF COPPER AND COPPER-BASE ALLOYS

Prepared Each Month by Bridgeport Brass Co. "Bridgeport" *Headquarters for BRASS, BRONZE and COPPER*





Brass is used for the reflector and housing of the Perfection Telebeam Spotlight. Both brass and silicon bronze serve best for the vital parts of the Vis-O-Lite illuminated cigarette lighter. Courtesy Casco Products Corp., Bridgeport, Conn.

Brass for Automotive and Electrical Accessories

Reduction of cost without sacrificing quality is uppermost in the minds of design and production engineers. The merits and demerits of available metals and alloys for fabricating long run items, such as automotive and electrical accessories, should be carefully weighed.

More Easily Fabricated

Brass, from long experience, takes the first choice because of its ease of workability and many other advantages. It can readily be stamped, formed, drawn, spun, swaged, drilled, threaded, soldered, welded, polished, plated.

For electrical applications the high conductivity of the brasses is advantageous where the parts are designed to carry current.

Aside from the fact that it can stand deep draws and can be made into intricate shapes, its low coefficient of friction with steel means remarkably long tool life. Its initial cost is partially offset by its high scrap value as compared with other materials.

Another important property that should not be overlooked is its excellent corrosion resistance to moisture and weathering.

Since automotive accessories are exposed to the rain, sleet, snow, dampness, and extremes of heat and cold, a non-rusting metal is desirable in the manufacture of high quality products. Although modern chromium plating gives an attractive finish to most metals, time soon reveals the weakness of an inferior metal since chromium plate may be porous and does not give complete protection from the elements. Chromium plated brass over an under coat of nickel plate retains its beauty for many years, requiring only an occasional removal of surface grime with a damp cloth.

Some savings can often be obtained in reducing the cost of polishing previous to plating. Because of its intrinsic hardness or resistance to abrasion and wear, brass takes on a polished finish quickly with the minimum of effort. However, in some cases, the polishing time can be reduced by obtaining metal of the proper grain structure. Informing the mill as to the operations and finish required will enable it to supply metal with the structure which will produce the greatest economy.

Importance of Annealing

At the same time, fabricators should realize that the original microstructure of the metal as it comes from the mill changes with the subsequent annealing operations which it may receive during fabrication. In other words, the fabricator should control the grain structure of the metal during his own annealing just as carefully as the mill performs this important operation. As frequently mentioned, a coarse grain structure results in a rough surface which requires considerable cutting down to produce the necessary high polished effect. A fine grain structure, on the other hand, produces a smoother surface which requires less polishing and color buffing.

Phosphor Bronze for Speed Nuts

The old adage, "a chain is only as strong as its weakest link," probably caused engineers at Tinnerman Products, Inc., Cleveland, Ohio, to select Phosphor Bronze for their speed nuts.

These small but vital spring parts must withstand constant tension and vibration. In the assembly of a mechanism, the metal in the nut must take a sizable deflection without setting, or the function of the nut would be nullified.

Phosphor Bronze Grade C, about 92% copper, 8% tin, and 0.1% phosphorus, 8 B&S numbers hard, has a tensile strength of about 112,000 psi. The Grade A alloy contains about 95% copper, 5% tin and 0.15% phosphorus and has a tensile strength of about 103,000 psi when rolled the same temper.



Speed Nuts made from Phosphor Bronze. Courtesy Tinnerman Products, Inc., Cleveland, Ohio.

Phosphor Bronze has many industrial applications because of its high corrosion resistance and excellent spring properties retained under repeated flexing. It is used widely for electrical snap switches, diaphragms, current collectors, spring contacts, and parts for electronic equipment.

BRASS · BRONZE · COPPER · DURONZE — STRIP · ROD · WIRE · TUBING

MILLS IN
BRIDGEPORT, CONNECTICUT
INDIANAPOLIS, INDIANA
In Canada:
Noranda Copper and Brass Limited, Montreal

BRIDGEPORT BRASS COMPANY
BRIDGEPORT 2, CONNECTICUT
Established 1865
"Bridgeport" *District Offices and Warehouses in Principal Cities*



HI-Q COMPONENTS

Capacitors
Trimmers • Choke Coils
Wire Wound Resistors

BETTER 4 WAYS

- PRECISION
- UNIFORMITY
- DEPENDABILITY
- MINIATURIZATION

● **HI-Q** BC Tubular Ceramic Capacitors for by-passing, coupling and filtering are available with any of three types of insulations:—clear non-hydroscopic styrene coating (CN)...Durez impregnated with low loss microcrystalline wax (SI) ... or a ceramic (steatite) cover tube sealed with a specially developed end seal (CI). The **HI-Q** trade mark is your assurance that like all **HI-Q** Components, they rigidly meet specifications and are uniformly dependable in every respect. As leading specialists in the ceramic field, **HI-Q** has come to be regarded by producers of radio, television, communications and electronic equipment as their best source of technical assistance in developing components to meet the needs of any circuit.

JOBBERS – Address: 740 Belleville Ave., New Bedford, Mass.

HI-Q *Electrical Reactance Corp.*
FRANKLINVILLE, N. Y.

SALES OFFICES: New York, Philadelphia
Detroit, Chicago, Los Angeles

PLANTS: Franklinville, N. Y., Olean, N. Y.
Jessup, Pa., Myrtle Beach, S. C.

MYCALEX

MINIATURE TUBE SOCKETS

7-PIN and 9-PIN . . . and SUBMINIATURES

New Low Prices



Now MYCALEX offers both 7-pin and 9-pin miniature tube sockets . . . with superior low loss insulating properties, *at new low prices* that offer ceramic quality for the cost of phenolics.

MYCALEX miniature tube sockets are injection molded with precision that affords uniformity and extremely close tolerances. MYCALEX insulation has high dielectric strength, very low dielectric loss, high arc resistance and great dimensional stability.

Produced in two grades: MYCALEX 410 conforms to Grade L4 specifications, having a loss factor of only .015 at 1 MC. It is priced comparably with mica filled phenolics.

MYCALEX 410X is for applications where low cost of parts is vital. It has a loss factor only one fourth that of "everyday" quality insulating materials, and a cost no greater.

Prices gladly quoted on your specific requirements. Samples and data sheets by return mail. Our engineers will cooperate in solving your problems of design and cost.

Mycalex Tube Socket Corporation
"Under Exclusive License of Mycalex Corporation of America"
30 Rockefeller Plaza, New York 20, N. Y.

SINCE 1919
MYCALEX
THE INSULATOR
TRADE MARK REG U.S. PAT OFF

MYCALEX CORP. OF AMERICA

"Owners of 'MYCALEX' Patents"

Executive Offices: 30 Rockefeller Plaza, New York 20, N. Y. Plant and General Offices: Clifton, N. J.





FORD for '50
HYTRON for '50

Thrifty, nifty fifty Ford. On the dash a fine new Ford radio receiver. And again tubes by Hytron. Hytron continues as a major supplier of Ford auto radio tubes. Because Hytron *specializes* in auto radio tubes. Engineered for leaders like Ford, these Hytron tubes are leaders too. 'Nuff said! Buying auto radio tubes? Buy wise . . . like Ford. Buy Hytron!

HYTRON

MAIN OFFICE: SALEM, MASSACHUSETTS

NEW 4TH EDITION — Hytron Reference Guide for Miniature Electron Tubes. Free from your Hytron jobber; or write us. Original . . . unique. Lists all miniatures to date, regardless of make. Six pages. 132 miniatures — 41 new. 70 basing diagrams. Lists similar larger prototypes. Get your copy today.

FREE — Hytron Tool Catalogue. Describes famous Hytron service-shop tools; Soldering Aid, Tube Lifter, 7-Pin and 9-Pin Straighteners, Tube Topper and Auto Radio Tool. Find out how these Hytron tools can ease your work . . . help you make more money. Write today.

ELECTRONICS

Designers



Simplify YOUR CONTROL CIRCUITS WITH THESE G-E COMPONENTS

● **MOLDED TERMINAL BOARDS**—Designed to give positive electrical connection without soldering lugs, these sturdy terminal boards are built of molded Textolite® with reinforced pole barriers. Hinged protective covers protect wiring; marking strips are reversible—white on one side, black on the other. Boards are available with 4 to 12 poles; are 2 inches wide, $1\frac{1}{4}$ inches long. See Bulletin GEA-1497.

● **"SWITCHETTES"**—Use them in tight places; depend on them for long life. They're available in single- or two-circuit, normally open or normally closed circuits; have momentary or maintaining contacts; are equipped with screw terminals, soldering lugs or quick-connect lugs. They're corrosion-proof, vibration-resistant, and have low r-f noise output. Ratings up to 10 amps at 230 vac. Size: $1\frac{1}{4}$ x $\frac{1}{2}$ x $\frac{1}{2}$. See Bulletin GEA-4888.

● **INDICATING LAMPS**—You can see from any angle whether these lamps are off or on. Color caps—made from a special translucent compound—are clear, green, red, yellow, white, or blue. Available for 24, 48, 125, 250, or 660 volts d-c; 125, 220, 440, or 550 volts a-c. Mount on panels up to 2 inches thick. All units include built-in series resistors, to insure long lamp life and eliminate the need for fuses. Size: about 5 inches long. See Bulletin GEA-3643.

GENERAL ELECTRIC

6674

Digest

TIMELY HIGHLIGHTS ON G-E COMPONENTS



PULSE TRANSFORMERS... MIDGET OR GIANT

A six-inch midget and two-foot giant, both are examples of G.E.'s family of oil-insulated, hermetically sealed pulse transformers. General Electric has built units with peak voltage ratings of from 10 to 100 kv and over, peak power ratings up to 30 megawatts, for pulse durations of from .05 to 20 microseconds and repetition rates up to 10,000 pps. Oil filled units have also been used for lower voltages to minimize internal corona. Typical applications: pulse voltage step-up or step-down, impedance matching, phase reversing, and transmitter plate-current measurement. What is your requirement? Write, giving complete details, to Power Transformer Sales Division, General Electric Co., Pittsfield, Mass.



ACCURATE RF MEASUREMENT

100 MA to 300 AMPS

The new, sturdy, and easy-to-read G-E panel instruments are available for measuring r-f from 100 ma or less to 300 amps. R-f meters are usually supplied with internal thermocouples, but for applications where remote location of thermocouple is required, or for measuring extremely high currents (over 20 amps), external units are available. For complete data on these or other G-E panel instruments for a-c, d-c, or a-f, see Bulletin GEC-368.



New! FOR COMPACT DESIGNS MINIATURE RECTIFIER CELLS

Here's a new series of rectifier cells that can help you fit your circuit into a smaller space. These new "K-type" cells may be used to replace tubes for dual-diode, voltage-doubler, and blocking applications.

The cells are built with a new G-E evaporation process which makes for long life and stable output. Forward resistance and back leakage are low. Standard cells are moisture resistant, special units are hermetically sealed. All have a $\frac{7}{16}$-inch diameter and can be mounted as easily as an ordinary resistor. Circuits: half-wave, center tap, or bridge. Ratings: as high as 40 RMS volts input, 56.5 maximum inverse peak volts at 10 d-c ma. Data in Bulletin GEC-655.

General Electric Company, Section C667-6
Apparatus Department, Schenectady 5, N. Y.
Please send me the following bulletins:

Indicate for reference only ✓	☐	GEA-1497	Terminal boards
	☐	GEA-3643	Indicating lamps
	☐	GEA-4888	Switchettes
for planning an immediate project X	☐	GEC-368	Panel instruments
	☐	GEC-655	Rectifier cells

Name .....
Company .....
Address .....
City ..... State .....

Now FOR INDUSTRIAL INSTRUMENTATION

ARMA MECHANICAL DIFFERENTIALS

To combine algebraically two mechanical quantities measured by angular displacement



Standard Differential furnished with overall length of approximately 6 in.

Arma Assem. No.	Dia. of Shaft A—in.	Dia. of Work Cir. B—in.	Width C —in.	Details of Shaft Ends D & E	Pitch Dia. of Gears 1 & 2—in.	* BACKLASH—MINUTES OF ARC		
						"F" Mesh	"C" Mesh	"P" Mesh
72044	3/16	2-3/16	1-1/8	TO CUSTOMER'S SPECIFICATIONS	1.187	24 ± 12	12 ± 6	6 ± 3
72045	1/4	2-1/16	1-23/32		1.062	26 ± 13	13 ± 6.5	6.5 ± 3
72046	5/16	2-7/16	1-7/8		1.312	22 ± 11	11 ± 5.5	5.5 ± 3
72047	3/8	2-13/16	2-11/32		1.500	18 ± 9	9 ± 4.5	4.5 ± 2
72051	1/2	3-1/16	2-5/8		1.687	17 ± 8.5	8.5 ± 4.3	4.3 ± 2
72052	5/8	3-1/2	2-7/8		2.000	14 ± 7	7 ± 3.5	3.5 ± 2

* Backlash (Min. of Arc.) measured on Gear #1 with Shaft "A" and Gear #2 locked.

DEFINITIONS OF ARMA DIFFERENTIAL MESHES

"F" Mesh = 0.002" ± 0.001 Backlash at Pitch Radius.

"C" Mesh = 0.001" ± 0.0005 Backlash at Pitch Radius.

"P" Mesh = 0.0005" ± 0.00025 Backlash at Pitch Radius.

New Differential folder just printed gives complete details.

ASK FOR A COPY

Construction Notes.

Dual ball bearings used throughout.

Shaft and spider are welded construction of stainless steel.

Spider gears and mating gears are of unlike materials—naval bronze and stainless steel.

***Output gear hubs* permit wide range of end gear sizes.**

ARMA CORPORATION

254 36th STREET, BROOKLYN 32, N. Y.

SUBSIDIARY OF AMERICAN BOSCH CORPORATION

ARMA PRODUCTS RELEASED FOR PRIVATE INDUSTRY

ARMA ELECTRICAL RESOLVERS* ARMA SYNCHROS ARMA INDUCTION MOTORS ARMA INDUCTION GENERATORS ARMA MECHANICAL DIFFERENTIALS ARMA ALTERNATING VOLTAGE COMPARATOR COMPUTING MECHANISMS INDUSTRIAL CONTROLS STABILIZATION DEVICES NAVIGATIONAL EQUIPMENT LIMITRON AUTOMATIC INSPECTION SYSTEM

* Licensed for use under Arma patents Nos. 2,465,634 and 2,467,446. License information available.

QUALITY ARMA INSTRUMENT PRECISION

Erie Disc and Plate Ceramicons®

for By-passing and Coupling Applications



High capacity in extremely compact size is the distinguishing feature of Erie Disc and Plate Ceramicons. For example, .01 mfd is now available in 19/32" diameter. Illustrations are exact size, and their shape as well as their compactness make them amazingly easy to install in small spaces. They simplify soldering and wiring operations and speed up the assembly line.

Erie Disc and Plate Ceramicons consist of a flat ceramic dielectric with silver plates fired onto the dielectric. Lead wires of 24 gauge tinned copper wire are firmly soldered to the silver electrodes and the unit is given a protective coating of phenolic.

Such simplicity of construction results in low series inductance and unusual efficiency in high frequency by-passing.

For complete information and samples to meet your particular needs, write us today.

STANDARD AVAILABLE CAPACITIES

ERIE TYPE	SIZE	CAPACITY RANGES	MARKING
831	9/32" Max. Dia.	.0008 MFD	Stamp ER 800
801	7/16" Max. Dia.	.001 MFD	Stamp ER .001
		.0015	Stamp ER .0015
		.002	Stamp ER .002
811	19/32" Max. Dia.	.005	Stamp ER .005
		.01	Stamp ER .01
812	19/32" Max. Dia.	Dual .001	Stamp ER 2—.001
		Dual .0015	Stamp ER 2—.0015
		Dual .002	Stamp ER 2—.002
822	5/8" Max. Dia.	Dual .003	Stamp ER 2—.003
		Dual .004	Stamp ER 2—.004
883	5/16" x 3/4" Max.	Triple .0015	Stamp ER 3—.0015

SPECIFICATIONS

Voltage: Units are rated at 500 VDC, except Type 811 .01 MFD which is rated at 400 VDC based on life test of 1,000 hours at 800 VDC and at 85° C. Dielectric strength test; 1,500 VDC.

Power Factor: 2.5% max. at 1 K.C. at not more than 5 volts RMS.

Insulation Resistance: 7,500 meg. Ω min.

Capacity: Capacity measurements are made at room temperature (25° C) at 1 K.C. and at not more than 5 Volts RMS. Standard tolerance is +100%, −0%. (Blue)

Temperature Characteristics:

The capacity of all units except Type 811—.002 MFD and below shall not decrease more than 50%, nor increase more than 25% from its value at room temperature (25° C), as the temperature is varied from +10° C to +75° C. (Characteristic Gold)

Type 811 units .002 MFD and below shall not decrease more than 20%, nor increase more than 10% from capacitance value at room temperature (25° C), as the temperature is varied from −40° C to +85° C. (Characteristic Silver)

Electronics Division

ERIE RESISTOR CORP., ERIE, PA.

LONDON, ENGLAND . . . TORONTO, CANADA

STANDARD RI-FI* METERS

14kc to 1000mc!

DEVELOPED BY **STODDART** FOR THE ARMED FORCES.

AVAILABLE COMMERCIALLY.

VHF!
15 MC to 400 MC
NMA - 5

Commercial equivalent of TS-587/U.
Sensitivity as two-terminal voltmeter, (95 ohms balanced) 2 microvolts 15-125 MC; 5 microvolts 88-400 MC. Field intensity measurements using calibrated dipole. Frequency range includes FM and TV Bands.

VLF!
14 KC to 250 KC
NM - 10A



Commercial equivalent of AN/URM-6.
A new achievement in sensitivity! Field intensity measurements, 1 microvolt-per-meter using rod; 10 microvolts-per-meter using shielded directive loop. As two-terminal voltmeter, 1 microvolt.

HF!
150 KC to 25 MC
NM - 20A

Commercial equivalent of AN/PRM-1.
Self-contained batteries. A.C. supply optional. Sensitivity as two-terminal voltmeter, 1 microvolt. Field intensity with ½ meter rod antenna, 2 microvolts-per-meter; rotatable loop supplied. Includes standard broadcast band, radio range, WWV, and communications frequencies.

UHF!
375 MC to 1000 MC
NM - 50A



Commercial equivalent of AN/URM-17.
Sensitivity as two-terminal voltmeter, (50-ohm coaxial input) 10 microvolts. Field intensity measurements using calibrated dipole. Frequency range includes Citizens Band and UHF color TV Band.

Since 1944 **Stoddart RI-FI*** instruments have established the standard for superior quality and unexcelled performance. These instruments fully comply with test equipment requirements of such radio interference specifications as JAN-I-225, ASA C63.2, 16E4/SHIPS), AN-I-24a, AN-I-42, AN-I-27a, AN-I-40 and others. Many of these specifications were written or revised to the standards of performance demonstrated in **Stoddart** equipment.

The **rugged** and **reliable** instruments illustrated above serve equally well in field or laboratory. Individually calibrated for consistent results using internal standard of reference. Meter scales marked in microvolts and DB above one microvolt. Function selector enables measurement of sinusoidal or complex waveforms, giving average, peak or quasi-peak values. Accessories provide means for measuring either conducted or radiated r.f. voltages. Graphic recorder available.

***Radio Interference and Field Intensity.**

Precision Attenuation for UHF!

Less than 1.2 VSWR to 3000 MC.
Turret Attenuator:
0, 10, 20, 30, 40, 50 DB.
Accuracy ± .5 DB.
Patents applied for.



STODDART AIRCRAFT RADIO CO.

6644 SANTA MONICA BLVD., HOLLYWOOD 38, CALIF.
Hillside 9294

How Karp Makes Custom-Built Metal Cabinets and Boxes at Prices that Compete with those of Stock Items

The advantages and true economies of Karp custom-built cabinets, boxes, or housings over stock items are these:

- Your own exclusive design distinguishes and "styles" your product . . . gives it more market value.
- Flexibility of construction details speeds and simplifies your final assembly —saving you time and money.
- Our vast stock of dies can save you special die costs.
- Our 70,000 square feet of modern plant, with hundreds of craftsmen, means ample capacity for many types of work—simple or elaborate—at one time.
- Plant is fully equipped with every mechanical facility that aids economical production.
- Fihishing is done in dustproof paint shop, with latest water-washed spray booths and gas-fired ovens mechanically and electronically controlled.
- We make no stock items or products of our own. Our plant, time and effort are 100% for our customers' work.
- Our engineering staff can help solve any possible design and production problems.
- It's results that count—and we give you the results you want.

Write for illustrated data book describing our facilities and showing the wide range of sheet metal fabrication we do.

CABINETS • BOXES • CHASSIS • HOUSINGS • ENCLOSURES

KARP METAL PRODUCTS CO., INC.

215 63rd STREET, BROOKLYN 20, NEW YORK

Custom Craftsmen in Sheet Metal



TV Monitor Console

Desk Panel Cabinet Rack

Induction Heater Housing



Chassis



Marine Radio Housing



Cabinet

OAK MFG. CO. DEMANDS

UNIFORMITY

INSUROK DOES THE JOB!

3 POPULAR ELECTRICAL GRADES OF LAMINATED INSUROK

T-725 An outstanding paper-base laminate that can be hot-punched to intricate shapes. Has excellent electrical and physical properties, is stable under moisture and heat, and only slightly affected by sanding.

T-800 Has unmatched electrical properties, yet punches with ease. It has a sensational ability to retain these properties in high humidity.

T-812 A further development in the electrical sheet field with insulation resistance on the order of T-800 and mechanical properties comparable to T-725.

In manufacturing components for this critical tuning head for RCA Victor television receivers, Oak Manufacturing Co. faced a tough insulation problem. The insulation had to be strong, yet produce clean, intricate, punched parts. It had to possess superior electrical properties—unchanged after sanding to close tolerances. And its electrical characteristics had to remain stable through a wide range of temperature and humidity.

INSUROK electrical sheets provide Oak with a unique combination of all of these desired properties. And even more important, from shipment to shipment, Oak engineers can depend on INSUROK's properties remaining uniform.

In hundreds of similar applications, laminated and molded INSUROK are solving difficult problems for industry. Richardson's years of experience in the engineering application of plastics is available to you without obligation. Write, today.

The RICHARDSON COMPANY

FOUNDED IN 1858

2797 Lake St., Melrose Park, Illinois (Chicago District)

CLEVELAND • DETROIT • INDIANAPOLIS • LOCKLAND, OHIO • MILWAUKEE
NEW BRUNSWICK, N. J. • NEW YORK • PHILADELPHIA • ROCHESTER • ST. LOUIS

MODERN APPLICATION DEMANDS...
Burnell TOROIDS & TOROIDAL COIL FILTERS
We know only too well what is modern today in Electronics can be obsolete tomorrow. We can reward obsolescence by designing our products with an eye toward the future and what future applications may demand of our products.
Burnell & Company has shaped its engineering policy with this viewpoint – by striving to keep well ahead – not just abreast of developments in the fi Q Coil and Filter business.
We search constantly for new design ideas that will permit the reduction of size and weight of filters that "fly"; new circuits and components that will give our customers "more for their money" – and new production methods that will speed output and guarantee the reliability and life of our products.
Even our price structure has been streamlined to conform with the increasing industry-wide demand for economy, with no sacrifice in our high standard of quality.
We say that modern applications demand Burnell & Company's toroids and toroidal filter products because we are modern in every sense of the word: modern in outlook and technique as well as in price.
Exclusive Manufacturers of Communications Network Compon
We particularly invite your inquiries concerning difficult filter applications
Burnell & Company
YONKERS 2, NEW YORK

The Right Switches... at the Right Price...

to modernize your product and to enhance its "saleability"



SS-26 Single-pole, single-throw

NEW!

Two slide switches rated
1 ampere at 125 volts DC
3 amperes
at 125 volts AC

SS-26-1 Single-pole, double-throw

These sturdy little switches are ideal for appliances, toys and electrical equipment requiring 3-ampere switch contact carrying capacity. Both are Underwriters approved. Write for SS-26 Switch Bulletin.

LINE OR SLIDE ACTION

Dozens of Contact Arrangements

Inexpensive types are available for practically any switching requirement and at prices that will please you. Samples to specifications on request to quantity users. Write for Stackpole Switch Bulletin RC7C.

Fixed and Variable Resistors
Iron Cores • Alnico II Permanent Magnets ...

ELECTRONIC COMPONENTS DIVISION,
STACKPOLE CARBON CO. St. Marys, Pa.

...and hundreds of molded iron powder, metal, carbon and graphite products.

STACKPOLE

2nd PRINTING!

NEW HANDBOOK

ON GENERAL ELECTRIC WELDED GERMANIUM DIODES

"IF YOU'RE AN ELECTRONICS ENGINEER, PAL, YOU NEED THIS BOOK!"

HERE'S the book that digests all the facts you should have on Germanium Diodes. Contains valuable pages of up-to-the-minute information on diodes and their applications in today's widening electronics market!

For designers and engineers who want basic facts on the development, characteristics, advantages and circuitry of diodes, this carefully prepared General Electric manual is a valuable tool. Includes specific data on diode problems, characteristics curves, electrical rating charts, circuit diagrams.

Assembled in loose leaf fashion, the book is tabbed by sections for easy reference. The $1.25 price of this leatherette bound handbook includes supplementary sheets on new diode developments which will be sent to you as they are published. Your copy is waiting. Mail the coupon today!

HERE'S WHAT IT TELLS YOU

- Design, manufacture, and specifications of G-E Welded Germanium Diodes
  - General purpose types
  - TV types
  - Quads
  - UHF diodes
- CHARACTERISTICS CURVES
  36 curves on resistance, current, voltage, temperature, and efficiency. Also typical distributions.
- SERVICE NOTES
  - How to install
  - How to check and inspect
  - Precautions
- DIODE APPLICATIONS
  Typical circuit applications and brief descriptions of diode characteristics as used in circuits covering AM & FM receivers, TV receivers, measuring equipment, carrier current, miscellaneous.
- Pertinent articles and public presentations on diode theory and application.

General Electric Company—Section 470
Electronics Park
Syracuse, New York

Please send me ..... copies of the new G-E Germanium Diode Handbook at $1.25 per copy—Postpaid.

☐ Check or M.O. enclosed

NAME.....

ADDRESS.....

CITY.....STATE.....

You can put your confidence in—

GENERAL ELECTRIC



BRADLEYUNIT DIMENSIONS—½ Watt—⅜ in. long x 9/64 in. diam. 1 Watt —9/16 in. long x 7/32 in. diam. 2 Watt—11/16 in. long x 5/16 in. diam.

QUALITY FIXED RESISTORS

for Electronic Circuits

Bradleyunit resistors are small in size . . . but "super" in the performance demanded by electronic engineers. Bradleyunits are rated at 70 C ambient temperature, not 40 C. Thus, they have a much wider safety factor. Furthermore, under continuous full load for 1000 hours, resistance change is less than 5 per cent. And, Bradleyunits require no wax impregnation to pass salt water immersion tests. Another advantage is the differentially tempered leads which prevent sharp bends near the resistor.

Bradleyunits are packed in honeycomb cartons to keep the leads straight and avoid tangling. They are available in ½, 1, and 2 watt ratings in standard R.M.A. values up to 22 megohms.

Allen-Bradley Co.
110 W. Greenfield Ave., Milwaukee 4, Wis.

SOLID MOLDED ADJUSTABLE RESISTORS

Available in single, dual, and triple unit constructions with solid molded resistor elements. Any resistance—rotation curve. Rated at 2 watts.

A-B

ALLEN-BRADLEY

FIXED & ADJUSTABLE RADIO RESISTORS

Sold exclusively to manufacturers of QUALITY radio and electronic equipment

TELEVISION ANTENNA DISK

Fabricated in ONE operation!



USING DURON, we punched this large and difficult part in one operation with a compound die. And it was one of those deliver-it-yesterday jobs. In the staid language of our representative, the customer "commented very favorably because we built this complicated die on short notice and because the piece was held to close dimensional tolerances not common for this type of punching." This type of job emphasizes the kind of services our Fabricating Division can offer on fibrous materials. We are specialists, with a background of experience in manufacturing high strength fibrous materials dating back to 1832. If you want *to cut costs on fibrous parts* and *get the job done*, see Rogers.

CATALOG AVAILABLE

Gives full description of services provided and some pertinent design considerations in using fibrous materials. Write Dept. E

SPECIALTY FIBRE PRODUCTS ELECTRICAL INSULATING MATERIALS AND BOARDS DUROIDS • SHOE PRODUCTS	MOLDING AND LAMINATING PLASTICS Boards • Blanks • Pre-shaped Preforms High Strength Molding Compounds Laminated Phenolics	COMPLETE FABRICATING SERVICES ON FIBROUS MATERIALS AND LAMINATED PHENOLICS

"AMERICAN Screw Company?

. . . please call the NEW NUMBER . . . at WILLIMANTIC CONNECTICUT!"

4-WINGED DRIVER CAN'T SLIP OUT OF PHILLIPS TAPERED RECESS

. . . and get fastest fastener-service from this modern, high-production plant

Save time and "wrong numbers" by changing your records *now* to the address of American's new main plant and home office.

This high-production operation . . . one of the most modern in the screw industry . . . is equipped and staffed to raise American quality and service to new high levels, both in American Phillips Recessed-Head Fasteners, and also slotted products. Whatever it takes to make better screws, American has it at Willimantic!

Photos at the right give you a good picture of American's present position on deliveries. So for either Phillips or slotted, mark your order *American* . . . and shoot it to Willimantic.

AMERICAN SCREW COMPANY

Plants at Willimantic, Conn., and Norristown, Pa.

Warehouses at:

589 E. Illinois St. Chicago 11

502 Stephenson Bldg. Detroit 2



Wire Storage

Cut Threading Dept.

Shipping Dept.

Phillips



Slotted

AMERICAN SCREWS

they may look alike, *but:* there is only one C-D

24 HOUR DELIVERY!

"SILVER MIKE"* MICA CAPACITORS

Now you can get the same dependability that has made C-D's famous in engineering circles the world over, on a twenty-four-hour delivery basis. The demand for "Silver Mike"* Micas through the years has been so great that every expansion program has proved insufficient. But with the completion of our last expansion program we are making available the entire Providence plant exclusively to the production of the famous, reliable C-D line of "Silver Mike"* Micas. Of course, in addition to the new, improved delivery standards, you still get these other features that have made C-D's "Silver Mike"* Micas so popular.

Extra heavy silver coating thoroughly bonded to mica – results in a uniform and low capacity-temperature coefficient (+.002% per degree C.); excellent retrace characteristics; practically no capacity drift with time.

Molded in low-loss red compound – results in an exceptionally high Q (3,000 to 5,000); fixed electrical characteristics.

Wax impregnated – results in a humidity-proof capacitor.

"Silver Mike"* Mica Capacitors are available in 300 and 500 V.D.C., and in capacities from .000001 to .005 mfd. at standard tolerance of ±5%. "Silver Mike"* Micas can also be supplied, on special order, to tolerances of ±3%, ±2% and ±1%.

Your inquiries are invited. CORNELL-DUBILIER ELECTRIC CORPORATION, Dept. K-7-0, South Plainfield, New Jersey. Other plants in New Bedford, Brookline and Worcester, Mass., Providence, R. I.; Indianapolis Ind., and subsidiary, The Radiart Corp., Cleveland, Ohio.

FOR A **CONSTANT LC** PRODUCT . . . FOR **DEPENDABLE** RESULTS . . . FOR **UNRIVALED** PERFORMANCE . . . **SPECIFY C-D!**

Best by Field Test!

CONSISTENTLY DEPENDABLE

CORNELL-DUBILIER

CAPACITORS · VIBRATORS · ANTENNAS · CONVERTERS



Design-Unlimited

WITH CORNING METALLIZED GLASS INDUCTANCES

About the only limiting factor in Corning Metallized Glass Inductances is that they cannot be designed to operate much below 30 Megacycles. Aside from that, just give us your specifications and Corning engineers will quickly design and send you samples. Once approved, they can be easily duplicated to surprisingly close tolerances on a production basis.

When special tuning characteristics or convenient terminating areas in inductances with fine turns are desired, variable pitch coils are easily supplied. Double pitch windings are available for r.f. transformer or inductive coupling purposes. The conductor width may even be modified to give you distributed parameters. Gaps between turns can vary from as little as .020" to as much as one-eighth of an inch.

Fixed tuned, permeability tuned, or permeability tuned inductance-trimmer combinations can be supplied with appropriate powdered iron cores and convenient mounting bushings. Assembly can be made by conventional methods.

Corning Inductances offer many special advantages. High temperature stability due to low expansion coefficient of the glass coil form, and the low temperature coefficient of the dielectric, results in negligible drift characteristics. Minimum allowable Q is 150. The smooth glass form assures noiseless tuning. Rugged and durable, they can stand repeated handling. Assembly costs are lower. Whatever your inductance requirements, Corning engineers can help you. Write for further information today.

CORNING GLASS WORKS
ELECTRONIC SALES DEPARTMENT

CORNING, N. Y.
Corning means research in Glass

METALLIZED GLASSWARE: INDUCTANCES · CAPACITORS · BUSHINGS · ALSO A COMPLETE LINE OF TELEVISION TUBE BLANKS

The new Eimac 4X150G will . .



DELIVER 20 KW AS A PULSED AMPLIFIER OR OSCILLATOR TO OVER 1200 Mc.

GIVE A POWER-GAIN OF 10 AT 1200 Mc.

PROVIDE 100 WATTS CW POWER AT 750 Mc. WITH A POWER GAIN OF 8.



These illustrations show an example of the simplicity made possible by the 4X150G. The cavity is for a broad-band 1200 Mc. power amplifier for a pulse application. The block diagram indicates the tube line-up of the IPA, tripler, and final PA stages. More detailed data on the 4X150G are available. Please make requests on your company letterhead.

The 4X150G has been specifically designed to make feasible relatively high power at UHF. It is excellent as an amplifier, oscillator or frequency multiplier in either pulse or cw service. Good efficiency is obtained over a wide range of plate voltages to over 1500 Mc.

Power-gains of 10 are easily obtainable at 1200 Mc. when pulsed, and peak pulsed outputs of 20 kw per tube are possible without extending the tube beyond its maximum ratings.

At lower frequencies, for instance around 750 Mc., the 4X150G operating as a cw amplifier will provide 100 watts output with but 12½ watts of grid-drive . . . a power-gain of 8, with complete stability.

These examples are only indicative of the tube's potentialities. More comprehensive data are contained in a new data sheet, available upon request.

EITEL-McCULLOUGH, INC.
San Bruno, California

Export Agents: Frazer & Hansen,
301 Clay St., San Francisco, California

Follow the Leaders to Eimac TUBES The Power for R-F

The 4X150G is another Eimac-developed contribution to electronic progress.

258

These Three

ALLIED POWER RELAYS

FROM SINGLE-POLE TO FOUR-POLE

TYPIFY ALLIED VERSATILITY





3-POLE & 4-POLE "PO" TYPE RELAY

This medium power relay is supplied with contact arrangements up to 4-pole double-throw. Standard silver contacts rated at 15 amperes for 24 volts DC or 110 volts AC non-inductive. Coil rating 2.5 watts up to 112 volts DC and 10.5 volt-amperes up to 230 volts AC. Dimensions: 3-pole 2-1/4" x 1-7/8" x 1-5/8". 4-pole 2-1/4" x 1-7/8" x 2-5/16".



SINGLE-POLE "AS" TYPE RELAY

This small, light-weight power relay is supplied with single or double-throw contacts. Standard silver contacts rated at 5 amperes for 24 volts DC or 110 volts AC non-inductive. Coil rating 1 watt up to 95 volts DC and 3.5 volt-amperes up to 230 volts AC. Dimensions: 1-3/8" x 1-5/8" x 15/16".

DOUBLE-POLE "BO" TYPE RELAY

This all-purpose power relay is supplied with single or double-throw contacts. Molded insulation throughout. Standard silver contacts rated at 15 amperes for 24 volts DC or 110 volts AC non-inductive. Coil rating of 2.5 watts up to 112 volts DC and 4.5 volt-amperes up to 250 volts AC. Dimensions: 1-7/8" x 1-13/32" x 1-5/8".

Like all Allied Relays, types "AS," "BO" and "PO" may be had hermetically sealed, with choice of standard octal plug-in base or solder-type terminals.

For complete information on these and other Allied Relays, write for latest Bulletin.

NEW RELAY GUIDE

This new folder shows 24 small, compact Allied Relays with a carefully detailed table of characteristics and specifications. Write for YOUR free copy today.

ALLIED CONTROL COMPANY, INC.

2 EAST END AVENUE, NEW YORK 21, NEW YORK

Ideal tube for electronic equipment that SEALS AND STITCHES PLASTICS

"HERE'S THE ANSWER TO YOUR NEED FOR A COMPACT, ECONOMICAL V-H-F TUBE TO POWER YOUR NEW HEATER. PROVED WIDELY IN INDUSTRY!"

PLASTIC film and sheet are "taking over" where protection from moisture or chemicals is vital. Shop-windows feature plastic rainwear. Acid-proof work garments shield from noxious liquids. Packages are plastic-sealed against dampness. Moreover, plastic wallets, handbags, novelties of all types are pouring off production lines.

Millions of yards of plastic material are being sealed and stitched, with electronic heating doing the whole job. Certainly, here's a steady, growing market for h-f-heating equipment . . . and just as surely, you want your share of this important business.

Build your circuit around General Electric's great GL-592 power tube! Its special suitability for the work, its reliability and "toughness", are industry-demonstrated. The tube carries substantial plate ratings. For still more power, a pair or two pairs may be used without undue increase in cost of the equipment. Frequency range is high. The tube is exceptionally efficient, with conversion efficiencies above 70 percent the rule in well-designed circuits. Cooling offers no problem, merely calling for an 8-inch household-type fan or a small and inexpensive pressure blower.

Ample tube stocks are available, along with sockets, grid connectors, and finned anode connectors. Specify and install—there'll be no intervening delay! You owe it to yourself as designer or builder of h-f-heating equipment to study the economical GL-592's application in *your* circuit. G-E tube engineers will be glad to assist. Phone your nearby G-E electronics office, or wire or write *Electronics Department, General Electric Company, Schenectady 5, New York.*

GL-592 POWER TRIODE

Study these SUPERIOR G-E design features!

- A one-piece graphite anode, with no welds, accents the tube's mechanical strength. Zirconium coating provides excellent heat-radiating properties and helps maintain high vacuum.
- Large-diameter anode lead is sturdy, also makes for low inductance.
- The GL-592 has a combined seal-and-anode-terminal of unit construction. No cemented cap or screw connections are used. Good for the life of the tube!
- Filament leads are solidly braced for greater internal strength.
- Large-diameter G-E cup seals of matching metal and glass feature all terminals.
- External leads and seals are silver-plated for better conductivity.

RATINGS

Class C Power Amplifier and Oscillator

Filament voltage		10 v
Filament current		5 amp
Max ratings:	CCS	ICAS
d-c plate voltage	3,500 v	3,500 v
d-c grid voltage	—500 v	—300 v
d-c plate current	250 ma	350 ma
d-c grid current	50 ma	100 ma
plate input	670 w	1,000 w
plate dissipation	200 w	300 w
Type of cooling		forced-air
Frequency at max ratings		150 mc

GENERAL ELECTRIC

180-J5B

Announcing the **H-14**
SIGNAL GENERATOR
108-118 megacycles
Newest in ARC's Line of Signal Generators



Checks on...

- 24 Omni courses
- Left-center-right on Phase-localizer
- Left-center-right on Amplitude-localizer
- Omni course sensitivity
- To-From and Flag-alarm operation
- All necessary quantitative bench tests

Use the H-14 for Testing Omni Receiving Units in Aircraft . . . . . or on the Bench.

The Type H-14 Signal Generator, 108-118 megacycles provides a standard signal source for the complete testing of VHF airborne omnirange and localizer receivers in aircraft or on the bench. It provides for testing 24 omni courses, plus left-center-right checks on both amplitude and phase localizers. Aircraft may be checked out quickly and accurately just before take-off. RF output for ramp checks, 1 volt into 52 ohm line and for bench checks, 0-10,000 microvolts. Provision for external voice or other modulation. AF output available for bench maintenance and trouble shooting.

PRICE: $885.00 net, f.o.b. Boonton, N. J.

MICROWAVE TEST SET . . . TYPE H-10
23,500-24,500 MEGACYCLES



Provides source of cw or pulse frequency-modulated RF, power level —37 to —90 dbm. RF power meter measures levels from +7 to +30 dbm. Frequency meter for measuring output or input RF accurate to better than 20 mc. Primary purpose of the H-10 is to measure receiver sensitivity, bandwidth, frequency, recovery time, and overload characteristics, plus transmitter power and frequency. Recommended as a standard source of RF for research or production testing. Equal to military TS-221/AP.

PRICE: $1692.00 net, f.o.b. Boonton, N. J.

UHF SIGNAL GENERATOR . . . TYPE H-12
900-2100 MEGACYCLES



Provides source of cw or pulse amplitude-modulated RF, power level 0 to —120 dbm. Internal pulse circuits with controls for width, delay, and rate, and provision for external pulsing. Single dial tuning, frequency calibration accurate to better than 1%. Built to Navy specifications for research and production testing. Equal to military TS-419/U.

PRICE: $1950.00 net, f.o.b. Boonton, N. J.

ARC COMMUNICATION AND NAVIGATION EQUIPMENT

Aircraft Radio Corporation also manufactures LF and VHF airborne communication and navigation equipments—all CAA-Type-Certificated for scheduled aircarrier use or for those whose type of flying requires a high degree of reliability and performance. Equipment consists of light, small units which can be combined to provide the required operation, whether it be the 1-Receiver/1-Transmitter (15-pound) installation in a 2-place helicopter, or a 3-Receiver/2-Transmitter/VHF Omni installation (70 pounds) in larger 2-engine aircraft.

Aircraft Radio Corporation
Boonton, N. J.
Dependable Electronic Equipment Since 1928

WRITE TODAY for descriptive bulletins on any of these instruments



—U·S·S Stainless Steel is in the television picture

PICTURE TUBE CONES OF U·S·S 17-TV REDUCE WEIGHT, HELP CUT COSTS

PUBLIC demand for bigger and better television at low price has brought manufacturers face to face with new problems in reducing weight and holding down set cost. And, like so many other industries, television has turned to Stainless Steel to solve this problem.

A new grade of U·S·S Stainless Steel, known as U·S·S 17-TV, has been developed especially for this television application. Having an appropriate coefficient of expansion, it permits fusing of the faceplate and neck to the metal cone with a strong air-tight seal.

By using U·S·S 17-TV instead of glass for the conical section of the picture tube, you can cut the weight of this key part over one-third. The result is important savings in handling, shipping and packing costs. The tube can be shipped installed in the receiver with little danger of damage in transit.

In addition to its light weight, other inherent advantages of Stainless make important contributions here. Its strength enables the tube to withstand extreme pressures and reduces breakage hazards. Because glass area is held to a minimum, and because of the protection provided by the Stainless Steel cone, hazards of implosion are minimized—in tube manufacture, in installation and in service. The U·S·S 17-TV cone permits the use of a flawless, smooth glass face, thus resulting in cleaner, and sharper pictures.

Whether you manufacture or use cathode ray tubes, investigate the possibilities of U·S·S 17-TV Stainless Steel, developed especially for the television industry. Like all other grades of U·S·S Stainless, it is made to give you the finest possible performance.

AMERICAN STEEL & WIRE COMPANY, CLEVELAND · CARNEGIE-ILLINOIS STEEL CORPORATION, PITTSBURGH
COLUMBIA STEEL COMPANY, SAN FRANCISCO · NATIONAL TUBE COMPANY, PITTSBURGH · TENNESSEE COAL, IRON & RAILROAD COMPANY, BIRMINGHAM
UNITED STATES STEEL SUPPLY COMPANY, WAREHOUSE DISTRIBUTORS, COAST-TO-COAST · UNITED STATES STEEL EXPORT COMPANY, NEW YORK

U·S·S STAINLESS STEEL

SHEETS · STRIP · PLATES · BARS · BILLETS · PIPE · TUBES · WIRE · SPECIAL SECTIONS

0-1324

UNITED STATES STEEL

HAMILTON STANDARD and FAIRCHILD rely on

BENDIX-SCINTILLA
ELECTRICAL CONNECTORS

Unfailing dependability is one of the requirements set by Hamilton Standard and Fairchild in their selection of equipment. The installation of Bendix-Scintilla electrical connectors in vital circuits of Hamilton Standard propellers is, therefore, a tribute to a fine product.

Wherever circuits must be arranged to connect and disconnect with ease and certainty, Bendix-Scintilla is the choice. Remember that whenever there is no compromise with quality, it pays to specify Bendix-Scintilla electrical connectors—the finest money can buy!

CHECK THESE ADVANTAGES

- Moisture-proof
- Radio Quiet
- Single-piece Inserts
- Vibration-proof
- Lightweight
- High Insulation Resistance
- Easy Assembly and Disassembly
- Fewer Parts than any other Connector
- No additional solder required
- Approved A-N source

Write our Sales Department for detailed information.

BENDIX SCINTILLA

SCINTILLA MAGNETO DIVISION of SIDNEY, N. Y.

Bendix AVIATION CORPORATION

Export Sales: Bendix International Division, 72 Fifth Avenue, New York 11, N. Y.

Buried Treasure

in Your Product?

No. 1239 Predetermining Counter signals operator or actuates mechanism to stop machine at end of pre-set run.

More than likely... if you can dig up New Ways to make it do more for your customers ...by COUNTING

Dig deeply into this million-dollar question: "How could *my* product increase its usefulness and sales . . . *by counting?*" And you may well uncover a new and distinctive merchandising appeal that will set your product apart from competition . . . as so many manufacturers have done.

It's as simple as this: If your product is mechanically or electrically operated, then it's definitely worth a search to see if there's hidden sales-treasure buried there. This can be quickly determined by some fast spade-work done by a Veeder-Root engineer, paired off with your design engineer. And the digging can get under way . . . *any time you say.*

Write for 8-page "Counter Book" which shows all types of V-R electrical, mechanical, and manual counters . . . standard and special.

VEEDER-ROOT INC., HARTFORD 2, CONN.

In Canada: Veeder-Root of Canada, Ltd., 955 St. James Street, Montreal 3.
In Great Britain: Veeder-Root Ltd., Kilspindie Road, Dundee, Scotland.

Veeder-Root COUNTERS

MEANING OF "VACUUMED" SELENIUM IN BRADLEY RECTIFIERS FOR HIGH POWER USE



Selenium rectifier performance — aging, stability, and rating-per-space-factor — is based to a large extent upon the quality of selenium used. The purer the selenium, the better the rectifier performs.

Therein lies the importance of the Bradley vacuum process to every user of rectifiers. Through this exclusive process, we remove impurities in the raw selenium and prevent contamination during manufacture. Only Bradley rectifiers have the advantage of this unique type of quality control.

Besides offering maximum rating per space factor and consistent uniformity of rating, Bradley power rectifiers provide an unusual margin of safety against over-loading. One manufacturer reported that he was able to eliminate costly over-voltage protective devices upon installing Bradley power rectifiers.

Bradley rectifiers are available for every power conversion purpose. Our engineers are always available for consultation. Investigate Bradley vacuum-processed rectifiers for your next application.

SELENIUM RECTIFIERS • COPPER OXIDE RECTIFIERS • PHOTOCELLS



Write for your copy of "The Bradley Line," booklet showing many additional rectifier and photocell models.

BRADLEY LABORATORIES, INC.

82 MEADOW STREET, NEW HAVEN 10, CONNECTICUT

A NEW TV SPEAKER BY

ROLA

MAGNETICALLY ENCLOSED Motor Structure*

. . . allows placement of the speaker in close proximity to the picture tube with minimum distortion.



Patents Pending

Available in sizes from 5" to 12". Send for literature giving complete technical and mechanical information.

*An especially designed Pot or Shell (not a separate enclosure) which magnetically and physically encloses the entire magnet, thus reducing to an absolute minimum the *external magnetic field* which is so prevalent and bothersome in the ordinary type of construction.

THE ROLA COMPANY, INC.

DIVISION OF THE MUTER COMPANY • 2530 SUPERIOR AVENUE • CLEVELAND 14, OHIO

EXPORT: AD. AURIEMA, INC., 89 BROAD STREET, NEW YORK 4, N. Y., U.S.A.

plus values

in the cords on your products

make a difference

a Belden Cord Means

+ **SAFETY and APPEARANCE**
+ **QUICK ASSEMBLY**
+ **FEWER REJECTIONS**
+ **LONG LIFE IN SERVICE**

Belden Engineered Cords give you real Plus Values because they are engineered to your product, complete with molded plugs or connectors. They are built far above minimum standards, to give your product a chance to operate without cord failure and to maintain your customer's good will.

All Belden Cords are factory tested to eliminate cord grief —extra assembly operations—rejections—extra cost. Investigate Belden Cords, today. Write

Belden Manufacturing Company
4625 W. Van Buren Street
Chicago 44, Illinois

CORDITIS-FREE CORDS BY

Belden

WIREMAKER FOR INDUSTRY

Announcing

RCA WV-97A

Senior VoltOhmyst*

reading peak-to-peak voltages

ONLY $62.50 Suggested User Price

Includes direct probe and cable, dc probe, ohms lead, and ground lead



TEN WAYS BETTER!

1. Reads peak-to-peak voltages directly
2. Has greater over-all accuracy
3. Reads down to 0.1 volt (1.5 volts full scale)
4. Reads up to 1500 dc volts full scale
5. Measures resistance from 0.1 ohm to 1 billion ohms
6. Has 7 *non-skip* ranges, for both ohms and volts
7. All scales increase in 3-to-1 ratio (approx.)
8. Has wider flat-frequency response
9. Better stability with line voltage fluctuations
10. Provides greater convenience due to small compact size and new slip-on type probes

The WV-97A measures peak-to-peak voltages directly. Hence, it quickly provides information essential for servicing TV receivers with their pulse-type waveforms.



The WV-97A has a range of usefulness extending beyond that of any other instrument in the field. Its quality, dependability, and accuracy make it a true laboratory instrument; it is exactly what is needed for television in the design laboratory, factory, and service shop.

The new Senior VoltOhmyst measures dc voltages in high-impedance circuits, even with ac present. It reads the rms values of sine waves and the peak-to-peak values of complex waves or recurrent pulses, even in the presence of dc. Its electronic ohmmeter has a range of ten billion to one.

Like all RCA VoltOhmysts, it features high input resistance, electronic protection from meter burn-out, zero-center scale for discriminator alignment, molded-plastic meter case, a 1-megohm isolating resistor in the dc probe, and sturdy metal case for good rf shielding.

An outstanding feature is its usefulness as a television signal tracer . . . made possible by its high input resistance, wide frequency range, and direct reading of peak-to-peak voltages.

For complete information on the new RCA WV-97A Senior VoltOhmyst, see your RCA Test Equipment Distributor, or write RCA, Commercial Engineering, Section C42Y, Harrison, New Jersey.

*Reg. U. S. Pat. Off.

SPECIFICATIONS

DC Voltmeter:
Seven Continuous Ranges . . . . . 0 to 1.5, 5, 15, 50, 150, 500, 1500 volts
Input Resistance (including 1 megohm in dc probe):
All ranges . . . . . 11 megohms
Sensitivity for the 1.5 volt range . . . . . 7.3 megohms per volt
Overall Accuracy . . . . . ±3% of full scale
AC Voltmeter:
Fourteen Continuous Ranges:
Peak-to-peak values . . . . . 0 to 4, 14, 42, 140, 420, 1400, 3400 volts
RMS values . . . . . 0 to 1.5, 5, 15, 50, 150, 500, 1200 volts
Input Resistance and Capacitance with direct cable:
1.5, 5, 15, 50, 150-volt ranges . . . . . 0.83 megohm shunted by 85 μμf
500-volt range . . . . . 1.3 megohms shunted by 85 μμf
1200-volt range . . . . . 1.5 megohms shunted by 85 μμf
Frequency Response:
With WG-218 Direct Probe and Cable . . . . . within ±5% from 30 cps to 3 Mc
Overall Accuracy . . . . . ±5% of full scale
Ohmmeter:
Seven Continuous Ranges . . . . . 0.1 ohm to 1000 megohms
Center Scale Values . . . . . 10, 100, 1000, 10,000 ohms; 0.1, 1, 10 megohms
Dimensions: 7¼" high; 5¼" wide; 3¾" deep
Available Accessories:
WG-264 Crystal Probe . . . . . Extends range to 175 Mc (price to be announced)
WG-289 High-Voltage Probe and Resistor WG-206 to extend range to 50,000 volts. $8.95, suggested user price.

Available from your RCA Test Equipment Distributor

RADIO CORPORATION of AMERICA

TEST EQUIPMENT **HARRISON, N. J.**



CARBOLOY COMPANY announces Special Metals Division to produce G-E ALNICO

All of Carboloy Company's experience, technical "know-how", and applicable facilities are being made available for mass production of Alnico permanent magnets. The pioneer in the development of cemented carbides, Carboloy Company, welcomes this addition to its line of special metals.

It is anticipated that the streamlining and conversion of necessary facilities will be completed at an early date.

LOOK to CARBOLOY
for the finest in special metals

Trim Assembly Time with the Tube with the Tab



● Superior's pioneering in tubing technology is constantly at work to bring electronic manufacturers new developments—to help them produce better equipment, faster, at lower costs. Newest of these improvements is the integral tabbed round Lockseam* cathode. It is designed to eliminate a welding operation, cut assembly time, and provide superior performance.

These integral tabbed round Lockseam* cathodes may be valuable to you . . . but whether they are or not one thing is sure. If you use Seamless or Lockseam* cathodes in your product a Superior tube is available to do a Superior job. Our research and engineering facilities are ready at all times to help solve your tubing problems.

For more information about Superior Tubing and its possible place in your operation write to Superior Tube Co., 2500 Germantown Ave., Norristown, Pa.



Electronic Engineering — Life test rack and emission test set. Checking Superior assembled standard diodes under simulated customer conditions to determine if material meets minimum requirements.



To guard against contamination by processing lubricants, Superior tubing is thoroughly degreased before each annealing operation.

Part of inspection procedure on Lockseam Nickel Cathodes as they come off the production machine. Each cathode must undergo many rigid tests before being approved.

Which Is The Better For Your Product...

SEAMLESS...? The finest tubes that can be made. Standard production is .010" to .121" O.D. inclusive, with wall thicknesses of .0015" to .005". Cathodes with larger diameters and heavier walls will be produced to customer specification.

Or LOCKSEAM*...? Produced directly from thin nickel alloy strip stock, .040" to .100" O.D. in standard length range of 11.5 mm to 42 mm. Round, rectangular or oval, cut to specified lengths, beaded or plain.

Superior

THE BIG NAME IN SMALL TUBING

All analyses .010" to ¼" O.D.
Certain analyses (.035" max. wall) Up to 1⅛" O.D.

Mfd. under U. S. Pats.—SUPERIOR TUBE COMPANY • Electronic Products for export through Driver-Harris Company, Harrison, New Jersey.

PICK A NUMBER

ANY FREQUENCY FROM 1 TO 1,000



Pictured here is a tuning-fork frequency standard with accuracy guaranteed to one part per million per degree Centigrade. The fork is temperature-compensated and hermetically sealed against variations of barometric pressure. This standard, when combined with basic equipment, facilitates accurate speed and time control by mechanical, electrical, acoustical or optical means.

The unit is available separately or in conjunction with complete timing instruments. Our engineers are ready to cooperate on any problem.

MOTORS · FACSIMILE · AIRCRAFT · LABORATORIES

American Time Products, Inc.

580 Fifth Avenue

[illegible] N. Y.

[illegible] OF THE WESTERN [illegible] MUSIC COMPANY



alliance
TENNA · ROTOR

INSULATED WITH NATVAR 400

AIMS THE ANTENNA IN ALL KINDS OF WEATHER

The ALLIANCE TENNA-ROTOR rotates the antenna at 3 rpm either clockwise or counter-clockwise through 365°, with a positive mechanical stop at end of travel. In the Model DIR (illustrated), sensor in rotator unit operates meter in control box to show direction. Reversible motor in rotator unit operates on 24 volts supplied by transformer in control box through a 3-position switch. Motor leads are insulated and protected by Natvar 400 extruded vinyl tubing.

The TENNA-ROTOR, made by Alliance Manufacturing Company, Alliance, Ohio turns a beam antenna to the compass point where interference is least and reception is best.

It is designed and built to operate for years exposed to rain, snow and sleet. For this rugged service, components are carefully tested and selected. Natvar 400 extruded vinyl tubing is used in the rotator unit for motor leads because of its superior resistance to weather.

Natvar 400 also has uniformly superior resistance to oil, and is approved for continuous operating temperatures of 105°C. Prompt deliveries can be made either from a nearby wholesaler's stock or from our own. Full Underwriters report on request.

Natvar

Natvar Products

- Varnished cambric—straight cut and bias
- Varnished cable tape
- Varnished canvas
- Varnished duck
- Varnished silk
- Varnished special rayon
- Varnished Fiberglas cloth
- Silicone coated Fiberglas
- Varnished papers
- Slot insulation
- Varnished tubings and sleevings
- Varnished identification markers
- Lacquered tubings and sleevings
- Extruded vinyl tubing and tape
- Extruded vinyl identification markers

Ask for Catalog No. 21

THE NATIONAL VARNISHED PRODUCTS Corporation

Telephone Rahway 7-8800

Cable Address NATVAR: Rahway, N. J.

201 RANDOLPH AVENUE ★ WOODBRIDGE, NEW JERSEY

40 years a *standard* metal

NICKEL

for vacuum-tube applications

More than four decades ago, when Dr. Lee De Forest developed his historic triodes, he made the elements of platinum.

But after the success of his first triodes, Dr. De Forest began a search for a more economical material of which to construct his tube elements . . . one that was inexpensive, workable, stable, with acceptable electronic characteristics.

He found his answer in pure Nickel . . . a metal that to this day has never been supplanted as the most practical for critical, high-precision, mass-production electronic tubes.

The qualities that recommended Nickel to De Forest . . . and to succeeding generations of electronics designers and research men . . . are:

1. **High and stable electronic emission.**
2. **Excellent high-temperature characteristics.**
3. **Good de-gassing properties.**
4. **High resistance to corrosion and fatigue.**
5. **Good workability and weldability.**

The value of Nickel in critical tube design can be inferred from the following. An ordinary large transmitting tube may contain virtually no Nickel, a large receiving tube may contain 50% or more Nickel, and a miniature receiving tube may employ Nickel for almost all its parts.

In addition to pure Nickel, many other nickel-bearing metals and high-Nickel alloys are used for special applications in the electronics field. Recent uses include non-magnetic "326" Monel and heat-resistant Inconel for cathode ray and television tube applications.

Nickel is available in a wide variety of mill forms easily adaptable to large-scale, low-cost production of vacuum tube components. Photo of Nickel cathodes courtesy of Superior Tube Company, Norristown, Pa.

• • •

If you would like to know more about the many important uses of these metals, ask for your copy of *"Inco Nickel Alloys for Electronic Uses."*



A TUBE THAT MEASURES A VACUUM

The VG-2 Ionization Gauge shown above measures the vacuum in a vacuum tube by counting the ions of residual gases. To achieve dependable characteristics, almost all of its metal components are Nickel . . . yet its selling price is under four dollars.

The VG-2 Ionization Gauge is manufactured by Heintz & Kaufman Division, The Robert Dollar Co., Redwood, California.

• • •

A partial list of the companies using the VG-2:

Argus, Inc.
Buhl Optical Company
Carbide & Carbon Chemicals Corp.
Curtis Laboratories, Inc.
Distillation Products, Inc.
Farrand Optical Co., Inc.
Johns-Hopkins University
National Research Corporation
National Technical Laboratories
Raytheon Manufacturing Co.
Technicolor Motion Picture Corp.

THE INTERNATIONAL NICKEL COMPANY, INC.
67 Wall Street, New York 5, N. Y.

EMBLEM OF SERVICE
NICKEL INCO ALLOYS
TRADE MARK

Monel® • "K"® Monel • "R"® Monel • "KR"® Monel • Nickel • "D"® Nickel
"L"® Nickel • Inconel® • Duranickel® • Permanickel® • Inconel "X"®



Announcing

DU PONT "RULAN"*

FLAME-RETARDANT PLASTIC for electrical insulation

Here's a new Du Pont material, especially developed for the electrical industry to meet the need for high-quality insulation that will not support combustion. Look at these features—

1. **Dielectric Properties.** "Rulan" flame-retardant plastic has a dielectric constant of 2.7 and high dielectric strength. It has a low power factor (0.002) that is constant over a wide range of frequencies. It is non-tracking. And "Rulan" retains its excellent electrical properties even after immersion in water for long periods at elevated temperatures.

2. **Nonflammable.** In flammability tests for insulation, "Rulan" has proved nonflammable. Further, it won't melt or drip, a big safety improvement.

3. **Mechanical Properties.** "Rulan" has good tensile strength, is tough and flexible. It has excellent low-temperature properties, is useful even below –60°C. (–76°F.). "Rulan" has very low water absorption (only 0.02 per cent by A.S.T.M. test).

for

High-voltage hook-up wire
Neon-sign cable
Signal-control wire
Multi-conductor control cable
Television lead-in wire
Radio feed-back wire
Flame-retardant line wire
High-voltage street-lighting cable
Other high-frequency uses

*Trade Mark

"Rulan" contains no plasticizer, hence is useful in non-migrating jackets. It can be extruded onto wire at high speeds and can be injection-molded. At present, molded electrical parts and extruded electrical tape are being developed for uses where flammability is a factor. Wire today for more information. Our salesmen and technical staff will be glad to help you. E. I. du Pont de Nemours & Co. (Inc.), Polychemicals Department, Plastics Sales Offices: 350 Fifth Avenue, New York 1, N. Y.; 7 S. Dearborn Street, Chicago 3, Ill.; 845 E. 60th Street, Los Angeles 1, Calif.

DU PONT
REG. U.S. PAT. OFF.
PLASTICS
Better things for Better Living
. . . through Chemistry

Plastic Laminates that Insulate—May


AN ELECTRICAL INSULATOR
. . . moisture resistant
AN ELECTRICAL INSULATOR
. . . light in weight
AN ELECTRICAL INSULATOR
. . . impact fatigue resistant
AN ELECTRICAL INSULATOR
. . . mechanically strong

SYNTHANE

Plastic Laminates are materials expressly made for industrial applications. They have an interesting *combination* of electrical, mechanical and chemical characteristics. This combination often stimulates new ideas in design or use, may improve a product or process or reduce fabrication or maintenance costs.

Synthane is an excellent electrical insulator. Synthane is high in dielectric strength, low in dielectric constant and power factor. It is also light in weight, hard, dense, strong, resistant to abrasion, corrosion and moisture, and is dimensionally stable.

Synthane speeds fabrication. Synthane laminated can be machined quickly and easily on standard production equipment or we will fabricate for you. It is also available from us in a variety of molded-laminated or molded-macerated shapes. These are only a few of many Synthane advantages.

Let us help you plan with Synthane. If you are designing a new product or have a materials problem, write and tell us about it. We will be glad to help you with design, grade selection, or fabrication of parts. Clip and mail the coupon today for your free copy of the complete Synthane catalog. Synthane Corporation, Oaks, Pa.



SYNTHANE

AT WORK IN INDUSTRY

The Moloney Electric Company selected Synthane for parts of the transformers it produces, because of Synthane's excellent electrical insulating ability, good structural strength and corrosion resistance. Shown at right is the Moloney 33,333 kva, three-phase, 60 cycle 132000 volts Delta high voltage to 34500Y/19920 volts low voltage. The complete unit weighs approximately 227,000 pounds.

PLASTICS WHERE PLASTICS BELONG

DESIGN MATERIALS FABRICATION SHEETS RODS TUBES

Stimulate new ideas *for You*

What else do you look for in an insulating material? Light weight? Strength? Resistance to moisture, corrosion and wear? Dimensional stability? Ease of machining?

Synthane is made in a variety of grades. Each excels in one or more particulars. Each offers a *combination* of useful qualities.

Grades are classified according to the base materials used in them. Paper, cotton, glass fabrics, and asbestos are some of the materials we laminate to produce Synthane. Various resins are used.

At the right are four applications. In each, a different grade of Synthane is used. In each, Synthane gives the manufacturer and his customer a better material because the essential properties are supplemented by a *combination* of other valuable characteristics.

Film Carrier for use in developing solutions. Fabricated from a grade of Synthane resistant to corrosion. The grade selected has the added advantages of mechanical strength and ease of machining.

Tip Insulators for Welding Electrode Holder. The requirements after electrical insulating ability are resistance to heat and impact fatigue, and, for long wear, toughness.

Automobile Water Pump Seal Washer. Moisture resistance, ease of machining and good wear resistance are essential advantages of the grade used for this part. Additional advantages are light weight and dimensional stability at comparatively high temperatures.

Power Shovel Parts. Electrical insulating ability and mechanical strength are the properties most needed in this application. The grade selected is also wear resistant, easily fabricated to precise dimensions, and can be laminated directly over metal parts for extra strength.

SYNTHANE

WHERE SYNTHANE BELONGS

MOLDED · MACERATED · MOLDED · LAMINATED

SYNTHANE CORPORATION
6 River Road, Oaks, Pa.

Gentlemen:

Please send me, without obligation, information on sheets, rods, tubes and fabricated parts.

Name _____

Company _____

Address _____

City _____ *Zone* _____ *State* _____

Before Any Other Consideration

Integrity of Circulation

OF THE several factors that enter into the use of published media, the distribution of the advertisers' sales messages, as governed by the selection of media, can of itself decide the success or failure of the advertising investment. That is why integrity of circulation is the first consideration with experienced space buyers.

The emblem shown above stands for the FACTS that make it possible for advertisers to select the right media and to know what they get for their money when they invest in publication advertising. It is the emblem of membership in the Audit Bureau of Circulations, a cooperative and nonprofit association of 3300 advertisers, agencies and publishers.

Working together, these buyers and sellers of advertising have established standards for circulation values and a definition for paid circulation, just as there are standards of weight and measure for purchasing agents to use in selecting merchandise and equipment. In other words, A.B.C. is a bureau of standards for the advertising and publishing industry.

A.B.C. maintains a staff of specially trained auditors who make annual audits of the circulations of the publisher members. Information thus obtained is issued in A.B.C. reports for use in buying and selling space. All advertising in printed media should be bought on the basis of facts in these reports.

This business paper is a member of the Audit Bureau of Circulations because we want our advertisers to know what they get for their money when they advertise in these pages. Our A.B.C. report gives the facts. Ask for a copy and then study it.

SEND THE RIGHT MESSAGE TO THE RIGHT PEOPLE

Paid subscriptions and renewals, as defined by A.B.C. standards, indicate a reader audience that has responded to a publication's editorial appeal. With the interests of readers thus identified, it becomes possible to reach specialized groups effectively with specialized advertising appeals.

SOME OF THE AUDITED INFORMATION IN A.B.C. BUSINESS PAPER REPORTS

- How much paid circulation.
- How much unpaid circulation.
- Prices paid by subscribers.
- How the circulation was obtained.
- Whether or not premiums were used as circulation inducements.
- Where the circulation goes.
- A breakdown of subscribers by occupation or business.
- How many subscribers renewed.
- How many are in arrears.

McGRAW-HILL PUBLICATIONS

A.B.C. REPORTS — FACTS AS THE BASIC MEASURE OF ADVERTISING VALUE

New Property Chart of ALSIMAG®

TECHNICAL CERAMIC COMPOSITIONS


CHART No 501 • MECHANICAL AND ELECTRICAL PROPERTIES OF ALSIMAG CERAMICS
AMERICAN LAVA CORPORATION, CHATTANOOGA 5, TENNESSEE

sent free on request

American Lava Corporation, Chattanooga 5, Tennessee, has issued a new chart giving the mechanical and electrical properties of AlSiMag custom-made technical ceramics.

WHAT ALSIMAG IS

AlSiMag is the trade name of a large family of technical ceramic compositions. These compositions have different physical, electrical, mechanical and chemical characteristics. AlSiMag ceramics are custom-made to specifications.

WHAT THE CHART TELLS

The chart covers seventeen of the more frequently used AlSiMag compositions and is the most complete chart yet issued in this field. A new feature is a selection chart which simplifies and speeds the selection of the most useful composition for the individual requirement. This selection chart indicates lower cost materials in BOLD FACE. This helps the product engineer to design for utmost economy.

Some properties, such as thermal expansion, dielectric strength, in relation to thickness and temperature are presented in graphic form.

ALSIMAG COMPOSITIONS NOT ON CHART

Many special AlSiMag compositions have been developed to meet specific conditions. These are too numerous to chart. If chart indicates general characteristics of value, modifications to suit your special application may be available.

WHO NEEDS THE CHART

Designing engineers, production technicians or purchasing agents will find chart helpful in their search for materials for unusual applications.

HOW TO GET THE CHART

The AlSiMag Property Chart is sent free on request. Request as many copies as you need to cover your organization.

WHERE ALSIMAG IS USED

AlSiMag custom-made technical ceramic parts are extensively used as:

Insulators for the electronic field • Insulators for electric appliances and other electrical applications • Thread Guides for textiles, wires, paper twine, etc. • Extrusion dies for such products as pencil leads, battery carbons, soft wires, explosives, etc. • Gas burner tips • Controlled atmosphere welding tips • Oil burner ignition insulators • Ceramics for hermetic seals • Metal-ceramic combinations • Air-acid jet nozzle inserts • Polishing heads for delicate final polishing operations • Cores and inserts for precision castings • Strainer cores for metal foundries • Cut-off cores for metal foundries • Refractory pins and plates in small sizes and special shapes • Work holders for electronic heating devices • As a replacement for parts made of plastic, wood or machined metal wherever a wear resistant part is required • In short, wherever electricity, heat, chemical or certain abrasive or friction conditions must be controlled.

49TH YEAR OF CERAMIC LEADERSHIP

AMERICAN LAVA CORPORATION

CHATTANOOGA 5, TENNESSEE

OFFICES: METROPOLITAN AREA: 671 Broad St., Newark, N. J., Mitchell 2-8159 • CHICAGO, 9 South Clinton St., Central 6-1721
PHILADELPHIA, 1649 North Broad St., Stevenson 4-2823 • LOS ANGELES, 232 South Hill St., Mutual 9076
NEW ENGLAND, 38-B Brattle St., Cambridge, Mass., Kirkland 7-4498 • ST. LOUIS, 1123 Washington Ave., Garfield 4959

the New
PYRAMID
"Humidi-Seal"
(TUBULAR PAPER CAPACITOR)

Repels Moisture!
Ruggedly built to withstand undue vibration and rough handling
Outer tube plastic impregnated to prevent moisture absorption
Light outer coat of high-temp wax provides double protection
Each end plastic sealed against moisture
Leads anchored securely in solid plastic end
PYRAMID
HUMIDI-SEAL
.05 M.F.D.
600 V.D.C.

Type 85TOC "Humidi-Seal" capacitors are specially designed for 85° C. operation, even in the most humid atmospheres, and will meet the severe present-day demands of endurance in television receivers, auto radios, etc.

WRITE FOR COMPLETE LITERATURE

Representatives and Distributors throughout the U.S.A. and Canada

PYRAMID

PYRAMID ELECTRIC COMPANY
155 Oxford Street
Paterson, N. J., U.S.A.
TELEGRAMS: WUX Paterson, N. J.
CABLE ADDRESS: Pyramidusa

BUSINESS BRIEFS

By W. W. MacDONALD

Scientific Apparatus needed by American laboratories for research and the development of new products was largely imported prior to 1917. When fighting in Europe cut off the supply our importers started to build their own, and the industry might be said to date from that time in this country.

Now a new condition has arisen. The average scientific apparatus maker comes under the heading of small business, with perhaps 35 employees. There are about 1,700 such concerns. And many of them find themselves squarely up against serious competition from countries in which labor rates are low and exchange very favorable. Certain optical items, for example, dropped off 20 percent in sales in 1949 and so far this year are off 30 percent.

Considered broadly, the situation seems to be this: Foreign trade agreements help our friends and therefore may ultimately help us. On the other hand, reduction in the number of people designing and building scientific apparatus here would reduce our self-sufficiency.

Largest Single Procurement action likely this year by the Army Signal Corps, still open for bids, is for $15-million worth of f-m equipment for vehicular and ground use.

David Sarnoff Says "If final standards are adopted and commercial operation in color is authorized soon, the RCA could and would be in factory production of color television receivers by June of next year. This would amount to a weekly production rate of 200 color receivers. By the end of that year, our color receiver rate of production will have reached over 1,000 per week. Thereafter, we expect production quantities to rise substantially."

Average TV Set contains 800 individual component parts and 15,000 feet of wire. There are 7,500 assembly operations, including 750 soldered joints. Capacitors, according to Aerovox, total 124, broken down as follows:

Ceramic	55
Paper	39
Electrolytic	17
Mica	13

Schwab House, 700-unit New York apartment building, is the biggest master antenna job for television we've heard of so far, RCA doing the work. Anyone know of an installation that tops it?

Milwaukee Journal survey produces the following interesting figures showing television receiver ownership as of January 1950 and families planning to buy sets this year, by income groups:

	Owners	Prospects
Under $2,000	10.0%	11.1%
$2,000 to $2,999	16.0	18.3
$3,000 to $3,999	17.2	17.6
$4,000 to $4,999	23.9	19.9
$5,000 to $7,500	25.9	20.9
$7,500 and up	25.0	17.0

Television Equivalent of radio's tone control is the contrast control. Joe Public likes tone controls adjusted to minimize noise (and high notes) and make music "mellow." He also thinks the best pictures are those that have the most contrast, and any attempt to make him think otherwise is probably futile.

Real Estate Office near this columnist's home has had half-a-dozen miniature houses constituting a model development in its window for several years. Last week antennas and reflectors were placed on the little rooftops.

Such is the influence of television upon the American scene.

Printer's Error, if we hadn't caught it before publication: ". . . . Standing-wave ratio reduced to $1.05 . . . .".

Broadcast Station Revenue increased 10.3 percent in 1949 over 1948, according to an FCC report just released. A total of 2,850 a-m, f-m and tv stations reported a $459,800,000 take. Expenses were up 14.4 percent to



for
economy,
long life and
low maintenance
in action

and you'll pick the

HONEYWELL
Mercury Switch

Designers, manufacturers and consumers alike have plenty of praise for these "miracle" midgets that do a giant job at a cost that's amazingly low. As the ideal switching medium, they offer the result-producing advantages of safety . . . long service life . . . minimum maintenance . . . and small initial cost.

You'd become dizzy counting the times they tirelessly provide positive on-off action in many varied products . . . but actual operating records show more than 50 million cycles without attention. That's economy and value in use!

Honeywell Mercury Switches are compact . . . easily adaptable to your product . . . operate at low angles . . . are sealed against dust, gas and corrosion. Available in hundreds of types from ½ amp to 45 amp, 115 volts a-c non-inductive load.

The complete line is at your command. For detailed discussion of possible product application call in your local Honeywell Engineer . . . he is as near as your phone. Write for Catalog 1343 and latest price schedule for manufacturers.

MINNEAPOLIS-HONEYWELL REGULATOR CO., *Industrial Division*, 4428 Wayne Ave., Philadelphia 44, Pa. Offices in more than 80 principal cities of the United States, Canada and throughout the world.

FOR • POSITIVE ACTION • LOW ANGULARITY • LONGER LIFE • WIDE SELECTION

Specify MINNEAPOLIS **Honeywell** MERCURY SWITCHES

SHOCK AND VIBRATION NEWS

There's a BARRYMOUNT for each of your needs!

AIRCRAFT MOUNTING BASES

Standard bases with dimensions to government specifications. Special bases to customers' exact requirements.

AIRCRAFT VIBRATION ISOLATORS

Unit isolators designed to meet Army, Navy, and CAA requirements. Stock mountings — 1/4 pound to 45 pound load range. Others on order.

SHOCK MOUNTINGS

For mobile, railroad, and shipboard electronic and electrical equipment. Also for isolation above 2000 c.p.m., and for general sound isolation.



INSTRUMENT MOUNTINGS

For electronic components, tiny fractional H.P. motors, record changers, dictating machines, and other lightweight apparatus.

INDUSTRIAL MOUNTINGS

For fans, motor generator sets, transformers, presses, other heavy industrial equipment.

Free Catalogs give dimensions and load ratings of stock BARRYMOUNTS. Catalog 502 covers aircraft applications. Catalog 504 covers industrial and general-purpose mountings. WRITE TODAY to

THE BARRY CORP.

Main Office 177 Sidney St. ● Cambridge 39 Massachusetts

New York · Rochester · Philadelphia · Washington · Cleveland · Dayton
Chicago · Minneapolis · St. Louis · Los Angeles · Toronto

BUSINESS BRIEFS (continued)

$425,000,000 however, so that income before Federal tax was $34,800,000, a decline of 24.5 percent.

Navy Accountant recently okayed a bill for a bale of diapers, but it took some explaining. The soft, lint-free cloth that is kind to Junior is apparently also good for cleaning the inside of certain electron tubes prior to evacuation and sealing.

Receiver Sales by licensees, first quarter 1950, totalled 4,201,891, worth $316,936,375. Here's the way the total broke down:

Type	Units	Dollars
Electric		
Table (under $12.50 billing price)	676,233	$7,022,686
Table (over $12.50 billing price)		
A-M	469,662	5,788,532
A-M/F-M	77,525	2,467,146
F-M (including converters)	2,933	57,168
Consoles		
A-M	1,748	123,702
A-M/F-M	2,743	245,802
Table-Radio-Phonos		
A-M	70,667	2,911,857
A-M/F-M	6,129	225,917
Console-Radio-phonos		
A-M	13,862	1,056,298
A-M/F-M	109,442	12,681,254
Battery		
Portable A-C/D-C	232,197	4,321,080
Table	20,977	355,271
Consoles	6	455
Auto	888,541	22,980,494
Television		
Converters	6	2,618
Radio Table Models	691,834	94,692,577
Radio Consoles		
Direct Viewing	610,864	115,868,045
Projection	6,276	1,531,597
Radio Phonos		
Direct Viewing	139,770	37,109,676
Projection	17	9,885
Phonographs		
Phono only	146,267	2,522,171
With radio attachment	11,551	191,635
Without Cabinets		
A-M	2,121	69,300
A-M/F-M	6,893	210,365
Television	13,638	1,496,080

Magnetic Tape Recorders manufactured by licensees of the Armour Research Foundation totalled 20,000 in 1949.

Figures presented at a recent conference on components again emphasize the importance of electronics in the aircraft field.

L. V. Berkner of Carnegie Institution: "In a patrol bomber costing $1,315,374 the electronic equipment costs $179,899 and includes 45 devices composed of more than 25,000 components."

Charles R. Banks of Aeronautical Radio: "The airlines now have 2,000,000 capacitors, 1,500,000 re-

sistors and 180,000 electron tubes operating in 750 aircraft. . . . The investment is $10,000,000, and maintenance cost is over $3,000,000 annually for materials and labor."

Employment was up 5.6 percent in March as against January among 190 communications equipment manufacturers reporting to the U. S. Department of Labor, and a further rise of 2.6 percent was anticipated by midyear. Television sparked the increase, easily counterbalancing a slight decline in employment among telephone and telegraph equipment makers.

A Bonus of $10,000 is paid by the AEC to anyone who discovers a new uranium deposit and delivers twenty short tons of ore containing 20 percent or more of uranium oxide to the Commission.

Reading Our Own Ads leads us to make the following observations:

Hermetic seals, and hermetically-sealed components, appear to be getting quite a play. Military applications undoubtedly provided the springboard, but aviation and other industrial users are now interested.

Solderless connections, commented upon in this column several times before, seem to be picking up adherents among industrial users. Communications applications still develop slowly.

Life-rating of a particular receiving-type tube is given as 10,000 hours.

A new amateur transmitter is said to be TVI-less in 97 percent of the installations made to date.

We very much like the phrase, used in connection with a test instrument "Industrial Endurance With Research Quality."

Reading time: 1½ hours.

Perils Of Publishing: For six months one of our distant representatives has been dickering with a man for a story. Queried recently from the home office concerning prospects of getting it, our rep replied: "The story in which you are interested seems to have gone a little sour . . . . *The engineer who had promised it shot a guy and is now in the jug.*"

SIGMA

Sensitive Relays

SERIES 4

SPDT GENERAL PURPOSE SENSITIVE D. C. RELAY. Inexpensive Balanced armature for vibration resistance on aircraft at 50 milliwatt adjustment. Sensitive enough for V-T operated relay circuits; can be set to operate down to 10 milliwatts. Precision adjustments for pull-on and drop-out. 2 amp. nominal contact rating. Coil resistance up to 14,000 ohms.

SERIES 5

SPDT VERY SENSITIVE D. C. RELAY. Balanced armature and magnetic efficiency resist aircraft vibration on inputs as low as 5 milliwatts. Withstands 500g shock without damage. Precision adjustments. 2 amp. nominal contact rating. Coil resistance up to 16,000 ohms. Special adaptations: Built-in rectifier, two-coil differential operation, constant voltage temperature compensation.



SERIES 41

SPDT SENSITIVE RELAY AC-DC—KEYING. Unusual characteristics at low cost. Same D. C. sensitivity as Series 4 but less flexibility of adjustment. Available with long life and bounce-free contacts, it is suited to high speed counting and keying. Mechanical life exceeds 10^8 operations. Good for plate circuits needing moderate precision and vibration immunity. Contact ratings up to 5 amps. Coil resistance to 14,000 ohms. A. C. sensitivity exceeds 0.1 V.A. at 60 cps. Serviceable on frequencies from 25—400 cps. Protects delicate thermostat or instrument contacts.



SERIES 6

MULTICIRCUIT POLARIZED SENSITIVE RELAY. Single or double (differential) windings. Resistance up to 25000 ohms total. Contacts up to 4PDT, 5 amp. nominal rating. Balanced armature for strong vibration resistance. FORM X—Three Position or Null Seeking. For automatic positioning or 2-Way process control. Sensitivity (depending on contact complexity) from 10 to 100 milliwatts. FORM Y—Biased (Spring Return). Use as an ordinary sensitive relay if a complex contact combination is needed. Combines function of pilot relay and contactor. Sensitivity same as Form X. Responds only to one polarity. FORM Z—Latching (*permanent magnetic*). Replaces mechanical latch electrical reset relays, where longer life and greater vibration resistance is required. Sensitivity from 100 to 250 milliwatts.

SERIES 7

SPDT SENSITIVE HIGH SPEED POLARIZED RELAY. Single or multiple windings up to 14,000 ohms (single). Balanced armature. Nominal contact rating 2 amps. For repeating *telegraphic signals* at speeds up to *250 WPM*. Small in size and weight. Hermetically sealed. Mechanical life exceeds 10^8 operations. FORMS X, Y and Z (see Type 6 above) available in Series 7. Sensitivities from less than 1 to 10 milliwatts depending on form and requirements. Form X is useful as the detecting element in positioning bridge circuits.



VARIETY OF ENCLOSURES

In addition to the open styles shown, SIGMA Relays are available with dust-proof or hermetically-sealed enclosures. Most types are available for either plug-in or permanent solder-lug connections.

WRITE FOR FULLY DESCRIPTIVE CATALOG

SIGMA Instruments, Inc.

SENSITIVE RELAYS

Critical Requirements of Television Prove

Remarkable Performance of Mallory FP Capacitors!

There can be no more convincing proof of superiority than the performance records hung up by Mallory FP Capacitors in the demanding field of television service.

In one case, an outstanding television manufacturer kept detailed records of field failures of component parts over a six month period . . . found only six Mallory failures, with nearly 400,000 FP Capacitors in service!

That's service beyond expectations!

That's why so many leading manufacturers insist on Mallory Capacitors that have set the pace in the industry for years. That's why you should specify Mallory, at no premium in price, for any application that demands continuous, trouble-free performance.

MALLORY FP CAPACITORS

Mallory FP Capacitors are designed to operate continuously at 85° C—and are famous for their long *shelf life*. Write for your copy of the Mallory FP Capacitor data folder.

FP is the type designation of the Mallory-developed electrolytic capacitor having the characteristic design pictured and famous throughout the industry for dependable performance.

P. R. MALLORY & CO. Inc.

MALLORY

P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

SERVING INDUSTRY WITH

Capacitors	Contacts
Controls	Resistors
Rectifiers	Vibrators
Special Switches	Power Supplies

Resistance Welding Materials

CROSS TALK

► **WORLD TV . . .** This is written in London, where your exhausted servant has just completed a tour of television systems in the USA, France, Holland and Great Britain. The trip was preparatory to the second meeting of the Television Study Group of CCIR. This group, carrying forward the work begun in Zurich last year, is attempting to find a common basis for agreement on international television standards.

Since the meeting is still in progress as deadline approaches, we cannot report the findings in this issue. A full account will be published next month. Meanwhile, some general impressions may be of interest.

Within the space of 15 days, we have seen television on 405, 441, 525, 625 and 819 lines, at 50 and 60 fields per second, on video bandwidths from 2.7 to 10 mc. Our impression, shared by many in the tour, is that the US standard of 525 lines and 60 fields per second with a 4.25-mc video band is the happiest compromise among the systems demonstrated to us.

This is not to say, however, that the American television industry leads the world in all respects. Our British cousins are showing their heels to us in four departments: First, the transient response of British television studio equipment, coaxial cables, radio relays and transmitters is generally superior to ours. It is a matter of personal pride with nearly every British operator to adjust the phase correction of the apparatus until the leading and trailing transients just balance. Admittedly their problem is somewhat simpler than ours, but their attitude toward phase correction is one we should adopt.

Second, the British transmission of movie films, by the flying-spot method of scanning, is wonderful to behold. Despite the fact that they use at least one megacycle less video bandwidth than do the US stations, the images are sharper and crisper and the tonal gradation is definitely superior.

Third, a new camera tube, the cathode-stabilized orthicon, is just coming into use and, for studio use at least, seems to have several distinct advantages over the image orthicon. The most notable of these are an inherently steady black level and a noise level which increases with light. These properties permit gradation correction circuits to be used, and the result is an image of truly photographic quality. Moreover, this tube (the c.p.s. emitron) will produce a respectable image with one foot-candle illumination at a lens aperture of f:1.9. American television engineers could use it to great advantage, despite the fact that the tube has a tendency to instability at high light levels. Certainly US television would be the richer if the cathode-stabilized orthicon were available here.

Fourth, the new Birmingham station has a visual power at 35 kilowatts into the antenna. Plans are afoot for future stations of 100 kw with antenna power gain of four times. We could use such power.

In most other respects, the American system leads the parade. European television images display an alarming tendency to flicker at brightness levels far below those demanded by the American public, due to the 50 per second field scanning rate. A Dutch demonstration of a long-persistence (about 10-millisecond) white-light phosphor was impressive in reducing flicker, but the image is subject to color fringing of objects in motion. The visible effect of ignition noise, which produces white spots on the screen due to the use of positive modulation in England, is definitely more annoying than the black spots of the American system. The sound channel of the British stations, transmitted by a-m rather than f-m, is apt to be noisy. The limiters used in some receivers to limit impulse noise have the unfortunate effect of introducing audio distortion.

The concept of standardizing on the line-scanning frequency, with a narrow tolerance, to permit interchange of programs even when the number of fields per second and lines per picture are not the same in different countries, is one of the noteworthy suggestions of the meeting.

► **QUIZ COMING . . .** Our query of several months ago concerning a series of electronic problems for the amusement and edification of readers has drawn a most encouraging response. Accordingly, in future issues we shall publish such problems as come to hand, with answers the following month. We have a few problems on hand, but need more. Look for problems and answers on the Backtalk page.

Why Television Receivers

WITH TODAY'S SPOTLIGHT on television receiver production figures and dollar volume of sales, there is a tendency to overlook the fact that television servicing is also big business. Based on current average prices for sets and yearly service contracts, every dollar paid for a television receiver will within five years be matched by another dollar paid to service organizations. Putting it another way, an estimated $325 million will be paid out in 1950 just to keep television sets running, in contrast with only $300 million of business (at factory prices) done by the entire electronic industry in 1939.

Why does it cost so much to keep tv sets running? To probe into this question, sampling surveys were made of the field experiences of tv manufacturers who have their own service organizations. In addition, independent service organizations who take on service contracts for all makes of sets were queried. This article presents in detail the results of an investigation by the staff of ELECTRONICS.

Breakdown of Calls

Reasons for calling a television serviceman are broken down in Table I for four representative organizations. A quick check shows that only about 30 percent of these reasons are traceable to human nature, to antenna systems and to other nonmanufacturing factors. The remaining 70 percent of the calls deserve detailed technical analysis here because they can be eliminated at least in part at the manufacturing level, with immediate savings in service division overhead and long-term gain in serviceman and consumer goodwill.

Just as in radio sets, a defective tube is by far the most common cause of trouble in a television receiver. In television, however, causes of tube failures are much more often attributable to set design engineers than to tube manufacturers. Tubes are worked close to the upper limits of their ratings in many tv circuits, leaving little margin for normal tolerances of other parts and for effects of ageing. As a result, tube testers are rarely if ever used for checking tubes in tv sets. Substitution of new tubes is the universal practice among service organizations. So critical is circuit design in some cases that it is not unusual to have to try half a dozen new tubes before finding one that works in a particular set.

Picture tube replacement ranks high, considering that it is the most expensive replacement part in a tv set. On a first-year service contract, about half the picture tube failures occur within the first three months, covered in all cases by the standard 90-day warranty of the manufacturer. The trend is toward free replacement by manufacturers during the remainder of the first year as well, usually under a first-year contract whereby the set manufacturer replaces all defective parts for a blanket price of $5 to $20 that is paid by the service organization or dealer.

Reasons for replacement of biggest troublemakers among other tubes are given in Table II. In general, the practice of tv servicemen is to replace a tube if that will make the set work again, even though some other part is the real cause of trouble. Replacement with a selected upper-limit new tube can cure a lot of other troubles in certain circuits, eliminating removal of the chassis to the shop for more expensive replacement of a cheaper under-chassis component.

Other Troubles

Antenna troubles vary greatly from one locality to another, and depend also on the number, location and effective signal strengths of the

Table I—Analysis of Television Receiver Service Calls

Reason for Call	Percent of Total Calls			
	Mfr. Service Organization No. 1	Mfr. Service Organization No. 2	Independent Service Co. No. 1	Independent Service Co. No. 2
Replace picture tube	10%	4%	5%	6%
Replace other tubes	30	21	35	25
Reorient antenna*	8	2	15	10
Repair antenna system*	3	6	2	2
Change antenna or add high band*	1	2	1	3
Readjust back-of-set controls	2	1	15	12
Correct deficiency in circuit design	1	7	6	2
False calls*	4	15	10	10
Replace paper capacitor	9	1	3	2
Replace resistor	9	1	3	3
Repair or replace tuner	8	15	2	5
Replace other components	4	15	1	6
Repair poorly soldered joint	5	1	1	1
Realign	4	2	1	8
Customer not at home*	2	4	2	5
* Total not fault of set manufacturer	13%	29%	30%	30%

Fail in Service

Three years of field experience by manufacturers and independent service companies reveals 15 major reasons for service calls. Many can be eliminated at design and production stages, often with accompanying savings in manufacturing cost

transmitters in the area. As localities reach their legal quota of stations, antenna calls diminish since the required compromise orientation can be made at the time of installation. New antenna types are proving highly satisfactory in the field and reducing antenna calls.

On the other hand, as more sets enter second and third years of service, antenna repair calls go up. Though the figures in Table I are for the entire three-year period since the war, 1949 sales of well over 2,000,000 tv sets pretty well weight the picture.

Readjustment of back-of-set controls is high in percentage for independents, low for manufacturer service organizations. Stability of circuits used by the particular manufacturers polled may be one reason. Another fact, more pertinent to independents who must know a little about a lot of different sets, is the psychological value of actually doing something to a set even when the picture is found to be of acceptable commercial quality for the particular set involved.

Corrections of circuit design come in batches coinciding with launching of new tv models. Least trouble comes from models using refinements or improvements of the previous year's circuitry, and most trouble when designers choose to toss out the experience of former years and start from scratch.

Where a capacitor goes, so often goes a resistor, hence figures for these two parts run hand in hand across the board. Importance of incoming inspection of components and quality control during assembly shows up in the total of 18 percent for resistor and capacitor replacements by one manufacturer as contrasted to a 2-percent total for the other.

Tuner troubles, particularly tuning switches, rank high with manufacturers, possibly because independents touch these critical units only as a desperate last resort. Men specializing in one make of set and having replacement tuners for them right on the service truck can make a changeover of a complete tuner quickly and at fairly low cost. Independent servicemen obviously cannot carry spare tuners for all sets, nor can they be expected to take apart double and triple-shielded tuners in the home for repairs. Fortunately, prevalence of tuner trouble is going down with improved design in 1949 and 1950 models of most sets.

Electrolytic capacitor troubles run as high as 3 percent for one independent who handles a lot of off-brand and lower-priced sets and also has a large number of second and third-year contracts on the books. The other three sources rated electrolytics as under one percent, however. Flyback transformers receive vitriolic comment in most shops, but troubles with these parts just about vanish when manufacturers change over to ceramic-core units.

An independent serviceman just cannot understand how a joint could

Table II—Tubes Failing Most Often in Television Receivers

Type and Function	Nature of Failure	Remedy
6BG6G and 19BG6G horizontal output	Gassy, resulting in dead tube, due to electrolysis at top connection	Change to new tube, which in some makes now have a leaded glass envelope
	Can't fill screen because near lower limit of sensitivity	Select new tube near upper limit of sensitivity
	Barkhausen interference, producing black line at edge of picture	Try new tube or put magnet around tube
6SN7 sync	Open filament, low gain, intermittent or gassy	Try new tube. If in relaxation oscillator, selection is needed
5U4 and other rectifiers	Open filament, or loss of emission	Install new tube; drive less hard if possible, as these tubes are often operated too close to rated limits
6J6 oscillator	Microphonic	Select nonmicrophonic new tube
12AT7 converter	Failure to oscillate on high channels because of low g_m	Select new tube that will oscillate
5V4 and other damping tubes	Flashover, causing burnout, apparently because of heater sagging	Replace tube
12AU7 video amplifier	Microphonic	Select nonmicrophonic new tube

get out of a factory without being soldered, hence doesn't look for bad joints as a rule. Manufacturer servicemen, on the other hand, are given guided tours through the factory so they can see how easy it is to miss a joint or two, and are specially drilled in hunting for bare joints hence find more of them in the field. Independents may offset an unsoldered high-resistance joint by replacing a tube or adjusting the screwdriver controls to compensate.

Realignment includes shifting the i-f value when two receivers in the same building interfere with each other. Most alignment work is done in the shop.

No matter how definitely an appointment is made for a service call, women still persist in "just stepping next door" at the appointed time, or even forget about it and go off for the day. False calls are high, but there isn't much that can be done about them until servicing is put on a charge-per-call basis. Temporary interference, transmitter troubles, and misrepresentation by salesmen as to merits of built-in antennas are just a few of the reasons for dry runs. In addition, there are times when work must be done to retain goodwill or prevent badwill even though the service organization has no responsibility.

Home vs Shop Repairs

The percentage of sets fixed in homes ranges from 20 percent to 96 percent, depending on the service organization. Top figure is logically that of a manufacturer's service organization, where men receive specialized training and acquire experience on just the one make of set and carry practically all needed repair parts and test equipment for that make right with them in the service truck. For high-caliber independent service organizations handling all makes of sets, an average of 70 percent of calls completed in homes is considered excellent because they cannot possibly carry spare parts for all makes.

Low figure of 20 percent is for independent service organizations that employ low-salary field men who know little more than how to replace tubes and remove the chassis. These firms rely heavily on at-the-shop experts despite obvious costliness of making two comes and goes per service call. Such practices have resulted in bankruptcies of some service organizations, with consequent headaches and loss of good-will for manufacturers of sets left stranded without service.

With an average of 5 to 6 service calls per set per year for all types of organizations and an installation cost running as high as $20 per set, almost any kind of bookkeeping quickly reveals the difficulties of breaking even on service contracts when a high percentage of sets have to be brought into the shop. Firms doing this can of course exist handsomely as long as new service contract money flows in at an accelerating rate, but eventually comes the day of reckoning. As a result of bitter experience along these lines, more and more manufacturers are exhibiting interest in the service organizations to whom their dealers farm out service contracts.

Design Economies

Another topic probed during this survey was the current accent on cost-cutting in tv receiver production. Some of the items and techniques being used or receiving consideration are listed in Table III, with advantages and drawbacks of each. Service organizations contributed equally as much as manufacturers to this tabulation, showing their intense interest in the effects of manufacturing economies on service calls.

Many of the items listed in Table III can give lower manufacturing costs than comparable earlier versions. Most of the changes have little or no effect on the number of service calls or the quality of set performance. A few of the changes actually improve performance and reliability, while still others have adverse effects on performance that in the long run can offset cost savings.

Although attention to individual items one after another can result in appreciable savings, much broader thinking is needed to get maximum benefits. One philosophy of television receiver design has the design engineer starting not with components or even circuits, but with pure logic. The overall receiver is designed first to do a certain commercial and technical job, using a number of separate system components corresponding to the blocks of a block diagram. Possible patterns of interconnection of the blocks are studied, with no concern for details of internal circuitry. Deliberations might follow a line like this:

"From an overall point of view a receiver should have a flat avc with gain to spare. Perhaps, therefore, the avc might stabilize the signal at the final output on the picture tube grid. In so doing it might be arranged to hold the black level to a constant bias. This would not only prevent variation of background but would also make it much easier to pick off sync at that point since the sync would be held by the powerful avc to a constant bias. A single stage of video, d-c coupled, is appropriate in this case. Instead of the usual complicated video contrast control circuit with its long hot leads, the gain control can now be a simple d-c control, arranged to add a variable bias in series with the video signal. The avc counteracts this to force the black level to remain at its proper bias, and in so doing changes the contrast."

Reasoning in this way, the design engineer carefully investigates the consequences of all sorts of interconnections, looking particularly for arrangements that make efficient use of tubes and circuits. Thus, by careful critical thinking he makes sure that the overall economy of the system is excellent and the performance is the best possible for the intended purpose and price range. Last rather than first comes attention to components and production practices such as are tabulated in Table III.

Broad overall reasoning during design stages is difficult and requires great familiarity with television circuitry and all its possible variations. Above all, such designing requires clear thinking without being distracted by the many details involved. Recent experience shows, however, that it is the best approach to the problem of obtaining improved television receiver performance at lower initial cost, with less complexity, and lower service cost.—J.M.

Table III—Examples of TV Receiver Design Changes, with Effects on Cost, Performance and Service

Technique	Effect on Cost	Effect on Performance
Standardize horizontal sweep transformer, focus coils, tuners	Permits ordering or making larger quantities at lower cost	None. Simplifies servicing since fewer replacement parts need be stocked
Use germanium diodes in video detector and sound discriminator	Easier to install and need no sockets	Better picture definition. Improvement in uniformity of production
Omit separate horizontal sync amplifier tube	Eliminates cost of one stage	Reduces sync stability, increasing service calls
Omit automatic brightness control	Simpler wiring	None, but makes set harder to operate
Use direct-coupled video amplifiers	Uses fewer parts; permits omitting d-c restorer	None if properly designed. Makes servicing simpler
Use fewer r-f and i-f stages	Appreciably lower cost	Reduces sensitivity and/or bandwidth
Less shielding of r-f units	A few pennies	None, but set may radiate interfering signal
Use separate narrow-band i-f amplifier for sync signals	Higher, but improves sales appeal	Better performance on extremely low and high signal strengths, by providing more reliable sync signals
Use 40–45 mc i-f value	Slightly lower cost though harder to align	Reduces oscillator radiation; practically eliminates diathermy and industrial interference
Use intercarrier system	Cheaper tubes; cheaper components	Good if properly designed. Easier tuning, practically no head-end contact noise. Drift almost unnoticeable
Omit one or more sound traps	Appreciable saving	Sound patterns on picture, more service calls
Use multipurpose tubes	Lower total cost of tubes, fewer sockets, less labor	None usually, but harder for servicemen to trace circuits
Use low voltage on c-r 2nd anode	Cheaper high-voltage supply	Dimmer picture; possible blooming and blurred highlights
Use larger picture tube	Higher, but greater sales appeal; fewer service calls	Same effect as low 2nd anode voltage
Use punched metal c-r masks	Cheaper than molded rubber	None. Gives impressive designs, more colors
Use rectangular picture tube	Smaller, cheaper cabinet	None. Good sales feature
Anchor picture tube to chassis rather than cabinet so one man can remove and replace chassis	Easier to test and repair sets in factory, shop and home, offsetting cost of bracket needed	Servicemen can work under chassis without damaging tube; eliminates adjusting coils each time chassis is removed
Use Alnico magnet for focusing	Cheaper than equivalent copper	None at first, but harder to readjust later
Use mechanical adjustments of yoke in place of pots	Appreciable saving	Little or none at first, but possible trouble later as components drift off value; harder to adjust
Use hot chassis with universal a-c/d-c power-supply circuits	Simpler and easier to wire	Dangerous to servicemen and to children poking fingers in set
Provide built-in antenna	Increased sales appeal	None in noise-free high signal-strength areas
Move as many controls as possible to back of set and hide others behind hinged, sliding or drop panel	Higher, but increases sales appeal by making customers think set is simpler to operate; improves appearance	More service calls as some people are afraid to touch essential at-rear controls, while others play with at-rear controls
Use lower-wattage resistors	Slight saving	Can impair performance; increases service calls
Use lower voltage ratings for paper capacitors	Slight saving	None at first; leakage may later affect performance, and breakdowns will increase service calls
Use cheaper output transformer and loudspeaker	Appreciable saving	Less volume, poorer tone, more distortion, more frequent failures hence more service calls
Use thinner gage metal for chassis, with less plating or just thin flash of copper	Lower materials cost and easier to punch	Chassis bends readily, upsetting alignment; easily damaged in handling or shipping; corrodes quickly in humid and salt air
Increase size of chassis	Lower assembly and wiring costs	None. Easier to service because circuits are easier to trace. Less danger of shorts
Put tubes wherever convenient	Simpler wiring, less labor	None, but serviceman must yank chassis to replace tubes that are underneath or crowded in
Provide test terminals or jacks at rear of chassis for servicing	Extra cost offset by easier aligning and troubleshooting both in factory and home	Allows diagnosis of trouble quickly in many cases without removing chassis
Use two equal-value resistors as f-m discriminator load	Extra resistor cost offset by speedup in f-m alignment	Allows serviceman to make direct connection of output meter without unsoldering
Make all fuses accessible without removing chassis	Extra cost offset by easier replacement	Allows quick checking and replacing of fuses blown by temporary line surges
Stamp date-coded serial numbers on all expensive components	Prevents unscrupulous firms from getting free replacement of parts over a year old	Improves manufacturer relations with honest organizations, eliminating need for suspicion of fraud and interposition of red tape
Hold up service manuals on new sets until production changes resulting from field experience have all been made	Saves cost of preparing and sending out notices of production changes or making new edition of manual	Makes repair of early sets difficult or even impossible, losing goodwill of both serviceman and owner of set
Use plastic cabinets	In large quantities, about half cost of comparable wood	None. About $100,000 tooling needed to get 1,000 cabinets a day. Striking styling possibilities
Use metal cabinets	Lower cost because dies are cheaper	Nonwarping, more durable, but almost impossible to repair scratches in finish
Use lighter wood cabinet, fewer glue blocks, less veneer	Cheaper because wood is high proportion of cost	Less durable cabinet, more subject to breakage, warping and loosening of joints
Use cold glue in wood cabinets	Cold glue sets faster hence is cheaper	Cabinet joints are weaker

Engineering Trends in Spot Welder Controls

Techniques for building electronic controls that meet reliability and quick-repair requirements of auto industry assembly lines, and details of six-thyratron timer circuit having potentiometer control of time for each sequenced function of a resistance welder

By

STUART C. ROCKAFELLOW

Robotron Corporation
Detroit, Michigan

PRESENT-DAY automobiles are built on a production basis, with each operation dependent on a preceding. As use of resistance welding increases, maintenance of controls becomes more of a factor in the flow of parts off the lines. The foreman responsible for the output of a particular line insists that the maintenance man keep his equipment in condition so that down time is minimized. Quick service or replacement of faulty control panels is a necessity.

To meet the requirements of the automotive industry, a welder control must be designed and constructed in such a way that a defective unit can be spotted and replaced in a few seconds. The defective unit can then be repaired later, in a more convenient location having the needed tools and test equipment. Factors that must be considered in order to meet these industrial requirements for electronic welder controls will now be taken up.

Quick change of defective units in a control system is essential. Quick-acting fasteners of the quarter-turn type are popular for holding chassis units in position on panels. Interchassis connections are made through husky connectors and plugs. External wiring to the electronic control unit is run to a permanently mounted terminal strip that also has plug-in connections to the chassis units. An entire chassis can thus be replaced in less than a minute, using only a screwdriver. External wiring is undisturbed during the change.

Quick conversion to a different type of operation is a highly desirable feature. If the quality of the metal being welded changes during production it may be necessary to change to pulsation welding in order to break through an oxide or coating in order to weld. This involves a different control that repeats the weld time at regular intervals so as to give several shots of weld current instead of the usual one. With interchangeable timer panels, the same power panel and welder connections may be used to produce pulsation welding, and changeover time is cut to a minimum.

Desirable Accessories

For fast gun welder operations the time required to get the welding points together becomes important. Once the points are together they will have to open only a short distance in order to move the gun to a new position. The use of an extra unit to produce a longer initial squeeze time is desirable. The initial squeeze time then delays the weld firing until the points are closed, and subsequent squeeze



FIG. 1—Simplified circuit of sequence timer for resistance welder. At rest condition is shown, in which V_1 and V_3 are fully conducting and the grid-cathode path of V_2 is conducting



Replacing timer chassis in electronic control system of resistance welder on auto fender assembly line. Entire operation is completed so quickly through use of quick-acting chassis fasteners and cable connectors that operator at left has time for only few puffs on cigarette while waiting for maintenance man to get his welder back into operation

periods may be considerably shorter so that the gun may be dragged along the work. This unit plugs into the regular timer panel.

Two pilot buttons are sometimes used on gun welders to give additional weld time on parts that are heavier and require more current. As the operator moves along the work, he pushes the button which gives the correct duration of weld current. The unit to accomplish this is also plugged into the regular timer panel.

The same type of electronic weld control may be used on a press welder in which a platen moves the parts into position. As the platen reaches position, a limit switch starts the control, which then processes the welder through the sequence. A release delay is necessary to get the guns out of the way before the platen retracts. This additional control is also plugged into the regular timer panel.

Speed Requirements

The limiting factor in the speed of gun welders as used on automotive production lines is the speed at which the welding points will close and open. This is limited by the action of the air valves and the delay in the bleeding of the air lines. As these components improve, automotive welding engineers are quick to ask for faster controls in order to use equipment at the fastest rate possible. They request a minimum time of 2 cycles squeeze (time for the welding points to get together and build up sufficient pressure), 2 cycles weld time (period of time during which current flows through electrodes), 1 cycle hold (time for molten metal to congeal and form a bond) and 3 cycles off (time for valve to open electrodes and move arm to new location). This total minimum time adds up to 8 cycles, which means a speed of 450 spots per minute if all times are minimum. While it seems that this maximum speed may never be used, there are certain conditions where the minimum time for any one

operation may be necessary.

Full-cycle firing becomes more important on fast operations. For instance, the timer may be set on 2 cycles weld time for a fast repetitive operation. If the timer gives 2½ cycles of current there will be 3 positive cycles and only two negative cycles. This will tend to saturate the transformer, with subsequent breakdown. The use of circuits giving full-cycle firing is necessary. This is accomplished by using a resonant circuit. The inductance of the relay coil is shunted by the correct value of capacitance for resonance. As the thyratron passes only one pulse, the capacitor holds the relay closed for the additional half-cycle, insuring full-cycle firing of the weld current.

Electronic Switching

Electronic sequencing becomes essential when operating speed is stepped up. Relays have an inherent delay which limits their speed in changing from one circuit to another. Tubes replacing relays can make a change instantly. Small thyratrons are generally used due to their high current-carrying capacity and ruggedness. In timing circuits these tubes are desirable because the current they control is either on or off. They act more like a complete switch than a vacuum tube. Vacuum tubes depend upon many factors for amount of current flow, one of which is cathode temperature. With varying voltage conditions in automotive plants, fluctuations in heater potential have little effect on the current passed through the smaller thyratrons. The current passed through thyratrons is much greater than through vacuum tubes of similar size. The miniature type 2D21, the metal type 502A and the 2050 types of thyratrons each have an average rating of 100 ma. This is heavy enough so that these tubes can directly control the larger type relays which are used to control the valve and the weld circuit. All the tubes in modern timers are of the same



Example of electron timer having quick-disconnect plugs, book-type hinged chassis, and wide ranges of independent time adjustments for squeeze, weld, hold and off cycles, as required for use with resistance welders on auto assembly lines. Power panel at upper right, used with timer, is replaced by pulling out three plugs and turning three quick-acting fasteners. At lower left is ignitron contactor assembly for resistance welder, showing how plug-in copper-oxide rectifier is replaced. Lower right—plug-in relay

type for easy interchangeability, although some pass only a few ma.

Because of the heavier current required to energize valves and fire ignitrons, octal-base plug-in relays with small pins sometimes fail due to overloading. The trend is toward heavier plug connections rated at 10 amperes continuous duty, which is sufficient for these welder applications. The contacts of the relays are also rated at 10 amperes, and to insure a clean break two of the four poles are connected in series. The heavier currents, which are a major cause of pigtail breakdown, do not pass through the pigtail connections. Only a few milliamperes of current, enough to lock in the timer once the pilot has been closed, pass through the pigtail leads of the relay.

The copper-oxide rectifier units which are used to pass a undirectional flow of current to the ignitors of the ignitrons have in some cases proved troublesome to change. One car manufacturer asked to have these units in a plug-in form for fast change.

Sequence Timing Circuit

An example of a circuit design that has adequately met auto industry requirements for efficiency and reliability as well as ease of maintenance is that of the Robotron model 3B weld timer shown in Fig. 1.

Identical type 2050 thyratrons are used throughout, simplifying the stocking of replacement tubes. Both the control grid and the shield grid may be used for control purposes. At 115 volts anode potential the control grid will hold the tube nonconducting until the grid bias goes below −2 volts. The shield grid is less critical and the tube will fire at about −4 volts shield grid potential. For accurate timing, the control grid is generally used. The shield grid will hold the tube nonconducting with a negative potential but is seldom used for timing.

The thyratron, being a grid-controlled rectifier, will conduct only when its anode is positive. The tube can be rendered nonconductive or blocked if a negative charge is placed on the grid between these positive pulses.



FIG. 2—Water-saving circuit for resistance welder

When the circuit of Fig. 1 is at rest, tubes V_2 and V_3 are conducting, charging weld time capacitor C_2 and hold time capacitor C_3. The squeeze time capacitor C_1 is charged by grid-to-cathode conduction of V_3 through R_5. Capacitor C_5 is being charged to a negative potential at its grid end by grid-cathode conduction of V_5.

When the initiating switch is closed, relay 1 is energized through V_1 and all of the contacts on it are closed. One set of contacts is used to lock in around the initiating switch and the other set to bring the cathode of V_3 to the potential of the L_1 side of the a-c line. The cathode end of R_1 is now at L_1 potential and the charging source for C_1 is removed so it now discharges through variable resistor R_1 for squeeze time.

When C_1 drains to a low enough value, tube V_3 will conduct and pull in relay 2 which starts the weld time. When V_3 conducts, the positive pulses which have previously been used to charge C_2 are effectively shorted to the L_1 side of the line. This brings the anode side of C_2 to L_1 and V_2 is blocked by a negative potential. With V_2 rendered nonconductive, C_2 now drains through variable resistor R_2 to a low enough value so that tube V_4 will finally conduct, giving the weld time.

When V_4 conducts, C_4 immediately charges to a negative potential at its anode side. This places a negative potential on the shield grid of V_5, which stops that tube from conducting, releases relay 2, holds V_3 nonconducting and blocks V_5. With V_5 blocked, C_5 can now drain through variable resistor R_4 (hold time) to a low enough value until V_4 will fire. When V_4 fires, the negative charge on C_5 is fed back to the grid of V_1, blocking that tube and releasing relay 1.

If the initiating switch is held closed, as is done in repeat operation, then as relay 1 opens at the end of the cycle the anode supply to V_1 is broken, rendering that tube nonconductive. This in turn releases the negative bias on V_2, V_3 and V_5 and these tubes immediately conduct, charging C_2 and C_3. As C_5 charges, it blocks V_4, which then allows C_4 to drain to a low enough value through variable resistor R_4 (off time) until V_1 fires again, starting another sequence.

Cooling Water Control

During the summer months the condensation formed around the coils of the welding transformer as they cool is a definite hazard. It is desirable to turn off the water flow as soon as the ignitron tubes and transformer have cooled down sufficiently. This usually takes about two minutes.

Means should be provided to turn on the water supply when the welder is first placed in operation and keep the water flowing as long as the welder is in use. Two minutes after the welder is stopped, the water flow should cease. This is accomplished with the circuit shown in Fig. 2. Closing the welder switch charges the grid capacitor positive as shown. This overcomes the negative bias on the other grid and the tube fires, pulling in the relay which closes the valve. The grid capacitor is of such value that it discharges in about two minutes. As long as the welder is being used, the capacitor is constantly being charged. After the last weld the capacitor drains off and the negative bias on grid 2 takes control, blocks the tube and turns off the relay controlling the water flow. Contacts on the relay are also provided to turn off the flow switch and open the ignitron firing circuit when the day's work is done.

The techniques and circuits herein described are readily applicable to other types of industrial electronic controls. The design principles involved are basic to widespread industrial acceptance of electron tube equipment on factory production lines.

TELEVISION ANTENNA

Convenience and economy are achieved when one transmitting antenna handles two or more closely spaced r-f carriers. Diplexers for such combination feed are impedance bridges having distributed parameter characteristics of coaxial lines. Power from two amplifiers operating at the same frequency can also be added with such devices

TELEVISION DIPLEXERS permit two or more radio-frequency signals to be transmitted simultaneously from one antenna without interaction of the signal generators. They are employed in the majority of television installations in this country to effect the combination of visual and aural carrier frequencies.

Diplexers were developed as a matter of sound engineering and economics: it is more convenient, and less expensive to arrange for one antenna to handle two or more closely spaced radio-frequency carriers than it is to install separate, close, non-interacting antenna systems.

Balanced Bridge

One of the first systems to be tried was the balanced bridge type of diplexer shown in Fig. 1. Both aural and visual outputs are balanced to ground. Bridge arm impedance values are so chosen that aural transmitter voltages will be equal at both visual transmitter terminals; hence, no aural carrier potential exists across the visual transmitter. Similarly, no visual carrier potential will exist across the aural transmitter.

Since the reactive elements must be isolated, they might be constructed in the manner shown, in which the reactance, a less than quarter-wave section, is effectively removed from ground by a shorted quarter-wave section.

If it were possible to make the reactances appear as an open circuit to the visual transmitter, and either a short circuit or extended transmission line to the aural transmitter, the diplexing function would be preserved and the reactances could be eliminated.

Figure 2 shows schematically a modified form of bridge diplexer[1] where bridge reactances are unnecessary. Visual signals are transformed at point *E* from an unbalanced to balanced voltage by the shorted quarter-wave section *E-G*. They are conducted across a short, heavy bar to inner coaxial line *D-H* and are transferred to output line *E-W* with effectively zero phase shift because of the properties of the open, inner coaxial, quarter-wave section. The visual signal, therefore, is placed on the pair of output transmission lines as a balanced, push-pull voltage. Video carrier voltage conducted along line *D-B* to point *A* will be equal to and out of phase with the voltage conducted along *E-C* to *A*. Therefore, cancellation of the visual carrier is obtained at the aural input.

Aural carrier power is equally divided at point *A* and is placed directly on the output lines through impedance transforming sections *ABD* and *ACE*. Ideally, no aural carrier gets into the visual carrier line because (recalling again the zero phase shift maintained by open quarter-wave section *D-H*) both inner and outer conductors of the visual input are at the same aural potential. For proper turnstile feed, one of the output lines is made 90 electrical degrees longer than the other at, usually, the visual carrier frequency.



FIG. 1 Balanced bridge type of diplexer



FIG. 2 Commercial type of balanced bridge arrangement

Slotted Bridge

Figure 3 shows a third type of bridge diplexer, called either a slotted bridge or coaxial hybrid junction[2,3]. This model is about as compact a unit as it is possible to make. Its unique feature is the slotted section which extends from the output lines back a quarter wavelength at the visual carrier frequency. To the aural input the slot makes little difference. It is

DIPLEXERS

By W. H. SAYER, Jr. and J. M. DE BELL, Jr.

Research Division
Allen B. Du Mont Laboratories, Inc.
Passaic, New Jersey



Coaxial hybrid ring or rat-race at lower left of this developmental transmitter adds the power output of two doubler stages

only necessary that the outer coaxial section from outputs to aural input have the proper impedance (37 ohms approximately) to transform the 51.5-ohm sound line to the 25-ohm impedance of the two output lines in parallel.

To the visual input, the slot acts as a balancing section, transforming an unbalanced to ground visual voltage at point 2 to a balanced, push-pull visual voltage at points 1-1. The visual signal sees the output lines in series, or sees their impedance as (for example) $2 \times 51.5 = 103$ ohms.

For proper matching, the characteristic impedance developed between center conductor *a* and the unshorted side of the split conductor must be approximately 73 ohms in the section 2 to 1-1. We might consider the inner coaxial section 2 to 1-1 as two transmission lines in parallel, having conductor *a* in common. One line is short-circuited one-quarter wavelength from the signal source (visual signal at 2) and therefore presents an open circuit to the source, so visual power incident at 2 is transmitted to 1-1 along a transmission line composed of conductor *a* and the unshorted side of split conductor *b*.



FIG. 3—Slotted bridge diplexer



FIG. 4—Voltage standing-wave ratio versus frequency for slotted bridge type of diplexer

Aside from being able to handle present-day transmitter powers (up to 10 kw) the diplexer must meet rather stringent impedance requirements. We should like it mainly to accommodate the video carrier frequency and all video modulation products without noticeable selectivity. In other words, the video input to the diplexer should be almost perfectly matched to the video transmission line over a range of at least 5 megacycles.

Typical plots of voltage standing-wave ratio against frequency for the slotted bridge diplexer are shown in Fig. 4. With output lines terminated in matched 51.5-ohm loads, the visual input (end input) possesses a broad frequency characteristic, having a voltage standing-wave ratio of less than 1.05 in the region of interest (channel 5 in this case). A much narrower characteristic is exhibited by the aural input, which, however, does not have to be broad to meet ± 40-kc aural requirements.

Notching Filters

An entirely different philosophy of diplexing is embodied in the filter type system of Fig. 5.[4] Various coaxial element filter structures have been devised and are generally inserted as shown. The filter in the sound transmitter line passes the



FIG. 5—Diagram of filter type diplexer



FIG. 6—Waveguide hybrid or magic T is useful above 1,000 mc



FIG. 7—Schematic of coaxial hybrid ring or rat-race

aural carrier and is adjusted to reject the visual carrier frequency. A reverse function is performed by the filter in the visual transmission line.

Unfortunately, aural and visual carriers are close together, percentage-frequency-wise, so that filters used are of a sharp cut-off variety. Such notching filters, as they are called, do not present a constant resistance to the video transmitter over the entire visual pass band; consequently, undesirable high video frequency transients appear in the picture, caused by the variation in voltage standing-wave ratio in the cut-off portions of the pass band. Furthermore, a sharp cut-off filter makes broadbanding of the transmitter output stage difficult, if not impossible. It is feasible, however, to insert a compensating network between visual transmitter and filter 1 so that broadbanding the transmitter output is possible, though video transients will still be broadcast.

An advantage of the filter-type system is that only a single transmission line is required to feed an antenna, whereas the bridge-type diplexers require two lines to the radiators. However, the double-output diplexers when combined with a turnstile-type antenna have a much wider bandpass characteristic than filter-type diplexers, and, for this reason apparently, have had much wider acceptance in television installations.

Magic T

If it is desired to have both diplexer inputs appear broad-band, as is the case when power from two low-powered video transmitters is added (one way of obtaining high uhf power), then another form of hybrid circuit becomes applicable. Figure 6 depicts a waveguide hybrid or magic T[6, 7]. This device has intriguing properties and several ingenious uses.

Electromagnetic waves incident on arm *A* will propagate down that arm and into arms *C* and *D* of the T, but because of odd symmetry will not propagate down arm *B*. Similarly, a generator at arm *B*, ideally, will have its power divided equally between arms *C* and *D*, and the even symmetry characteristic of the *B*-arm signal will prevent its transmission up arm *A*. This device could give dual output, and would meet requirements that the signal generators do not interact. However, for necessary waveguide dimensions of 0.35 by 0.7 wavelength, this type of hybrid is practical only for frequencies above 1,000 megacycles. It also requires expenditure of considerable design and experimental effort to get broad-band probe matching and broad-band junction-matching irises. An alternate solution is a simple coaxial equivalent.

Rat-Race

The schematic of Fig. 7 shows a coaxial hybrid ring[6, 7, 8] or rat-race. Characteristics of such a hybrid are properly deduced through an application of network theory combined with a judicious use of matrices. The starting point is to assume a general, 4-terminal device which is both linear and lossless; then in a comparatively short series of steps it is possible to develop the essential theory of the rat-race.

Average circumference is one



FIG. 8—Voltage standing-wave ratio versus frequency at any junction of the hybrid ring in two frequency ranges. Remaining junctions are terminated in 51.5-ohm loads

and one-half wavelengths. Input and output terminals are one-quarter wavelength apart. The circular coaxial line is of constant characteristic impedance equal to the square root of two times the impedance of one of the arms. For the moment consider lines *B*, *C* and *D* to be properly terminated.

If an incident wave of length λ_0 enters the ring at *A*, it will divide equally at the junction. At points *B* and *D*, the subdivided waves, one going in each direction around the ring, arrive in phase with each other, while at *C* they arrive out of phase. If the incident wavelength is the same λ for which the ring is designed, complete cancellation will occur at *C*, and no voltage will exist at this point. Because there is no voltage, we could place any impedance at *C* without affecting the input impedance at *A*. Point *C* may be termed a balance point.

If an incident wave of length λ_1 ($\lambda_1 \simeq \lambda_0$) incident at *C* will produce no voltage at *A*. We have then a desired combination of conditions for a diplexer; that is, a generator at *A* will not be aware of a generator at *C*, and vice versa, provided each source is of the proper frequency. Each output carries half of both aural and visual carrier powers, and here as before, the dual outputs serve to feed a turnstile type antenna.

Figure 8 shows plots of input impedance versus frequency for hybrid rings in two widely separated frequency ranges. Either ring can comfortably handle an entire tele-

vision channel, since each possesses a greater than ten-percent bandwidth taken on the basis that the voltage standing-wave ratio be less than 1.1. This broad-band impedance holds for all terminals of the ring when the remaining connections are properly terminated.

Figure 9 shows assembled and dissembled views of a hybrid ring designed for operation at 611 megacycles. This first development model was, for all practical purposes, just like its schematic. The 51.5-ohm transmission lines connect to the type N fittings at all four arms. Center conductor diameter of the ring was approximately 0.2 inch, and the outer conductor diameter approximately 0.7 inch.

Halves of the outer conductor have been turned in a 12-inch square by ½-inch block of aluminum, and the two blocks when faced together form the complete sheath. The center conductor, 29.16 inches in circumference and rolled from brass, was lined up by Teflon spacers before being soldered to the connectors, and two thin spacers remain in the ring for support.

This particular ring diplexer was to function at 611.5 megacycles—midway between a video carrier frequency of 609.25 megacycles and a sound carrier frequency of 613.75 megacycles. Since the ring is inherently a fixed-frequency device, these departures from design center frequency lead to incomplete cancellation at the balance points, so that a small amount of visual transmitter power gets into the aural transmission lines and vice versa.

Figure 10 indicates the measured percentage of total power which is lost as frequency is varied around the ring's design center frequency. Power lost appears as cross-talk between aural and visual transmitters and in this instance was 27 db less than carrier power at the frequencies of operation, and greater than 20 db over almost a 100-megacycle range.

A 27-db rejection may be considered adequate for television operation, but is not particularly good as far as hybrid ring properties are concerned. That better rejection ratios were possible was demonstrated by a coaxial ring built for channel 5 operation. This second ring was constructed of standard 1⅝-inch tubing with $\frac{7}{16}$-inch diameter center conductor supported on Teflon beads, and occupied a rectangle of about three by six feet. Average sound power of 3.5 kw was fed into the ring loaded by a standard superturnstile antenna system. It was possible to measure only ½ watt at the balance point—a 7,000 to 1 ratio or slightly greater than 38 db. Cross-talk of this small magnitude is more satisfactory.

Power Adding

Another aspect of diplexing, and one in which the hybrid ring may be used more efficiently, is the combining of the outputs of two synchronized power units in order to obtain additive power. Addition of low-powered units is one answer to the problem of obtaining higher powers at ultra and very high frequencies.

Consider Fig. 7 again, and imagine two equal-powered, in-phase generators at *A* and *C*. Signals at *B* from each generator will arrive in phase, and are additive at *B*. Signals at *D*, however, arrive out of phase, since the wave from *A* has to travel 180 degrees farther than the wave from *C*, so cancellation occurs at *D*. The summation of powers from *A* and *C* can thus be extracted at point *B*.

By similar super-position reasoning it may be agreed that if two equal, out-of-phase generators are placed at *A* and *C*, the summation of their powers may be extracted at point *D*, and no power will appear at *B*. Figure 11 shows calculated percentage total power out at one arm as the phase between two equal - powered, equal - frequency generators is varied. Measured powers agree closely.



FIG. 9—Open and closed views of a hybrid ring or rat-race designed for 611 mc



FIG. 10—Percent of power out at balance point plotted against frequency


% TOTAL POWER—ONE ARM
OUTPUT A
INPUT P_B
INPUT P_A
OUTPUT B
POWER OUT AT ONE ARM WHEN P_A OR P_B=0
PHASE RELATION OF TWO INPUTS IN DEGREES

FIG. 11—Percent of total power out at one arm versus phase relation between inputs

References

(1) G. E. Hamilton, Performance Characteristics of the WABD Antenna System, *Communications*, **27**, p 18, July 1947.

(2) G. H. Brown, W. C. Morrison, W. L. Behrend and J. C. Reddeck, Multiple Operation of Transmitter Tubes, *RCA Review*, **10**, p 169, June 1949.

(3) D. D. King, Two Simple Bridges for VHF Use, *Proc. IRE*, **30**, p 37, Jan. 1950.

(4) L. R. Krahe, A Single-ended Television Diplexer, Paper Presented at National Association of Broadcasters Engineering Conference, Apr. 8, 1949.

(5) W. A. Tyrrell, Coupling Arrangement for Use in Wave Transmission Systems, U. S. Pat. No. 2,445,895.

(6) W. A. Tyrrell, Dielectric Wave Guide Coupling Arrangement for Use in Two-Way Signaling Systems, U. S. Pat. No. 2,445,896.

(7) C. G. Montgomery, "Microwave Measurement Techniques," Ch. 9, M.I.T. Radiation Laboratory Series, Vol. 11, McGraw-Hill Book Co., New York, N. Y.

(8) G. H. Brown, Antenna System, U. S. Pat. 2,397,645, Fig 1.

Bibliography

C. Gilliam, The Diplexer, *Wireless World*, LVI, 3, p 88, Mar. 1950.

TESTING TURNTABLES

Equipment being used to test a standard production turntable

By R. O. MAZE
Project Engineer
Bendix Radio Division
Bendix Aviation Corp.
Baltimore, Md.

THE INSTRUMENT to be described allows rapid testing of record players in production quality control for speed, extent of fluctuations in speed, and magnitude of unwanted low-frequency outputs. The equipment required includes a standard nominal 1,000-cps recording.

Controls are arranged in such a manner as to facilitate easy understanding of their function by ordinary personnel. All measurements made are based on a single reference-voltage setting, which allows them to be taken consecutively by merely moving the function switch to the desired position. A push-to-read switch is provided on the wow scales to prevent the delay that might otherwise be caused by the effect of switching transients on the long-time-constant circuits involved.

The design is unique in providing a means for measuring the relative amplitude of the spurious low-frequency output or rumble of the record player in the same instrument with wow and rpm measuring equipment. The use of a heterodyne method for making wow and rpm measurements greatly increases their accuracy.

Measurement Methods

Percentage wow is expressed as the maximum (peak) variation of turntable speed in terms of the average speed. Mathematically,

$$\text{percentage wow} = \frac{\text{Max. speed} - \text{min. speed}}{\text{average speed}} \times 100$$

Since a standard tone recording is used with the device, the above equation may be written in terms of the maximum and minimum frequency of the tone output.

$$\text{percentage wow} = \frac{f_{max} - f_{min}}{f_{avg}} \times 100$$

It was found convenient to express wow in terms of the output frequency of the recording at the nominal turntable speed. This eliminates a step in the wow measurement and results in errors that are not significant in production-line work. If desired, the wow readings may be corrected by multiplying by nominal speed divided by actual speed. The actual speed is read on the rpm scale.

Rumble is defined as the level of spurious low-frequency output caused by hum and vibration expressed in terms of the output from a standard nominal 1,000-cps recording. Revolutions per minute (rpm) scale calibration is in terms of the 78-rpm recording, but can be interpreted in terms of 33⅓ or 45-rpm recording.

The actual frequency of various standard tone records was found to vary from the nominal value. Therefore, a commonly available recording, the RCA No. 84522B (12-5-7C), was chosen for use with the device. The actual frequency of this recording is 1,013 cps when the turntable is revolving at a speed of 78.26 rpm. Calibration in terms of other standard recordings may be made by resetting the meter calibration resistors. This operation can be simply accomplished.

The accuracy obtained in the wow measurement is ± 0.1 percent up to 2-percent wow, and ± 5 percent of scale reading above 2-percent wow. Speed indications are accurate to ± 0.25 percent. Rumble indications are correct within 0.5 db at 100 cps.

The accuracy and repeatability of the wow and rumble measurements are such as to make the equipment eminently suitable for use in engineering work. For rumble measurements alone, the single instrument replaces several other pieces of test equipment including an attenuator, two filters, and a vacuum-tube voltmeter. The shielding provided is much more reliable than that generally obtained if several pieces of equipment are used. Previous to the construction of this instrument it was difficult to obtain a consistent reading of rumble from one day to the next even when the same

for Wow, Rumble and Speed

Equipment contained in a single cabinet is used for rapid testing of record players on production line. Signal is obtained from standard test record. Indications of the various characteristics are shown directly upon a calibrated meter

pieces of equipment were used. Now, readings that have been taken over a long period of time agree within 0.5 db.

The measurement of wow is of particular interest to the turntable manufacturer. It is also of importance to the radio-phonograph engineer who is charged with selection of a turntable that will allow reproduction of recordings with the quality desired. The presence of 3-percent wow is not particularly objectionable to the untrained listener when listening to some recordings. When listening to other recordings, especially when prolonged tones are presented, the presence of wow greater than 1 percent is detectable. Of course, the presence of wow even at levels lower than 1 percent may be undesirable in reproducers intended for studio work or, in any case, where high quality is important. The particular maximum level considered satisfactory will therefore vary with the application, but up to 1.5 percent is usually acceptable for radio-phonograph use.

Common Trouble Sources

The causes of wow have been ably discussed[1] and will be mentioned



Complete schematic of the wow, rumble and speed meter showing the modified tuning-fork oscillator with ceramic pickup (lower left) and voltage-regulating transformer (lower right) that is recommended for industrial use

only briefly here. Eccentricity of the turntable will cause wow to occur at the turntable speed—for example, 1.3 cps for a 78-rpm turntable. Warpage of the turntable surface will cause wow at this frequency also. Some types of warpage might theoretically cause wow at other than the fundamental frequency except for the fact that the record disc is a relatively unyielding surface and will prevent higher frequency wow from being produced from this source.

Any standard recording used must be of good quality and itself be free from warpage. The 1,000-cps standard recordings in common usage meet these requirements. Careful handling of the recordings is required.

Wow may occur at other frequencies owing to the motor drive-pulley arrangement. High-frequency wow components or flutter will be attenuated because of the turntable inertia to an extent depending on the frequency, the turntable inertia, and the stiffness of the coupling involved. In general, it was decided that wow components at frequencies above 30 cps were negligible. The wow caused by wobble of the drive pulley or by a slick spot on the drive pulley will occur at frequencies of roughly 7 to 15 cps in the usual record-player mechanism.

A wow output jack is provided on the instrument so that the waveform of any speed variation can be observed by use of an oscillograph. Observation of this waveform will afford a clue as to the source of the trouble. At the fundamental frequency of the turntable, for example, it must be produced by defects in the turntable itself as noted above. If the wow occurs at some higher frequency it may be traced to the motor shaft, or to the coupling mechanism. An erratic source of wow will be observed as such and might be traced to slippage of the coupling mechanism or to end play in some rotating part.

Input Circuit

The input impedance was made about 5 megohms in order to insure proper operation with high-impedance pickups. The input voltage may be any level from 0.1 to 5 volts rms. All measurements may be made at input levels as low as 1 millivolt rms except that the measurable rumble range will decrease to only 6 db below the reference signal.



FIG. 1—Frequency response (A) on the reference and rumble scales and response (B) on the wow scale with 3-percent wow input (B)

Frequency response of the reference and rumble filters is shown in Fig. 1A. The procedure for measuring rumble is first to set to a reference level by adjusting the continuously variable control in the input to produce a meter indication of the reference level. Then the 1,000-cps band-pass filter is switched out by the function switch and the 150-cps low-pass filter is switched in. The meter will now indicate the rumble level in decibels above or below the 1,013-cps reference signal. A step attenuator in the input stages allows the range of the rumble indication to be extended to 46 db below the reference level. A representative phonograph pickup may have a rumble level of −20 db. Rumble levels will not ordinarily be lower than −26 db.

The 1,000-cps band-pass filter is used when the reference level is set. This setting allows rumble levels to be measured that approach the level of the standard tone. The use of the filter when metering wow prevents spurious indications from being obtained due to the presence of low-frequency components encountered in the rumble.

The meter amplifier is a two-stage amplifier with negative feedback stabilization. The meter is placed across the output of this amplifier in the reference and rumble positions of the function switch.

When metering wow and rpm the output of the amplifier is fed into the mixer. Here it is heterodyned with the output of the 857-cps tuning-fork standard oscillator shown in the lower left corner of the circuit drawing. The difference frequency is distorted and used to trigger a one-shot multivibrator. This multivibrator has constant pulse length at all trigger rates. The plate current of the section that is nonconducting in the stable state is proportional to the difference frequency between the tone recording output and the 857-cps oscillator. The rpm metering is therefore accomplished by measuring the plate current in this section of the multivibrator.

Among the methods that have been previously used for wow detection are the use of a discriminator[2], and the use of pulse counter circuits.[3] The latter method was selected as being most satisfactory for use in this instrument because of the difficulty of producing a stable linear discriminator of suitable bandwidth for these frequencies. The pulsed output of the rpm multivibrator is fed through a cathode follower into a 30-cps low-pass filter. The output of this filter is directly proportional to the input frequency and reproduces variations in this frequency occurring at rates below 30 cps. This output waveform that represents the wow of the turntable is metered by means of a peak-reading vacuum-tube voltmeter circuit. The wow voltage is also fed to an output jack so that the actual waveform of the speed variations may be observed or recorded. The frequency response of the wow metering circuit is shown in Fig. 1B.

References

(1) U. R. Furst, Periodic Variations in Pitch of Sound Reproduction by Phonographs, *Proc. IRE*, 34, No. 11, Nov. 1946.

(2) C. R. Miner, "Wow Meter", Vol. 2 of "Measurements Equipment and Technique" General Electric Meter and Instrument Div., West Lynn, Massachusetts.

(3) Type 1170-A FM Monitor for Broadcast and Television Service, *General Radio Exp.*, Oct. 1947.

High-Frequency Operation of TRANSISTORS

Discusses factors contributing to loss of gain in transistor amplifiers at high frequencies. Explains use of magnetic bias to reduce transit time and transit angle dispersion to extend range. Gives circuit and data on 23-mc amplifier with gain of 8

By C. BRADNER BROWN

Chief, VT Fuze Division
U. S. Naval Ordnance Laboratory
Silver Spring, Maryland

IN ORDER TO UNDERSTAND the reasons for loss of high-frequency gain in transistors it is necessary to review briefly the fundamentals of conduction in semiconductors. Since presently available transistors use N-type germanium, only this material will be considered.

Conduction can take place by two mechanisms. Electrons may be transferred from one electrode to another as free electrons. This is the manner in which most metals conduct. A second method consists in removing an electron from a bound state at the positive electrode in which case the hole migrates to the other electrode, constituting a current. Both types of conduction can take place simultaneously, but since N-type germanium has a preponderance of free electrons in the bulk state, recombination takes place between holes and electrons, the former having a life of approximately 2×10^{-7} second[1].

The basic action by which the transistor amplifies can now be stated in a simple manner. The collector is operated at a high negative voltage, that is, 10 to 50 volts. Most of this potential drop takes place within a very small region around the collector contact, by reason of the barrier layer which impedes the flow of electrons from the metal to the semiconductor. Holes are injected at the emitter at a low voltage (0.03 to 0.3 volt) and under the influence of the field due to the collector current move to the collector, where they lower the barrier layer height, causing an increase of collector current.

Transit Time

It is apparent that the transit time between emitter and collector will be controlled by the internal field strength in the crystal. Since the collector current is large compared to the emitter current, the field strength will be largely a function of the resistivity of the germanium and the collector current. Bardeen[1] presented a theoretical relationship from which

$$T = \frac{2\pi S^3}{3 U_h \rho I_c}$$

where T = transit time, S = spacing, U_h = hole mobility, ρ = resistivity and I_c = collector current. An examination of the geometry of the type-A transistor shows that since all holes do not flow over paths of the same length, a dispersion in transit time results in a diffuse transit angle. This has the result of reducing the average value of collector modulatior and is the primary cause for loss of high-frequency response.

The most important element in



Magnetic bias of 16,000 lines per square inch is provided by the small magnet visible in center compartment of the 23-mc transistor amplifier



FIG. 1—Transistor characteristics show gain for short-circuited output [4] for various electrode spacings (A), collector currents (B) and bulk resistivities (C) as a function of frequency

determining the frequency response of type-A transistors is spacing, since it appears in the transit time expression as a cube function. Figure 1A shows the variation of α (current gain for short-circuit output) as a function of frequency. The spacings are taken from center to center of the electrodes, which are approximately 1 mil in diameter. Spacings less than 2.5 mils are not usable in the present design of transistors, and it is evident that high-frequency operations require the use of the minimum practical separations.

Since the internal field strength, accelerating the holes from emitter to collector, is proportional to collector current it would appear desirable to use the highest practical collector current. Figure 1B shows the variation of α with frequency for a family of collector currents. It has been found that currents of about 5 milliamperes are the maximum values that can be used without introducing instability due probably to overheating of the collector contact.

One of the most important variables in frequency response, one that has not been well controlled in presently manufactured transistors, is the bulk resistivity. Figure 1C shows the effect of this factor on α as a function of frequency. Since these measurements were made on different transistors chosen for bulk resistivity as the variable, the value of α has been normalized.

It has been established from the data presented that a high-gain—high-frequency transistor must have small emitter-collector spacings, small contact areas, high bulk resistivity and must be operated at the highest practical collector current.

Magnetic Bias

A recently discovered method[4] of extending the high-frequency range



FIG. 2—Frequency range of transistors may be extended by applying a magnetic bias of the proper sign at right angles to the plane of the electrodes

consists of applying a magnetic bias of the proper sign at right angles to the plane of the collector and emitter as shown in Fig. 2. This field acts in such a manner as to beam the emitter and collector currents along a more direct path. While it does reduce transit time, it also reduces the transit angle dispersion and thus increases the frequency range.

Figure 3 shows a typical result using plus and minus magnetic bias fields. Not all transistors respond to the bias field in the same way, and more experimental work is in progress to determine the details of the effect.

It has been found that transistors having wide spacings show larger increases in α than those with small spacings and that transistors having small contact areas show higher values of α when magnetically biased. Thus the magnetic bias not only increases α at high frequencies but also decreases the variation between transistors.

Circuit Considerations

A handy circuit representation of the transistor at high frequencies can be obtained using a three-terminal network having one generator as shown in Fig. 4, where R_s is the input resistance, R_s the coupling resistance and R_c the collector resistance. Capacitor C_c is the barrier-layer capacitance and C' the emitter-collector contact capacitance. The generator current may be represented by $i_c \alpha, \phi, R_c$



FIG. 3—Gain response curves show importance of proper direction of magnetic bias field

where i_e is the a-c input current, α_f the short-circuit current gain at frequency f, and ϕ_f is the phase shift with frequency f.

It is evident that the input impedance will depend largely on the load current flowing through R_b. At low frequencies this current is opposed to the input current i_e, and acts as a positive feedback. At higher frequencies the phase shift in α causes the input impedance to become complex and at very high frequencies, phase shifts of nearly 180 degrees will increase the input impedance. It should be remembered that complex load impedances obtained when tuned collector circuits are used will alter this condition. The collector impedance likewise can vary greatly due to feedback. At low frequencies, this positive feedback characteristic of a transistor reduces the collector impedance but at higher frequencies it becomes dependent on the input impedance which may be complex if tuned inputs are used. The barrier layer capacitance C is of the order of 1 $\mu\mu$f in the type A transistor and C_c is somewhat less, varying with collector voltage. The coupling resistance R_b does not change much with frequency but is a function of both emitter and collector current.

From the foregoing, it is apparent that care must be taken at low frequencies to insure sufficiently high input and output impedances to reduce the positive feedback. Much of the lack of d-c stability can be traced to inadequate coupling impedances. It is desirable to have both input and output impedance high at all frequencies both in and outside the amplifier passband, but some compromises must be made in order to obtain sufficient gain.

Design of a 23-mc Amplifier

The problems of high-frequency operation of transistors are best exemplified by examining a particular design. Figure 5 shows the circuit diagram for a 23-mc amplifier used for testing the high-frequency response of transistors.

Shunt feed of both the emitter and collector currents was used to insure high d-c stability. Since the emitter current was only 0.4 ma, it was possible to use a high value of emitter bias coupling resistance without unduly high bias voltage. In the collector or output network, L_c, C_c, L_c, C_c constitute a band pass whose impedance is high at frequencies in the pass-band and remote from the pass-band. There are minima however on both sides, and some difficulty may be encountered if overall phase shifts are such as to satisfy the conditions for oscillation.

Transistor amplifiers should always be designed for high-impedance outputs, tapping the diode down on L_c to meet the requirements for diode load resistor matching. Since the emitter is a current-fed element, the input impedance must be kept low at the frequency of amplification and high at all others. This can be satisfied in most cases with a series tuned input network if necessary to prevent oscillation at frequencies outside the pass-band.



FIG. 4—Three-terminal representation of transistor at high frequencies



FIG. 5—Circuit of 23-mc amplifier used for testing high-frequency response of transistors



FIG. 6—Frequency response of amplifier circuit shown in Fig. 5

Figure 6 shows the frequency response of the amplifier. The input impedance is approximately 1,000 ohms at 23 mc. The output impedance of L_c C_c was 16,000 ohms, thus the gain between 1,000-ohm input and output would be 8. This results in a gain bandwidth of 8.8 mc.

The transistors used with this amplifier had bulk resistivities of greater than 30 ohm-cm and spacings of 2 mils between emitter and collector. It should be noticed that present manufacturing methods lead to relatively few transistors which satisfy these requirements. However, it appears reasonable to expect that experience with manufacturing methods will allow the manufacturer to supply transistors within these specifications. The small magnet used gave a field strength of 16,000 lines per sq in. Slightly higher gain could have been obtained on most transistors if more field strength were available.

The stability with time was very good. No changes in gain of more than 5 percent were noticed for any given transistor over a period of several weeks of operation. Emitter voltages were not critical, and could be varied by 30 percent with very little change in gain. The collector voltage controlled the gain by varying the collector current, hence this voltage must be regulated to the same extent to which it is desired to hold the gain. This suggests that ave in this type of amplifier can be obtained by control of this voltage through auxiliary circuits.

The temperature stability was good for most of the transistors tested over the range from 40 F to 120 F. The d-c collector potential (E_c) at 120 F, however, is reduced to less than ½ the value at 40 F since the d-c collector resistance falls sharply at the higher temperatures. This results in lower maximum power output and reduced maximum voltage output at 120 F.

References

(1) J. Bardeen, *Phys. Rev.*, p 1,225, 75, Apr. 15, 1949.
(2) C. Bradner Brown, *Phys. Rev.*, p 1,736, 76, Dec. 1, 1949.

Modulated-Light DENSITOMETER

Instrument for determining reflectivity and density of materials with low light intensity. An incandescent dial light is 100-percent modulated at 20 cps by a two-tube multivibrator-amplifier circuit. Reflected or transmitted light produces 20-cps phototube signal which is amplified by circuit which passes 20 cps but rejects 120-cps signals

By HENRY P. KALMUS and MILTON SANDERS
Washington, D. C.



FIG. 1—Circuit shown in (A) excites dial light with 20-cps square wave to produce a 20-cps sinewave modulation of light output, as shown in (C). Operation is shown in (B)



FIG. 2—Terminal impedance R_T seen by phototube is 25 megohms

IT IS USUALLY DESIRABLE to keep the sensitivity of a light-measuring device as high as possible. High sensitivity permits the transmission or reflection coefficients of high-density and low-reflectivity materials to be measured with a small amount of light impinging on the medium. This is especially advantageous for chemical or biological applications where an excessive amount of heat would be detrimental to the specimen.

There are three basic light-measuring techniques: a light-sensitive element in conjunction with a d-c amplifier, a phototube whose output is periodically interrupted and applied to an a-c amplifier, and a phototube whose light input is periodically interrupted and whose output is applied directly to an a-c amplifier. The latter method combines two advantages. First, it eliminates the need for successive stages of d-c amplification, with their inherent instability and need for constant adjustment; and secondly, it reduces the average amount of light that falls on the medium, if the light is chopped at its source.

Another requirement for a good light-intensity meter is a stable zero reading in the absence of light; and if compensation circuits are provided the zero adjustment should have long-time stability. Also, the instrument should not have to be used in a dark room, nor should the optical path require shielding from background light. And it is desirable that the instrument be unaffected by such phototube characteristics as dark current and leakage.

The instrument described here employs an incandescent light source which is excited by an a-c current of such frequency and waveshape that 100-percent sinewave light-output modulation can be obtained. The average light flux is held constant and is independent of line-voltage fluctuations. The frequency of the light-flux modulation is a subharmonic of line frequency, giving sufficient stability so that sharply-tuned filters can be used. The instrument is devoid of leakage and dark-current effects, may be used in a normally lighted room, and no zero adjustment is necessary.

Light Modulator

It was found that a 20-cycle square wave produces 100-percent light-output modulation in a bulb of the GE 104 type. This is a conventional dial light, dissipating 6 watts at 125 volts. Figure 1A shows the light-modulating circuit. The 6SN7 is used as a multivibrator with the grid of one triode directly coupled to the grid of a 6V6. Resistors R_1 and R_2, together with the coupling capacitors C_1 and C_2, determine the frequency of the multivibrator which is set to 20 cps. The grid of V_1 is returned through R_1 to



FIG. 3—Complete schematic of photometer portion. Filament voltage for 1L4 is obtained through dropping resistor from B supply

one side of the filament to derive a 3-v rms 60-cps signal for synchronization at the third subharmonic of the line frequency.

Figure 1B shows the operating conditions for the modulator on the i_b-e_c characteristic for the 6V6. With the constants chosen, the pentode is driven from cutoff to a value of 100 ma at 20 cps.

The voltage on the grid of the multivibrator oscillates about an average value, close to the cutoff value of the 6V6, in such a way that only the square-top portion cuts into the conducting region of the pentode. The pulse shape is square and was found to be best for sinusoidal light output from the bulb. The average plate current is 50 ma—well within the long-life operating rating of the lamp.

The light output of the lamp is made independent of line-voltage changes by making use of the fact that if the pentode screen voltage is kept constant, the plate current is independent of the plate voltage. Furthermore, the multivibrator is unaffected by line-voltage changes because the gain of a triode of the 6SN7 type, terminated by a high-resistance plate load, is constant. The lamp can be inserted in the cathode of the pentode with the proper choice of circuit constants if it is desirable to have one side at ground potential.

Figure 1C is a plot of one cycle of the light output produced by the lamp as measured by high-speed motion picture camera technique. The light output very closely follows a sine wave. Measurement of the a-c light output, simultaneously with the average value, shows that well over 90-percent modulation is obtained. Of course, more or less modulation can be obtained by limiting the spectral range covered, increasing or decreasing the driving voltage and hence the average temperature, or by use of a bulb with different luminescent and nigrescent characteristics.

20-cps Photometer

In designing a light-measuring instrument for use with the 20-cps modulated light source, many factors must be considered. The amplifier must have sufficient sensitivity at the signal frequency to provide adequate deflection of the indicating instrument, but it must also be capable of rejecting extraneous signals.

The useful sensitivity of any instrument is determined by the signal-to-noise ratio. Modern phototubes have a very small dark current so that most of the noise is of a thermal nature, generated by the resistor terminating the phototube.

The input signal is an a-c voltage with a well defined frequency and phase. The noise, however, is a random effect with a definite rms value. There are two ways to obtain high sensitivity: a selective amplifier followed by an averaging detector, or a broadband amplifier followed by a phase-sensitive detector. In both cases, the signal-to-noise ratio depends on the allowable time of observation. If, for instance, the bandwidth of an amplifier is 1 cps we have to wait at least 1 second until the voltage at the rectifier has been built up to its terminal value. If a phase-sensitive detector is employed, the integrating network after the rectifier has to have a time constant of one second, for the same signal-to-noise ratio.

Figure 2 shows the input circuit of the amplifier. The d-c load resistor of the phototube is R_1, and R_2 is the biasing resistor of the first amplifier stage. The coupling capacitor C has a negligible impedance for the signal frequency. The phototube is, therefore, terminated by a resistance R_T consisting of R_1 and R_2 in parallel. If k is the phototube constant in microamperes per lumen, L_m is the average value of a sinusoidally varying light flux in lumens, and R_T is the dynamic input impedance in megohms, the input voltage for the amplifier is:

$$E_s\,(\text{rms}) = \frac{k\,L_m\,R_T}{\sqrt{2}}\ \text{volts}$$

An instrument designed in such a

way that $L_m = 5 \times 10^{-7}$ lumen produces full scale deflection of the indicating instrument, k is 20×10^{-6} amperes per lumen and $R_f = 25$ megohms, will have an input voltage of $E_i = 177$ microvolts.

If the bandwidth of the amplifier is Δf cycles per second, the noise voltage at the amplifier input is E_n (rms) $= 1.3 \times 10^{-4} \sqrt{\Delta f}\ R_i$ which for a bandwidth of $\Delta f = 1$ cycle per second is E_n (rms) $= 0.65$ microvolt. If the meter at the amplifier output shows a deflection of 1,000 μa for an input voltage of 177 μv, the required amplifier gain is $G = 5.65$ μa per μv. The rms value of the meter current produced by noise is therefore $i = E_n G = 3.65$ μa.

This current appears as a series of pulses which occur at random rate with random amplitudes. If the bandwidth is 1 cps, the pulses are spaced by about 1-second intervals so that the needle is well able to follow them. The amplitude of the majority of the pulses is identical with the rms value of current. However, theory shows that a few percent of the pulses have four times this amplitude, which was found to be in good agreement with experimental results. The noise produces, therefore, needle deflections with an amplitude of 1.6 percent of the full meter scale and the signal-to-noise ratio is thereby determined.

These fluctuations can be avoided by mechanical damping in the meter or by an R-C filter as shown in Fig. 3, provided that the time of response is not important. The error in the reading due to noise nevertheless is not removed. An improvement in signal-to-noise ratio by a further increase in Q, and hence a decrease in Δf, would make the instrument too sluggish and is impractical; however, since signal voltage increases linearly with the input terminal resistance R_i whereas the noise voltage increases as $(R_i)^{1/2}$, a gain in signal-to-noise ratio can be obtained by increasing R_i.

Tuned Amplifier

Experiments were conducted with a phase-sensitive detector circuit and compared with the tuned amplifier to be described below. The superiority of the tuned amplifier was demonstrated in a series of exhaustive tests.



FIG. 4—Second stage of signal amplifier contains this 20-cps parallel-T feedback network

If the signal to be amplified is in the low-frequency range, say 20 cycles, it is impossible to obtain narrow-bandpass filters with conventional resonant circuits containing inductance and capacitance. For such low frequencies, however, circuits with only resistors and capacitors are available which give the desired bandpass characteristics. One of the best solutions is the use of a parallel-T network as a negative feedback element.

Figure 4 shows one amplifier stage in which a parallel-T network is used as a degenerative feedback element. The network has zero transmission for a frequency f_0 if the parameters are chosen as shown. Thus no degeneration exists at f_0. At all other frequencies, the gain of the amplifier is reduced. The steepness of the frequency response depends on the terminating impedance. If the amplifier is controlled from a voltage source with an internal impedance which is small in comparison with the output impedance of the network, a resistor R_i has to be inserted. The value of the biasing resistor R_g can, of course, be kept high enough to avoid any damping effect on the network.

A 6SJ7 pentode is used as the amplifier. The network was tuned to 20 cycles.

If the tube is used as a straight amplifier, a gain of 240 at 20 cycles is realizable. With the network connected as shown, this gain is reduced to 108. Figure 5A shows the relative response characteristic of the stage with feedback. The bandwidth at the half-power point is less than 1 cycle per second. It should be noticed that the frequency selectivity curve is steeper than that which could be obtained if a tuned L-C circuit at 20 cps were used as the plate load. The steepness of this characteristic depends on the matching of the resistors and capacitors and a Q of 25 or better can be obtained with 2-percent components.

Any attempt to include more than one stage in the parallel-T feedback circuit requires an extremely linear phase characteristic in the amplifier in order to avoid a change from negative to positive feedback at very low or very high frequencies. This demands that the amplifier response be flat down to frequencies less than one cycle per second. If conventional R-C coupling is used, the coupling capacitor and cathode bypass capacitor become prohibitively large.

Overall Circuit

Figure 3 shows the complete circuit diagram of the light-intensity meter, whose design was based on the above considerations. A four-stage amplifier is used with a parallel-T network across the second tube. The phototube is terminated dynamically by a resistance of 25 megohms. The phototube plate voltage is supplied through 50 megohms and a second 50-megohm resistor is used as biasing resistor for the first stage. The instrument is designed to give full deflection in a one-milliampere meter for a light flux of 5×10^{-7} lumen. This corresponds to an input voltage at the first grid of 177×10^{-6} volts.

The input level to the first stage is so low that the stray voltage from the 6-volt heater supply of an indirectly heated tube can be harmful. Consequently, a filament-type input tube connected as a triode is used. The heater current of 50 milliamperes is derived from the B+ power supply. A bias voltage of 2.5 volts is obtained by inserting a 50-ohm resistor between filament and ground. This bias is of extreme importance since grid current must be avoided to prevent reduction of the dynamic load resistance of the phototube. An active parallel-T network tuned to 120 cps is inserted between the first and second stages to eliminate the 120-cycle modulation due to artificial light.

Figure 5B shows the relative response characteristic of this network. The gain of the first stage including the 120-cycle attenuation network is 2.6.

For many applications, the phototube has to be housed in a separate search unit. If a shielded cable is used between the terminating resistor of the phototube and the amplifier input, microphonic effects make the handling of the search unit impractical. If the cable is tapped just slightly, voltage surges are produced which cause fluctuations of the meter needle. It was first thought that these surges were due to capacitance changes in the cable. Later, however, it was found that the surges exist even with no voltage supplied, and it is felt that the effect is probably of a piezoelectric nature. These difficulties can be avoided by including the first triode in the search unit. The output impedance of the tube is so low that any shielded cable can be used.

A barrier-layer photo element can be employed instead of the phototube, so that a wider spectral response is obtained. In addition, the photo element is a low-impedance generator and can be coupled to the grid of the first amplifier stage by means of a transformer. Leads from the element to the transformer are insensitive for hum pickup and microphonic effects. The transformer is mounted in the main amplifier chassis, so that the search unit becomes very small since now it has to contain only the photo element.

A calibrated volume control P_1 is inserted between the first and second stages. This control must be inserted here if the instrument is to have a full-scale sensitivity range of 1,000 from 0.5×10^{-6} to 0.5×10^{-3} lumen. This means then that the input voltage varies from 177×10^{-6} to 177×10^{-3} volt and the input to the second grid varies from 0.460×10^{-6} to 0.460 volt.

If the second stage has a gain of 100, it must be capable of delivering 46 volts undistorted. This is not practical if we wish to maintain a high degree of linearity in spite of deterioration of tube characteristics. If the volume control is used as shown, the voltage at the grid of the second stage will never exceed 0.460×10^{-3} volt. It is clear that even the highest light input will not cause overloading of the first grid since this corresponds to 0.460 volt.

Meter Rectifier

Special care must be taken in designing the rectifier. The meter must indicate the average output voltage in order to maintain a good signal-to-noise ratio. The circuit should be linear over above twice the useful range so that accurate calibration can be maintained in spite to tube ageing. If diodes are used, the contact potential will cause a reading of the meter in the absence of signal. This reading can be made negligible, about 0.5 percent of full scale, by reducing the filament voltage. This is accomplished by inserting a 7-ohm resistor in the filament circuit.

Figure 3 also shows the circuit of the rectifier which uses a double-diode 6H6. It is preceded by two amplifier stages with 20-db negative feedback from the diode output to the cathode of the first of these stages. A one-milliampere meter with 70 ohms resistance is used, and a voltage of 23 volts at point P_3 produces full-scale deflection. At point P_2, 40×10^{-3} volts will produce full-scale deflection. The overall relative frequency response curve of the instrument is shown in Figure 5C. The half-power bandwidth is about 1 cycle per second, and the effect of the active 120-cps network is indicated by the 98-db dip at 120 cps. The 0-db point at 20 cps represents an input of 177×10^{-6} volt.



FIG. 5—Individual parallel-T network responses are shown in (A) and (B). Overall response curve (C) shows 98-db dip at 120 cps, which permits use of instrument in normally lighted room

Conclusion

The overall voltage gain of the amplifier is 150,000. This is a small value for a high-sensitivity instrument, but the high-efficiency system of modulation used makes it possible to obtain full deflection of the meter with a light flux of only 0.5 microlumen. There are no special problems with regard to feedback so that the location of components and the choice of ground connections are not critical.

The instrument needs no zero adjustment since with no incident light there is no signal developed. Furthermore, the 98-db rejection for 120 cps makes possible the use of the instrument in a normally lighted room.

The compactness of the search unit, especially in the case when a barrier-layer cell is used together with the stable high sensitivity and linear output, makes the instrument particularly useful in the biophysical field for such purposes as oxymeters and shadow cardiographs. An instrument similar to the one described has been constructed by S. Guilford of the National Bureau of Standards to be used as a hemoglobin densitometer in cardiovascular diseases research at Walter Reed Hospital.

For applications in spectral densitometers, the advantage of the wide spectral response of the barrier-layer cell can be obtained without the disadvantage of having to use rotating shutters, time gates or stabilized power supplies.



Arrangement of mirrors and camera pickup at left enables operator to look into six furnaces at a glance on remote monitor screen at extreme right

Closed-Circuit Industrial

Wired system employs new type image dissector with translucent cathode that permits use of wide-angle lenses. Three cables carry sync pulses and video signal to remote monitor, which may be up to 1,000 feet from the camera. Resolution is 300 lines per inch

By ROBERT W. SANDERS*
Capehart-Farnsworth Corporation
Fort Wayne, Indiana

INDUSTRIAL APPLICATIONS of television are constantly increasing in number and importance. The equipment to be described was originally designed for power plant use where a need for remote viewing of the boiler water level at the control room was necessary. It later became apparent that other industries have as great, or even greater, need for such a system, so the Utiliscope was designed as a universal system. It has a standard 4-to-3 aspect ratio, and the vertical and horizontal resolution is 300 lines, as shown in the test pattern of Fig. 1.

Main Components

The three component units of the industrial system are shown in Fig. 2. The camera pickup unit uses an image dissector tube whose advantageous characteristics are as follows: (1) It is an instantaneous-type tube, thus no shading compensation is necessary. (2) The tube has no heater, hence it is extremely rugged and its life is not limited by the filament or thermionic emission. (3) The gamma of the tube is unity and linear over extreme contrast ranges. (4) The tube uses an eleven-stage electron multiplier which is not subject to microphonics and will deliver a video signal of approximately ½ volt in amplitude. (5) The spectral response of the dissector is such that it peaks in the near infrared (approximately 8,000 angstroms) sector of the spectrum.

Because of these advantages, particularly the instantaneous characteristics and high video output, the Utiliscope is reliable and simple to operate. Simplicity of operation is of major importance in industrial television applications. Another important requirement, continuous operation with low service time, is accomplished by using a minimum number of tubes in the overall system. The complete system requires only fifteen standard receiving type tubes plus cathode-ray tube and image dissector.



FIG. 1—Test pattern sent by industrial tv system shows 300-line resolution

The camera unit is connected through a multiple-conductor cable to the power unit. These units may be separated by as much as twenty-five feet. This sending end is then coupled by three coaxial cables to the monitor, which may be separated by a distance of one thousand feet or less. These three cables transmit the video, horizontal sync pulses and vertical sync pulses to the monitor. The use of three cables, rather than

* Now Chief Radio and Television Engineer, Hoffman Radio Corp., Los Angeles, California.



FIG. 2—A complete setup consists of camera, monitor and power units

Television

one cable carrying a composite signal, adds to simplicity.

Overall System

Figure 3 is a block diagram of the complete system. The image is focused optically on the cathode of the dissector. Deflection and focus power and the multiplier voltage are supplied to the dissector from the power unit. The video signal from the dissector and blanking pulses are fed in to the automatic black-level setter. The composite signal is then amplified and matched to the line.

The vertical oscillator in the power unit supplies vertical deflection power to the camera unit as well as vertical sync pulses for the monitor and vertical blanking pulse former. The beam relaxor supplies horizontal scanning power to the dissector and horizontal blanking pulses to the blanking pulse former, which mixes, clips, and shapes the horizontal and vertical blanking pulses. The beam relaxor also supplies horizontal sync pulses to the monitor and furnishes high-voltage pulses which are rectified to furnish multiplier and cathode voltage to the dissector. The vertical sync pulses trigger the vertical deflection oscillator in the monitor unit. Horizontal pulses are amplified and fed to the monitor beam relaxor. This beam relaxor supplies horizontal deflection and high-voltage pulses which are rectified to supply approximately 8 kv to the picture tube. The video signal from the camera is amplified and applied to the grid of the picture tube. A 1N34 is used as the d-c restorer.

Figures 4, 5 and 6 are schematic diagrams of the camera, power unit, and monitor respectively. The lens used in the camera unit has a 90-mm focal length and a speed of f:1.4 or better. The lens is coated for 7,000 A transmission. The mounting uses a rack gear and pinion type focus adjustment, and the angle of coverage for a two-inch horizontal scan is approximately 27 degrees.

Image Dissector

Figure 7 shows a photograph of the dissector. The front of the tube (right) is the translucent cathode which replaces the solid cathode of earlier tubes of this type. This construction permits the use of fast, wide-angle lenses, and eliminates picture degradation due to light reflecting from the walls of the tube.

Directly behind the cathode are five rings, behind which lies the nickel-wall anode. The anode is 400 volts positive with respect to the cathode, and the five rings are at intermediate voltages with 75-volt intervals. The purpose of the rings is to improve the field in the vicinity of the cathode and decrease the amount of distortion.

An eleven-stage multiplier is



Camera at right views level of liquids in two tubes at left in this industrial application of the television system

Operator sees liquid levels on remote monitor screen

mounted at the rear of the tube. The aperture, which in most cases is a 30-mil square, is located at the front of the multiplier housing.

Each multiplier stage has a gain of 3 or 4 when the voltage per stage is 200 volts. Total gain of the 11-stage multiplier is over 1 million. The Ag-Mg type of multiplier is used instead of the Cs-O-Ag which was used in the solid-cathode type dissector in order to provide better uniformity in multiplier performance from tube to tube and eliminate the problem of cesium shorts in the multiplier. The tube is relatively nonmicrophonic. The cathode photosensitivity is approximately 20 μa per lumen.

Figure 8 shows the dissector coil assembly that contains the horizontal deflection coil, vertical deflection coil and focus coil. The horizontal coil is the inner coil and is approximately nine inches long. The vertical coil is a toroidal type approximately one inch long wound over an iron form. This coil fits snugly on the horizontal coil and is directly behind the focus coil. These two coils are rotated 90 degrees, electrically, with respect to each other. The focus coil is semilayer-wound directly over the dissector cathode in the coil assembly housing. The coil assembly can be rotated to align the picture.

Video Amplifier

A schematic of the video unit is included in Fig. 4. Its function is to mix the blanking pulses with the video from the dissector collector, provide an automatic black level setting, amplify the composite signal, and match the output to the transmission line.

The operation of the automatic black level setter is as follows: Relatively large blanking signals are fed to the cathode in series with the video from the dissector collector. This video is developed across R_1 which is the dissector collector load. The d-c voltage developed across R_1 due to random noise in the dissector will remain constant. Any light which strikes the dissector cathode will cause a corresponding increase in collector current, hence increased negative voltage of the collector. Since more light causes more electrons to flow to the collector, the collector becomes more negative with respect to ground.

The initial clipping level of the automatic black-level setter can be properly adjusted by applying just enough positive voltage to its cathode to allow only a very small amount of the blanking pulses to come through. This is accomplished by varying R_2 to give the proper potential. An isolating resistor R_3 is used to minimize the capacitance across the collector load. Any light on the dissector cathode will cause more negative voltage to appear at the clipper cathode, which will pass through the diode, so the pedestal will always be full but no video can ever extend beyond the black level.

The 6AC7 video amplifier has a gain of approximately 18, and the cathode follower provides a low-impedance output for the video line with a gain of approximately 0.3.

The dissector multiplier voltage divider is shown in the upper left-hand portion of the schematic. The overall voltage across the multiplier is approximately 2,000 volts. Capacitors C_1 and C_2 improve the low-frequency response of the multiplier due to the high impedance of the multiplier divider. Actually the width control is an overall size adjustment in that it changes the cathode-anode voltage. An increase in this voltage will decrease the width of the scanned image and also the height of the image.

The video overload control R_4 controls the gain of the multiplier. It is necessary due to variation in dis-



FIG. 3—Block diagram of image dissector industrial television system



FIG. 4—Circuit showing image dissector connections and camera video unit



FIG. 5—Sync pulses and video are fed to monitor by three separate cables



FIG. 6—The power unit supplies all operating voltages for the camera unit

sector tubes and extreme light conditions which may be encountered, otherwise the last stages of the multiplier might be overloaded. Since this overload problem concerns only the last two or three multiplier stages, control is in the sixth stage.

Figure 9 shows clearly the power unit which delivers heater voltage, B+ voltage, multiplier voltage, scanning power and blanking signals to the camera unit, and also supplies vertical and horizontal sync pulses to the monitor. It draws approximately 100 watts and will operate on a line voltage of between 95 and 135 volts. A self-regulating type power transformer is used.

Figure 5 shows a schematic of the power unit. A single 6L6 in a beam relaxor circuit is used to provide horizontal scanning power for the camera as well as to supply high-voltage pulses to the multiplier voltage supply rectifiers. The beam relaxor is a horizontal deflection power oscillator of L and R type. The frequency of this type oscillator is determined by the inductance in the plate circuit and the internal resistance of the tube. The inductance in the plate circuit is approximately 100 mh and is determined by the impedance of the deflection coils and the transformer ratio. The frequency of the oscillator can be varied by changing the resistance in the cathode of the tube. This is a free-running oscillator which operates at a frequency of 21.5 kc. This frequency is controlled by the adjustable cathode resistor. This control is not critical but may vary slightly from transformer to transformer. This horizontal deflection circuit was chosen for stability and durability.

Figure 10 shows a close-up of the horizontal deflection transformer. This transformer consists of a grid winding of approximately 100 turns. The 500-turn plate winding is wound directly over the grid winding. The high-voltage winding consists of 300 turns connected in autotransformer fashion. The transformer must serve three interdependent functions. It must provide scanning power to the camera, the high voltage for the dissector multiplier, and its return time must be slightly faster than the blanking return time. These criteria must be met with satisfactory scanning linearity. The return time of this transformer is 5.7 microseconds or 0.12 H. A damping resistor removes the overshoot which would otherwise occur through the scanning coils causing severe nonlinearity.

The positive impulse derived from the horizontal deflection transformer is rectified by the two 1B3's in parallel. This provides a negative voltage of approximately 2,500 volts. Since the current drain very nearly approaches the current rating of a single 1B3, two are used in parallel. This is done as an added precaution against failure in the field.

The vertical deflection circuit, which consists of the dual triode, must supply vertical deflection power to the camera, vertical blanking pulses to the blanking mixer and vertical sync pulses to the monitor. One-half is used as a blocking oscillator. The lower end of the

FIG. 7—Translucent-cathode image dissector tube



FIG. 8—Image dissector deflection and focus coils

blocking oscillator transformer is returned to the 6.3-volt heater winding on the power transformer. A resistor is inserted in the cathode circuit of the vertical oscillator. A positive pulse is developed across this resistor which is used for blanking and monitor synchronization. Capacitor C_1 reduces the horizontal pickup on this lead. Transformer T_1 is the vertical output transformer used to present the proper plate load impedance on the vertical amplifier from the vertical scanning coils.

One section of the blanking mixer tube is used to mix the horizontal and vertical blanking pulses while the other section is used as a cathode follower. A positive vertical pulse is fed to the cathode of the blanking mixer. A negative horizontal pulse from the beam relaxor cathode is injected on the grid of the blanking mixer. A very low plate voltage is used, hence the blanking pulses cause very early saturation of the tube. This causes the base line of the blanking pulses to be absolutely flat which is extremely important, otherwise at low light levels a shading component will appear. The values of R_1 and R_2 were picked very carefully to provide proper phasing of the horizontal blanking pulse with respect to the initial sync pulse delivered to the monitor.

A cathode follower isolates the cathode of the vertical oscillator from the monitor vertical oscillator. If this is not done a large pulse is fed back to the power unit from the monitor vertical oscillator. This pulse, if applied across the cathode resistor of the power unit vertical oscillator, is slightly out of phase with the cathode pulse and will make it impossible to derive a clean vertical blanking pulse from this point.

The horizontal synchronizing pulse is derived across the cathode resistor of the 6L6 beam relaxor. This provides a low-impedance source of horizontal sync pulses. The amplitude of these pulses will vary as the frequency of the beam relaxor is changed. However, a pulse amplitude of only ½ volt is ample to insure positive synchronization of the monitor and higher amplitudes are not detrimental. The cathode resistor obviously cannot be shorted since this would reduce the pulse amplitude to zero.

Monitor

The monitor is quite conventional and will not be treated in detail. All controls are available from the front. Brilliance, contrast and focus controls are screwdriver adjustments. Other controls are behind a hinged door. Two controls are provided on the monitor for remote operation of the camera unit from the monitor position when desirable.



FIG. 9—Power unit with cover removed to show placement of components



FIG. 10—Horizontal deflection transformer

A 6L6 is used in a beam relaxor circuit to provide horizontal deflection and high voltage for the picture tube. Circuitwise, this is quite similar to the beam relaxor on the power unit. Synchronization is controlled by injecting the horizontal sync pulse from the power unit on the screen of the 6L6 and controlling the frequency by means of a variable cathode resistor.

The monitor beam relaxor transformer is similar to the power unit beam relaxor transformer with the addition of two heater windings for the 1B3 rectifiers. The transformer is designed to match a 2 mh deflection yoke. It also provides 8,000 volts for the picture tube; the return time must be faster than the camera blanking time. Two 1B3 tubes are used in a voltage doubler circuit to provide the picture tube high voltage.

The vertical deflection system is very similar to the camera vertical deflection system. Frequency determining elements are fixed and the oscillator will stay in sync over large variations of voltage and other parameters. The vertical sync from the power unit is injected directly into the vertical oscillator.

The grid, cathode and plate time constants of the horizontal sync amplifier were chosen to properly phase the triggering of the beam relaxor with respect to the blanking pulse. The monitor raster has approximately ⅛ inch blanking on either side.

Acknowledgment is given to the Diamond Power Specialty Corporation of Lancaster, Ohio, who sponsored the development of the equipment and who are the exclusive sales agents.

The DIOTRON... An Aid To RMS Instrumentation

Novel circuit comprising temperature-limited diode, d-c amplifier, and feedback path solves wide variety of electronic problems. Simple unit provides basis for true square-law voltmeter, wattmeter, video program level meter, and several computing elements

By R. D. CAMPBELL

Reed Research, Inc.
Washington, D. C.

DURING RECENT YEARS a need has grown for a vacuum-tube voltmeter whose indication depends only on rms values. When nonsinusoidal waveforms are to be measured, and particularly when the signal is a random noise, reliable data cannot be acquired from any rectifying instrument.

Bolometric and thermocouple devices accurately give rms values independently of waveform, but suffer from two serious difficulties: (1) The instruments are sluggish, and brief samples of signal cannot be measured. (2) Both devices operate close to the burnout point. This often forces the designer to incorporate an overloading amplifier stage to protect the instrument, with the result that large spikes, such as those of noise, are clipped. To this error is added uncertainty during the recovery period after overload.

The circuit of Fig. 1 constitutes the basis of a vacuum-tube voltmeter which overcomes these defects. As indicated, the diode and d-c amplifier form a tight feedback loop which will regulate the diode plate current with considerable accuracy. Since the voltage at the diode plate is always sufficient to collect all the emitted electrons, a constant value of space current implies a constant filament temperature and accordingly a constant value of filament heating power. It is upon this last relation that the properties of the device are based.

Theory

If a source of a-c is introduced into the filament along with the d-c of the feedback loop, the circuit must immediately regulate away part of the latter in order that the average filament power remain constant. The defining equation for this behavior is

$$I_{a\text{-}c}^2 R_F + I_{d\text{-}c}^2 R_F = \text{constant}$$

Since the filament is of fine diameter, skin effect may be neglected below 100 mc and a simpler form of the equation results.

$$I_{a\text{-}c}^2 + I_{d\text{-}c}^2 = \text{constant}$$

Since the effect of introduced a-c depends only on the heat it produces, it is evident that the circuit constitutes the basis of a vacuum-tube voltmeter which truly reads only rms values. Such a meter will at all times agree with a thermocouple and has these additional advantages: (1) A thermocouple operates close to its burnout current, whereas the diode circuit operates at 12 percent of its burnout current. (2) Thermocouple time-constants are of the order of 0.5 second. The diode and amplifier loop can be made to have a time constant of 15 milliseconds for all applied frequencies above 1 kc. (3) The accuracy of the device is that usually associated with feedback devices, and the accuracy of the readings depends only on the values of a few precision wirewound resistors.



FIG. 1—Diode and d-c amplifier form feedback loop which accurately regulates diode plate current

Linear Power Scale

The circuit of Fig. 2 shows a practical vacuum-tube voltmeter constructed on this basis. It will be noted that the diode filament is heated from a negative bias and that the d-c amplifier supplies a current which subtracts from this. This refinement is necessary in order that the feedback be degenerative for signals fed through the capacitance and leakage of the diode as well as for those signals which are thermally transmitted. Two additions have been made to the feedback path from amplifier output

to input. First, a new path, consisting of a single capacitor, decreases the bandwidth of the amplifier so that filament temperature variations during a cycle are not amplified and transmitted around the loop to produce an additional heating current not indicated by the d-c meter. Secondly, the R-C network from output cathode to diode filament supplies first-derivative damping for optimum stability and speed of response. Both of these circuits can be adjustable, so that high frequencies can be measured in the shortest possible time without sacrificing accuracy when low frequency measurements must be made.

Since the defining equation

$$I_{oc}^2 + I_{ac}^2 = K$$

is a circle, it is evident that this meter will have a voltage scale expanded at the top and very cramped at the bottom, quite similar to the usual thermocouple calibration. A power scale fitted to this instrument will be slightly expanded at the top and linear throughout the remainder of the range. By means of a simple approximation, complete scale linearity in power may be achieved. If the defining equation is expanded in series solution for I_{ac}, we have

$$I_{ac} = K^{1/2} - \frac{1}{2K^{1/2}} I_{oc}^2 - - - -$$

and a linear relation exists between I_{ac} and I_{oc}^2 provided that I_{oc} is restricted to small values. For engineering purposes, I_{oc} may be as great as 45 percent of the initial value of I_{ac}, with a resulting error of only 0.8 percent.

The circuit of Fig. 2 is arranged in this manner, and I_{oc} is always restricted to small values. Accordingly, the scale is linear in watts. The full scale deflections are 0.775, 2.45, 7.75, 24.5 and 77.5 input volts, which correspond to 1, 10, 100 milliwatts, 1, and 10 watts when the instrument is bridged across a 600-ohm load. The frequency response of the commercial version of this instrument extends from 40 cps to 10 mc and the response time is the order of 15 milliseconds for all applied frequencies above 1 kc.

It is fortunate that in many practical applications a linear power scale is just as acceptable as a linear voltage scale. In measurements of random noise, in fact, the former is usually preferable.



FIG. 3—Block diagram of vacuum-tube voltmeter with linear voltage scale

Linear Voltage Scale

In those cases where a linear voltage scale is essential, an extension of the basic scheme may be employed. Figure 3 is a block diagram of such a system. Here two diodes are so arranged that the filaments are independent for a-c signals but are essentially in parallel for d-c signals produced in the first feedback loop. The second diode is arranged to control a local source of square-wave a-c which constitutes the heating power in its own feedback path. The frequency and wave shape of this local source of heating power may be selected by the designer to give easy measurement and simplicity of control.

With this arrangement the output



FIG. 2—Wide-band vacuum-tube voltmeter using temperature-limited diode has linear power scale



FIG. 4—Two signals, *A* and *B*, can be multiplied by the arrangement shown

voltage must be accurately proportional to the rms input voltage, provided the zero has been properly set, whether the two diodes are identical or not. The only source of error worth noting is that which might be caused by a gradual change in waveform of the local source of heating power. This might result in a change in rms value which would not be indicated by the peak-reading instrument. For this reason, it is unwise to use a multivibrator as the source of square-wave a-c, since the ratio of on to off time for such circuits is not usually very stable.

The most convenient diode for any of the foregoing arrangements is the Victoreen type 5799, since the necessary filament current for temperature limited operation is only 6 ma. Computation based on the internal geometry of this tube places the resonance of the filament above 400 mc. Accordingly, the device should be directly applicable as the first detector in vhf propagation studies and as the second detector in signal-to-noise measurements at i-f frequencies. For these purposes, about 0.7 milliwatt should be delivered to the filament for full-scale deflection, and the filament resistance is 135 ohms. The wide-band instrument of Fig. 2 is of course directly applicable to power level monitoring on video program loops.

Other Possibilities

Electronic addition, subtraction, time integration and time differentiation can easily be accomplished by well-known techniques. However, successful circuitry has not existed for multiplying or dividing two voltages, for integrating or differentiating one voltage with respect to another, or for triangle solution. In consequence, these latter problems have been attacked by mechanical methods involving servomechanisms, with a resultant minimum time for problem solutions of the order of 0.1 second. The diode-amplifier-feedback loop arrangement can solve such problems with far greater speed wherever the inherent error of about 0.5 percent in each step can be tolerated.

The basic circuit of Fig. 2 with a restriction on the size of the input signal has been shown to constitute a computer element capable of producing an output proportional to the square of the input, and possessing good accuracy and speed of response. Since accurate and simple methods exist for interchanging a slowly varying d-c and an amplitude-modulated carrier, no serious complication arises from the a-c to d-c conversion which occurs within the diode itself. The basic circuit of Fig. 2, together with any necessary modulator or demodulator, can therefore be thought of as a building block that produces a square.

This computer element, by feedback methods, can be made to extract square roots by forcing itself to acquire an input signal such that the output equals the voltage whose square root is desired. A pair of such blocks then constitute a multiplier as indicated in the block diagram of Fig. 4. Here the two voltages to be multiplied, A and B, are assumed to be slowly varying d-c. Ordinary electronic addition and subtraction produces two new voltages equal to $A + B$ and $A - B$. These two voltages are then converted to amplitude-modulated carriers and fed to diode circuit blocks which produce a square. The outputs are then proportional to $(A + B)^2$ and $(A - B)^2$. Their difference is therefore proportional to

$$A^2 + 2AB + B^2 - A^2 + 2AB - B^2 = 4AB$$

In a manner analogous to that employed for square root computation, the process of division may be accomplished by including gain and feedback around the multiplier of Fig. 4.

The combination of these processes, together with one more block having unrestricted input range, then permits right triangle solution for all cases where angular data can be provided (or taken out) in terms of a trigonometric function of the angle, rather than in terms of the angle itself. Since the filament may carry currents of three different frequencies just as well as two, the extension to vector computation is obvious.

In most practical cases the device can also integrate or differentiate one voltage with respect to another. It seems reasonable to suppose that any quantities which will be dealt with in electronic computation will not only be analytic functions of each other, but will also be continuous in time and have continuous first derivatives with respect to time, whether time enters the problem directly or not. If so, we may write

$$\int A\,dB = \int A \frac{dB}{dt}\,dt$$

and the integration involves ordinary differentiation and integration with respect to time and multiplication by methods already described. Similarly

$$\frac{dA}{dB} = \frac{\frac{dA}{dt}}{\frac{dB}{dt}}$$

and the process involves ordinary time differentiation and division.

For certain of the applications outlined above, a diode is not essential and a thermistor, for example, would do equally well. Investigation of feedback around other available nonlinear circuit elements may lead to other useful and novel circuits having pleasing and desirable properties.

Kilomegacycle Buzzer



The Ashcan model. Overall can is 22⅛ in., depth to bottom plate, 14 15/16 in. and 18¾-in. diameter, wooden plunger is 5⅛ in. in diameter

Front panel view of the oscillator, showing single adjustment for buzzer. The dial for frequency control is directly calibrated in kilomegacycles



Internal view of oscillator with batteries and cavity end plate removed. Attenuator rack and pinion at right



Buzzer removed from its shield. The small loop protrudes into the cavity

Test Oscillator

Pulses of broad-band energy are injected into a tunable cavity at 800 cps. Output at any desired frequency between 3 and 11 kmc can be selected. A piston attenuator permits variable output up to 200 microvolts into a 50-ohm load. Development technique is traced from a model twenty-five times desired scale

By GOMER L. DAVIES, CHARLES B. PEAR, Jr. and P. E. P. WHITE

The Davies Laboratories, Inc
Riverdale, Maryland



Mechanical layout of the oscillator, with detail of cavity at lower right. The buzzer generator is coupled to the cavity through a loop

ALTHOUGH activity in the kilomegacycle region has increased greatly in recent years, signal sources are still largely restricted to narrow-band tuning. This is an annoyance when testing fixed-frequency detecting devices, and a real handicap in testing wide-range receivers.

One of the latest instruments to help solve this problem is a simple, compact test oscillator covering 3,000 to 11,000 mc in one continuous tuning range. No tubes are used. A battery-driven buzzer operating on the doorbell principle provides audio-modulated signals everywhere in the band, and a plunger-tuned cavity selects the desired frequency. A piston-type attenuator controls the output level.

Scaled-Up Model

The lack of wide-range signal-generating equipment was in itself a difficulty during the oscillator's development. Problems in tuning-cavity design showed the desirability of experimental work, but no satisfactory signal source was available. An interesting application of the model technique in reverse solved the difficulty by providing a cavity in which every dimension was twenty-five times the corresponding dimension of the cavity in the final unit. Thus, frequencies were scaled down into the scope of readily available test equipment.

The simplicity of the buzzer test oscillator is evident from the schematic diagram in Fig. 1. A buzzer, energized by the 3-volt battery through the r-f filter produces short, sharp pulses of current, which are coupled into the cavity through the input coupling loop. The cavity is sharply resonant at a single frequency determined by the position of the tuning plunger. It selects a component from the broad spectrum of frequencies comprising the buzzer output. This signal is coupled to the loop on the variable-attenuator piston that controls the output amplitude. The output sig-

nal is in the form of short pulses of r-f energy recurring at the rate of 800 per second. Maximum output voltage is at least 200 microvolts into a 50-ohm load.

The original unit employed an open-ended cylindrical cavity, which was poor from the shielding standpoint. The tuning dial calibration was considerably cramped at one end of the scale, and the available output signal varied appreciably over the frequency range. The desire to improve these characteristics led to the use of the scale model.

The Ashcan

In this development, an expanded model was used rather than the smaller scale customarily employed in antenna experiments. All measurements were made in the region of 120 to 440 mc, where suitable equipment was readily available and the frequency data multiplied by an appropriate factor. The idea for the use of this method was derived from experiments performed by Barrow and Mieher[1] at MIT.

Since the actual cavity in the unit was approximately ½ inch in diameter by one inch long, a model twenty-five times this size was considered reasonable. Accordingly, a local tinsmith was commissioned to make a large cylinder 18½ inches in diameter and 25 inches long, and a smaller cylinder, to simulate the tuning plunger, six inches in diameter and 36 inches long. The material used was 22-gage galvanized steel, and the appearance of the assembly made its title certain: the Ashcan.

It was fitted with a plywood cap over the large cylinder, through which the smaller cylinder could move. The inside of the wood cap was covered with copper sheet and suitable fingers made contact with the two cylinders. The inner cylinder was capped to simulate the solid plunger to be used in the actual cavity. Standard uhf connectors were mounted in the wall of the outer cylinder near the capped end to serve as connections to the small coupling loops mounted on the inner ends of these connectors.

The coupling loops were positioned 90 degrees apart around the circumference of the cylinder, as this was the position desired in the final uhf cavity. One of these loops was used to feed energy into the cavity from an oscillator covering the desired frequency range, and the other loop was used for output coupling. A type 1N21B crystal and microammeter served as a detector. Frequency measurements were made by means of a General Radio type 720-A heterodyne frequency meter.

Despite the crude construction and use of sheet steel for the inner and outer cylinders, the Q of the cavity was in the vicinity of 1,000, permitting precise settings to be made. Lines drawn on the portion of the inner cylinder extending above the wooden cap permitted reading of length of plunger inside the cavity.

The first tests made with an open-ended cavity showed the same tuning curve as the original buzzer test oscillator cavity unit, as well as the rather wide variation of output previously noted. Data given by Barrow and Mieher suggested that the low-frequency end of the tuning curve could be controlled through a considerable range by the use of a closed cavity. Appropriate adjustment of the spacing between the plunger and the end of the cavity at the limit of plunger travel was necessary. It was also reported that the cavity oscillations were very weak in an open-ended cavity at the high-frequency end of the tuning range.

It appeared that closing the open end of the cavity would, in our case, achieve the results desired. This effect was tried and found to improve Q throughout the operating range and to provide a much flatter



FIG. 1—Circuit of the buzzer test oscillator



FIG. 2—Calibration of the scale model, showing improvement resulting when end was closed. Spurious modes are outside operating range



FIG. 3—Calibration of buzzer oscillator. Small circles are values predicted from large-scale model for which an equivalent frequency scale is shown

tuning curve, as shown on Fig. 2. However, resonances at higher modes became apparent. This condition was undesirable since it meant that more than one resonance frequency could exist for a given setting of the tuning plunger. The unwanted modes were identified[2] as the $TE_{1,1,1}$ and the $TE_{2,1,1}$ types.

Mode Suppressors

In the large-scale sheet-metal Ashcan it was a simple matter to introduce a set of mode-suppressing slits[3] that eliminated the $TE_{1,1,1}$ mode of oscillation. However, since the $TE_{1,1,1}$ is appreciably higher in frequency than the desired $TM_{2,1,0}$ and unlike the latter is a function of cavity length, it was decided to make the cavity shorter. This change raised both the undesired modes out of the chosen frequency range of the oscillator. The mode suppressing slits became unnecessary. The final position of the $TE_{1,1,1}$ and $TE_{2,1,1}$ modes is indicated at the top of Fig. 2.

It should be noted that the desired resonance curve represents a transition from the $TM_{1,1,0}$ mode (when the tuning plunger is entirely backed out of the cavity) towards the $TM_{0,0,p}$ mode[1], which would occur when the plunger almost touched the opposite end wall. However, the resonant frequency would then be much below that required for this application and motion of the plunger is stopped while operation is still a combination of the two modes mentioned above.

Experimental work at the Ashcan's convenient frequency range and physical size having been concluded, the resulting design was scaled back to 3,000-to-11,000-mc dimensions. The closed-end cavity now employed presents much less of a shielding problem than the original open-end unit. Provision was made for batteries, buzzer, and a piston-type attenuator with 100-db range.

The action by which the buzzer excites the cavity seems to be a high-frequency oscillation causing a pulse of perhaps five amperes maximum amplitude in the contacts at their break, when the voltage across the coil rises sharply to a value over 200 volts. It is necessary that each pulse be clean, and that the repetition rate be high enough to furnish an easily distinguished audio note for the operator's convenience while not being so high that the average battery current is excessive.

Test oscillator being used with receiver. In this case, reception is at harmonic of receiver local oscillator

Selection of Buzzer

Several commercial buzzers were tried. Inherent unsuitability for this application ruled out some units—for example, a standard power-pack vibrator was found to have excessive bounce at contact make, causing one or more break pulses at this time. Other buzzers drew more battery current than operating economy could permit, had an unstable repetition rate or operated at a frequency outside the desired range. The buzzer finally employed was conventional, but it was carefully designed and constructed to avoid the above faults. The operating value of 800 cps was chosen as a modulation value permitting low battery current and yet capable of being distinguished through receiver noise.

In use, the buzzer test oscillator has been found to perform almost exactly as the large scale model had predicted, as shown by the calibration curve of Fig. 3. Available test equipment has not permitted a full search of the upper frequency region to make sure that the undesired modes of oscillation are in the same relative position that model tests had shown. At each frequency where tests have been made, the agreement with the model's results has been excellent.

The unit is compact and rugged, weighing less than 11 pounds complete. The current drain on the self-contained batteries is between 30 and 150 ma, depending on buzzer adjustment. When operated at normal temperatures the battery life for continuous operation should be in excess of 300 hours, or considerably more for intermittent operation. The oscillator thus provides a completely self-contained, relatively trouble-free, portable source of uhf signals. No heating-up time is required, the unit being ready for operation as soon as the battery switch is thrown.

The first example of a test oscillator of this sort was made at the Radio Research Laboratory[4] at Harvard during the war. A second model was later made by the Naval Research Laboratory, Bellevue, D. C., and the design development described here was supported by the Bureau of Aeronautics of the Department of the Navy.

REFERENCES

(1) W. L. Barrow and W. W. Mieher, Natural Oscillations of Electrical Cavity Resonators, *Proc. IRE*, **28**, No. 4, p 184, April 1940.

(2) J. G. Wilson, C. W. Schramm, and J. P. Kinzer, High Q Resonant Cavities for Microwave Testing, *B. S. T. J.*, **25**, No. 3, p 408, July 1946.

(3) J. P. Kinzer and I. G. Wilson, End Plate and Side Wall Currents in Circular Cylinder Cavity Resonator, *B. S. T. J.*, **26**, No. 1, p 31, Jan. 1947.

(4) Buzzer Signal Generator for 3,000 MC, ELECTRONICS, p 149, Oct. 1946.

CASTING RESIN

Step-by-step instructions for potting electron tube assemblies in NBS casting resin, including typical sources of ingredients, preparation and mixing, use of air-piston injector for filling, curing data, fire and explosion precautions, and product design aspects

By JACK BAYHA

Senior Engineer
Emerson Radio & Phonograph Corp.
New York, N. Y.

ALTHOUGH a great deal of general literature on the so-called NBS casting resin has been written, little data as to actual preparation techniques and application has been available. It is the intent of this article to present workable preparation and usage details.

Basically, this resin combines the requirements of reasonable mechanical properties and castability with excellent electrical properties, as indicated in Table I. The formula is quite simple, but formulating techniques are somewhat involved and require great care.

Preparation of Ingredients

The actual ingredients should be obtained in advance. Those starred below should be stored under refrigeration. By weight, we use the following proportions and brands:

2.5 Dichlorostyrene monomer	33.0%*
Styrene monomer	21.0%*
Polydichlorostyrene	21.5%
Polystyrene P-8 (Koppers)	11.0%
Divinyl benzine solution	0.5%*
HB-40 (Monsanto)	13.0%
Benzoyl peroxide	0.2%

The preparation of the ingredients is exceedingly important and may best be given step by step, along with our source information.

The 2.5 dichlorostyrene monomer is obtained from Dow Chemical, Midland, Michigan. As supplied, it contains an inhibitor which is used to decelerate polymerization, to make possible reasonable transit and storage. This inhibitor must be removed. Removal of the inhibitor must be done as close to actual use as possible. Uninhibited material may start to polymerize at room temperature in a matter of hours. The technique of inhibitor removal is shown in Fig. 1A. The activated alumina can be obtained from Aluminum Co. of America. The noninhibited material must be kept under refrigeration below 40F until used.

Excellent results are obtained with Koppers styrene monomer, obtainable from Koppers Co., Inc., Chemical Div., Pittsburgh, Pa. Freedom from dissolved gases is an important consideration if bubble-free material is desired, and containers should therefore be kept tightly closed. This material is also treated with inhibitor, and the set-up shown in Fig. 1A must again be used to extract the inhibitor. This monomer also is highly inflammable.



FIG. 1—Simple filter for removing inhibitors from casting resin monomers, and air-piston injector developed by Emerson for applying the prepared product. Source of vacuum for filter can be a vacuum cleaner

No treatment of polydichlorostyrene is necessary. We obtain the material itself from Mathieson Chemical Co., Niagara Falls, N. Y.

In order to facilitate preparation we use Kopper P-8 polystyrene in small bead form. This greatly reduces mixing time.

Divinyl benzine solution is best stored under refrigeration, and is obtainable from Dow Chemical as Experimental Monomer Q-302.4. No special preparation is necessary.

Monsanto HB-40 is procurable from Monsanto Chemical Co., 445 Park Ave., New York, N. Y. Unless especially clear cast items are needed, no preparation of this material is necessary. If extra-clear material is desired, the filtration process shown may be used. Viscosity of HB-40 makes this a tedious job, and the resulting resin clarification is not too satisfactory.

Benzoyl peroxide is obtainable from Eastman Kodak, Rochester, N. Y. This is an unstable material, prone to explosion. As supplied, it contains a filler material intended to deaden its sensitivity. This material must be removed for proper action. The removal of filler is a simple process, and involves only normal and reasonable safety precautions:

(1) *Do not handle large amounts.*

(2) *Do not grind or otherwise submit to abrasion or impact.*

(3) *Keep from flame or sparking of metal mixing tools.*

Removal of filler is accomplished by a simple precipitation process. Dissolve a suitable quantity of filled benzoyl peroxide in a quantity of acetone C. P. When dissolved, add enough cold water to produce a heavy white precipitate. Filter the suspension through a disc of filter paper. The material remaining is filler-free benzoyl peroxide. This

material is exceedingly sensitive and must be carefully handled. When thoroughly dry, it is ready for use. If an oven is used for desiccation, do not exceed 50 C or selfignition may occur.

Mixing

The actual mixing process requires a ballmill or other form of enclosed milling device. Many methods of combining ingredients are possible, but laboratory experience has shown milling to be best suited.

The fluid ingredients, which are styrene, polydichlorostyrene monomer, HB-40 and divinyl benzine solution, are combined after being carefully weighed. Fumes are moderately toxic and require ventilation. The benzoyl peroxide is also added and dissolved. Thorough mixing of these ingredients will be brought about with little effort by normal stirring.

The addition of the polydichlorostyrene and polystyrene may offer difficulty with lump formation if care is not taken. It has been found convenient to premix these two ingredients, then add them rapidly to the fluids, stirring constantly. The container is at once closed and immediately placed on the rolling mill.

The material is then milled until all lumps have disappeared. This may be done at normal room temperature. The mixed material, taking about 12 hours of milling, must be refrigerated at once or polymerization will occur. All materials must be allowed to return to room temperature prior to exposing to air, or surface condensation will occur. A disastrous loss of electrical properties attends this moisture absorption.

Potting and Curing

The actual preparation of the resin is less complicated than it seems, and reasonable care will result in a reliable product.

The dispensing of a product with as high a viscosity as NBS casting resin presents quite a problem.

Table I—Physical Properties of Casting Resin Developed by National Bureau of Standards

Water Absorption (24-hour immersion)	Less than 0.01%
Volumetric Shrinkage	8.0%
Power Factor (100 mc—50%RH)	0.0004-0.0008
Dielectric Constant (100 mc—50%RH)	2.5
Dielectric Strength (1/16 in. sample)	610-660 v per mil
Resistivity	10^{17} meg-cm

Pour potting may be used, but if any quantity of work is to be done, the air-piston injector shown in Fig. 1B is recommended. It is merely a cylinder with an outlet, into which casting resin is put. Air is admitted to the top by means of a pressure regulator. This forces the resin from the nozzle at the bottom when the base valve is opened.

The nozzle is tapered so it can be pressed into a hole in the container to be filled. The flow ceases when the valve is closed. Oil and dirt in the air supply collect on the top surface of the resin along with untrapped moisture, and are discarded. This injector permits bottom-up potting, which assures a better fill and minimizes air entrapment problems.

Design Aspects

The curing of potted articles requires the use of ovens which are free from open flame or incandescent filaments, as inflammable vapors are released during curing. A cure is generally secured after 12 hours at 50 C. The use of higher temperatures is risky, as is the presence of oven hot-spots; both result in excessively rapid polymerization, a poor material and likelihood of component damage. Longer time periods for curing will generally yield a more stable end product, with improved mechanical properties.

Casting resin of the type described has considerable shrinkage. Tubes and other incompressible components must therefore be protected by a compressible sleeve member of some sort. Care in selection of the sleeve material must be taken to assure it does not stop resin polymerization.

Inductances and circuit capacitances are changed by this casting resin. Experimentation with circuit constants before and after potting is essential in r-f circuits. In many types of equipment the values will vary enough, when potted, to affect operation.

A polystyrene case may be used to contain components for potting if care is taken in curing to avoid high temperatures. A polydichlorostyrene case will withstand higher cures and longer schedules.

The amount of catalyst (benzoyl peroxide) used has a great effect on the quality of the finished product. A larger amount will yield a poor mechanical product, and may cause loss of assemblies due to evolution (rapid polymerization).

Components used must be able to withstand temperatures in excess of the 50 C curing heat. Considerable exothermic (selfgenerated) heat occurs during curing. Lengthy room temperature curing will avoid this problem.

Potting failures due to lead breakage or failure of polymerization will occasionally occur, and should not be looked upon necessarily as failure of the technique. They can in many cases be traced to faulty technique, but in some cases they are without explanation. Generally a familiarity with the techniques involved will yield trouble-free results.

This work was performed with the assistance of the National Bureau of Standards. Special acknowledgment for assistance in the work described is due Phillip Franklin and Emma Lee Hebb of NBS.

BIBLIOGRAPHY

P. J. Franklin, Application and Performance of N. B. S. Casting Resin, National Bureau of Standards Technical Report No. 1148.

Nine-Tower Broadcast Array

First installation of its kind suppresses total of 247 degrees of radiation. Day-night pattern change is accomplished by single pushbutton control. Four phase monitors are employed so that several phases can be seen simultaneously

By CHARLES W. WINKLER

Chief Engineer
Stations KFOR, KOIL and WDGY
Minneapolis, Minnesota

and M. BRASSEUR

Westinghouse Electric Corporation
Chicago, Illinois



Six foot square cubicle in the transmitter building contains one of the four distribution tanks

THE FIRST nine-tower broadcast antenna array in the United States is in operation at WDGY, Minneapolis, producing a pattern unobtainable with fewer towers.

Suppression is required in three directions as shown in Table 1. The noncontrolled areas are so narrow that the effective antenna pattern gives suppression from 73 to 320 degrees, or a total of 247 degrees suppressed radiation.

Late in 1948, a single tower was erected for an elaborate survey of the antenna site and determination of the nondirectional characteristics to predict expected field strengths before erection of the other towers.

In collaboration with consulting engineer John Creutz, Westinghouse engineers designed and constructed the phasing and antenna tuning equipment diagrammed in Fig. 1. This equipment was designed to provide the greatest possible flexibility of control.

Table I—Directions of Suppressed Radiation

Station	Degrees Angle of Suppression	Maximum Permissible Field Strength, 1 Mile
WNEW		
New York City	73–128	10–70 mv/m
KWKH		
Shreveport, La.	159–229	10–70 mv/m
CBR		
Vancouver, B. C.	291–320	34 mv/m

Tuning

Motor-driven coils are connected in the antenna arm of each antenna network. In addition, the two coils of the T-phasing networks are driven by a motor mechanically



Towers of the WDGY antenna system


TRANSMITTER
FOR ANTENNA ARC OVER PROTECTION
FOR ANTENNA R-F OUTPUT CURRENT METER
COMMON POINT IMPEDANCE MEASUREMENTS
ANDREW CO. TRANSMISSION LINE
MOTOR DRIVE
TRANSMISSION LINES
TOWER NETWORKS
CURRENT TRANSFORMER FOR ARC OVER PROTECTION
SAMPLING LOOPS AND LINES FOR PHASE MONITORS, ALL CABLES BURIED 12"

FIG. 1—Schematic diagram of WDGY phasing and antenna tuning equipment



Interior view of one of the nine antenna tuning houses



Sampling loops to feed the phase monitors are mounted on each tower



FIG. 2 Measured day time pattern at 50 kw



FIG. 3 Measured night time pattern at 25 kw

coupled to both coils. Controls for these motor-driven coils are located under the phase monitors in the transmitter building, at one central location. At this central point are located all control and monitoring facilities to adjust and observe the operation of the antenna array.

Pattern change is accomplished by single pushbutton control, operating a series of some 30 r-f contactors to rephase and retune the nine towers for the desired pattern. The day and night-time patterns are illustrated in Fig. 2 and 3.

The room or cubicle which houses the phasing equipment is 12 feet deep by 24 feet long. Its walls are constructed of two thicknesses of ¾-inch plywood, with a sheet of aluminum interspaced for shielding purposes. The room has four 6 × 6-foot cubicles along the front, one for each of the distribution tanks required.

The phasing networks associated with each tank are also located in the cubicle corresponding to the tank circuit from which it is fed. Four phase monitors are used so that several phases can be seen simultaneously.

Two sampling loops are mounted on each of the center north-south row of towers, and one loop on each of the other six towers. These loops are constructed of one-inch steel tubing and mounted 20 feet above the base insulators. The center north-south row feeds one phase monitor, and each of the three east-west rows feeds a phase monitor. Solid dielectric coaxial cable is used for the sampling lines.

A feature of the transmitter which was found to be a real time saver is the variable inductive coupling to the final amplifier tank inductor. The adjustable coupling together with the variable tank capacitor provide a means of matching the power amplifier to the resistance of the load under operating conditions.

Excitation to the final stage can also be adjusted under operating conditions. During this adjustment period, the load impedance varies over very wide ranges, but due to the flexibility of the transmitter and its output circuits, power is maintained at the specified value during the adjustment of the array.

GEIGER COUNTER for Lectures

Circuit and construction details of reliable portable Geiger counter providing up to 50 watts audio output for demonstrations. Auxiliary indicators are Strobotron flasher and thyratron-driven rate meter

By RONALD L. IVES
Department of Geography
Indiana University
Bloomington, Indiana

DISSATISFACTION with the performance of commercially available Geiger counters with sufficient power output for lectures and demonstrations before large assemblages led to a series of experiments from which an instrument with high power output, low hum level, and good overall performance under a variety of conditions was developed.

Customarily, when a high power output is required from a Geiger counter, the output of the instrument is connected to the input of an adequate public address system. This produces plenty of noise, but also an unavoidably high background of hum in most instances. Custom-built instruments of this general type are commonly as large and costly as a piano.

For effective lecture demonstrations, a Geiger counter must have a power output sufficient to disrupt love's young dream in row 15 and awaken the halfback in row 37, while at the same time having a low enough hum level to satisfy the engineer in row 2, and mechanical construction pleasing to the instrument-maker in row 5. Unless the lecturer is a former baggage-smasher who also enjoys spending his spare time in repair work, the instrument must be readily movable, yet rugged enough to stand repeated transportation.

To keep first and maintenance costs low, components should as far as possible be standard items, available over the counter in any medium-sized city. This has been achieved in the circuit shown in Fig. 1, which provides 50 watts of audio output for lecture-hall loudspeakers.

Design Details

Because the life of the Victoreen 1B85 thyrode counter tube is determined by the number of counts, and because the tube may be damaged by warmup surges of the power supply, disconnect switch S_1 is provided. This also controls a pilot light, which is on when the high voltage is connected to the counter tube. In the off position, a 1-megohm resistor is connected across the high-voltage supply to reduce the voltage slightly.

The first two stages of amplification are entirely standard except that the cathode and screen bypass capacitors need not be large. The circuit is designed to amplify surges rather than complex sinusoidal waves, and tone quality need not be considered. Sensitivity of the 6J7 input circuit increases as the input resistors increase in value, but hum pickup and instability increase faster than signal output after a certain point.

Power supply for the first two stages, as well as high voltage for the counter tube, is obtained from a small power transformer which supplies 940 volts at 1 ma and 250 volts at about 40 ma by use of a step-and-a-half voltage addition circuit.

It was necessary to shield the re-



Indicators and controls are arranged in three rows on front panel of counter. Top row, left to right: pilot lamp; monitor speaker; Strobotron flasher tube. Center row: counter tube projecting straight out from panel; volume control; rate meter; power supply control; pilot lamp. Bottom row contains three toggle switches and two tap switches

sistors of the first stage and the Geiger tube socket with a heavy aluminum can to prevent electrostatic pickup and to surround the first tube with a magnetic shield to prevent electromagnetic pickup. An aluminum shield between the power supply and the audio elements of the first two stages reduced hum to a negligible value. Magnetic and electrostatic shielding, by use of a sheet-steel partition, was found necessary between the first two stages and the driver-power amplifier stages to prevent oscillation and magnetic pickup.

The 6F6 pentode-connected driver and the power amplifier using a pair of 6L6's connected in push-pull class AB, are standard in circuit arrangement.

To permit use of the instrument in small classrooms and in the laboratory where a 50-watt audio output is undesirable, switch S_4 is provided so the front end and the auxiliaries can be used separately. This permits use of the counter with no audio output (position 1), with 4-watt output on the local speaker (position 2), with both local and external speaker operated from the power amplifier (position 3), and with all output connected to the external speaker (position 4). The cooling fan for the power stage is also controlled by this switch, so that it is inoperative when not needed.

Coupling of the first two stages to the driver-power amplifier stages is unconventionally accomplished by use of a neon-tube base clipper. With this arrangement, any output surges in the plate circuit of the 6SJ7 that are smaller than the striking voltage of the neon tube are not passed on to the 6F6 driver. Those large enough to fire the neon tube also drive the 6F6 grid strongly positive. This arrangement effectively eliminates hum originating in the first two stages or picked up by them, as well as tube noise and microphonics. In order that the first two stages can be used independently; leaving the power stage available for other uses, switch S_4 is provided to connect the first stage to either the intermediate jack or the neon coupler. This permits external input to the power stages. Motorboating of the neon tube circuit is prevented by putting a sweaty fingerprint on the bulb base or connecting the capacitor side to ground through a 10-megohm resistor as in Fig. 1.

Auxiliary indicators, consisting of a Strobotron flasher and a rate meter, are operated from a parasitic circuit shunted across the driver plate transformer. The Strobotron flasher is entirely conventional, and is powered by a transformerless voltage doubler using selenium rectifiers. Switch S_5 is provided to disconnect this for count rates exceeding about 200 per second. The Strobotron tube is mounted on the panel by means of a tuning-indicator bracket, and the panel hole is rimmed with the accompanying bezel, reamed out to allow full visi-



FIG. 1—Counter tube at upper left feeds 5-tube amplifier (top row) having push-pull output stage delivering up to 50 watts to speakers. Six separate power supplies (two using selenium units) serve the amplifier, flasher and rate-meter circuits

bility of the Strobotron flasher.

The rate meter is a thyratron adaptation of the Grinnell recorder, with constants chosen so that the values are in decade relation to each other, position 1 of S_1 being 10^1 counts per second, position 2 being 10^2 counts per second, etc. A separate filament supply is required for the first thyratron, because its cathode-ground potential exceeds the safe limit for the tube once per count. At high counting speeds, the capacitance of the filament transformer must be considered in evaluating the charging capacitor. Grid bias is provided for each tube by use of a small transformer, one half of a 6H6 diode, and a filter capacitor. About 30 volts of negative grid bias was found desirable in this application. If desired, the 0 position of the switch can be connected to a 20-μf capacitor to provide a one-count-per-second range, provided some improvements are made in the regulated power supply or the rate meter series resistor is changed for this range only.

Calibration by formula was found entirely satisfactory[2,3]. With the constants shown and a 0-1 d-c milliammeter, the top mark of all ranges will be substantially correct if the total resistance across the 2,000-μf smoothing capacitor is about 8,700 ohms.

The transformers feeding the thyratron grids can be any small single-plate-to-single-grid a-f transformers, although counting-rate meter transformers will perform best if they are on the same core.

Mechanical Construction

Because this instrument must function satisfactorily in the office and laboratory, must be readily movable from place to place and must work dependably in new locations, preferably without any intervening repair work, special attention was paid to the mechanical construction. To prevent undue flexion in transit, panel and chassis were firmly bolted together, with shields forming angle braces.

To facilitate transportation, strong garage-door handles were firmly bolted to the ends of the case. The back of the chassis was anchored to the back bottom of the case by three angle brackets and bolts.



Driver and power amplifier stages, their power supplies, flasher components and rate meter components. Small fan near speaker operates only when power amplifier is turned on. At right of shielding partition are first two stages and strobotron power supply, with spare counter tube mounted on partition at top. No heat-producing component is boxed in

Vibration of components in transit was minimized by use of tie strips, cabling of leads, and careful anchoring of parts and cables at strategic points.

As constructed, this counter fits conveniently into a standard 12 x 12 x 20-inch cabinet, with a 12 x 18-inch panel and a 11 x 17-inch chassis base. Weight is about 65 pounds. By rearranging the components and shaving the factors of safety, reduction in both weight and bulk is possible, at an increase in first and upkeep cost and a loss of dependability. With a smaller volume, cooling also becomes a problem, and packing-factor troubles loom.

Performance

Tests of this counter under a variety of conditions, before audiences of various types from engineering groups to casehardened luncheon-club assemblages, disclose that its performance is very effective if accompanied by carefully-prepared lectures, devoid of fumbles.

Sonic output is about 50 watts at 1,000 counts per second, but does not appear to be very loud, perhaps because of the absence of the ordinary background noises. A 50-watt lamp, arranged so that it can be plugged into the output and illuminated brightly on demand, was found a desirable lecture adjunct.

Because of the rugged construction and the use of plug connectors, the counter can be brought into the lecture hall, connected, and put into operation in about two minutes, with confidence that it will perform satisfactorily.

References

(1) S. W. Grinnell, Some Instruments Used by Division 10, NDRC, for the Continuous Recording of Micrometeorological Conditions, *OSRD 6088*, 1945, p 6, 24 and Fig 3.

(2) R. L. Ives, Kick-Coil Operation of Impulse Registers or Counters, *Instruments*, 21, p 444, 1948.

(3) R. L. Ives, Capacitor Discharge Recorder Applications, ELECTRONICS, p 104, Feb. 1949.

Sync Separator Analysis

Response of a sync separation circuit to the nonsinusoidal composite television signal is analyzed. Equations are given for circuit design and calculated values are compared with measured values for monoscope and broadcast test pattern inputs



FIG. 1—Sync clipper circuit analyzed in text



FIG. 2—Solid arrow shows discharge path for C and dashed arrow the charging path

By W. HEISER

Receiver Engineering
Allen B. DuMont Laboratories, Inc.
East Paterson, New Jersey

CIRCUITS used for sync separation are not complex in nature but their response to the composite television signal is quite different from that which a conventional sinusoidal analysis would show.

The requirements for an ideal sync separation system are threefold, namely:

(1) The sync pulses should be entirely free of any video signal or the blanking pedestal.

(2) The horizontal sync pulses should all have the same amplitude and shape; moreover, the vertical sync and equalizing pulses should be consistent in their waveforms also.

(3) A reasonable amount of noise immunity should be achieved in the separating system.

These requirements should be met for all conditions of modulation, percent sync and picture content that are within the FCC requirements.

The sync separation circuit to be analyzed is shown in Fig. 1. The input signal at point A is a composite video signal with positive sync pulses and the sync pulses alone are obtained at point B. With the proper choice of the constants in the grid circuit, the grid of the 6AG5 will restore in the sync pulse region.

The location of the restoring point in the sync pulse region is dependent upon the ratio R_1/R as will be shown subsequently. The tops of the sync pulses are removed since grid current is drawn during this time, attenuating that portion of the sync above the restoring level by the ratio of r_g to R_1 (see Fig. 2), while the bottoms of the sync pulses and the video signal are removed since they are below the low cutoff point (−1 to −1.5 v) established by the low plate and screen voltages of the 6AG5.

With the grid of the 6AG5 restoring near the blanking level the noise immunity of this circuit is quite good. However, restoring in this region rather than near the sync tips tends to make the restoring level more critical since changes in the restoring level due to variations in the average video signal or the advent of the vertical sync pulses will cause a variation in the shape or width of the sync pulses at the output of the sync clipper since the sync pulse is trapezoidal rather than rectangular in shape.

The variation due to changes in the average video signal is usually slow enough to be negligible, while that due to the vertical sync pulses may be eliminated by using a large enough coupling capacitor as will be shown later. While increasing C above a certain minimum value does not affect the restoring level, it will decrease the immunity of the circuit to some types of noise.

Pulse Amplitude

The magnitude of the sync pulses desired at the output of the clipper as well as the size of the input composite signal play a large part in determining how far down from the sync tips we may restore without having video and pedestal present in our clipped sync output. For example, with a 25-v peak-to-peak composite signal at point A with 20-percent sync, or 5 v of sync, we will only have 30 percent, or 1.5 v of sync at the clipper grid if we are restoring 70 percent down.

To keep the sync clean, the cutoff point of the tube, determined largely by the screen voltage, must be closer to zero than —1.5 v, or we must restore closer to the sync tips with perhaps some decrease in noise immunity. With the cutoff point



FIG. 3—Composite video signal fed to circuit of Fig. 2



FIG. 4—Idealized input signal used for analysis of the circuit action



FIG. 5—Idealized waveform during vertical blanking time

closer to zero the magnitude of the sync pulses in the output will be less.

It is proposed to show a method for calculating the following:

(1) The restoring level at the grid of the clipper tube, assuming for the present that the vertical sync pulses have no effect on this level.

(2) The variations in this restoring level with different values of percent sync in the composite video input signal and with changes in average picture content.

(3) The value of the coupling capacitor above which any increase in capacitance has no effect on the restoring level when the vertical sync pulses are not considered.

(4) The change in restoring level due to the vertical sync pulses with various values of coupling capacitors larger than the value found in item 3 above.

(5) The minimum value of the coupling capacitor to eliminate this change in restoring level during vertical sync pulse time.

Restoring Level

For these calculations we need only consider that portion of the circuit shown in Fig. 2. For the first three computations the input signal at point *A* is as shown in Fig. 3. The concept of an average level (K_s) for the video signal is not strictly rigorous unless we have a constant video signal such as given by a test pattern. Since all measurements made in this article were taken using a test pattern and since the variations in the restoring level from line to line are small, the average level K_s is taken over a complete field for the purpose involved.

(1) In calculating the restoring level when neglecting the vertical sync pulses two assumptions are made. Capacitor C discharges between sync pulses through $R_i + R_s$ toward the average level, E_c $(1 - K_s)$. We may neglect R_s as compared with R_i. Capacitor C is charging during the sync pulses toward the sync tips through $R_s + r_p$. We may neglect r_p as compared with R_i.

For purposes of computation, the idealized signal is shown in Fig. 4. Then E and E' represent the charge on capacitor C at the end of the discharge and charge times respectively. Since the voltage across C at the end of the charge time equals the voltage at the beginning of the sync pulse plus the amount the capacitor is able to charge up, we may write Eq. 1. Similarly, we may write Eq. 2 by noting that the voltage across C at the end of the discharge time is equal to the voltage at the beginning of the discharge minus the amount the capacitor has discharged during the time interval.

$$E' = E + (E_c - E)\,(1 - e^{-t_1/R_iC}) \qquad (1)$$

$$E = E' - [E' - E_c\,(1 - K_s)]\,(1 - e^{-t_2/R_iC}) \qquad (2)$$

To simplify the notation let

$$\frac{t_1}{R_iC} = x \quad \text{and} \quad \frac{t_2}{R_iC} = y$$

$$\text{Then } E' = E_c - (E_c - E)\,e^{-x} = E_c\,(1 - e^{-x}) + E\,e^{-x} \qquad (3)$$

$$E = E_c\,(1 - K_s) + E'e^{-y} - E_c\,(1 - K_s)\,e^{-y} = E_c\,(1 - K_s)\,(1 - e^{-y}) + E'\,e^{-y} \qquad (4)$$

It is immaterial whether we solve at this time for E or E' since they are almost equal.

Solving for E' by inserting Eq. 3 in Eq. 4,

$$E = E_c\left[1 - \frac{K_s\,(1 - e^{-x})}{1 - e^{-x}\,e^{-y}}\right] \qquad (5)$$

To simplify Eq. 5, consider the series

$$e^z = 1 + z + \frac{z^2}{2'} + \frac{z^3}{3'} + \cdots$$

As long as z is less than 0.1 we may use the approximation $e^z \simeq 1 + z$ with an error less than 1 per-



Circuit of narrow-band sync amplifier and sync detector that caused rounding of pulses shown in Fig. 6



FIG. 6—Horizontal sync pulse at clipper grid with the tube removed from its socket shows rounding

cent. If x and y are less than 0.1,

$$1 - e^{-x} = 1 - \frac{1}{1+x} = \frac{x}{1+x}$$

$$\text{and } 1 - e^{-x}e^{-y} = \frac{x+y+xy}{(1+x)(1+y)}$$

Let us define $K_1 = \frac{1-e^{-x}}{1-e^{-x}e^{-y}}$

$$= \frac{x}{x+\frac{y}{1+y}}$$

If we restrict y to being 0.05 or less we may then approximate with less than a 5-percent error by calling

$$K_1 \doteq \frac{x}{x+y}$$

Substituting the values of x and y and simplifying,

$$K_1 = \frac{1}{1+\frac{R_1 \cdot t_1}{R_2 \cdot t_2}} \quad (6)$$

so Eq. 5 becomes

$$E = E_0(1 - K_1K_2) \quad (7)$$

Let us define the restoring level as $L = (E_0 - E)/E_0$. Examination of Fig. 4 shows that when this ratio is zero we are restoring at the top of the sync tips and when it is 1 we are restoring at the blanking level. Using Eq. 7 and $E_0 = K_2E_i$

$$L = \frac{K_1K_2}{K_2} \quad (8)$$

Change in Restoring Level

(2) Examination of Eq. 8 shows that the restoring level moves closer to the blanking level with a whiter picture (K_2 increasing) and/or a decrease in the percent sync in the input signal (K_1 decreasing).

(3) Examination of Eq. 6 shows that K_1 is independent of C as long as our assumption of y being 0.05 or less holds. This means that for any set of constants R_1 and R_2 the restoring level is independent of C as long as it is greater than the value given below. This, as stated previously, does not mean that the value of C will not affect the change in restoring level due to the vertical sync pulses.

For $y < 0.05 = t_1/(R_2C)$

$$C''_{min} = \frac{20t_1}{R_2} \quad (9)$$

(4) During the time when the vertical sync pulses are present, capacitor C of Fig. 2 is charging toward the sync tips. This charging time may be assumed to be $3H$ or 190.5 μsec (see Fig. 5). The voltage E'' on the capacitor at the end of the vertical sync pulses is the voltage at the beginning plus the amount the capacitor charges or

$$E'' = E + (E_0 - E)(1 - e^{-t_1/R_2C})$$

The restoring level at the end of the vertical sync pulses L_v expressed as percent of sync down from the sync tips is then

$$L_v = \frac{E_0 - E''}{E_0} = \frac{(E_0 - E)}{E_0} e^{-t_1/R_2C} \quad (10)$$

But $(E_0 - E)/E_0 = L$, the restoring level considering only horizontal sync pulses. We have therefore

$$L_v = L\, e^{-t_1/R_2C} \quad (11)$$

Equation 11 shows the change in the restoring level after the vertical sync pulses.

(5) In a manner similar to that in which Eq. 9 was developed we may compute a value of the coupling capacitor C necessary to reduce the change in restoring level after the vertical sync pulses to a 5-percent change.

From Eq. 11, $e^{-t_1/R_2C} = 0.95$

$$\text{or } \frac{t_1}{R_2C} = 0.05$$

$$\text{or } C''_{min} = \frac{20t_1}{R_2} \quad (12)$$

Thus C''_{min} is the minimum value of C necessary to eliminate the shift in restoring level caused by the vertical sync pulses.

FIG. 7—Sample calculation of measured restoring level



FIG. 8—Exponential change in restoring level during vertical sync pulses with various values of C



Circuit of second sync clipper whose output feeds the horizontal discriminator and vertical integrator



FIG. 9—Composite video signal at clipper grid with tube out

Measured Values

To illustrate all of the above points the components in an actual circuit were measured as 21,000 ohms for R_2, C of 0.01 μf and R_1 as 1.5 megohms. Measurements were made at the sync clipper grid with a suitable oscilloscope to measure sync pulse width and percent sync without excessive loading of the grid resistance R_1. Since the probe used with the scope had an input impedance of 5 megohms, this is taken into account by using a value of 1.155 megohms for R_1, the value of a parallel combination of 1.5 meg with 5 meg.

Using an r-f monoscope signal the percent sync was 17.5 percent (K_1 = 0.175) and the average level measured down from the sync tips was 68 percent (K_2 = 0.68) at the clipper grid with the tube removed. The relatively low percentage of



FIG. 10—Composite video signal at clipper grid showing restoring level



FIG. 11—Horizontal sync pulse before vertical sync pulse, 7.4 μsec wide



FIG. 12—Horizontal sync pulse after vertical sync, 5.2 μsec wide

sync and the rounding of the sync pulses as shown in Fig. 6 are due to a narrow-band sync amplifier used for greater noise immunity in the particular receiver on which these tests were made. This rounding of the sync pulses makes it more difficult to find the correct value for the charging time, t_1, so measurements of the sync pulse width were made at the top of pedestal and at 50 percent up toward the sync tips with results as shown in Fig. 6.

With the clipper tube back in the socket the percent sync was 7.1 percent before the vertical sync pulses and 14.0 percent after these pulses. From these readings we may find the measured restoring levels in percent down from the sync tips as shown in Fig. 7. The results are $L' = 64$ percent and $L_v' = 23.3$ percent.

To calculate the restoring levels we must know t_1 and t_2. When the sync pulses do not have a fast rise time a trial and error method for finding t_1 must be used. When the sync pulses are trapezoidal in shape with a fast rise time a close estimate of t_1 may be made; however this trial and error method should give more accurate results. Let us first assume $L = 65$ percent. Then interpolating linearly from Fig. 6 for t_1 between the bottom of the sync pulse and the 50-percent point we have $t_1 = 4.84$ μsec and $t_2 = 58.66$ μsec.

Putting the values into Eq. 6, $K_1 = 0.1805$. From Eq. 8, $L = K_1K_4/K_s = 70.2$ percent. Since this does not check with our assumed value of L we next assume $L = 68$ percent and find t_1 to be 4.96 μsec and $t_2 = 58.54$; K_1 is now 0.177 and L is 68.7 percent. The calculated value of L is between the two values and may be assumed to be 68.4 percent. This compared with the measured value of $L = 64$ percent. To find the calculated value of L_v from Eq. 11,

$$L_v = L\,e^{-t_2/R_2C} = 27.5 \text{ percent},$$

as compared with the measured value of 23.3 percent.

Checking assumptions of the value of x and y,

$$x = t_2/(R_1C) = 0.0051 \text{ and } y = t_1/(R_2C) = 0.0236.$$

Since x is less than 0.1 and y is less than 0.05 the assumptions are verified.

Coupling Capacitor

Using Eq. 9, we may find for particular values of R_1 and R_2 the value of capacitance above which any increase in capacitance has no effect on the restoring level when the vertical sync pulses are neglected. This value is

$$C'_{min} = 20t_1/R_2 = 0.0047 \ \mu f.$$

Table I—Calculated and Measured Values

	WCBS	Monoscope
With 6AG5 Clipper Out		
Percent sync—K_s	24%	17.5%
Average level from sync tips—K_4	66%	68%
Width of hor. sync pulse at bottom	6.74 μsec	6.28 μsec
Width of hor. sync pulse at 50% point	4.34 μsec	4.22 μsec
With Tube in Socket		
Percent sync at clipper grid before vertical sync pulse	12%	7.1%
Percent sync at clipper grid after vertical sync pulse	20.6%	14.0%
Measured Restoring Levels		
Before vertical—L'	56.8%	64 %
After vertical—L_v'	18.0%	23.3%
Calculated Restoring Levels		
Before vertical—L	53 %	68.4%
After vertical—L_v	21.4%	27.5%

The larger the value of C, the less will be the change in restoring level due to the vertical sync pulses. To compute this necessary value of C to reduce this restoring level change to 5 percent from Eq. 12,

$$C'_{min} = 20t_2/R_2 = 0.181 \ \mu f.$$

Figure 8 shows the effect of various values of the coupling capacitor on the restoring level change during the vertical sync pulses. These curves were found using Eq. 11 with R_s of 21,000 ohms.

As a further check, measurements were made on WCBS with a test pattern. The results of this and the above work are shown in Table I. The calculated and measured values of the restoring levels check well within the accuracy of the measurements.

Shown in Fig. 9 and 10 are photographs of the composite signal at the sync clipper grid with the tube out and with it in. This illustrates the restoring level variations with $C = 0.01$ μf. The photographs of Fig. 11 and 12 show the horizontal sync pulses before and after the vertical sync pulse respectively after another stage of amplification which has widened both pulses slightly.

The sync pulse before the vertical sync pulse is 27.7 percent wider than the one after this pulse; this may cause some trouble in the afc circuit for the horizontal sweep. Figure 8 shows that in order to eliminate this effect the coupling capacitor should be at least 0.1 μf when $R_1 = 1.155$ meg and $R_s = 21{,}000$ even though the noise immunity may suffer somewhat.

The writer thanks Bernard Amos for his comments and encouragement in the writing of this article.

VHF Field Intensities

Nomograph shows fields in microvolts per meter for transmitter powers up to 500 watts, antennas up to 500 feet, over obstructions as high as 10,000 feet in the frequency range between 20 and 260 mc

By E. A. SLUSSER *Assistant Radio Engineer, General Telephone Service Corp., New York, N. Y.*

IN PLANNING a new vhf point-to-point radio circuit, it is first necessary to make some estimate of the expected transmission between the two points in question in order to determine the feasibility of such a circuit. Likewise, in planning a new vhf mobile system the expected coverage over flat land and into shadowed areas must be predetermined. These estimated transmission figures can be used to assist in the selection of equipment and location of transmitter sites. Such estimates are usually made by means of profile maps and transmission nomographs.

Previous nomographs for estimating field intensities in the vhf frequency range have been made for small segments only of the total band of frequencies, thus necessitating several charts to cover the entire band. This nomograph enables one to select a given frequency in the range between 20 and 260 mc and estimate the field intensity for either transmission over smooth land or transmission over paths involving shadow losses. It assumes either horizontal or vertical polarization over land and horizontal polarization over sea water. It also assumes 50-watt transmitters and half-wave antennas elevated 40 feet above the ground, but supplementary conversion data is given for other powers and antenna heights.

To use the nomograph, it is necessary to draw an elevation profile of the intervening terrain between the two proposed station sites. An example is shown in Fig. 1. A triangle is constructed by drawing two lines from the station sites, *X* and *Y*, each tangent to the nearest hill or obstruction that blocks the line-of-sight path. A base line is also drawn to intersect the two sites, and a vertical line is drawn through the apex of the triangle and intersecting the base line.

The information taken from this figure includes: *D*, which is always the shortest distance in miles from one of the station sites to the vertical line; *H*, which is the height in feet along the vertical line between the apex of the triangle and the intersection of the base line; and the total transmission distance *D*. This information, along with a given frequency *F* in the vhf range, can be applied to the nomograph. The steps follow:

(1) A point on graph 1 is

(Continued on page 114)





FIG. 1—Sample elevation profile used with nomograph

CINCH FACILITIES AND ENGINEERING DEVELOPMENT

produced "first" and "another first" as rapidly as the need arose. And so well has each emergency been met in a fast progressing industry that each "first" has become a STANDARD. An example: the terminal strip designed by CINCH in the early days of sound transmission, "a first" is today a standard in TV sets.

CINCH'S Engineering Department invites you to submit your particular problem with the assurance, testified to by the record, of a satisfactory solution.





Cinch ELECTRONIC COMPONENTS

--are STANDARD

Available at leading Electronic Jobbers—everywhere

Cinch ELECTRONIC COMPONENTS

CINCH MANUFACTURING CORPORATION

CHICAGO 24, ILLINOIS

Subsidiary of United-Carr Fastener Corporation - Cambridge 42, Massachusetts

VHF Field Intensities (Continued from page 112)

located representing (F, D_1), and this point is projected horizontally to a point on scale A.

(2) H is determined and a line is constructed through H and the point on scale A. This line intersects B at some point.

(3) A point representing the frequency and the total distance (F, D) is determined on graph 2, and this point is projected horizontally to scale C.

(4) A line is constructed passing through the points on scales B and C and intersecting scale D.

(5) The estimated field intensity in db, referred to one microvolt per meter, is taken at the point where this line intersects scale D.

For estimating field intensity over smooth land, scale A is not used and H is taken as being zero.

The transmission estimates made by use of this nomograph are based on standard conditions. The data that are obtained are in general agreement with experience for smooth or mountainous terrain. The factors affecting vhf transmission are both natural (such as meteorological effects, type of soil and surrounding vegetation) and artificial (for example, antenna height, antenna gain, transmitter power and transmission-line loss). The latter items can be taken into consideration when making an estimate and a new equivalent field intensity (equivalent on the basis of a half-wave antenna) can be found.

A sample calculation can be made between locations X and Y by using the profile given in Fig. 1. Assume the following: at the transmitter end a 100-watt 150-mc transmitter using a three-element parasitic antenna having a gain of 6 db mounted on a 90-foot pole; on the receiving end another three-element 6-db-gain antenna mounted on a 30-foot pole; a combined transmission-line loss of 3 db at both ends. The answer is + 14.5 db.

By comparing the estimated data with the receiver input level requirements one can determine whether or not the circuit will be probably satisfactory. For the average receiver the performance can be taken from Table I.



FIG. 3—Conversion graph for receiver input voltage



FIG. 2—Conversion graph for antenna elevation and transmitter power

Table I—Expected Circuit Performance With Average Receiver

Frequency Range in Mc	Equivalent estimated field intensity in db referred to 1 μv per meter		
	Probably Unsatisfactory	Questionable	Probably Satisfactory
20–30	< − 5db	− 5 to + 5db	> + 5db
30–70	< 0	0 to + 10	> + 10
70–100	< + 5	+ 5 to + 15	> + 15
100–120	< + 10	+ 10 to + 15	> + 15
120–160	< + 10	+ 10 to + 20	> + 20
160–220	< + 15	+ 15 to + 20	> + 20
220–260	< + 15	+ 15 to + 25	> + 25

The above figures are based on average noise conditions but in extremely noisy areas it may be necessary to increase the figures by about 20 db.

In order to compare the above data with receiver sensitivity, it may be desirable to convert field intensity, which is given in terms of db above one microvolt per meter, to microvolts appearing at the receiver terminals. This can be done by means of Fig. 3. This figure assumes a half-wave antenna connected to the receiver terminals (72 ohms input) by means of a zero-loss transmission line. The voltage (for half-wave antennas) appearing on the receiver terminals is $0.32LE$ where L is the length of the antenna in meters and E the field intensity in microvolts per meter.

For the previous example, + 14.5 db equivalent field intensity at 150 mc corresponds to approximately 1.7 microvolts at the receiver terminals.

Mallory Vibrators

Roll Up Big Savings . . .
Protect Customer Good Will!

Reducing component parts costs—and at the same time, improving performance—is a welcome combination! The economy and dependability of Mallory Vibrators have made important contributions of this kind for Mallory customers.

Here's just *one* example! A radio manufacturer was receiving serious field complaints on vibrator performance. The substitution of two Mallory Vibrators—one a standard type, and the other especially designed for his problem—not only eliminated the difficulty but saved the customer $30,000 in vibrator costs alone! And the changes were accomplished with virtually no modification in circuit designs.

That's service beyond the sale!

And whether your problem is electronic or metallurgical what Mallory has done for others can be done for you.

MALLORY VIBRATORS

Mallory Vibrators are based on exclusive design and manufacturing methods that assure long, trouble-free service. Send the details of your application. Get Mallory's recommendation on the Vibrator or Vibrapack* power supply best suited to your needs.

Vibrators and Vibrapack* Power Supplies

P. R. MALLORY & CO. Inc.

MALLORY

P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

SERVING INDUSTRY WITH

Capacitors	Contacts
Controls	Resistors
Rectifiers	Vibrators
Special Switches	Power Supplies
Resistance Welding Materials	

*Reg. U. S. Pat. Off.

TUBES AT WORK

Including INDUSTRIAL CONTROL

Edited by VIN ZELUFF

Tubes Control Color Prints 116
Parallel-Pair Resistance Table of RMA Values 116
Shuttle Detector 118
Circuit of Photo-Etch Tuner 118
Curve Generator for Tubes 144
Checking Crystals 150
Thermistor Thermostats 154

Tubes Control Color Prints

MANY a company which wanted, say, 100 prints of its product in color for use by salesmen or point of sale displays, has winced when it got the estimate and decided to use black and white prints instead.

Electronic controls, plant air conditioning and improved transfer dyes have proved to be economical investments at Dye-Trans Color Photo Inc., of Oceanside, Calif., which has mechanized the dye transfer process of making color prints to about $24 a dozen for full-color 8 by 10-in. size and much less for larger runs.

Normally, filters are matched visually to the original color by an operator, but in a short time his eyes become tired and lose accuracy. Engineers at Dye-Trans combined an electronic scanner and a densitometer which keeps on judging colors accurately. The color separation and filter selection employs electronic gear which translates its readings into choice of the correct filter. Variations of one percent are the maximum compared with around 25 percent by conventional methods.

Dyes of the type used for fast fabrics prevent early fading of the color prints. Dye-Trans maintains uniform strength by means of electronic gages which can register imperceptible changes as little as one percent. Paper stretch and uniform drying of each matrix used in the color printing is controlled in the interest of exact registry by especially designed drying cabinets with closely regulated temperatures and slowly circulating air which reduces humidity gradually.

By these and other control methods, the new company is turning out prints at the rate of one every four minutes. The number of prints from each set of matrices is being limited to 100, although tests show much higher runs are possible. For subsequent prints,

(Continued on p 118)

Parallel-Pair Resistance of RMA Values

THE TABLE shown below gives the nominal resistance resulting from putting standard RMA resistors in parallel. Although some values are given to four-figure accuracy, only the first two figures are significant because the RMA resistors making up the pair may have at least five-percent tolerances.

Table of Resistance For Parallel Pairs of Standard RMA Values

	10	12	15	18	22	27	33	39	47	56	68	82
10	5	5.46	6	6.43	6.88	7.30	7.68	7.96	8.24	8.48	8.72	8.91
12	5.46	6.00	6.67	7.20	7.71	8.38	8.80	9.23	9.58	9.88	10.2	10.5
15	6.00	6.67	7.50	8.81	8.92	9.64	10.3	10.8	11.4	11.8	12.3	12.7
18	6.43	7.20	8.18	9.00	9.90	10.8	11.6	12.3	13.0	13.6	14.2	14.8
22	6.88	7.71	8.92	9.90	11.0	12.1	13.2	14.1	16.0	15.8	16.6	17.4
27	7.30	8.38	9.64	10.8	12.1	13.5	14.8	16.0	17.2	18.2	19.3	20.3
33	7.68	8.80	10.3	11.6	13.2	14.8	16.5	17.9	19.4	20.8	22.2	23.5
39	7.96	9.23	10.8	12.3	14.1	16.0	17.9	19.5	21.3	23	24.8	26.4
47	8.24	9.58	11.4	13.0	15.0	17.2	19.4	21.3	23.5	25.6	27.8	29.9
56	8.48	9.88	11.8	13.6	15.8	18.2	20.8	23.0	25.6	28.0	30.7	33.3
68	8.72	10.20	12.3	14.2	16.6	19.3	22.2	24.8	27.8	30.7	34.0	37.2
82	8.91	10.47	12.7	14.8	17.4	20.3	23.5	26.4	29.9	33.3	37.2	41
100	9.09	10.71	13.0	15.2	18.0	21.3	24.8	28.1	32.0	35.9	40.5	45.0
120	9.23	10.91	13.3	15.6	18.6	22.0	25.9	29.4	34.0	38.2	43.4	48.7
150	9.38	11.11	13.6	16.1	19.2	22.9	27.0	31.0	35.8	40.7	46.8	53.0
180	9.47	11.25	13.8	16.4	19.6	23.5	27.9	32.0	37.3	42.7	49.3	56.3
220	9.57	11.37	14.1	16.6	20.0	24.0	28.7	33.1	38.7	44.6	51.95	59.7
270	9.64	11.49	14.2	16.9	20.3	24.6	29.4	34.1	40.0	46.4	54.3	62.9
330	9.71	11.57	14.35	17.1	20.6	25.0	30.0	34.9	41.1	47.9	56.4	65.7
390	9.75	11.64	14.44	17.26	20.8	25.2	30.4	35.4	41.9	49.0	57.9	67.8
470	9.79	11.70	14.53	17.34	21.0	25.5	30.8	36.0	42.7	50.0	59.1	69.8
560	9.82	11.75	14.56	17.44	21.2	25.8	31.2	36.4	43.3	50.9	60.6	71.5
680	9.86	11.79	14.68	17.53	21.3	26.0	31.5	36.9	44.0	51.7	61.8	73.2
820	9.88	11.82	14.73	17.61	21.4	26.1	31.7	37.2	44.4	52.4	62.8	74.5
1000	9.90	11.85	14.78	17.68	21.5	26.3	32.0	37.5	44.9	53.0	63.6	75.8

The finest solder made for all television and radio work . . . Everything Electrical

Kester Solder

Uniform

Efficient

Kester Plastic Rosin-Core and Kester "Resin-Five" Core Solders are recognized by the trade as outstanding for the finest type of radio, television and electrical work.

These two Solders, which are available in the usual single-core type, can now also be had in a 3-core form.

Only highly skilled craftsmen are employed by the Kester Solder Company. Flux formulas and specifications are rigidly adhered to for perfect uniformity.

Making Kester Solder is an exact science from the raw material to the finished product. Everyone knows and prefers Kester because it can be relied upon to do the job right every time, even under the most difficult soldering conditions.

WRITE FOR FREE COPY "SOLDER AND SOLDERING TECHNIQUE"

Be sure to get your free copy of Kester's Technical Manual filled with valuable information regarding the most advanced and efficient industrial solders and fluxes.

EASIER TO USE

MADE FROM VIRGIN METALS

FASTER

ELIMINATES REJECTS

DEPENDABLE

SAVES TIME

Kester...Standard for the TV and Radio Fields

KESTER SOLDER

KESTER SOLDER COMPANY

4204 Wrightwood Avenue, Chicago 39, Illinois

Newark, N. J. • Brantford, Canada

matrices are soaked again in the dyes and the process repeated. Conventional methods find 10 color prints from one set of matrices is good and 20 or more exceptional. The time required for each print also is much longer than by the new process and skilled artisans must do the work.

Full color presentations of products has meant fine-screen four-color engraving or lithographing, with high plate costs, or individually processed color prints costing as high as $40 to $65 a print. The new type print, priced at $2 apiece in small runs and less in larger runs, will be made available through franchised commercial photographers and advertising agencies.

Shuttle Detector

AN ELECTRONIC shuttle detector in conjunction with dynamic braking control has been successfully applied to large felt looms to ascertain when a faulty shuttle flight occurs and to stop the loom before there is resulting damage to the fabric. Formerly, mechanical stops were used.

The equipment consists of two coils with cores connected by a bar magnet, a rotary switch, and a small control panel. The coils are imbedded in the lay; the switch is coupled to the loom topshaft. The electronic circuit is, in effect, a switch which closes as a result of the signal transmitted to it when the shuttle, in which a soft iron plate is embedded, passes over the coils. This electronic switch is connected in parallel with the rotary switch, and the two switches are together in series with the braking control of the G-E equipment.

During the sixty-degree interval in which the rotary switch is open, the electronic switch must be closed (signifying proper shuttle travel) for the loom to continue to operate. If the shuttle is late in its flight for any one of several reasons, opening of the rotary switch interrupts current flow to the braking relay and the direct current is applied to the driving motor. The device provides detection early in the loom lay cycle, and at a point where stored energy is low.

THE FRONT COVER

PHOTO-ETCH PROCESS used in manufacturing the RCA printed-circuit tuner begins with the photographing of the required coil arrangement. A contact print is made from the negative on a copper-clad sheet of phenolic plastic coated with a light-sensitive material. The print of plastic sheet is developed and placed in an etching solution where that part of the copper not covered by the circuit pattern is etched away. The desired copper circuit is left on the plastic sheet. The sheet is then placed in a die, cut into separate sections and pierced for contacts.

Circuit of Photo-Etch Tuner



Complete circuit of the RCA tuner shows the low-pass pi network and m-derived bandpass filter

THE PRINTED-CIRCUIT front end developed by RCA engineers is a turret-type tuner covering television channels 2 through 13, intended for use with stagger-tuned i-f systems such as used in the RCA 8TS30 receiver.

The input circuit consists of a pair of elevator transformers, with terminations for matching the tuner to a balanced 300-ohm line, followed by a high-pass filter section with cutoff at approximately 47 mc, and maximum attenuation at 23.5 mc for i-f rejection. This is followed by the tuned input section, composed of a low-pass pi network with cutoff tuned for each channel, providing gain and selectivity at the grid of the r-f amplifier, and reducing oscillator radiation at the antenna.

Controlled negative resistance has been introduced at the r-f grid to lower the input conductance on the high channels, and to neutralize partially the effects of cathode inductance. The constants and configuration of the pi network are arranged to provide a varying impedance transfer to the grid, and have been selected to provide optimum noise factor for all channels, rather than perfect impedance match. This compromise favors operation with indoor and built-in antennas.

The output of the r-f amplifier contains a double-tuned *m*-derived bandpass filter with the frequency of maximum attenuation tracked at approximately the image frequency of each channel. Use of the *m*-derived circuit provides high image attenuation and at the same time reduces oscillator feed-through to the r-f amplifier plate.

The circuit configuration and constants and the introduction of negative resistance at the mixer grid are such as to provide essentially constant gain and selectivity on all channels. Adjustable elements have been provided in each circuit to permit alignment for proper characteristics.

The oscillator employs a Colpitts

(Continued on p 144)

THE INSIDE STORY:

WHY SPRAGUE MOLDED TUBULARS OUTPERFORM ALL OTHERS!

Molded paper tubulars may look alike from the outside. But there's a whale of a difference inside—the part that really counts in the performance of your products.

The *exclusive* difference in Sprague molded phenolic tubulars is that: *each is made by the same dry-assembly process as large metal-encased oil capacitors.* They cannot be contaminated during manufacture!

Every Sprague molded tubular from 200 to 12,500 volts is molded *dry.* After molding it is impregnated under high vacuum through an opening in the eyelet terminal. A lead is then inserted and the terminal solder sealed. Result? A capacitor that offers you superior heat and moisture protection . . . top insulation resistance . . . high capacitance stability and retrace under wide temperature variations.

Small wonder then why Sprague molded tubulars are preferred for the toughest television and auto radio applications. Take advantage of this superiority by calling in a Sprague representative today. Or, write for Engineering Bulletins 210B and 214.

Hollow eyelet terminal for impregnation after molding
Non-flammable, dense bakelite phenolic-molded housing
CUT-AWAY VIEW
Solder seal as in large metal-encased oil capacitors
Uniform windings of high purity paper and aluminum foil

SPRAGUE®

PIONEERS IN ELECTRIC AND ELECTRONIC DEVELOPMENT

SPRAGUE ELECTRIC COMPANY
North Adams, Massachusetts

THE ELECTRON ART

Edited by JAMES D. FAHNESTOCK

Recording Microwave Refractometer 120
Phototransistor 122
Wideband Series-Parallel Transformer Design 122
Radiation Alarm with 0.5-Second Response 162
Television Picture Evaluation 163
Multiplier Phototube Improvements 166
Transistor and Fieldistor 167
Linear Sweep Generation 171
Surface Wave Transmission Line 175
Survey of New Techniques 176

Recording Microwave Refractometer

SMALL DIFFERENCES in frequency between two resonant cavities can be accurately measured and recorded by a refractometer recently developed at the National Bureau of Standards. The instrument can be adjusted over a wide band of microwave frequencies for measurements of dielectric constants of lossless gases and changes in the dielectric constant of such gases and very low-loss liquids and solids. Its extremely high sensitivity permits operation with small test samples.

The microwave refractometer should be readily adaptable to manufacture as a field instrument since the components and circuits are straightforward and compact. It has direct application in several fields of research and production, providing a convenient method for continuous monitoring of impurities in gases or liquids and for rapid testing of small solid samples. It can also be used as an ultramicrometer and to measure the thermal expansion of cavity materials.

The key operating principle of the refractometer is the comparison of two cavity resonators. A test sample (gas, liquid, or solid) is introduced into one of two otherwise identical cavities. The resultant difference in resonance frequency between the two cavities is then a measure of the dielectric constant of the test sample. Tests have shown that the sensitivity of the present instrument under laboratory conditions is 200 cycles per second at an operating frequency of 9,000 megacycles.

A klystron oscillator is used as a microwave signal source and is frequency-modulated with a sawtooth wave. The r-f output from the klystron is fed to a T-junction which sends equal parts of the signal to the two cavity resonators, one functioning as a test cavity, the other as a frequency reference. The cavity outputs are then fed through identical crystal detectors, amplifiers, and pulse sharpeners as shown in the block diagram. The pulse pairs, repeated at a rate determined by the sawtooth frequency, then go to a trigger circuit. The first pulse turns it on and the second turns it off. The output of the trigger circuit is a rectangular wave with constant amplitude but variable width. The average value of this wave as measured in a meter circuit is then directly proportional to the frequency difference between the two cavities, provided that the on time of the trigger circuit is also directly proportional to the frequency difference. The circuits have been designed to give this linear relation between time and frequency.



Block diagram of recording microwave refractometer



Refractive index of an artifically-controlled atmosphere is being measured by the refractometer. The difference in frequency of the two cavities is measured and recorded

In calibrating the microwave refractometer, it is desirable to use rare gases such as argon or helium whose dielectric constants have been measured very precisely at optical frequencies. For convenience the reference cavity is equipped with a tuning plunger calibrated in terms of the gas pressure in the test cavity.

The maximum sensitivity achievable by the refractometer is determined by its short-time stability, which depends essentially on background noise. Long-time stability depends chiefly on variations in temperature difference between the two cavities and the drift in center frequency of the klystron with temperature. When long-time stability is needed, both of these effects

Laboratory Instruments for TELEVISION

Type 202-B
FM SIGNAL GENERATOR

Frequency Range
54-216 mc.

Additional coverage from 0.4 to 25 mc. with accessory UNIVERTER Type 203-B

FM SIGNAL GENERATOR Type 202-B

The Type 202-B FM Signal Generator is specifically designed to meet the exacting requirements of television and FM engineers working in the frequency range of 54 megacycles to 216 megacycles. Following are some of the outstanding features of this versatile instrument:

- **RF RANGES: 54-108, 108-216 mc. ± 0.5% accuracy. Also covers 0.4 mc. to 25 mc. with accessory 203-B Univerter.**
- **VERNIER DIAL: 24:1 gear ratio with main frequency dial.**
- **FREQUENCY DEVIATION RANGES: 0-24 kc., 0-80 kc., 0-240 kc.**
- **AMPLITUDE MODULATION: Continuously variable 0-50%, calibrated at 30% and 50% points.**
- **MODULATING OSCILLATOR: Eight internal modulating frequencies from 50 cycles to 15 kc. available for FM, AM.**
- **RF OUTPUT VOLTAGE: 0.2 volt to 0.1 microvolt. Output impedance 26.5 ohms.**
- **FM DISTORTION: Less than 2% at 75 kc. deviation.**
- **SPURIOUS RF OUTPUT: All spurious RF voltages 30 db or more below fundamental.**

If you have an FM or television instrument requirement, let us acquaint you with full particulars and technical data concerning the Type 202-B FM Signal Generator and Type 203-B Univerter.

UNIVERTER Type 203-B

AVAILABLE AS AN ACCESSORY is the 203-B Univerter, a unity gain frequency converter which, in combination with the 202-B instrument, provides the additional coverage of commonly used intermediate and radio frequencies.

- **R. F. RANGE: 0.4 mc. to 25 mc. (0.1 mc. to 25 mc. with no carrier deviation).**
- **R. F. INCREMENT DIAL: ± 250 kc. in 10 kc. increments.**
- **R. F. OUTPUT: 0.1 microvolt to 0.1 volt, ± 1 db. Also approximately 2 volts maximum (uncalibrated).**
- **OUTPUT IMPEDANCE: Approximately 60 ohms at 0.1 volt jack, 470 ohms at 2 volt pin jack.**

BOONTON RADIO Corporation
BOONTON · N.J. · U.S.A.

DESIGNERS AND MANUFACTURERS OF THE Q METER · QX CHECKER FREQUENCY MODULATED SIGNAL GENERATOR · BEAT FREQUENCY GENERATOR AND OTHER DIRECT READING INSTRUMENTS

can be controlled by proper temperature regulation.

With solids and liquids very high sensitivity to small changes in dielectric constant could be obtained by filling the entire test cavity with the material. Except in the case of practically lossless substances, this would seriously decrease the Q of the cavity. If only a small fraction of the cavity volume is occupied by a low-loss substance (a small diameter cylinder is convenient for this work) the Q would not be appreciably affected and sufficient sensitivity would be maintained. The position of the sample with respect to the electric field in the cavity will determine the sensitivity of the refractometer to changes in dielectric constant. Small liquid samples can be measured by placing the liquid in a quartz tube.

The restriction to low-loss materials is necessary because the present equipment is sensitive to changes in the Q of the test cavity. However, a direct extension of present techniques would avoid this limitation completely and permit simultaneous recording of changes in dielectric constant and loss.

In measuring the dielectric constants of gases it is often convenient to use a flow technique in which a continuous stream of gas is drawn through the test cavity. This method has actually been used in a preliminary experiment to record variations in the dielectric constant of an artificially controlled atmosphere.

Similar measurements of the atmosphere are needed in radio propagation and meteorology. The recording microwave refractometer is now being studied for possible application to measurement of atmospheric refractive index. Such measurements might help to explain how high radio field intensities are produced at great distances by atmospheric scattering and duct processes. Many of the radio observations thus far made at frequencies above 30 megacycles cannot be explained by the ordinary refraction and diffraction calculations. Above 30 megacycles the change in refractive index with altitude and the fluctuations in refractive index in any small region of the atmosphere have a direct effect on radio propagation.

Phototransistor

THOUGH still in the experimental stage, the Bell Telephone Laboratories' new photoelectric transistor



Phototransistor has a single contact which rests on one side of a thin germanium disc. Light on other side of disc controls current flow

is expected to become an important component in the field of electronics.

The extreme compactness of the device is illustrated in the accompanying photograph. Operation of the phototransistor is similar to that of its parent device, the transistor, except that current flow is controlled by light rather than by the current of the emitter. Only one contact, the usual collector, is required, as shown schematically in Fig. 1.

This contact rests in a depression in a disc of germanium at a place where the germanium thickness is only 0.003-inch thick. Varying amounts of light falling on the opposite side of the germanium will cause corresponding variations in the collector current.

In operation, the collector is biased negatively with respect to the peripheral contact through a resistance R. Load power responses of the order of several tenths milliwatt per millilumen can be realized, and light modulation up to 200 kc has been followed with good fidelity.



FIG. 1—Schematic representation of phototransitor

Other advantages include low impedance and high sensitivity to the wavelengths emitted by incandescent light bulbs.

Wideband Series-Parallel Transformer Design

By VINCENT C. RIDEOUT
University of Wisconsin
Madison, Wisconsin

SERIES-PARALLEL tuned transformers may be used to match a low-impedance transmission line to a higher impendance line (Fig. 1A), or to give a flat-band connection between a low-impedance line and the capacitive input or output of an amplifier (Fig. 1B). Maximally-flat-response formulas are based upon a filter theory approach which uses the fact that the series-parallel transformer may be put into the

(Continued on p 160)



FIG. 1—Series-parallel transformers and normalized response curves for various bandwidth-to-midfrequency ratios

PHOTOGRAPHY

helps adjust an amplifier

Kodak
TRADE-MARK



A perfect square wave, photographed by engineers of Allen B. DuMont Laboratories, Inc., at the output of a high-frequency amplifier. This is the result of repeated adjustment and readjustment of a compensated attenuator and peaking coils.

Improper adjustment results in poor low-frequency response. Note tilt in top and bottom flats. Percentage of tilt is a measure of low-frequency response and low-frequency phase shift.



Effect of "under peaking" of high-frequency compensating inductances. Note that rise time of square wave has been distorted so that the leading edge is rounded instead of sharp.

"Over peaking" with extremely fast rise. This produces "ringing" in the leading edge of the square wave.



Far subtler differences than shown here can have large effects on performance.

How can you remember the all-important details of wave form? How can you show improvements achieved in the course of design changes and adjustments? How can you prove that a circuit long since gone from your bench behaved in a certain way?

With photography, of course. It's simple, it's indisputable, and it's permanent!

ONE FILM FOR ALL OSCILLOGRAPHY

To photograph cathode-ray traces from almost any kind of screen—whether repetitive patterns or the fastest transients—just load your camera with 35mm. Kodak Linagraph Pan Film. Your Kodak Industrial Dealer carries it in 100-foot rolls and 36-exposure cassettes.

EASTMAN KODAK COMPANY
Industrial Photographic Division
Rochester 4, N. Y.

INSTRUMENT RECORDING

...a function of photography

NEW PRODUCTS

Edited by WILLIAM P. O'BRIEN

Broadcast Engineers Are Offered a Wide Selection of Audio Equipment . . . Long Life and Small Size Continue as Major Factors in Tube Design . . . Current Catalogs and Other Manufacturers' Publications Are Summarized

Wide-Range Loudspeaker

JENSEN MFG. CO., DIVISION OF THE MUTER CO., 6601 S. Laramie Ave., Chicago 38, Ill. Model G-610 Triaxial loudspeaker spans the full frequency range of the ear. It actually consists of three distinct and separate loudspeaker units combined into one assembly no larger than a conventional 15-in. speaker and can be mounted in any cabinet or baffle suitable for a 15-in. unit. An electrical crossover network built into a separate chassis unit divides the input into separate bands of frequencies which are fed to the individual speaker units. Frequency response extends to at least 18,000 cycles with exceptional uniformity. Complete technical information is given in data sheet 160.



Micro-Manometer

CLARKE INSTRUMENT CORP., 910 King St., Silver Spring, Md. Model 179 micro-manometer is particularly adapted to the accurate measurement of pressures in the 5 to 50-micron range. It consists of the sensing unit and a separate sensitive and stable electronic indicator which can be mounted at some distance from the sensing unit. Indication of the pressure is independent of condensable vapor in the system and is read directly from the scale of a 4-in. meter calibrated in 1-micron steps and having a full-scale value of 50 microns.



Audio Oscillator

RADEX CORP., 2076 Elston Ave., Chicago 14, Ill. Model 500 audio oscillator was designed to meet the need for a lightweight, compact unit which retains the qualities of an R-C tuned oscillator with a wide range of output frequencies. It is desirable for use in conjunction with distortion meters or where an accurate check is to be made of any electronic circuit. Output is 10 volts into 2,000 ohms; internal impedance, 100 ohms at full output; frequency range, 14.5 to 145,000 cycles in 4 ranges; distortion, 0.25 percent with high impedance loads, 1.0 percent with 2,000-ohm load; power required, 30 watts, 110 volts a-c, 50 or 60 cycles.



Miniature Tubes

GENERAL ELECTRIC CO., Schenectady, N. Y., offers five new types of miniature tubes designed especially for long life and dependable service under conditions encountered in mobile and aircraft service. Type 5749 remote cutoff pentode has a transconductance of 4,400 μmhos and a plate current of 11 ma. The 5750 pentagrid converter for superhet receivers features a conversion transconductance of 475 μmhos. Features of the other three are as follows: the 5725 semi-remote pentode has a control grid and suppressor grid useful as independent control elements; the 5726 twin diode features high perveance; the 5686 pentode power amplifier has multiple leads on the cathode and screen grid which facilitate r-f by-passing at high frequencies.



Wide-Band D-C Amplifier

FURST ELECTRONICS, 12 S. Jefferson St., Chicago 6, Ill. Model 120 wide-band d-c amplifier has been designed to serve as a preamplifier in connection with a-c and d-c oscilloscopes, v-t voltmeters and similar instruments to extend their ranges to smaller signals. It has a frequency response d-c to 100,000 cycles within $\pm$ 1 db, 6 db down at 200,000 cycles. Noise and hum are less than 40 μv at maximum gain

HERE'S HOT NEWS FOR YOU!

RAYTHEON

FILAMENTARY SUBMINIATURES

OFTEN OUTPERFORM HEATER-CATHODE TUBES

1. They're *Rugged.* Many Raytheon filamentary subminiature types are just as shock resistant as the best ruggedized heater-cathode types. Many filamentary types also stand amazingly high accelerations.

2. They're *Long-Lived* Some Raytheon filamentary subminiatures have less than 1.5% rejects at 5000 hours. Others are designed for unusually high performance and shorter life. A wide range of tube designs are available.

3. They have *Low Microphonic Output.* Some Raytheon filamentary subminiatures actually have less microphonic output than the best heater-cathode types, particularly at frequencies below that of filament resonance for which 6000 cycles per second is typical.

4. They use *Low Operating Power.* For example, a voltage gain of 60 db may be obtained with only 0.019 watts of A power and less than 0.0001 watts of B power. Similarly many other electronic functions may be performed with a minimum of power, thus facilitating subminiaturization of equipment by reduction of heat.

5. *New types are constantly coming along.* Raytheon is constantly introducing improved types with new standards of performance. For example consider these filamentary long life types developed for the U. S. Navy.

A rugged triode which has passed tests up to 900 g. high impact shock and is particularly suited as an osc. up to 500 mc.
Medium-mu Twin-Triode for general purpose uses up to 500 mc. The total filament drain is only 120 ma per section yet the transconductance is 2300 umhos for each section. A similar tube, but of higher mu, is capable of unusual performance as a 400 mc mixer.
Remote cutoff 100 mc. pentode. The filament current is 60 ma. A remote cutoff twin pentode also has been developed for push-pull Class A amplifiers.
This VHF twin-tetrode is designed for Class C push-pull amplifiers. A power output of 600 mw can be obtained at 300 mc from a 135v plate battery.

Ask us to mail you a copy of the NEW Raytheon Special Tube *Characteristics Chart*

RAYTHEON

Excellence in Electronics

RAYTHEON MANUFACTURING CO.

SPECIAL TUBE SECTION
Newton 58, Massachusetts

SUBMINIATURE TUBES
GERMANIUM DIODES
and TRIODES
RADIATION COUNTER TUBES
RUGGED, LONG LIFE TUBES

referred to input terminals. Gain is set at 100. Input impedance is 1 megohm for single-ended; 2 megohms for push-pull signals.



Tweeter and Filter

ATLAS SOUND CORP., 1449 39th St., Brooklyn 18, N. Y. Model HR-2 multicellular tweeter reproducer and high-pass filter is designed for use in connection with any suitable type of cone speaker woofer. The horn, being of six-cell construction, offers a wide-angle distribution pattern and the response is clean and efficient to 15,000 cycles. The unit will handle 25 watts of program material above 1,000 cycles.

Oscillosynchroscope

BROWNING LABORATORIES, INC., 750 Main St., Winchester, Mass. Model ON-5 oscillosynchroscope is designed to provide wide-band amplifier and versatile sweep facilities in a single portable unit. It is well adapted to the study of pulse and transient phenomena and is useful in all conventional oscillographic applications. Vertical amplifier response is flat within 3 db from 5 cycles to 5 mc. The horizontal amplifier is direct-coupled with h-f response extending to 500 kc. Triggered sweep speeds from 1.0 μsec per in. to 25,000 μsec per in. and recurrent sweeps of 10 to 100 kc are available.

Rectangular Picture Tube

GENERAL ELECTRIC CO., Syracuse, N. Y. The 14CP4 rectangular tv picture tube is a 14-in. tube with a useful picture area of 99 sq in. and a neutral density faceplate for increased picture contrast and detail. Its electron gun is designed to be used with an external ion-trap magnet for prevention of ion-spot blemish. Maximum ratings are: anode voltage, 14,000 v; grid no. 2, 410 v; grid no. 1, 125 v negative and 0 volts positive bias.



Twelve-Channel TV Tuner

RADIO CORP. OF AMERICA, Harrison, N. J., has announced the type 206 E3 twelve-channel tv tuner employing printed-circuit coils and rotary-turret switching. The unit is for use with a stagger-tuned picture i-f system having a carrier of 25.75 mc and a sound i-f system having a carrier of 21.25 mc. This tuner provides a voltage gain of between 28.7 and 34.9 db for all channels under typical operating conditions. It is particularly useful in providing improved performance from receivers in fringe areas as well as from those operated with built-in antennas.



Tape Recorder

SONAR RADIO CORP., 59 Myrtle Ave., Brooklyn 1, N. Y., has introduced the T-10 high-fidelity, high-quality tape recorder for home and semi-professional use. The power amplifier has inputs for 2 low-gain and 3 high-gain microphones or radio. Frequency response is 20 to 20,000 cps, within 1 db, with a wow and flutter of less than 0.3 percent.



Subminiature Pentode

RAYTHEON MFG. CO., 55 Chapel St., Newton 58, Mass., is producing the CK5889 subminiature pentode designed for electrometer applications. Its more important design features are a 7.5-ma low microphonic filament, double-ended construction and a metallic guard ring. Maximum grid current is 3×10^{-9} amperes but the nominal value will be

(Continued on p 178)

Improved Lacquer Formulation gives

audiodiscs*

LOWEST SURFACE NOISE



GEORGE M. SUTHEIM, *Audio's Chief Chemist, has developed* two major improvements *in Audiodisc lacquer*



Plotted above are actual surface noise measurements made on an Audiodisc, and on two other makes of discs. Note particularly the *consistently lower noise level* of the Audiodisc.

This drastic reduction in surface noise is the result of an improved lacquer formulation – perfected last Fall, after almost 4 years of research. It has been gradually introduced into production, and since the first of the year, *all* Audiodiscs have been of the improved formulation.

Basically, it contains the same time-tested ingredients that have been used so successfully for the past decade. And it offers the same advantages of recording quality, uniformity, smooth cutting, long life and ease of processing.

The importance of this improvement will be appreciated by all professional recordists.

First was the moisture-resisting lacquer, perfected in 1948. This made all Audiodiscs permanently resistant to humidity – put an end to the "summer troubles" that had plagued the recording industry from the very start. This was followed by his development of the improved, low-surface-noise lacquer—a significant contribution to recording quality.

Mr. Sutheim, a graduate of the Institute of Technology in Vienna, is a chemist of exceptional experience in the field of lacquers and emulsions. He authored "The Introduction to Emulsions" and contributed largely to Dr. J. J. Mattiello's "Protective and Decorative Coating." He has also written many articles on coatings, films, etc., for both French and English periodicals.

Audiodiscs are manufactured in the U.S.A. under exclusive license from PYRAL, S.A.R.L., Paris.

AUDIO DEVICES, INC.

*Reg. U.S. Pat. Off.

444 MADISON AVE., NEW YORK 22, N. Y.

Export Dept.: ROCKE INTERNATIONAL, 13 East 40th St., New York 16, N. Y.

NEWS OF THE INDUSTRY

Edited by WILLIAM P. O'BRIEN

FCC Organizational Changes

THE Federal Communications Commission has announced the following organization and personnel changes concerning its broadcast engineering work:

The f-m, noncommercial educational (f-m) and facsimile broadcast functions of the F-M Broadcast Division, together with the personnel dealing with those functions, and the functions and personnel of the A-M Broadcast Division, are being placed in a new division to be called the Aural Broadcast Division. James E. Barr is to be chief of this division.

Functions and personnel of the F-M Division concerned with auxiliary broadcast (including developmental, remote pick-up, and studio-transmitter services) are being transferred to the Television Broadcast Division.

Cyril M. Braum, chief of the present F-M Broadcast Division, is being made chief of the Television Broadcast Division to fill the vacancy created by the promotion of Curtis B. Plummer to chief engineer.

Functions and personnel concerned with international broadcasting are being transferred from the Television Broadcast Division to the immediate office of the chief engineer.

Parts Distributors Show

OVER two hundred manufacturers exhibited their wares at the 1950 Parts Distributors Conference and Show held at the Hotel Stevens, Chicago, May 22–25. The affair was conducted by Radio Parts & Electronic Equipment Shows Inc. which in turn is sponsored by the Association of Electronic Parts and Equipment Manufacturers (Midwestern sales managers group); Radio Manufacturers Association; Sales Managers Club, Eastern Group; West Coast Electronic Manufacturers Association; and National Electronic Distributors Association.

Credit for the successful affair goes to the show officers: K. C. Prince, general manager; J. J. Kahn, president; W. W. Jablon, vice-president; L. A. Thayer, treasurer; W. O. Schoning, secretary; and directors Sprague, Golenpaul, Jenkins, Hansen and Howard, plus many other cooperating groups including the Representatives of the Radio Parts Manufacturers Inc.

Exhibits numbering 290 filled the exhibit hall and demonstration rooms on the fifth and sixth floors. Fifty companies showed components and accessories; 28, television antennas; 16, loudspeakers; 12, transformers; 12, electron tubes; plus others exhibiting tape and disk recorders, needles, test equipment as well as all other kinds of parts and equipment.

Signal Corps Exhibits at Fort Monmouth

ARMED FORCES WEEK ending May 20, 1950 was celebrated at Fort Monmouth, N. J., Signal Corps Center by open house for both military and civilian visitors. Exhibits housed in tents or in their own mobile trailers were arranged to show a cross-section of the activities in which the various laboratories are engaged. Nearly 60,000 visitors were estimated to have seen the hundreds of standard equipments, prototypes and mock-ups displayed.

One tent housed a historical display that traced the rise of the Signal Service from Civil War days. Besides documents relating to the founder, Gen. Myers, an Army surgeon, there were several equipment firsts, including Major Armstrong's superheterodyne built in France during the first World War.

In direct contrast were the Watson Laboratory developments in high-definition radar suitable for airport ground surveillance and a cloud-height finder to show graphically the thickness and elevation of a cloud layer directly overhead.

This new inflateable rayon radome displayed at Fort Monmouth is selfsupporting and therefore requires less radar-opaque material. Once inflated, it requires only as much pressure as that generated by the conventional tank-type vacuum cleaner. Its purpose is to protect the pedestal and antenna of radar set against Arctic cold

In the field of communications, one striking development is a vhf 1-kw amplifier that automatically tunes itself to the frequency of the 100-watt driving signal and matches its output into an antenna.

Other exhibits included the MARS network station K2USA, radar with moving-target indicator, long-range navigation equipment, rocket telemetering devices, improved power supplies, arctic shelters and a teletypewriter repair school.

RCA Expands Tube Manufacturing

PURCHASE of a new building by RCA provides an extra 126,000 sq ft of space to expand electron tube manufacturing facilities at its Harrison, N. J., plant. This highlights a major program of expansion (of plant facilities, machinery and personnel) by the RCA Tube Department to meet increased requirements of the television and electronic industries. Over 500 additional people will be employed at the new building.

Currently, all of the company's tube plants—at Indianapolis, Lancaster, Marion and Harrison—are



Lavoie

DEVELOPED and PRODUCED ELECTRONIC SYSTEMS





For Example:

① **VHF Omnidirectional Radio Range System** for aircraft navigation. This system has been standardized by international agreement as the best method of short range navigation for aircraft.

② **Time Standard.** A precision time standard, providing standard frequency and time service.

③ **Range Transmitter.** A 200 to 400 KC four course aural A-N Radio Range Transmitter with an output of 100 watts. Adcock or loop antenna; simultaneous voice modulation; telephone dial remote control.

. . . DEVELOPED • DESIGNED • PRODUCED by LAVOIE LABORATORIES and typical of both LAVOIE engineering versatility and LAVOIE manufacturing skill. As UHF *specialists*, we have the experience and the facilities for precise production at low cost.



LAVOIE FACILITIES REPORT

• Address us on your letterhead—and we shall be glad to send you a copy, or consult with you at your convenience.

Lavoie Laboratories, Inc.
RADIO ENGINEERS AND MANUFACTURERS
MORGANVILLE, N. J.

Specialists in the Development and Manufacture of UHF Equipment

RCA'S new Harrison tube plant

running at full capacity and progressively achieving new all-time highs in the volume of their output. All are working on extended-hour, extra shift schedules, and collective employment is at its peak.

Electronic Aero-Aid Tests

FIELD operations were recently completed at Hill Air Force Base near Ogden, Utah, on a comprehensive evaluation of a new electronic aid to air navigation. This evaluation has been carried out jointly by engineers of Airborne Instruments Laboratory, Mineola, N. Y., and of Aero Service Corporation, Philadelphia, Pa., assisted by several government agencies, including the U. S. Air Force and the Civil Aeronautics Administration.

The tests were carried out under a contract between the All-Weather Flying Division of the USAF and AIL as prime contractor. Aero Service Corp., as subcontractor, was responsible for certain phases of the work. The basic planning of the tests was done by the Air Navigation Development Board, a governmental board having general cognizance over the development of aids to air navigation. The board consists of representatives from CAA, the Air Force, the Army and the Navy.

The principal equipment which was tested is the Visual Omnidirectional Range, or VOR. The VOR station located just west of Ogden was selected for these tests as being typical of a valley installation in mountainous terrain. Previously, the same group had tested the VOR stations located at Philipsburg, Pa., and at Patuxent River, Md. These sites were chosen as typical of a mountain-top installation and of a flat-land installation, respectively.

During the tests a C-47 aircraft was tracked by shoran (Short Range Navigation), a war-developed aid to precision blind bombing. At intervals, photographs were taken of an array of instruments which could then be interpreted at some later time. In the course of the tests of the Ogden VOR some 22,000 pairs of photographs were taken of the two instrument panels. Altogether, 55,000 pairs of photographs were made.

In addition to the VOR equipment, a special distance measuring equipment or DME was tested. This equipment provides the aircraft pilot with a simple direct visual reading of his distance away from the VOR-DME station, while the VOR provides similar information of his magnetic bearing from the station.

A considerable number of VOR stations have been installed and are being operated throughout the U. S. by the CAA. These are coming into use by military, commercial and private aircraft. The DME feature, while not a part of the present stations, will become one within the next few years. For these tests, a special experimental model equipment was installed at each of the sites tested. It is anticipated that as these newer facilities come into widespread use, the older and less versatile low-frequency four-course ranges will be retired from use.

UHF Experiments Planned

CHEYENNE MOUNTAIN, Colorado, has been selected as the most suitable site for a series of uhf radio experiments conducted by the Central Radio Propagation Laboratory of the National Bureau of Standards. The transmitters placed on this point (9,300 feet above sea level) will be used in obtaining the radio propagation information needed for the development of systems of air navigation, air traffic control and aircraft communication. Measurements will be made over a simulated aircraft-to-ground radio propagation path by use of sensitive receiving stations located on a radial path extending eastward to distances of about 400 miles.

The research is undertaken as one of the many services of the Laboratory to all users of radio, including the Department of Defense, the Civil Aeronautics Administration, the Federal Communications Commission and other government agencies, as well as the radio indus-

(Continued on p 202)

MEETINGS

JUNE 26–30: Annual Meeting and 9th Exhibit of Testing Apparatus and Related Equipment, Hotel Chalfonte-Haddon Hall, Atlantic City, N. J.

JUNE 26–JULY 22: Summer Electronics Symposium (Microwave Electron Tubes), University of Michigan, Ann Arbor, Mich.

JULY 24–AUG. 19: Summer Electronics Symposium (Semiconductor Electronics), University of Michigan, Ann Arbor, Mich.

JULY 24–27: Conference on Ionospheric Physics, The Pennsylvania State College, State College, Pa.

AUG. 27–31: NEDA National Convention and Exhibition, Cleveland Public Auditorium, Cleveland, Ohio.

AUG. 28–31: APCO National Conference, Hotel Hollenden, Cleveland, Ohio.

SEPT. 11–23: URSI Ninth General Assembly, Zurich, Switzerland.

SEPT. 13–15: 1950 IRE West Coast Convention and Sixth Annual Pacific Electronic Exhibit, Municipal Auditorium, Long Beach, Calif.

SEPT. 18–22: Fifth National Instrument Conference and Exhibit, Memorial Auditorium, Buffalo, N. Y.

SEPT. 25–27: National Electronics Conference, Edgewater Beach Hotel, Chicago, Ill.

SEPT. 30–OCT. 8: Third Annual National Television & Electrical Living Show, Chicago Coliseum, Chicago, Ill.

OCT. 3–5: AIEE District No. 2 Meeting, Lord Baltimore Hotel, Baltimore, Md.

OCT. 23–27: AIEE Fall General Meeting, Skirvin Hotel, Oklahoma City, Okla.



Typical 1N56 Resistance Characteristic

For low impedance applications...

SYLVANIA Germanium Diodes

All Germanium Diodes are notable for their low forward impedance. But the 1N56 is specially engineered to make the most of this quality.

Use this diode for high efficiency circuits with low input and output impedances. Use it for relay activation, heavy current and surge applications with low impedance coils, transformers and condensers.

Try the 1N71 varistor in carrier telegraphy and telephony work. The low shunt capacitance insures high efficiency throughout the high frequency range. You will find this varistor equally efficient in low impedance modulator circuits of the carrier suppression or carrier transmission type.

Both the 1N56 Germanium Diode and 1N71 Varistor are available from Your Sylvania Distributor. Also ask him for a copy of the new book "40 Uses for Germanium Diodes." Priced at only $1.00, it is the most complete collection of germanium diode applications yet published. ***Call him today . . . or mail the coupon below.***



1N56 DIODE with a potential of +1 volt will pass a current of 15 ma. or more. With a potential of −30 volts, less than 300 μa. will flow.

For Carrier Communications

1N71 VARISTOR—The 1N71 consists of 4 matched low impedance diodes each of which, with +1 volt impressed, will pass a current within one ma. of the average current of the four.

ELECTRONIC DEVICES; RADIO TUBES; TELEVISION PICTURE TUBES; ELECTRONIC TEST EQUIPMENT; FLUORESCENT LAMPS; FIXTURES; SIGN TUBING; WIRING DEVICES; LIGHT BULBS; PHOTOLAMPS; TELEVISION SETS

SYLVANIA ELECTRIC

Sylvania Electric Products Inc.
Dept. E-1007, Emporium, Pa.

Please send me a copy of "40 Uses for Germanium Diodes." Enclosed is $1.00.

*Name*_____

*Street*_____

*City*_____ *Zone*___ *State*_____

NEW BOOKS

Recent Advances in Radio Receivers

BY L. A. MOXON. *Cambridge University Press, New York*, 1949, 183 *pages*, $3.75.

ABOUT half of this book is devoted to one of the most important concepts in present-day receiver design —that of noise factor. Its applications to minimum noise factor design of amplifiers and mixers are covered along with procedures for measurement of noise factor. The remainder of the book is a miscellaneous collection of odds and ends which the author has apparently studied and used. Chapter titles are selfexplanatory: Intermediate Frequency Amplifiers; Trends in Practical Receiver Design; Some New Kinds of Receivers; Some New Circuit Tricks.

Unfortunately, the style wanders between conciseness and looseness. A number of unfortunate typographical errors (such as in the basic definition of noise factor) and poor use of the English language (as in a sentence using "very high bandwidths and . . . . narrow bandwidths" as a parallel construction) detract from the utility of the book. However, in spite of the many criticisms that may be leveled at the author for his errors, there are many examples of clear thinking on his part, which bring out points in the noise factor concept not always appreciated by receiver designers. The first half of the book is worth-while reading for anyone associated with the subject. The second half of the book reads like a review article for a magazine and contributes nothing of consequence.

A book of about the level of the first half of the book reviewed, and of about the same size, devoted entirely to the concept of noise factors and its impact on modern receiver design, would be welcomed. Moxon has tried to fill this need, but has not quite succeeded.—MATTHEW T. LEBENBAUM, *Airborne Instruments Laboratory, Mineola, N. Y.*

RELEASED THIS MONTH

Electronics Engineering Master Index 1947-1948: *Electronics Research Pub. Co., New York: $19.50.*

Electronic Navigation: Leonard M. Orman: *Weems System of Navigation. Annapolis: $4.50.*

Electronics—Principles and Applications: *Ralph R. Wright: Ronald Press: $5.50.*

Electronic Valves *(Philips Technical Library): Elsevier Pub. Co., New York: Book II. $2.75; Book III. $1.90; Book IV. $5.00.*

Questions and Answers in Television Engineering: *Rabinoff and Wolbrecht: McGraw-Hill: $4.50.*

Aerials for Metre and Decimetre Wavelengths

BY R. A. SMITH. *Cambridge University Press, New York*, 1949, 218 *pages*, $3.75.

THIS volume is one of the Modern Radio Technique Series which deals with the advances made in Great

(Continued on p 134)

BACKTALK

This Department is Operated as an Open Forum Where Readers May Discuss Problems of the Electronics Industry or Comment Upon Articles that ELECTRONICS has Published

Automatic Focusing

DEAR SIRS:

SINCE I MISSED Mr. Kallmann's IRE presentation, your story in the April issue on Optar is a very welcome substitute, especially because the subject matter is one that has also engaged my attention.

Some four years ago, I submitted to the Bureau of Ships (Navy Department), for certain radar applications, an almost identical method of automatic image focusing. This was based upon some original experimental work of about 15 years ago, in which the image field was scanned laterally by a lens, which was also given an axial motion sufficient to vary the focus within the required range; a photocell and a small optical aperture completed the arrangement. When in sharp focus, the highlights and shadows produce abrupt discontinuities in the rapidly changing illumination of the photocell, whose amplified a-f output is heard as a strong band of random noises. With out-of-focus, fuzzy images, the illumination discontinuities are gradual or hardly discernible, so that the signal noise is weak and in a lower frequency band. Suitable responders provided the focusing control.

I have also applied these principles of automatic focusing with some additional arrangements for use in an aid-to-the-blind device. In this a tone signal is produced in which loudness corresponds to image brightness, pitch corresponds to image distance, and tone quality corresponds to image color.

All of these correlations between visual and aural characteristics are obtained by a very simple arrangement with only one moving part, driven by a spring motor.

B. MIESSNER
Miessner Inventions, Inc. Morristown, N. J.

Industrial Revolution?

DEAR SIRS:

LET ME be one of the readers (and I'll bet it will be many times the five you specified) to urge the publication of the electronic problems series proposed in the "Quiz" paragraph in the March, 1950 issue.

While commenting on "Crosstalk" I should like to call your attention to the article on "Egg Processing Equipment" in *Tubes at Work*, same issue, in connection with your paragraph on cybernetics,

(Continued on p 208)

A NEW LINE OF TV TEST EQUIPMENT FOR PRODUCTION LINES . . .

Designed and Field Tested for Speed Testing by your line operators . . . . .

THE MARKA-SWEEP
MODEL RFP



SWITCHABLE 12 CHANNEL RF SWEEP with CRYSTAL POSITIONED MARKERS—

- SAWTOOTH SWEEP: No phasing controls—
- SWEEP WIDTH: 15 megacycles
- ALL ELECTRONIC: No mechanical moving parts.
- MARKER PIPS ALWAYS VISIBLE: Crystal positioned pix and sound carrier pulse type marks not affected by test circuit.
- OUTPUT LEVEL and IMPEDANCE: Approx. 0.5 volts from 70 ohms unbalanced, 1.0 volt from 300 ohms balanced into open circuit —
- ATTENUATORS: Switched and continuously variable independent controls on sweep and marker pips —
- BASELINE establishes true zero amplitude
- MODEL RFB at lower price with crystal controlled "birdie" markers and CW at TV pix and sound carriers and 4.5 mc at CW available.
- POWER SUPPLY: Electronically regulated —

Price $795.00

THE MARKA-SWEEP
MODEL IF

A COMPLETE SWEEP with CRYSTAL CONTROLLED MARKERS

- SAWTOOTH SWEEP: No phasing controls
- SWEEP WIDTH: 15 megacycles
- ALL ELECTRONIC: No mechanical moving parts
- FREQUENCY COVERAGE: Front panel switch selects any IF band
- MARKERS: Up to nine pip type marks (not affected by test circuit) at frequencies specified by customer, individually switched on or off by front panel switches—Crystal controlled, easily changed to new frequencies.
- SOUND I.F. SWEEP: Panel switch selects sweep for sound in either dual i.f. or inter-carrier sets.
- OUTPUT LEVEL and IMPEDANCE: Approx. 0.5 volt from 70 ohms unbalanced into open circuit.
- ATTENUATORS: Switched and continuously variable controls on sweep and pips.

Price $295.00 plus $15.00 for each marker.

THE SWITCHA-SWEEP

SWITCHTABLE 12 CHANNEL RF and IF SWEEP —

- SAWTOOTH SWEEP: No phasing controls
- SWEEP WIDTH: 15 megacycles
- ALL ELECTRONIC: No mechanical moving parts
- OUTPUT LEVEL and IMPEDANCE: Approx. 0.5 volts from 70 ohms unbalanced into open circuit.
- IF SWEEP: Available for all present I.F. ranges
- ATTENUATOR: Switched and continuously variable controls.
- BASELINE: Establishes true zero amplitude
- MARKERS: May be used with all KAY marker devices

Price $295.00

THE DUAL-MEGA MARKER SR.

- A crystal-controlled high output TV RF marker generator provides both sound and picture RF markers on each TV channel.
- Crystal controlled 4.5 mc signal also available.
- Output attenuators on RF and 4.5 mc signals.
- Carrier frequency accuracy 0.01% for picture.
- Carrier separation 4.5 mc±500 cps.

Price $350.00

All prices F.O.B. Factory—10% Higher Outside U. S. A. and Canada

ELECTRIC KAY COMPANY

25 Maple Avenue — Pine Brook, N. J.

Phone CAldwell 6-4000

always ahead WITH THE NEWEST AND THE BEST IN PLUGS

RADIO TERMINAL SERIES (left)

for radio chassis installations where low separation force is required. Leaf type contacts, with eyelet on terminal of plug side; crimp or solder holes on receptacles. Available in more than 5 sizes, for 18 or 20 wire; 5-amps; 2500 volts min. flashover.



HERMETICALLY SEALED SERIES (right)

The "GS" or glass-sealed types are built for special equipment requiring a hermetic seal. AN-type layouts in limited selection for No. 12 wire or smaller; steel shell and contacts. Available with coupling nut (GS06 types) as well as GS02.

DPM RACK AND PANEL TYPES (left)

Smaller than standard "DP" types with similar contact arrangement for mounting where dimensions must be kept at a miuimum. Phenolic insulators; 120 volt, 10 and 5-amp. contacts. Fourteen and twenty contact arrangements available.



RUBBER SEALED TYPES FOR RELAYS (right)

The "RS" types are rated as AN-"D" seal, which allows a minimal leakage. Used with relays, and carries standard AN inserts and coupling nuts.

Write to Cannon Electric Development Co., Division of Cannon Manufacturing Corp., 3209 Humboldt St., Los Angeles 31, Calif. Canadian offices and plant: Toronto, Ontario. World Export: Frazar & Hansen, San Francisco.

SINCE 1915

CANNON ELECTRIC

REG. U.S. PAT. OFF.



Britain during the war. The author discusses the theory and technique of antennas for the wavelength range between 12 meters and 10 cm, and deals primarily with linear antennas and dipoles.

The first four chapters cover the basic theory of the linear antenna and give a concise and excellent discussion of polar diagrams, input impedance, mutual impedance, power gain, reciprocity and other elements of antenna theory. The impedance properties are based largely on the sinusoidal theory, but a short discussion of the integral equation method and the theory of the biconical antenna along with a comparison of theory and experiment serves to give the reader some orientation as to the present state of the fat dipole theory.

Chapter 5 discusses reflectors and directors and their effect on the polar diagram and input impedance. Chapters 6 through 14 deal with the applications and techniques of antenna design which have been selected to illustrate the general principles. These applications include receiving and transmitting antennas for low-frequency radar, aircraft antennas, wide-band antennas and slot antennas. The applications are selected mainly from British experience.

Dr. Smith closes his book with a short chapter on antenna noise and its effect on the receiver. The book is written in a very readable fashion and has a fairly complete list of references. It is recommended to those engineers who have occasion to design or use antennas. —HENRY JASIK, *Airborne Instruments Laboratory.*

Cathode-Ray Tube Traces

BY H. M. MOSS. *Published by Electronic Engineering, 28 Essex Street, Strand, London, W. C. 2, England, 66 pages, 10/6.*

THE MAIN purpose of this book is to analyze the more common cathode-ray tube traces by means of the geometrical theory of the pattern. The text is chiefly mathematical derivations of the formulas of the more common waveshapes, with little attention given to the production of the waveform or the specific



The Less Getter the Better

BECAUSE FREQUENCIES ARE HIGHER AND TUBES ARE SMALLER

IF you manufacture small electronic tubes, DPi's new VMF-5 Exhaust Unit pictured here can provide a happy ending to your quest for lower, more consistent residual gas pressure.

With today's push toward ever-higher frequencies, you can't afford to ignore the effect of residual gas on the low capacitance demanded in tubes. And with the small size of today's tubes, you can't use much getter to "clean up" residual gas, because the metallic film deposited can result in serious inter-element leakage.

VMF-5 Exhaust Units quickly take pressure down to 0.1 micron Hg before the getter flash, as compared with the 10- to 100-micron pressures to which older equipment limits you. They come equipped with water-cooled ports that fit any standard tubulation or can be fitted with ports of your own design. Two a-c solenoid valves (or three if required by the design of your rotary exhaust machine) isolate the diffusion pump during roughing.

The VMF-5 is just one of a series of high vacuum pumps designed by DPi for the specific conditions of the electronics industry. They are made in a wide range of pumping speeds.

Before you go ahead with the design and production of a tube exhaust system, call on DPi. There's no obligation, of course, and chances are that DPi can help build better reliability into your product at less cost.

VACUUM EQUIPMENT DEPARTMENT

DISTILLATION PRODUCTS *industries*

727 RIDGE ROAD WEST, ROCHESTER 3, N. Y.

Division of Eastman Kodak Company

DPi

HIGH VACUUM RESEARCH AND ENGINEERING

PRESTO... *most carefully made recording discs in the world*

step 1-preparing the aluminum base

The manufacture of recording discs is one of the most exacting industrial processes known. That's why PRESTO... makers of the world's finest recording disc ... insist on perfection from the beginning. They know that the slightest flaw in the aluminum base will always show up as an imperfect disc. Consequently, the careful selection and preparation of every aluminum blank is PRESTO'S first requirement.

Aluminum...milled to exacting specifications...rolled to absolute uniformity of thickness...die-cut into perfect circles...must pass rigid inspection before it is used. Approved aluminum discs are then punched and the burr removed from the edge. With special solvents, the aluminum surface is cleaned and polished to shimmering smoothness...the perfect foundation for every PRESTO disc.

The next time you buy recording discs ... look for the PRESTO label. It is your assurance of the most carefully made, most permanent, best-performing disc anywhere.

The famous PRESTO "Green Label" ... world's finest recording disc.

PRESTO
RECORDING CORPORATION
Paramus, New Jersey
Mailing Address:
Box 500, Hackensack, New Jersey

In Canada:
Walter P. Downs, Ltd.
Dominion Sq. Bldg.
Montreal, Canada

Overseas:
The M. Simons & Son Co., Inc.
25 Warren Street
New York, N. Y.

circuit from which it was obtained. This is a novel approach and certainly worthy of the engineer's attention.

This is an excellent book for the engineer who has had considerable experience with the cathode-ray oscillograph. The author presupposes a knowledge of oscillography and electron physics, so that the book is not suitable for beginners.

Chapter 1 is devoted to the basic theory of the Lissajous figure and its geometric derivation. Various cases are discussed and the formulas for determining phase angle and frequency ratio are derived.

Chapter 2 is concerned with straight-line time bases, covering both sinusoidal and linear time bases. The same mathematical treatment is accorded to every topic. Chapter 3 covers the other types of time bases, chiefly circular and spiral.

Chapter 4 deals with Fourier analysis of complex waveforms, with considerable attention given to the subject of beats. Chapter 5 discusses amplitude-modulated waves, giving a careful distinction between modulated waves and beats.

This book may be summarized as being an excellent and careful mathematical text for the engineer specializing in oscillography. It is well written, and judiciously illustrated with very excellent oscillograms.—J. H. RUITER, *Allen B. Du Mont Laboratories, Instrument Division, Clifton, N. J.*

The Recording and Reproduction of Sound

BY OLIVER READ. *Howard W. Sams & Co., Inc., Indianapolis, Indiana,* 1949, 364 *pages,* $5.00.

THIS is a book written more from the point of view of the technician than that of the engineer. It begins with a brief discussion of sound waves, the ear and music, followed by a chapter on the history of acoustical recording. The historical material, although incomplete, is fascinating reading for anyone interested in the field of the storage and reproduction of music. Basic methods of recording are then considered as a group, with subsequent individual chapters on disk and magnetic recording. Microphones

A SIMPLE ACOUSTIC CALIBRATOR for Your Sound-Level Meter



THE G-R Type 759-A and -B Sound-Level Meters have built-in calibrators for their electrical circuits; no means are readily available, however, to check the condition and calibration of their associated microphones.

The new Type 1552-A Sound-Level Calibrator is introduced as a simple, convenient and accurate method for calibrating both the microphone and the over-all system. Essentially it consists of a small, stabilized and rugged loud-speaker mounted in an enclosure which fits over the microphone in the sound-level meter. The acoustic coupling between the calibrator and the microphone is fixed and can be repeated accurately. Any audio oscillator with a harmonic content of less than 5%, supplying 2 volts at 400 cycles, can be used to operate the calibrator. A 500-ohm potentiometer is required as an output control if the oscillator is not equipped with such a control. An accurate vacuum-tube voltmeter is needed to measure the voltage across the calibrator.

The level at which the calibrator is used is such that its operation is not affected by ordinary background noises. This simple device is an ideal means not only for assuring consistency of calibration and locating defective microphones, but also for inter-standardization of several sound level meters.

The audio oscillator, v-t voltmeter and potentiometer shown in the set-up photograph are standard G-R items. If you need these or if you do not know about the complete line of G-R noise and vibration measuring and analyzing equipment. **WRITE FOR THE "NOISE PRIMER".**

The Sound-Level Calibrator was designed for use primarily with the Shure Brothers Type 98S8 microphone as used on the G-R Type 759-B Sound-Level Meter. It can be used on other microphones such as the Brush BR2S Sound Cell Microphone and the Western Electric Type 633-A Dynamic Microphone.

TYPE 1552-A Sound-Level Calibrator $45.00

GENERAL RADIO COMPANY Cambridge 39, Massachusetts

90 West St., New York 6 · 920 S. Michigan Ave., Chicago 5 · 1000 N. Seward St., Los Angeles 38

● *Our Engineering Department will assist you in the design and application of high quality fine pitch gears, worms, etc., without obligation. We invite you to submit your prints for quotation.*

Gear

REFLECTIONS...

● Gears are the motivating force in such units as highly sensitive instruments, fishing reels, timers, tuning devices, or gear reducers. The smooth operation and often the success of these units depends on the quality of gears used.

● Quality-made gears reflect the ability and experience of their maker. In turn, they also reflect the reliability of the unit in which they are installed.

MEMBER OF

SEND FOR BULLETIN

Beaver Gear Works Inc.

1021 PARMELE STREET, ROCKFORD, ILLINOIS

Permanent Magnet Problems
Can Be Simple . . . If You Have:

✓ Quality Magnets
✓ Prompt Delivery
✓ Complete Engineering Service
✓ Low Unit Cost

For 49 years Thomas & Skinner has geared its facilities to provide the answer to all permanent magnet problems.

Why not let Thomas & Skinner engineers work with you in the design and production of the *right* permanent magnet for your application? Write or call us today.

THOMAS & SKINNER — *Specialists in magnetics: permanent magnets and laminated cores*

THOMAS & SKINNER Steel Products Company
1120 East 23rd Street · Indianapolis, Indiana

and loudspeakers are treated, and considerable material on pickup devices and tone-arms is given.

Although perhaps not an outstanding contribution to the literature of electrical sound recording and reproduction from the engineer's point of view, the book contains much useful material for the technician and for the enthusiast who is interested in phonograph recording and reproduction. It brings together in one set of covers information which until now has largely been scattered through back issues of periodicals and various instruction manuals.

The opinions or assertions contained in this review are those of the reviewer, and are not to be construed as official or reflecting the views of the Department of the Navy.—EMERICK TOTH, *Naval Research Laboratory, Washington, D. C.*

Facsimile

BY CHARLES R. JONES. *Murray Hill Books, Inc., New York, 1949, 422 pages, $6.00.*

A FEW steamship catastrophes in the early years of the century provided a stimulus that did much to advance the cause of wireless, even though the average person never experienced first-hand contact with the science. Facsimile has had no such favorable opportunity. In an age when the telephone is used increasingly over the telegraph and spot news over the radio competes with the printed word, one wonders what chance facsimile has against television for more than a few special uses. It may well be that Ultrafax, a facsimile system utilizing television techniques, is the trend. Only time will provide the answer.

However this may be, anyone interested in the story of facsimile, how it works and what the commercial equipment is like will find much to interest him in this book.

It describes in detail eight commercial systems with many details of the transmitting apparatus, receiving apparatus, transmission facilities and synchronizing means, and even includes a considerable number of pages of service notes. Other chapters cover the application of facsimile to various services,

BUY HIGH-VOLTAGE COMPONENTS

that give you

*** a wide range of ratings**

*** hermetic sealing for long life**

Illustrated here are typical medium- and high-voltage pulse transformers manufactured by General Electric. Rectifiers, reactors, and filament and plate transformers are also available in a correspondingly wide range of sizes. Where space is at a premium—or where better coupling is desired—components that are adjacent in a circuit can be furnished combined in a single tank.

These components are oil-filled—a construction that is desirable not only because of voltages involved, but also where corona is a problem. They are hermetically sealed. They have shown excellent ability to withstand mechanical shocks and to operate continuously for long periods in widely varying temperatures and atmospheric conditions. They are built to conform to applicable parts of JAN specifications.

Your inquiries will receive prompt attention. Since these components are usually tailored to individual jobs, please include with your inquiry the functional requirements and any physical limitations. Address your letter to Section 42-328A, Transformer Sales Division, General Electric Co., Pittsfield, Mass. *Apparatus Department, General Electric Company, Schenectady 5, N. Y.*

GENERAL ELECTRIC

FUSES

FOR RECORDING
TELEMETERING SIGNALS
(up to 40 kc.)

Almost overnight Ampex Magnetic Tape Recorders revolutionized radio network broadcasting. Ampex succeeded in this most critical service because of simple and dependable operation, plus a tone quality that is unequalled. Ampex is now available in several models for a wide range of requirements. Inquiries for special instrumentation and industrial control application promptly answered.

• MODEL 300-C $1575
• VU METER PANEL 42XTRA $105
F.O.B. San Carlos

IMPORTANT NEW TOOL FOR INDUSTRY AND SCIENCE

Standard units have dual-speed recording 7½-15 or 15-30 i.p.s.

AMPEX
MAGNETIC TAPE RECORDER
"STANDARD OF THE GREAT RADIO SHOWS"

Get FREE BOOKLET today!

AMPEX ELECTRIC CORP., San Carlos, California

Without obligation please send 16 page illustrated booklet containing technical specifications of Ampex Magnetic Tape Recorders

NAME _____

ADDRESS _____

CITY _____ STATE _____

Our need is for:
☐ Laboratory Research
☐ Multi-Channel Recording
☐ Recording Broadcasting
☐ Telemetering
☐ Industrial Recording
☐ Aeronautical Research

Distributed by
BING CROSBY ENTERPRISES (Hollywood)
AUDIO & VIDEO PRODUCTS CORP. (New York City)
GRAYBAR ELECTRIC COMPANY (Everywhere)
EXPORT: WESTREX (New York City)

the existing standards and broadcasting.

In the first chapter, the author gives a brief but excellent history of the art. The references cited are wholly patent numbers rather than technical articles. Of course, only a very small number of the total patents on the subject are cited, but it does emphasize the author's story of the important inventions in this science.

Radio engineers will be disappointed in not finding much material on bandwidth requirements and comparisons with such other communication methods as the teletypewriter and television. Also, little is included on the economics of facsimile and no information on the number of transmitters and receivers in use at the present time. Except in Chapter I, there are no references. The book itself, however, will be a valuable reference as to what facsimile was like in 1949.

The text is generously provided with pictures, charts and circuit diagrams and a comprehensive glossary.—W. C. WHITE, *General Electric Co., Schenectady, N. Y.*

THUMBNAIL REVIEWS

OCEAN ELECTRONIC NAVIGATIONAL AIDS. Revised Edition (1949). CG 157. Available from U. S. Government Printing Office, Washington, D. C., 73 pages paper-covered, $.50. Details of loran, radio-beacon and radarbeacon systems, radio direction-finders and radar ship equipment, prepared by the U. S. Coast Guard to answer inquiries received on these subjects. Included are advisory minimum specifications for marine radar, loran and d-f equipment.

A MEASURE FOR GREATNESS. By David O. Woodbury. McGraw-Hill Book Co., New York, 1949, 236 pages, $4.00. Short biography of Edward Weston, electrical inventor and co-founder of the Instrument company bearing his name. Emphasis is placed on the many personally prosecuted patent infringement suits, mostly around the turn of the century, that are described in fascinating human-interest anecdotes by the author and concluded thus: "His judgment was sound; in every case, by intense application and the devotion of all his time and strength, he won. Finally he stood on top, having beaten small fry and giants alike, and made the Weston Electrical Instrument Company the unassailable leader in its field."

ARRL AMATEUR RADIO MAP. American Radio Relay League, West Hartford, Conn. Revised edition, 1950, 30 by 40 inches, four colors, on heavy map paper, $2.00. Modified equidistant azimuthal projection of the world centered on Wichita, Kansas, allowing distance measurements and great circle bearings of reasonable accuracy between points in U. S. A. and the



For Police, Commercial and General Mobile Use

You always get strong signals with Premax cadmium-plated or stainless steel "whip type" Antennas. Strong, sturdy—will stand abuse. Available in Center-Loaded, Base-Loaded and plain "Whip" styles.

All types of mountings to fit any job.

Send for special Mobile Antenna Bulletin.

PREMAX PRODUCTS
DIVISION CHISHOLM-RYDER CO., INC.
5001 Highland Ave. Niagara Falls, N. Y.

A TIME-TESTED DEPENDABLE SOURCE FOR
HIGH-PRECISION FRACTIONAL H.P. INSTRUMENT-TYPE
MOTORS & GENERATORS
PRODUCED TO ORDER

GOVERNOR CONTROLLED
SELF-SYNCHRONOUS
DRAG CUP
VELOCITY & ACCELERATION
DC & AC TACHOMETER
SHUNT
SERIES
COMPOUND
PERMANENT MAGNET
SPLIT-FIELD
SEPARATELY EXCITED
UNIVERSAL
INDUCTION
RELUCTANCE
HYSTERESIS
ONE, TWO & THREE PHASE
DC & AC SERVO
TOTALLY ENCLOSED
AC DYNAMICALLY BRAKED
REELMOTORS
ONE, TWO, THREE & FIVE SPEED SYNCHRONOUS MOTORS

Experienced for years in meeting customers' exacting requirements for high-precision instruments designed by engineers of ability and ingenuity, and manufactured with extreme care and skill. Over 500 different basic types may be varied to meet your own unique requirements of use, either electrically or physically.

ELECTRIC INDICATOR CO
PARKER AVENUE
STAMFORD, CONNECTICUT

CLEVELAND COSMALITE* and CLEVELITE*

LAMINATED PHENOLIC TUBES
OUTSTANDING AS THE STANDARD FOR QUALITY!

COSMALITE known for its many years of Top Performance. CLEVELITE for its ability to meet unusual specifications.

Available in diameters, wall thicknesses, and lengths desired.

These CLEVELAND TUBES combine . . . High Dielectric Strength . . . Low Moisture Absorption . . . Great Mechanical Strength . . . Excellent Machining Properties . . . Low Power Factor . . . and Good Dimensional Stability.

For the best . . . "Call Cleveland." Samples on request.

*Trade Marks

Ask about
CLEVELAND TUBES
in various types and specifications being used in the Electrical Industry.

The CLEVELAND CONTAINER Co.
6201 BARBERTON AVE. CLEVELAND 2, OHIO

PLANTS AND SALES OFFICES at Plymouth, Wisc., Chicago, Detroit, Ogdensburg, N.Y., Jamesburg, N.J.
ABRASIVE DIVISION at Cleveland, Ohio
CANADIAN PLANT: The Cleveland Container, Canada, Ltd., Prescott, Ontario

REPRESENTATIVES

NEW YORK AREA	R. T. MURRAY, 614 CENTRAL AVE., EAST ORANGE, N. J.
NEW ENGLAND	R. S. PETTIGREW & CO., 968 FARMINGTON AVE. WEST HARTFORD, CONN.
CANADA	WM. T. BARRON, EIGHTH LINE, RR #1, OAKVILLE, ONTARIO

STUPAKOFF



Available as:
SHEET
ROD
WIRE
FOIL
TUBING
EYELETS
LEADS
FABRICATED SHAPES

KOVAR

The Ideal Alloy for Glass Sealing

Made under conditions that approach laboratory precision methods, KOVAR* is the ideal alloy for sealing to glass. For manufacturers of electron tubes, or for others making pressure or vacuum-tight seals, Kovar provides these definite and practical advantages over other sealing alloys:

- KOVAR is designed for sealing into hard, thermal shock-resistant glass.
- KOVAR permits strain-free seals, because its expansitivity matches that of the glass over the entire working temperature range.
- KOVAR is not attacked by mercury.
- Uniform composition permits duplication of results.
- Easy to use.
- Available in a wide variety of standard and special shapes.

Complete information is available on shapes, sizes and use of Kovar. We will be glad to give you specific recommendations if you will describe your proposed applications.

*Westinghouse Trade Mark No. 337962

STUPAKOFF
CERAMIC & MANUFACTURING COMPANY
Latrobe, Pennsylvania

rest of the world. Also gives time zones. A somewhat similar map of the world, based on New York City, is obtainable from U. S. Coast and Geodetic Survey as Map No. 3042, for 40 cents.

AUTHOR'S GUIDE FOR PREPARING MANUSCRIPT AND HANDLING PROOF. Prepared and Published by John Wiley & Sons, Inc., New York, 1950, 80 pages, $2.00. Suggestions that simplify writing and handling of technical book manuscripts and revising existing editions.

INDUSTRIAL ELECTRONIC CONTROL. By W. D. Cockrell. McGraw-Hill Book Co., New York, 1949, Second Edition, 385 pages, $4.00. Revised to cover closed-cycle control or regulating systems, new counting circuits and new instrumentation and control equipment. Questions have been added after chapters and illustrations changed over to ASA symbols for *L* and *C*.

EFFECTIVE TEACHING. By Fred C. Morris. McGraw-Hill Book Co., New York, 1950, 86 pages, paper-covered, $.60. Manual for engineering instructors, covering planning and organization of instruction, instructional aids, conducting classes, testing and grading, and instructor self-appraisal and selfimprovement.

AN INDEX OF NOMOGRAMS. Compiled and edited by D. P. Adams. Published jointly by The Technology Press and John Wiley & Sons, 1950, 174 pages, $4.00. Compilation of approximately 1,700 alignment diagram references in all fields of engineering and science, of which 211 deal with electricity, electronics and radio.

OPERATION AND CARE OF CIRCULAR-SCALE INSTRUMENTS. By James Spencer. Instruments Pub. Co., Pittsburgh, 1949, 90 pages, $1.50. Tools, equipment and procedures for taking meters apart, making repairs and assembling again are described and illustrated, with separate trouble charts for d-c instruments and a-c instruments. Wattmeters, frequency meters, power-factor meters and synchroscopes are also covered.

VADE-MECUM. Published by P. H. Brans, Ltd., Antwerp and distributed in North America by Editors and Engineers, Ltd., Santa Barbara, Calif. New 8th edition, 1950, 508 pages, $3.20. Compilation of characteristics of over 15,000 different types of tubes in use throughout the world. New data not in previous editions was supplied by 247 tube manufacturers. New types listed include nonodes, transducers, accelerometers, phasitrons, crystal diodes and transistors. Military types used by the British, American, Australian, French, German, Italian, Russian and Japanese armed forces are included.

TRANSIENT PERFORMANCE OF ELECTRIC POWER SYSTEMS. By Reinhold Rüdenberg, Gordon McKay, Prof. of E. E., Harvard Univ. McGraw-Hill Book Co., New York, 1950, 832 pages, $12.00. Enlarged edition in English of classic German text dealing with phenomena in lumped networks and covering the reaction of electric circuits and their associated machines and apparatus to any nonstationary influence. Traveling waves on lines with distributed parameters are to be treated in a separate book. Communication problems are excluded but many of the solutions given can be applied to that field.

ELECTRONIC ENGINEERING MASTER INDEX 1947-1948. Electronics Research Pub. Co., New York, 1950, 339 pages, $19.50. Third volume of its type (previous ones covered 1925-1945 with 15,000 entries and 1946 with 7,500 entries), with many more publications indexed this time and with patents and declassified documents now included to give a total of over 18,000 entries for the two years. Cumulative cross-index is included, covering all three volumes.



Everything points to SYLVANIA as today's Picture Tube Leader

Radio Tube Leadership—Improved manufacturing techniques and quality control methods, acquired during 25 years of perfecting Sylvania's world-famous line of radio tubes, have contributed to the fine performance and nation-wide acceptance of Sylvania's TV Picture Tubes.

Electronics Leadership—During the war, Sylvania's all-out efforts in designing and producing precision electronic equipment, electronic and cathode-ray tubes, resulted in much of the valuable data applied today in making Sylvania's improved TV Picture Tubes.

Lighting Leadership—A background of half a century of lighting experience has further contributed to the outstanding quality of Sylvania TV Picture Tubes. From this experience has come the development of improved coatings, and phosphors for brighter, longer-lasting screens.

Sylvania Picture Tube leadership is a "natural" . . . resulting from continuous research plus a happy combination of experience in *radio, electronics, and lighting.*

Of special importance is the invention of the famous Ion Trap...now adopted, under Sylvania license, by other important TV tube makers. Today, Sylvania has 2 great plants devoted exclusively to picture tube manufacture.

For the latest data and ratings on all Sylvania TV Picture Tubes, write today to Sylvania Electric Products Inc., Dept R-2107, Emporium, Pa.

SYLVANIA ELECTRIC

RADIO TUBES; TELEVISION PICTURE TUBES; ELECTRONIC PRODUCTS; ELECTRONIC TEST EQUIPMENT; FLUORESCENT LAMPS, FIXTURES, SIGN TUBING, WIRING DEVICES; LIGHT BULBS; PHOTOLAMPS; TELEVISION SETS

Leach RELAYS
ARE PERFORMANCE PROVED!



You get better service from LEACH RELAYS because thousands of types of relays for thousands of applications have been proved-in-use for over 30 years.

LEACH RELAYS are designed with an exceptionally high factor of safety for *extra* dependability. Simplicity of designs makes installation quick, easy and inexpensive. Get *all* the facts and make your own comparisons. LEACH RELAYS' outstanding performance, reliability, sturdiness and economy have been *proved-in-use*.

Highest standards of engineering, materials and workmanship assure long, safe, efficient, trouble-free service.

FOR BETTER CONTROLS THROUGH BETTER RELAYS—CONTACT *LEACH*

LEACH RELAY CO.

6815 AVALON BOULEVARD, ● LOS ANGELES 3, CALIF.

Representatives in Principal Cities of U. S. and Canada

(Continued from p 118)

circuit, and is temperature compensated for best characteristics on all channels. The high-channel oscillator coils are of metallized construction, while the low-channel coils are of conventional wound construction to provide uniform temperature stability.

Fine tuning is provided by a variable dielectric capacitor, connected directly across the tank circuit. The two stator plates are constructed in a single rigid molded assembly using Mycalex insulation. The variable dielectric cam is made of glass-base melamine for low loss and temperature stability. This construction, together with the direct tank circuit connection of the plates, which results in wide plate spacings, minimizes the possibility of microphonics and also minimizes oscillator chassis current paths which might result in undesirable radiation.

The mixer plate circuit contains a tuned low-pass filter section for the picture i-f output and a high-Q trap providing sound i-f attenuation for the picture output as well as sound i-f output. The low-pass filter configuration minimizes oscillator feedthrough to both sound and picture i-f grids. The picture converter i-f coil, while designed to provide output nominally at 22 mc, has sufficient range of adjustment to work at any frequency in that vicinity to match various stagger tuned i-f combinations. The gain of the unit from the antenna to the first picture i-f grid is from 28 to 35 db over the 12 channels. Measurement of the oscillator radiation, in terms of oscillator voltage produced across 300 ohms at the antenna terminals, shows less than 3,000 microvolts for the low-band channels, an average of 7,500 on the high-band channels with a maximum of 10,000 on channel 10.

Curve Generator for Tubes

THE LATEST instrument for instantaneous visual display of electron tube characteristics has been developed by Milton L. Kuder at the National Bureau of Standards. The curve generator plots directly on the screen of a cathode-ray tube the

NEW "MIGHTY MITES"

Seletron

SELENIUM RECTIFIERS

Rectifiers are shown actual size

Keyed to the requirements of modern electronic circuits

Chalk up another first for SELETRON! Here is "mite-size" 8J1, especially desirable for inexpensive record players and similar applications . . . a new and *smaller* 65 mil rectifier with particularly low reverse leakage, built to the following specifications: Input 130 V rms; Max. Peak Inverse Voltage 380 V; Max. D.C. Output Current 65 MA; Plate Size 11/16" square; Stack Thickness 9/16". . . And don't forget the 130 Volt, 20 mil "Mite"—No. 8Y1, designed especially for power and bias supply in Radio and Television!

A complete tabulation of all SELETRON miniatures is available. For your copy, write Dept. ES-30.

SELETRON DIVISION

RADIO RECEPTOR COMPANY, INC.

Since 1922 in Radio and Electronics

Sales Department: 251 West 19th St., New York 11, N. Y.

Factory: 84 North 9th St., Brooklyn 11, N. Y.

a COMPLETE LINE of CAA APPROVED* TOWER LIGHTING EQUIPMENT BY Andrew

Designed for Dependability . . .
Immediate Delivery . . .



300 MM CODE BEACON, Type 660. Sturdily constructed, completely dependable. To provide steady, uninterrupted service for many years of exposure to rigorous weather conditions, metal parts are made of cast aluminum with hardware of corrosion resistant bronze. Insects are kept out by screens placed in ventilating openings.

ISOFORMERS, Types 2015 and 2030. Interlocking ring, air-insulated lighting transformers; particularly adapted for use with towers that develop a high voltage across the base insulator.

REPLACEMENT LAMPS, for code beacons and obstruction lights. Carried in stock in variety of filament voltages.

LIGHTING FILTERS, for use with insulated towers developing moderate voltages above 1 MC. Models available unhoused or in weatherproof steel housing.

BURNOUT INDICATORS, to show lamp failure.

PHOTOELECTRIC CONTROL SWITCHES, to turn tower lights ON and OFF.

FLASHERS, for code beacons.

COMPLETE TOWER LIGHTING KITS, including conduit, wire, and all fittings for towers of any height.



SINGLE (Type 661A) and DOUBLE (Type 662A) OBSTRUCTION LIGHTS. Easy to service, rugged, reliable. To replace burned out lamps, just loosen one thumb screw and open the two piece cast aluminum housing.

Write for descriptive bulletins or further information—today.

Andrew CORPORATION
363 EAST 75TH STREET CHICAGO 19

**CAA approvals cover only lighting fixtures themselves. Associated equipment is not subject to CAA regulations but more than meets all local regulations.*

ANDREW

TRANSMISSION LINES FOR AM-FM-TV • ANTENNAS • DIRECTIONAL ANTENNA EQUIPMENT
ANTENNA TUNING UNITS • TOWER LIGHTING EQUIPMENT • CONSULTING ENGINEERING SERVICES
WORLD'S LARGEST ANTENNA EQUIPMENT SPECIALISTS

family of plate current versus plate voltage curves for any receiving tube. A standard rectangle is displayed along with the characteristic curves to provide a direct scale for voltage and current readings.

The plate voltage applied to the tube under test is swept continuously from zero to predetermined positive values. The voltage drop appearing across the plate load resistance is then a measure of the plate current. This voltage drop is applied to the vertical deflecting plates of a cathode-ray tube and the plate voltage applied to the horizontal plates.

The combined voltages generate a plate current-plate voltage curve on the crt screen for the entire sweep interval. The sweep sequence is repeated automatically for several values of grid bias, forming the family of plate characteristic curves. A series of bright dots appearing at the end of each curve in the family gives a useful representation of the load line of the tube for the operating conditions selected.

A visual representation of plate current plotted against grid voltage is also provided. In this case, the display is particularly convenient since grid voltage increments are directly defined by calibrated vertical bars appearing on the screen; a standard current reference is given by a horizontal bar. All of the possible displays are produced by the curve generator without overloading the tube under test. Overall accuracy of voltage and current readings from the tube screen is within plus or minus five percent.

A complete family of curves is retraced sixty times a second and the resulting image is stationary and



Plate characteristics of a 6AC7 as shown on the screen of a cathode-ray tube

The look that keeps telephone costs DOWN

Examining specimen on metallographic microscope at Bell Telephone Laboratories.

Through his microscope this Bell metallurgist examines a bit of material which is proposed for telephone use. From what he sees of grain structure, he gains insight into performance not provided by spectrum or chemical analysis. He learns how to make telephone parts stand up longer, so that telephone costs can be kept as low as possible.

The items which come under scrutiny are many and varied, ranging from manhole covers to hair-thin wires for coils, from linemen's safety buckles to the precious metal on relay contacts.

In joints and connections—soldered or welded, brazed or riveted—photomicrographs reveal flaws which would escape ordinary tests. They show if a batch of steel has the right structure to stand up in service; why a guy wire let go in a high wind or a filament snapped in a vacuum tube; how to make switchboard plugs last longer.

In their exploration of micro-structure, Bell Telephone Laboratories scientists have contributed importantly to the metallographic art. You enjoy the benefits of their thoroughgoing testing and checking in the value and reliability of your telephone system, and the low cost of its service.



Photomicrograph of white cast iron which is hard and brittle.



Same iron rendered malleable by heat treatment. Shows spots of nodular carbon.

BELL TELEPHONE LABORATORIES

WORKING CONTINUALLY TO KEEP YOUR TELEPHONE SERVICE BIG IN VALUE AND LOW IN COST

TROUBLE . . .
in
the
field



call on Coto-Coil

Call on Coto-Coil if the coils you use have failed you, or if your requirements are very exacting.

For 32 years, COTO-COIL windings have served with distinction above and below ground . . . on the sea and undersea . . . in the air.

They are wound to your specifications but employ special techniques to meet extremes of heat and cold, moisture and vibration. Whatever your requirements, we can meet them. You will be pleased with price, quality, delivery and performance.

BOBBINS
ACETATE INTERLEAVE (Coalesced)
PAPER INTERLEAVE
COTTON INTERWEAVE
TAPED FORM WOUND
UNIVERSAL SINGLE or
MULTI-PIE CROSS WOUND

COTO-COIL CO. INC.
COIL SPECIALISTS SINCE 1917
65 PAVILION AVE.
PROVIDENCE 5, R.I.

free from flicker. Characteristic curves may be quickly obtained in permanent form by photographing the screen image.

All driving signals are produced by a single oscillator. Voltage excursions for the tube under test are obtained from the oscillator in the form of a rising sawtooth wave whose magnitude is controlled without any oscillator loading effect. A cathode follower isolates the power supply for the tube under test from the rest of the generator circuit, so that only the plate current of the tested tube is plotted on the oscilloscope.

Step Counter

When the sawtooth plate sweep signal is most negative, the master oscillator sends a pulse into a pulse former. Pulses from the pulse former then operate a step counter to provide a fixed bias voltage for the grid of the tube under test, successively becoming more positive. Each time the plate voltage is driven negative the grid bias voltage rises to a new level. These stepwise increasing bias voltages are fed through a video divider which reduces their amplitude to the desired level.

From the divider, the stepped voltages go through a cathode follower to the test grid. A special control acting on a clipper circuit allows manual selection of a definite calibrated voltage for the highest positive grid step.

A special linearizing circuit provides for uniform increments in the step sequence of grid voltages, each oscillator pulse, through an inverse feedback arrangement, transferring a fixed charge into a large capacitor. The feedback can be controlled manually to provide any size grid voltage increment. The number of steps is controlled indirectly by the output of a step counter, arresting the entire process after a predetermined number of steps.

Two circuits have been included which are not vitally necessary but which add to convenience and reliability. One is a servo-sweep circuit whose timing is controlled through the frame synchronizing switch. This circuit is especially



1900 ★ THE MIRACLE OF AMERICA ★ 1950

Freedom and Progress

It's no stretch of the imagination, rather, robust realism to call our past half century a Miracle—U. S. A.

America has set an amazing record of progress in 50 years—but a moment in the history of civilization. A record unequalled by any other political or economic system.

Merely by broad brush strokes, we can all visualize this miracle. Remember the crystal set, the hand-cranked car, the biplane? A far cry from our FM radio, television, hydro-matic drive and supersonic planes.

And here's another phase of the miracle that went hand-in-hand with these and the myriad of intertwined technological advances—ranging from the radio telephone and Bakelite to the X-ray tube and teletype . . . and to atomic energy and its untold potentialities.

- ★ Since 1900 we have increased our supply of machine power 4½ times.
- ★ Since 1900 we have more than doubled the output each of us produces for every hour we work.
- ★ Since 1900 we have increased our annual income from less than $2400 per household to about $4000 (in dollars of the same purchasing power), yet . . .
- ★ Since 1900 we have cut 18 hours from our average work week—equivalent to two present average workdays.

How did we do it? The basic cause for this composite miracle has been the release of human energy through FREEDOM, COMPETITION and OPPORTUNITY. And one of the most important results is the fact that more people are able to enjoy the products of this free energy than in any other system the world has ever known.

THIS IS THE MIRACLE OF AMERICA . . . it's only beginning to unfold.

A PUBLIC SERVICE PROJECT ★ THE ADVERTISING COUNCIL ★

Published in the public interest by:

McGRAW-HILL PUBLICATIONS

An EASY and ACCURATE Way to Measure Audio Frequency Voltages

Ballantine Model 300
SENSITIVE ELECTRONIC VOLTMETER
Featuring a Logarithmic Voltage Scale and Uniform Decibel Scale

● Designed for the measurement of AC Voltages from .001 Volt to 100 Volts over a frequency range of 10 to 150,000 cycles. ● Accuracy of readings is ±2% at any point on the scale. ● Very stable calibration—unaffected by changes in line voltage, tubes or circuit constants. ● Range switching in decade steps—easy to use—only ONE scale to read. ● Output jack and output control provided so that Voltmeter can be used as a high-gain (70 DB) high-fidelity amplifier. ● Accessories available to extend readings up to 10,000 Volts and down to 10 microvolts. ● Precision Shunt Resistors convert Model 300 Voltmeter to very sensitive direct-reading milliammeter. ● Write for complete data.

PRICE $200.00

BALLANTINE LABORATORIES, INC.
BOONTON N. J. · U. S. A.

In addition to the Model 300 Voltmeter, Ballantine Laboratories also manufacture Battery Operated Electronic Voltmeters, R. F. Electronic Voltmeters, Peak to Peak Electronic Voltmeters, and the following accessories—Decade Amplifiers, Multipliers, Precision Shunt Resistors, etc.

useful for viewing the step-function signal at the grid of the tube under test. Another circuit, using four tubes, identifies the curves which have positive values of grid bias by means of a small marking pip superimposed on the positive grid lines.

Checking Crystals

By P. O. Farnham
Aircraft Radio Corp.
Boonton, N. J.

Maintenance and repair of military aircraft radio communications equipment in large quantities has evolved a means of checking crystals with a fundamental frequency in the region between 6 and 13 mc are considered. The equipment, the frequencies and the procedures can be modified slightly to include many other applications.

The equipment is arranged as shown in Fig. 1. Outputs at 10, 100 of 1,000-kc intervals can be selected at will from the substandard of frequency. Each of the receivers is equipped with a beat-frequency oscillator that can be turned off if the receiver is used as a detector for beats from two other signal sources.

Direct frequency calibration is provided on the tuning dials of the receivers and the two tunable oscillators. Headphones and an output meter are used to indicate beat-frequency output from a receiver.

Before making measurements, the 1,000-kc crystal frequency of the substandard (5th harmonic) is checked against the 5-mc standard frequency signal from WWV by feeding both these signals to receiver 1 tuned to 5 mc. The 100-kc substandard intervals are next checked with receiver 2 in the beat-frequency condition. Beats should be observed only at each 100-kc scale line of the receiver dial.

With receiver 2 set nearly to zero beat on an even 100-kc mark (for example, 8 mc) the 10-kc intervals are then switched on in the substandard. The same beat frequency should be observed. As the receiver is tuned slowly towards 8.1 mc, it should be possible to count ten beats. Leaving the receiver near zero beat at the tenth count, the

TWELVE HUNDRED HANDS TO FIND THE FACTS

Four hundred field correspondents ferret out, spade up, shoot in stories from all over the world of industry. Two hundred editors, bristling with Ph.D.'s and practical engineering and scientific knowledge, cull and correct and explain and expound. That's McGraw-Hill.

It *takes* a huge staff like this to keep abreast of events and developments in such a giant sphere as American industry. And the vote of thousands upon thousands of regular readers of McGraw-Hill publications seems to be: McGraw-Hill *has* what it takes to get the facts – fast.

To be well versed in the latest developments in *your industry*, be a cover-to-cover McGraw-Hill reader. Editors *and advertisers* collaborate to make your job easier. The advertising pages of all McGraw-Hill publications are packed with news-worthy information . . . the latest news on products and services that contribute to profits.

McGRAW-HILL

Publishing Company, Inc., 330 West 42nd Street, New York 18, N. Y.

HEADQUARTERS FOR INDUSTRIAL INFORMATION

RCA TUBES ...

the complete line for industry...

RCA-5675 "Pencil-Type" Triode for ultra-high frequencies*

(Actual Size)

For the newest tube types

...call your RCA Tube Distributor

Your RCA Tube Distributor carries fresh stocks of dependable RCA electron tubes to meet virtually every industrial and laboratory requirement. Look to him for prompt service and information on the tubes you need.

*Another "RCA First" in advanced tube design, the unique RCA-5675 "pencil-type" triode employs a coaxial-electrode structure of the double-ended type. As an oscillator in grounded-grid service, the 5675 is capable of a power output of 475 milliwatts at 1700 megacycles . . . about 50 milliwatts at 3000 megacycles.

RADIO CORPORATION of AMERICA

ELECTRON TUBES HARRISON, N.J.



FIG. 1—Complete setup of receivers and oscillators for crystal calibration

100-kc interval is again switched in from the substandard. The beat frequency tone remains the same.

Measurement Method

The method of measurement of crystal oscillator frequency can be most clearly followed with a numerical example. Receiver 2 is used for crystal frequencies from 6 to 9 mc, receiver 3 for crystal frequencies from 9 to 13 mc. Assume that the frequency indicated on the nameplate of the crystal is 7,361.1 kc, which will be called f_o. Using receiver 2, set the 6-13 mc oscillator accurately to the substandard 10-kc harmonic that lies somewhere between 10 and 20 kc below f_o.

In this example, the oscillator will be set to 7,350 kc and this frequency will be called f_o. The 10–20-kc oscillator is then turned on to modulate the 7,350-kc output and produce an upper sideband output adjustable from 7,360 to 7,370 kc.

The frequency of the 10–20-kc oscillator will be called Δf. The value of f is adjusted to produce zero-beat in the receiver output between the crystal and the upper sideband frequency of the 6–13 mc oscillator. The true crystal frequency f is obtained by adding the values of f_o and Δf.

The output-meter is used as a zero-beat indicator when bringing the 6–13 mc oscillator to zero beat

with the desired 10-kc harmonic of the substandard. To establish the modulation frequency Δf of the 10–20-kc oscillator it is necessary to beat the crystal frequency and the modulated output of the 6–13-mc oscillator together in receiver 2.

The 10–20-kc oscillator is tuned approximately to 11.1 kc (for this case the value of f_c–f_o). Near this setting and with the receiver gain reduced to prevent pickup of an undesired sideband output ($f_o + 2\,\Delta f$) a relatively clean beat output tone of low frequency should be obtained from the receiver. This signal corresponds to pickup of the desired sideband output ($f_o + \Delta f$). It is distinguished from pickup at the undesired sideband by being free of extra, high-frequency beat components.

The receiver should be tuned to maximum beat output and then the 10–20-kc oscillator adjusted for zero-beat output using the output meter. If this reading of Δf should come out 11.65 kc, this value will then be added to 7,350 (f_c) giving an actual crystal frequency f of 7,361.65 kc. The error (f–f_c) based upon the value stamped on the crystal holder will then be + 0.55 kc or the percentage error will be + 0.00748 percent.

If the actual crystal frequency f should be such that zero-beat setting of the 10–20 kc oscillator lies off its tuning range, it will be necessary to re-establish the setting of the 6–13-mc oscillator.

Suppose the actual crystal frequency f had been 7,359.3 kc instead of 7,361.65 used in the example. It would then be necessary to tune the 10–20-kc oscillator to a Δf value of 9.3 kc.

Since this value is not attainable, f_o (the 6–13-mc oscillator) must be reset to a new lower value of 7,340 kc. The value for Δf will then be 19.3 kc.

Similarly, if the actual crystal frequency were much higher than its nameplate value, it would then be necessary to reset the 6–13-mc oscillator to a new higher value of 7,360 kc. In either case, the actual frequency of the crystal is given by $f = f_o + \Delta f$.

Receiver 4 is used as a detector for beats between the substandard 10-kc intervals and the 20th har-

NOW... GREATER

ROME CABLE CORPORATION

Versatility

with New Rome Synthinol* No. 901

Newly developed, Rome Synthinol 901 offers electronic equipment and appliance manufacturers many important advantages. Suitable for *continuous operation at 90° C.*, it affords much greater resistance to heat deformation than conventional 80° C. thermoplastic compounds . . . has higher heat aging properties. Due to the absence of volatiles, Rome Synthinol 901 is ideal for coil lead applications, with baking brittleness, shrinkage and cracking reduced to a minimum. Improved solderability of wires insulated with Rome Synthinol 901 makes assembly work easier . . . more economical.

Rome Synthinol 901 is available in a wide range of colors and can be supplied plain or with coverings of extruded nylon or lacquered braids of glass, rayon and cotton. Underwriters' Laboratories approved for ratings of 300 and 600 volts.

Regular Rome Synthinol approved for 80° C. operation, is likewise, available for hook-up and appliance wiring, either plain or with braided coverings in a variety of color combinations.

Rome Hi-Temp rubber insulated appliance wires are highly resistant to heat and moisture and are approved for 75° C. operation.

Whatever your electronic wiring requirements may be, get the habit of coming to Rome for them. The high quality of Rome hook-up and appliance wires is the result of sound engineering, combined with modern manufacturing facilities in the hands of experienced wire makers . . . you can depend upon it.

*T. M. Reg

Rome manufactures a wide variety of wires and cables for electronic use as listed below:

- Television Camera Cable
- Microphone Cables
- Intercommunication Cables
- Specification JAN-C-76 Types SRIR, SRHV and WL
- Radio Frequency Transmission Line
- Supervisory Control Wires
- Flexible Cords
- Specification MIL-C-915 Types SRI and SRIB

IT COSTS LESS TO BUY THE BEST

ROME CABLE CORPORATION
Dept. E7, Rome, N. Y.

Please send me your Radio and Appliance Wiring Bulletin

Name.....
Company.....
Address.....
City..... State.....

ROME CABLE CORPORATION
ROME, NEW YORK

FIRST SLIM TRIM DYNAMIC for TV

RESPONSE: 40-15,000 c.p.s. ± 2.5 DB

POWER RATING: −53

OMNIDIRECTIONAL

ACOUSTALLOY DIAPHRAGM

POP-PROOF HEAD

CHANGEABLE LOW IMPEDANCE

REMOVABLE SWIVEL

⅝" OR ⅝"-27 THREAD MOUNTING

CANNON XL-3 CONNECTOR

ALL PARTS PRECISION GROUND

Shows TV 655 suspended on a boom. Omnidirectional polar pattern and firm swivel permits easy, diverse use.

- New '655' Microphone Provides Ultra-Wide-Range, High Fidelity Response
- More Rugged, More Versatile
- Stops Wind and Breath Blasts
- Individually Laboratory Calibrated

Here, *for the first time*, you have a slim, trim microphone with all the advantages of *dynamic* performance and utility! Only because of the ingenious *Acoustalloy* diaphragm and other E-V developments has it become a reality! Meets the highest standards of TV, FM and AM.

You can use the *TV 655* on a stand, in the hand, or on a boom...or you can easily conceal it in studio props. *No additional closely-associated auxiliary equipment is required!* Provides effective individual or group pick-up. Reproduces voice and music with remarkable accuracy.

New E-V Blast Filter makes the *655 pop-proof*. Acoustically-treated, strong wire-mesh grille head stops wind and breath blasts. Eliminates wind rumble in outdoor pick-up. *Fully field tested and proved!* Ideal, too, for recording and high quality sound amplification.

See for yourself! Write today for Bulletin No. 156 and full information on how you can try this amazing new microphone.

Model 655. *List Price* **$200**

Shows the popular Patsy Lee with the TV 655. Note how swivel permits aiming at sound source without hiding face.

Shows TV 655 in the hand with swivel removed. Note how convenient it is to handle for announcing or interviewing.

Electro-Voice INC.

401 CARROLL STREET • BUCHANAN, MICHIGAN

Export: 13 East 40th Street • New York 16, N. Y., U. S. A. • Cables: Arlab

monic of the 10–20-kc oscillator when it is desired to check the frequency calibration of the latter unit.

Thermistor Thermostats

By Albert H. Taylor
Radio Ranch
Alamosa, Colorado

THERMISTORS, a type of semiconductor with large but stable negative temperature coefficient, are now manufactured in numerous types for a variety of purposes. Many of them are inexpensive, and a few types are available from war surplus sources. Because of the sensitivity and quick response of some thermistors, they are particularly suitable for thermostat and remote thermometer applications.

The accompanying two circuits were designed for simplicity and low cost, and are used to control refrigerators. They could easily be adapted to other thermostatic applications. In both, the thermistor is excited by a-c to avoid polarization, and the thermistor dissipation is kept low enough so that with the thermistor in air there is no noticeable heating error. More excitation could be used in water. The thermistor used is in each case a Western Electric V-514.

The simpler circuit of Fig. 1 uses a small thyratron with a-c anode supply and d-c grid bias upon which the a-c signal from the thermistor is superimposed. The tripping temperature is adjusted by setting the grid bias with R_b. This thermostat holds the temperature of a domestic refrigerator within one degree at about 5 C.

In this application the sole drawback is radio interference. The interference did not disturb a good communications receiver at 5 to 18 mc in the same room, but it is severe on a broadcast receiver. Enclosure in a shielded box with all leads filtered and bypassed to a good ground would be necessary to eliminate this disturbance.

The circuit of Fig. 2 employs an a-c bridge, and a-c amplifier stage, a differential detector, and a sharp-cutoff d-c keying amplifier. The bridge is excited at 60 cycles from the same transformer winding

which heats the tubes, and the center leg of the differential detector is excited from the 60-cycle line through an ordinary plate-to-grid interstage transformer used stepping down.

The sensitivity is about the same as that of the thyratron circuit and no radio interference has been observed. The tripping temperature is adjusted by varying the bridge arm adjacent to the thermistor.

Design Considerations

The resistance of a thermistor at any temperature can be calculated by the equation $R = Ae^{B/T}$ where A and B are constants and T is the temperature in degrees Kelvin, that is to say, 273 degrees plus the temperature in degrees centigrade. If A and B are given, the resistance can be calculated for any temperature with the help of a table of exponential functions (such as that in the Smithsonian Physical Tables) or the log-log scale on certain slide-rules.

To determine the constants of an unknown thermistor one can measure its resistances R_1 and R_2 at two temperatures T_1 and T_2 and solve for A and B the two simultaneous equations $R_1 = Ae^{B/T_1}$ and $R_2 = Ae^{B/T_2}$. The solution, using natural logs, is

$$\ln A = \frac{T_1 \ln R_1 - T_2 \ln R_2}{T_1 - T_2}$$

and

$$B = \frac{T_1 T_2}{T_2 - T_1} \ln \frac{R_1}{R_2}$$

The type of thermistor to be pre-



FIG. 1—The thyratron may be a 2050, 1665, 2051 or 2D21

Timing Ideas

PRECISION PERFORMANCE

Manufacturers, recognizing that components of quality insure outstanding product performance, look to Haydon® at Torrington for timers and timing devices. All Haydon timers are made with the same precision as the Haydon motor — your guarantee of satisfactory performance. If you need a special design, you'll find Haydon's extensive engineering and development facilities without equal for service and results.

A few examples of basic Haydon timing units are featured below.

SERIES 8010 INTERVAL TIMER WITH BUZZER

Compact, low cost timer for volume production. Wide range of intervals. Audible (buzzer) signal optional. Quick break. Load contact rated 10A, ½ HP 250 VAC.



SERIES 8006 INTERVAL TIMER

Designed for heavy duty, this unit is available in quantities in standard models. Wide range of intervals. HOLD feature optional. Quick break. Totally enclosed. Switch rated 28A, 1 HP 250 VAC.

SERIES 5900 TIME DELAY RELAY

For use where positive, accurate time delay relay is imperative. Automatic reset. Fixed models for volume production; adjustable models in 4 delay ranges for general use.



SERIES 5700 ELAPSED TIME INDICATOR

Synchronous timing motors with cyclometer type counters for metering elapsed time. Rugged models for wide range of timing, recording operations; in several registers, resettable or non-resettable.

® TRADE MARK REG. U.S. PAT. OFF.

For complete design and engineering specifications, write for catalog: Timing Motors No. 322 — Timers No. 323 — Clock Movements No. 324. Yours without obligation.

HAYDON AT TORRINGTON

HEADQUARTERS FOR TIMING

HAYDON Manufacturing Co., Inc.
2431 ELM STREET
TORRINGTON, CONNECTICUT
SUBSIDIARY OF GENERAL TIME CORPORATION

S.S. WHITE FLEXIBLE SHAFTS
GIVE YOUR TV SETS THIS
EXTRA SALES APPEAL

Tuning Convenience

You can make channel change and reception regulation on your TV equipment an easy, effortless task, when you couple the tuning knobs to their respective circuit elements with S.S.White flexible shafts.

The shafts will provide the sensitivity you require and at the same time will remove all limitations on the location of the control knobs. They'll permit you to position the knobs on the top of the set, on the side or even in a remote location—wherever necessary to assure maximum convenience.

Take advantage of the extra selling features S.S.White flexible shaft couplings can give your sets. Check their possibilities today. For details,

S.S.White MAKES IT RIGHT

WRITE FOR BULLETIN 4501

It contains basic facts and data on flexible shaft selection and application. Copy sent on request. Write today.

S.S.WHITE INDUSTRIAL DIVISION
THE S. S. WHITE DENTAL MFG. CO. DEPT. E 10 EAST 40th ST., NEW YORK 16, N. Y.

FLEXIBLE SHAFTS AND ACCESSORIES
MOLDED PLASTICS PRODUCTS—MOLDED RESISTORS

One of America's AAAA Industrial Enterprises

ferred depends upon the application and the operating temperature. The V-514 is embedded in glass for immersion in liquids, but nevertheless follows very quickly a sudden change in temperature, making 0.9 of its total resistance change in one second. It is intended for rapid, accurate calorimetry and resistance thermometry and is really too good for a refrigerator. It starts the refrigerator immediately whenever the door is opened.

A typical V-514 has A equal to 0.0364 and B equal to 3,896 C. At 0 C the resistance is 58,200 ohms; at 40 C it is 47,200 ohms. A safe current at these temperatures is 100 microamperes, which means that the change of 4 degrees produces a change of 1.1 volts across the thermistor. Operation at higher or lower temperatures would require a different thermistor or a different input circuit if the same sensitivity is to be maintained.

If a V-514 were to be used for controlling a crystal oven at 50 degrees, where its resistance is only about 6,000 ohms, the thermistor current should be increased to maintain the same dissipation as before, and a step-up transformer should be interposed between the thermistor and the tube. At very low temperatures, the resistance would be so high that there would be trouble from stray capacitances and hum pickup.

The thyratron in Fig. 1 is biased far enough below cutoff so that positive half cycles of the thermistor and anode voltages do not fire it at temperatures above the regulating temperature. When the thermistor resistance increases with falling temperature, the tube fires and operates the relay to open the motor circuit, which must be on the normally-closed relay contacts.

The low anode voltage, used for simplicity and economy, necessitates several precautions. First, a relay with comparatively little inductance is preferred in order that transients across the coil shall not snuff the tube and make the contacts chatter. A 24-volt, d-c, 250-ohm coil in a relay from the SCR-274-N equipment was found preferable to a 115-volt coil.

To eliminate chatter it was also found advantageous to connect C_1

and R_5 to the thyratron shield grid as shown. Thus, when the thyratron snuffs and the relay is released to start the motor, the extra contacts on the dpdt relay operate to throw a large negative surge on the shield grid thru C_5. This blocks the tube until the switching transients subside.

Before the refrigerator warms up again, the extra electrons leak off from shield grid to ground, through R_5, leaving C_5 charged. This results in a positive surge being applied to the shield grid when the thyratron fires again and C_5 is discharged, and tends to keep the tube fired until the switching transients have again subsided.

To prevent damage to the thyratron, R_5 limits the instantaneous peak current to the peak rating of the tube (1 ampere for 2050).

Figure 2 is a crude form of direct-reading a-c bridge and detector which have been used in very precise resistance thermometry. The balanced bridge eliminates the constant component of about 6 volts which was present in Fig. 1, and allows an amplifier to be used.

The differential detector is necessary for a sense indication with the bridge, so as to distinguish between unbalance voltages due to upward and downward variations of temperature. The keying tube should be a type having high mutual conductance and sharp cutoff. It is blocked and unblocked by the detector output in accordance with bridge unbalance.

The controlled device can be fed through either the normally-open or normally-closed relay contacts of



FIG. 2—Improved circuit uses a 5,000-ohm relay that makes at 16 ma and breaks at 8 ma



THE HATHAWAY SC-16A SIX ELEMENT
RECORDING CATHODE-RAY
OSCILLOGRAPH

NEW HIGHS IN RESOLUTION are obtained by this new oscillograph because of its unusually HIGH FREQUENCY RESPONSE and HIGH CHART SPEED...designed for recording fast transients and continuous phenomena.

FREQUENCY RESPONSE 0 to 200,000 cycles per second
RECORDS up to 1000 ft. long at speeds up to 600 inches per second
RECORDS up to 10 ft. long at speeds up to 6000 inches per second
WRITING SPEED above 100,000 inches per second

Note these additional unusual features.

- SIX ELEMENTS with convenient interchangeable lens stages for 1, 2, 3, or 6 traces on full width of chart.
- INTERCHANGEABLE RECORD MAGAZINES for CONTINUOUS RECORDING on strip chart, either 6 inches or 35mm in width up to 1000 feet in length, DRUM RECORDING for short, high-speed records, and STATIONARY CHART for very short transients.
- PRECISION TIMING EQUIPMENT, tuning fork controlled, for 1-millisecond or 10-millisecond time lines.
- Crystal-controlled Z-AXIS MODULATION for 1/10 millisecond time marks.
- QUICK-CHANGE TRANSMISSION for instantaneous selection of 16 record speeds over a range of 120 to 1.
- AUTOMATIC INTENSITY CONTROL.
- CONTINUOUS SWEEP OSCILLATOR which permits viewing as well as recording.
- Single-pulse LINEAR OSCILLATOR for recording transients on stationary film. The record can initiate the transient to be recorded, or the transient can initiate the record.



Each recording element is a complete unit, fully housed, which can be instantly inserted or removed. Recording element contains high-intensity cathode-ray tube, and both AC and DC amplifiers. Control panel is located on outside end.

FOR FURTHER INFORMATION, WRITE FOR BULLETIN 2 G1G

Hathaway
INSTRUMENT COMPANY
1315 SO. CLARKSON STREET • DENVER 10, COLORADO

HOW LORD BONDED RUBBER MOUNTINGS Protect HIGH FIDELITY PERFORMANCE



LORD Mountings increase the listening pleasure of millions by protecting microphone performance. Unwanted vibratory disturbances are prevented from interfering with the faithful reproducing qualities built into these instruments.

Two standard LORD Plate-Form Mountings protect the broadcast fidelity dynamic microphones made by Electro-Voice, Inc., Buchanan, Michigan. Mountings are arranged in tandem to supply maximum lateral stability—and at the same time to provide the vertical softness necessary for maximum vibration isolation.

If the performance of your product, whether large or small, is affected by external vibration . . . or if its vibrations affect performance of other instruments and equipment . . . you should investigate LORD Vibration Control Mountings. For assistance in selecting and applying LORD Mountings, write to attention of Product and Sales Engineering Department.

LORD MANUFACTURING COMPANY · ERIE, PA.
Canadian Representative: Railway & Power Engineering Corp. Ltd.

the relay used; but it was found preferable to feed the refrigerator motor through the normally-open contacts and to connect C_1 to one set of contacts as shown to hold the relay closed after making until transients subside.

The tube circuit operates rather gradually in response to a slow drift of temperature, so that the normally-closed contacts open slowly and arc severely as the coil is gradually energized by increasing plate current. The normally-open contacts, on the other hand, are both made and broken quickly because of the inherently unstable magnetic equilibrium of a typical relay.

Adjustment

The heater transformer and tubes and wiring have capacitances to ground which are not likely to be symmetrical. An unbalance due to this cause produces an out-of-phase component which does not show in the output of the differential detector, but which may overload the amplifier. To balance it, open the primary (high side) of T_1 and connect a high-resistance d-c voltmeter across C_2 or C_3. An a-c vtvm or a scope may be used across T_1 primary with blocking capacitor.

Balance the bridge, with the thermistor in its operating position at operating temperature, by adjusting R_5. Connect C_4 of the necessary size across whichever bridge



FIG. 3—Circuit for precise thermometer or thermostat

arm may require it for perfect balance, readjusting R_1 for finer balance.

To balance the differential detector, remove keying tube V_3 and connect a high-resistance d-c voltmeter across the detector output. With the bridge not excited or with amplifier tube V_1 out of the socket, but with T_1 connected, adjust R_7 for zero output.

Triode rather than pentode connection of the keying tube is preferable to avoid excessive screen current at zero bias.

Sensitivity

The sensitivity which can be utilized in a more elaborate version of Fig. 2, shown simplified in Fig. 3, is limited only by stability. The thermistor is stable enough to hold calibration to 0.01 C-degree or better if a suitably aged unit is chosen, according to one of the engineers of the principal manufacturer. Its inherent sensitivity and higher impedance gives it an advantage over the platinum thermometer and both it and its circuit are less expensive. The most obvious way to increase the sensitivity of a resistance thermometer or thermostat is to increase the amplification. The balanced d-c amplifier and differential milliameter or relay indicated in Fig. 3 are also much more sensitive than the tube operating near cutoff as shown in Fig. 2. If the sensitivity is to be increased very much, the bridge should be excited by an oscillator at about 500 cycles through an isolating transformer such as General Radio type 578 or a Leeds & Northrup equivalent. The amplifier is designed for that frequency only but not sharply tuned.

For thermometry only, without control action, the null method is best, calibrating the bridge arms and using the amplifier solely as a bridge detector. Headphones could replace the differential detector.

The author once constructed a differential thermometer on the principle of Fig. 3 which read to 0.001 degree C the difference in temperature between two platinum thermometers. It is believed that this project would have been easier with thermistors because of the greater sensitivity and the lesser effect of lead resistance.



Exactly As Specified

JOHNSON

ANTENNA PHASING EQUIPMENT

Typical phasing unit in JOHNSON cabinet. We can match in design and finish any make of transmitter cabinet.

Careful attention to specifications is an outstanding characteristic of JOHNSON Antenna Phasing Equipment. It is made possible principally because each installation is individually designed. There are no "standard units" which must be adapted, no need of compromises with good engineering. You get what your consultant specifies!

Does this cost a lot? Emphatically no! Because JOHNSON manufactures nearly every component in an adequate variety of ratings and types, our engineers have available just the right material for any application. The cost is no more—frequently it is lower than less flexible, less generously rated equipment.

The same appreciation of technical and economic requirements is evident in other related JOHNSON equipment such as: coaxial line, phase sampling loops, isolation filters, tower lighting filters, RF contactors, pressurized capacitors, variable inductors and open wire line supports.

FOR DETAILED INFORMATION ON ANY OF THESE PRODUCTS WRITE:



Weatherproof antenna coupling unit. Features an interior door which remains closed during adjustments.



Panel mounted coupling network saves money where a tuning house is used. Every major component but the meter is JOHNSON built.

JOHNSON . . . *a famous name in Radio!*

E. F. JOHNSON CO., WASECA, MINNESOTA

DEPEND ON LEWIS SPRING ENGINEERS to keep abreast of the latest delevopments in television coil design and application. New and improved types including double coils with four leads, units with coils cemented to ceramic resistors and other choke, contact, band-tuning and channel coils such as shown above are being mass-produced by Lewis for leading TV manufacturers.

Take advantage of the up-to-the-minute know-how, experience and facilities of Lewis to help design and produce television coils to your specifications. You'll appreciate the efficiency, prompt delivery and economy in which Lewis will satisfy your demands.

There is a Lewis Engineer near you who will welcome the opportunity to check your requirements and quote delivery and price. Call or write us today without obligation.

LEWIS SPRING & MANUFACTURING COMPANY
2656 West North Avenue, Chicago 47, Illinois

Lewis PRECISION SPRINGS
THE FINEST LIGHT SPRINGS AND WIREFORMS OF EVERY TYPE AND MATERIAL

(continued from p 122)



FIG. 2—Series-parallel transformer in equivalent-T form is shown in (A). Inductive coupling (B) must be used in balanced-to-unbalanced transformers

form of a half-section constant-k band-pass filter plus an ideal transformer. The bandwidth Δf_c between cutoff frequencies f_1 and f_2 of the constant-k filter becomes the bandwidth between one-db points on the corresponding transformer. Let f_m be the geometric mid-frequency. We then have

$$f_2 - f_1 = \Delta f_c \equiv \Delta\omega_c/2\pi \quad (1)$$

$$\sqrt{f_1 f_2} = f_m \equiv \omega_m/2\pi \quad (2)$$

The design formulas for a maximally-flat transformer of the form shown in Fig. 1 may be expressed in terms of $\Delta\omega_c$, ω_m, the generator (or load) resistance R_1 and the input (or output) capacitance C_2.

$$C_1 = \Delta\omega_c/\omega_m^2 R_1 \quad (3)$$

$$L_1 = [1 + (\Delta\omega_c/\omega_m)^2]R_1/\Delta\omega \quad (4)$$

$$R_2 = 1/\Delta\omega_c C_2 \quad (5)$$

$$L_2 = 1/\omega_m^2 C_2 \quad (6)$$

$$k = M/\sqrt{L_1 L_2} = \frac{\Delta\omega_c/\omega_m}{\sqrt{1 + (\Delta\omega_c/\omega_m)^2}} \quad (7)$$

The amplitude response of this transformer is geometrically symmetrical about f_m, with a loss curve given by $p = 1 + \frac{1}{4}(\Delta\omega/\Delta\omega_c)^4$ where $\Delta\omega$ is the bandwidth between any two points of equal loss. In Fig. 1C loss curves are plotted against normalized frequency for three values of the ratio $\Delta\omega_c/\omega_m = (f_2 - f_1)/\sqrt{f_1 f_2}$.

EXAMPLE: A matched input transformer is to be designed to connect a coaxial line ($R_1 = 50$ ohms) to the first tube (a 6AK5, $C_2 = 8.5$ $\mu\mu$f) of an amplifier. One-db points are to be at $f_1 = 80$ mc

FOR IMPROVED PERFORMANCE

Specify the NEW

GENERAL CERAMICS

FERRAMIC

magnetic cores

- HIGHER EFFICIENCY
- NON-METALLIC
- HIGHER PERMEABILITY
- NON-DETERIORATING
- LIGHTER WEIGHT

Superior Performance—FERRAMICS, the new ferro-magnetic materials produced and developed by General Ceramics and Steatite Corporation, offer many important advantages over other core materials.

Non-Metallic – FERRAMICS are non-metallic materials possessing permeabilities of 15 to 3500 and volume resistivities of 10^3 to 10^9 ohm centimeters. Specific gravity is between 4 and 5. Therefore, FERRAMICS are displacing other core materials where greater circuit efficiency is required.

Uniform Structure – FERRAMICS are similar to ceramics since they have uniform structure and contain no organic compounds. Thus, non-uniformity of magnetic properties and physical decomposition, common failings with materials containing organic compounds, are eliminated.

Adaptable – FERRAMICS are suitable for all types of core applications and can be mass produced in most shapes and sizes to close tolerance. For complete details, write for Bulletin 1 or submit specifications for recommendations. There is no obligation.

GENERAL

General CERAMICS and STEATITE CORP.

KEASBEY • NEW JERSEY

Makers of STEATITE, TITANATES, ZIRCON PORCELAIN, FERRAMICS, LIGHT DUTY REFRACTORIES, CHEMICAL STONEWARE, IMPERVIOUS GRAPHITE, COAXIAL CABLE

EISLER

Television Tube

MACHINERY





- ECONOMICAL
- MODERN DESIGN
- PRODUCTION ENHANCING

EISLER'S Electronic Equipment is especially Designed and Built to your exact requirements.

From 5" to huge 24" Television Tube

No. 102-VID

No. 57-VID

EISLER specializes in GLASS WORKING MACHINERY for the manufacture of: Cathode Ray; Radio Tubes (Standard, Miniature, Sub Miniature); Fluorescent Lamps; Glass Ampoules; Vials; Incandescent Lamps.

• Consultation without any obligation on your part is cordially invited.

No. 57-8-4 CT

RESISTANCE WELDERS

•

¼ to 300 KVA

EISLER TRANSFORMERS

STANDARD • SPECIAL

Air, Oil or Water Cooled

•

Sizes From ¼ to 500 KVA

EISLER ENGINEERING CO., INC.

751 SOUTH 13th ST. • NEWARK 3, NEW JERSEY

Kenyon *Fits Your Production To A "T"*

Kenyon "T's"—high quality, uniform transformers, are your best bet for development, production and experimental work. For over 20 years, the KENYON "K" has been a sign of skillful engineering, progressive design and sound construction.

Now—reduce inventory problems, improve deliveries, maintain your quality—specify KENYON "T's," the finest transformer line for all high quality equipment applications.

New Catalog Edition! Write Today!

Kenyon new modified edition tells the complete story about specific ratings on all transformers. Our standard line saves you time and expense.

Send for your copy of our latest catalog edition *now!*

KENYON TRANSFORMER CO., Inc.

840 BARRY STREET · NEW YORK 59, N. Y.

TOROIDAL COMPONENTS

PRECISION TUNED CIRCUITS FOR YOUR SELECTIVE AMPLIFIER

ACTUAL SIZE

High Q precision tuned resonant circuits, accurately adjusted to your specified frequency. Toroid coil and capacitor are permanently protected by tough thermosetting plastic. Pigtail leads and light weight allow direct or terminal board mounting.



TYPICAL APPLICATION



FREQUENCY IN K. C.

CUSTOM MADE TOROID COILS



Toroid coils, transformers and discriminators in a large range of inductances, frequencies and power levels. Permalloy dust cores. Uncased, mounted in hermetically sealed cans or coated with thermosetting plastic. Close tolerances with taps at any point. Multiple windings. Up to 2 Henries on wedding ring size. Larger sizes to 30 Henries.

MINIATURE TOROID FILTERS

1⅛" x 1⅛" x 2" HIGH



Specialized design and complete production facilities for your filter requirements. Where space is critical, miniature filters with wedding ring toroids and special capacitors. Supplied in standard units, or designed to your specification. A miniature band pass filter and curve are shown.

RAPID PRODUCTION DELIVERY. Engineering requirements given special attention. Wire, phone or write complete specifications.

COMMUNICATION ACCESSORIES Company

HICKMAN MILLS, MISSOURI

and at $f_s = 120$ mc. The design formulas give:

$\Delta\omega_s = 2\pi\ (120 - 80)\ 10^6 = 2.51 \times 10^8$ rad/sec

$\omega_m = 2\pi\sqrt{120 \times 80} \times 10^6 = 6.15 \times 10^8$ rad/sec

$C_1 = 13.27\ \mu\mu f$

$L_1 = 0.2325\ \mu h$

$R_s = 468$ ohms

$L_2 = 0.311\ \mu h$

$k = 0.378$

It may be preferable to build the T (or π) equivalent of the transformer as shown in Fig. 2A. Since $M = k\sqrt{L_1 L_2} = 0.102\ \mu h$ in our example, $L_a = 0.130\ \mu h$ and $L_b = 0.209\ \mu h$. It is obvious that certain designs may call for a negative L_a or L_b and so cannot be built in equivalent T (or π) form. In the case of balanced line inputs a construction such as that shown in Fig. 2B may be used.

Radiation Alarm with 0.5-Second Response

PULSE-TYPE ionization chamber circuits for radiation detection fail to operate if the radiation intensity rises high enough and fast enough. Direct-current amplifiers used with ionization chambers have shown either a high pickup sensitivity for switching transients, or a slow response if transients were eliminated by bypassing.

The detector shown in the accompanying circuit diagram was designed with the following requirements in mind: (1) Activation of alarm circuit within 0.5 second after intensity reached predetermined level, (2) freedom from false alarm such as might be caused by circuit failure, instability or pickup, (3) assurance of proper



Rapid response radiation alarm circuit

operation even though radiation levels rise well above alarm level in a matter of miscroseconds, and (4) provision for remote operation.

The circuit comprises a battery-operated photomultiplier tube and, one stage of d-c amplification which provides an output signal of the right polarity to fire the relay-operating thyratron. The signal fed to the thyratron grid is smoothed by the 0.05-second time constant network. An anthracene crystal is employed as a scintillator.

Experimental Tests

Tests made with radiation intensities of 1½ and 3 times tripping level show response time to be 0.13 and 0.03 second respectively. Tripping intensity for circuit shown is 0.3 mr per second. Using a 1P21 photomultiplier in place of the 931A, and a 1-meg—0.01-μf grid-leak, the tripping intensity is reduced to 0.03 mr per sec. A further improvement in sensitivity could be realized by providing fixed bias to eliminate background signal and by using a larger input resistor for the 6SJ7.

According to the authors of an article describing this piece of equipment (R. L. Macklin and E. R. Rohrer, *Rev. Sci. Inst.*, p 966, Dec. 1949), the anthracene scintillator will also respond to fast neutrons, but the intensity required is rather beyond that available with small gamma ray from neutron sources. Thus over-all operation checks are periodically made with a small gamma-ray source to ensure that the equipment is connected and functioning properly. The original paper describes work performed for the AEC by Carbide and Carbon Chemicals Corp., Oak Ridge, Tenn.

Television Picture Evaluation

EVALUATION of a television image, as seen by the ultimate viewer, is a subjective rating of the quality of the image. It is desirable that some quantitative means for evaluation be established, and that as nearly as possible, the same scale be used for the various impairments.

Two techniques have been ex-

NOW- A *Practical* SOLUTION TO HIGH-SPEED COUNTING PROBLEMS...

Berkeley DECIMAL COUNTING UNITS

★ **HIGH SPEED** . . . up to 30,000 counts per second; resolves individual pulses separated by as little as 5 microseconds!

★ **DIRECT READING**... Decimal count is indicated directly by illuminated numbers on front panel.

★ **RUGGED, COMPACT** . . . Components mounted in sturdy plastic moulding, moisture and fungus-proofed; enclosed in stamped aluminum case only 1-3/16" wide by 5⅜" high. (5¾" deep, including tubes.)

★ **PLUG-IN MOUNTING** with standard octal base.

TYPICAL APPLICATIONS



MODEL 410 INDUSTRIAL COUNTER uses 3 Decimal Counting Units plus 6-place mechanical register . . . handles up to 10,000 counts per second, gives direct-reading total up to 1,000,000,000 counts.

MODEL 500 TIME INTERVAL METER gives direct-reading indication of elapsed time in units of .0001 second; uses 4 Decimal Counting Units which register cycles from a 10 kc crystal-controlled source during the interval to be measured.

MODEL 2000 DECIMAL SCALER is a complete laboratory instrument for the accurate measurement of nuclear radiation; uses 3 Decimal Counting Units and mechanical register—built on high voltage power supply and automatic control for predetermined count.

Write Department E for Literature, Prices.

Berkeley Scientific Company

SIXTH & NEVIN AVENUE • RICHMOND, CALIFORNIA

Anyone
Can build a
HEATHKIT
Heathkit
SIGNAL
TRACER KIT
$19.50
Heathkit
VACUUM TUBE
VOLTMETER KIT
$24.50
Heathkit
TUBE CHECKER KIT
$29.50
Heathkit
BATTERY
ELIMINATOR KIT
$22.50
Heathkit
AUDIO GEN.
KIT $34.50
Heathkit
CONDENSER
CHECKER KIT $19.50
Heathkit
ELECTRONIC
SWITCH KIT
$34.50
Heathkit
IMPEDANCE
BRIDGE KIT $69.50
Heathkit
R. F. SIGNAL
GEN. KIT . .
$19.50
Heathkit 5"
OSCILLOSCOPE
KIT
$39.50
Heathkit
TELEVISION
GEN. KIT. . .
$39.50
Heathkit
HANDITESTER
KIT . . . $13.95
Heathkits are beautiful factory engineered quality service instruments supplied unassembled. The builder not only saves the assembly labor cost but learns a great deal about the construction and features of the instrument. This knowledge aids materially in the use and maintenance of the equipment. Heathkits are ideal for and used by leading universities and schools throughout the United States. Each kit is complete with cabinet, 110V 60 cycle transformer (except Handitester), all tubes, coils assembled and calibrated, panel already printed, chassis all punched, formed and plated, every part supplied. Each kit is provided with detailed instruction manual for assembly and use. Heathkits provide the perfect solution to the problem of affording complete service equipment on a limited budget. The basic three instruments — an Oscilloscope, Vacuum Tube Voltmeter, and Signal Generator can be purchased in Heathkits for $83.50, about the cost of a factory-built VTVM alone. Write for complete catalog.
HEATH COMPANY
BENTON HARBOR 14,
MICHIGAN
EXPORT DEPT., 13 E. 40th ST., NEW YORK 16, N.Y. · · · CABLE ARLAB — N.Y.

plored for establishing such a rating of image quality, as outlined by P. Mertz, in a paper entitled "Quality Rating of Television Images" presented at the 1950 IRE National Convention. The first employs the time-honored system of presenting an observer with pairs of pictures having slightly different, but known characteristics, and asking him to vote his preference for each pair. A television picture of a lantern slide, with a wide range of controlled echo, is presented side-by-side with an optical projection of the same slide, with varying and controllable degrees of focusing. Color and contrast compensation are provided by a tinted projection screen and a controllable side light on the projection screen. By this system, the impairing effect of the echo is compared in subjective seriousness to that of a sharpness degradation.

By analyzing the vote between off-focus projections and television pictures, it is possible to determine how much the preference amounts to in the case of any given pair. The vote analysis consists of setting as one limen the difference between two pictures where 75 percent of the observers prefer the one to the other. The vote distribution is found to follow approximately the normal error law, so that the difference becomes two limens where the preference vote is about 91.1 percent, and three limens for 97.8 percent. The image quality difference between two pictures is measured by the number of liminal units computed from the vote preference.

Another Technique

The second system consists of presenting to the observer a picture affected by differing and controlled amounts of a given impairment in random sequence. The observer is asked to rate the impairment with any one of seven classifications from 1 (not perceptible) to 7 (not usable). The echo amplitudes are then plotted against the seven possible comments, and the resulting curve represents a median. From the distribution of votes around this median, it is also possible to set up a system of liminal difference ratings for the pictures. One

Just Published

TELEVISION SERVICING

1. A practical guide on television installation, adjustment, and servicing procedures. It covers typical circuits used in receiver sections, the problems and solutions of antenna installation, external noise, interference, weak signals — everything the serviceman needs to know to track down and repair defective television reception. **By S. Heller, Instr. Amer. Radio Inst., N.Y.C. and I. Shulman, Ch. Engr., Fed. Telev. Corp. 434 pages, $5.50**

Questions and Answers in TELEVISION ENGINEERING

2. This new manual gives you the most recent data on television transmitters, commercial receivers, and all phases of general theory in television engineering. Covers intercarrier sound, dual focus, germanium crystal detectors, and selenium power rectifiers. Answers the problems of the television serviceman, technician and others . . . gives FCC standards and regulations . . . discusses latest design factors in RF section of television transmitter, etc. **By C. V. Rabinof, Dean, Amer. Telev. Labs. of Calif. and M. E. Wolbrecht, Former V.P., Amer. Telev. Labs of Calif. 380 pages, $4.50**

BASIC TELEVISION

Principles and Servicing

3. An A-to-Z manual for everyone concerned with TV receiver installation and servicing. Elaborate trouble-shooting charts show symptoms, causes and cures for over 50 common TV receiver problems. Simplified diagrams, drawings and photographs clearly illustrate every topic. **By R. B. Grob, Teacher, R.C.A. Inst. 592 pages, $6.50**

ELECTRON-TUBE CIRCUITS

4. Timely new book discusses different classes of circuits with widespread application in radar, television pulse communication, and general electronic control. Shows how to combine circuits of various types to achieve one or a number of operations. Treats power rectifiers, filters, regulators, amplitude modulation, etc. **By S. Seely, Prof. of Elec. Eng., Syracuse U. 529 pages, $6.00**

SEE THEM 10 DAYS FREE

McGRAW-HILL BOOK CO.,
330 W. 42nd St., N. Y. C. 18, N. Y.

Send me book(s) corresponding to numbers encircled below for 10 days' examination on approval. In 10 days I will remit for book(s) I keep, plus few cents for delivery, and return unwanted book(s) postpaid. (We pay for delivery if you remit with this coupon; same return privilege.)

1 2 3 4

Name .....
Address .....
City ..... Zone ... State ...
Company .....
Position L-7-50

This offer applies to U. S. only

AGASTAT TIME DELAY RELAY

The magnetic circuit of an AGASTAT makes it a dependable, efficient instrument.
Time delay with the basic type 1 starts when the coil is energized.
Catalog and information on request.

AGA AIRPORT LIGHTING · AGA VISIONLITE REFLECTORS · AGA MARINE SIGNALING EQUIPMENT · AGA AGASTAT TIME DELAY RELAYS

AMERICAN GAS ACCUMULATOR COMPANY
1027 NEWARK AVENUE • ELIZABETH 3, N. J.

New! Revolutionary!

Superspeed
WHITE FLASH Activated ROSIN CORED SOLDER

SAVES TIME AND COSTS

SCIENTIFICALLY DESIGNED *to meet Modern Production Methods in the fields of*

Radio • Television • Telephone • Telecommunications • Railroad Signalling • Automotive Industries Can Manufacturing • Machinery • General Electrical Work Aeronautics and many others.

SAFE! SPEEDY!! EFFICIENT!!!

THE FLUTED CORE

—stellate in section—contains a fluxing medium of unrivaled efficiency close to periphery of the solder at six points. It permits instantaneous "wetting" and fluxing at correct temperature, and obviates dry and high resistance joints.

SUPERSPEED WHITE FLASH Activated Rosin Cored Solder comes in different diameters and alloys—YOU CAN SELECT THE SOLDER TO GIVE MAXIMUM EFFICIENCY AT THE CORRECT TEMPERATURE—FOR YOUR JOB—or—we make it to fit your requirements.

Check these Important Features:

★ Activated rosin flux insures maximum "wetting" and spreading
★ No dry or high resistance joints. No risk of corrosion.
★ Economical. Goes further. Gives more joints per pound of solder.
★ Faster. Operators solder more joints.
★ Cuts down rejects.
★ Non-hygroscopic residue of high dielectric strength.
★ No unpleasant odor.
★ Complete continuous core.

Write to our U. S. Representative for samples, technical literature, and prices. Stocks maintained in Rochester for immediate delivery to all points.

Manufactured Solely by
H. J. ENTHOVEN & SONS LTD.
LONDON, ENGLAND

U. S. Representative
MAURICE H. ESSER
Dept. A, 113 N. WATER STREET
ROCHESTER 4, NEW YORK

AVOID LOSSES FROM
"NICKING"
Not being an extruded plastic, absolute uniformity of diameter can be guaranteed. Therefore:—
NO NICKING OF CONDUCTORS
NO CONSTANT RESETTING OF BLADES

specify
CORNISH

"NOFLAME-COR"
the TELEVISION hookup wire

APPROVED BY UNDERWRITERS LABORATORIES AT 90° CENTIGRADE — 600 VOLTS

Proven BEST, and specified regularly, by leading manufacturers of television, F-M, quality radio and all exacting electronic equipment. For maximum output and minimum rejects. Available in all sizes, solid and stranded. Over 200 color combinations.

PRODUCTION ENGINEERS: Specify "NOFLAME-COR" for absolute uniformity of diameter, permitting clean stripping of insulation without damage to the copper conductor...

NO NICKING OF CONDUCTORS
NO CONSTANT RESETTING OF BLADES

AVOID LOSSES FROM
"BLOBBING"
Not being an extruded plastic, eliminates the costly "blobbing" of insulations under soldering heat

- Flame Resistant
- High Insulation Resistance
- Heat Resistant
- Facilitates Positive Soldering
- High Dielectric
- Easy Stripping
- Also unaffected by the heat of impregnation — therefore, ideal for coil and transformer leads

COMPLETE DATA AND SAMPLES ON REQUEST

"made by engineers for engineers"

CORNISH WIRE COMPANY, Inc.

609 North Michigan Avenue, Chicago 11 | 15 Park Row, New York 7, N. Y. | 1237 Public Ledger Bldg., Philadelphia 6

MANUFACTURERS OF QUALITY WIRES AND CABLES FOR THE ELECTRICAL AND ELECTRONIC INDUSTRIES

liminal unit turns out to be about one comment number spacing, over the center portion of the scale.

The first system is somewhat more complicated to set up, but the results obtained are more absolute, since only a comparison is involved, rather than evaluation in terms of words. The comparison system has also been applied to the comparison of sharpness as a quality parameter of the picture with highlight luminance and contrast ratio.

Multiplier Phototube Improvements

PHOTOMULTIPLIER tubes have become standard equipment in the fields of nuclear research, astronomy, photoelectric spectrometry, and other fields involving light measurements at extremely low intensities. A significant improvement in the type 1P21 has recently been announced by the RCA Tube Department.

The equivalent noise input of the improved 1P21 has been reduced to 5.1×10^{-13} lumen at room temperature. This value represents a sixfold reduction in operational noise and permits a corresponding reduction in the lower limit of measurable light intensities.

Typical application of the new tube in atomic research involves the use of a light-piping technique to measure radiation generated by a cyclotron. To overcome the problem of introducing a test instrument into the cyclotron itself, this technique utilizes a long light-conductive rod of quartz or clear plastic with a phosphor on the end of it. Flashes of light or scintillations produced when radioactive particle radiation strikes the phosphor are

Light-piping device for remote detection of radioactivity using an anthracene crystal coupled to a 1P21 multiplier phototube by a lucite rod

conducted down the rod to the phototube, which is housed in a light-tight box outside the cyclotron. In this way radioactivity caused by the cyclotron beam can be conveniently and accurately measured.

The photograph shows the unit used in the Rochester cyclotron. The heavy shield guards the photomultiplier from the strong magnetic fields surrounding the cyclotron. The top section houses a 6J6 cathode follower which permits sending the photomultiplier signal over a 300-foot 93-ohm cable.

The anthracene crystal is mounted on the end of an 8-inch lucite rod which conducts scintillations caused by radioactive particles striking the crystal. The lucite rod is covered with black paper to keep out room illumination, and the crystal is wrapped with aluminum foil which is penetrable to the radioactive particles.

Transistor and Fieldistor

By Otmar M. Stuetzer

Controls and Systems Laboratory
Air Materiel Command
Wright Field, Ohio

Recently, development work on a high-input-impedance crystal amplifier, the fieldistor, was disclosed by the Air Force. It is related to and was evolved from the Bell transistor[1]. Although in the early stages of development and not industrially available, a brief comparison of the devices shall be given.

The transistor, fieldistor and germanium and silicon photocells have one essential element in common; a rectifying metal-to-semiconductor-contact, operated in the direction of high resistance. We will choose a germanium high-back-voltage rectifying contact to remind the reader of the present concept of such a function[2].

On a free surface, as well as under a negatively-charged metal electrode, the semiconductor is bound by a double layer, very much related to the one on a metal surface, which counteracts the enormous pressure of the electron gas. In our case it consists of a negative surface charge and a positive space-charge layer underneath, about 10^{-4}

MOLDITE IRON CORES
KEEP THE OWNER OF THIS SET HAPPY



CONSISTENT HIGH QUALITY PERFORMANCE ...IS THE ANSWER

HERE'S WHY:
- Our own formulas are used exclusively
- We specialize in making iron cores only
- Our engineers are thoroughly familiar with every iron core application
- Continuous manufacturing controls assure uniformity, quality, economy, dependability
- Special powder mixing equipment and procedures
- Increased production, test, and inspection facilities (Note new address below)

Samples promptly submitted upon request for design, pre-production, and test purposes.

SEND FOR CATALOG 104

NATIONAL MOLDITE COMPANY

1410 CHESTNUT AVENUE HILLSIDE 5, NEW JERSEY

Jerry Golten Co.
2750 W. North Ave., Chicago 22, Ill.

Martin P. Andrews, Garden City, N. Y.
(Northern N. Y.)

Perlmuth-Colman & Associates
1335 South Flower, Los Angeles, Cal.

Jose Luis Pontet
Cordoba 1472, Buenos Aires

There's a TIC Potentiometer for every application

TIC for top electrical and mechanical precision



Type RV2 High Precision Potentiometer
One of a series of semi-standardized types of metal-base potentiometers with exceptionally high electrical accuracy and mechanical precision. For both linear and *non-linear* functions. Designed for precision instrument, computer and military applications. Accurate phasing of individual units possible with exclusive clamping method of ganging.

TIC for precision and economy



Type RV3 Precision Potentiometers
. . . available in models for either *linear* or *non-linear* functions with stock resistance values ranging from 100Ω to 200,000Ω and power ratings of 8 and 12 watts. 360° mechanical rotation or limited by stops as desired. Models with 5% total resistance accuracy — $6.00 . . . 1% accuracy — $8.00. Special models available for high humidity applications.

TIC for special use . . .



Type RVT Translatory Potentiometer
Actuated by longitudinal instead of rotating motion providing linear electrical output proportional to shaft displacement. Used as a position indicator, high amplitude displacement type pickup and for studying low frequency motion or vibration. Features exceptionally high linearity and resolution. Available in various lengths depending on amplitude being studied.

Valuable catalog — yours for the asking. Contains detailed information on all TIC Instruments, Potentiometers and other equipment. Get your copy without obligation — write today.

TIC TECHNOLOGY INSTRUMENT CORP.
1058 Main Street, Waltham 54, Massachusetts
Engineering Representatives
Cleveland, Ohio — PRospect 1-6171
Manhasset, N. Y.—Manhasset 7-3424
Chicago, Ill.—Uptown 8-1141 Boonton, N. J.—Boonton 8-3097 Rochester, N. Y.—Charlotte 3193-J
Cambridge, Mass.-ELiot 4-1751 Canaan, Conn.-Canaan 649 Hollywood, Cal.-HOllywood 9-6505

cm thick. The latter is formed by the positively charged donator ions, about 10^{-5} cm apart, which are not compensated by free electrons as in the interior of the crystal.

A few mobile electrons, decreasing in number from 10^{18} from the inner part of the barrier layer to around a millionth of this value right under the surface, account for one part of the conductivity. If the carrier density decreases below a certain value, conduction due to defect electrons, or holes, becomes important. This will occur first close to the surface, as indicated roughly in Fig. 1 illustrating our concept. It might be increased by acceptor surface contaminations.

For the electron current indicated by arrows as flowing from the collector electrode into the semiconductor the barrier layer constitutes a high impedance; currently used contacts show about 10^4 to 10^5 ohms.

In this rather simplified concept surface charge, space-charge layer thickness, electron distribution, and hole distribution are in a complex mutual equilibrium. All semiconductor amplifiers or transducers work by disturbing this equilibrium, thus modulating the thickness of the space-charge layer and hence the impedance seen by the collector current.

In the semiconductor photocell f-i carriers are knocked out of the crystal lattice by photons. They diffuse into the barrier layer, decreasing its depth. In general, this action leads to a higher collector current. Sometimes the decrease in hole surface conduction, however, may be dominant.

The transistor is explained most simply by assuming that the current injected into the crystal by a second contact point, the emitter, is mostly carried by holes. These are attracted by the negatively-charged collector and modulate the



FIG. 1—Rectifying germanium contact control configuration

"Springs are Springs"

maybe so
for most people
... but NOT
for ACCURATE



HOW often have you heard a spring user or even a manufacturer say "Springs are springs, what difference who makes them if the price is right?" Here at Accurate, we think it makes a big difference and our experience proves it. *Exact* conformance to specifications can be mighty important if it means easier, faster assembly and better performance for your product. Quality control is important, too, when it saves you time and trouble. "Know-how" and facilities for making springs the least costly way can mean many dollars for you.

It all adds up to lower overall spring costs for you and that's what we at Accurate have to sell. Before you place your next spring order we would like to show you what it means to you in particular. There's no obligation; write today.

Accurate Springs

COST CONSCIOUS QUALITY
Since 1930
ACCURATE SPRING MFG. CO.
3830 W. Lake St. • Chicago 24, Ill.
Springs, Wire Forms, Stampings

INSULATION
FORMVAR • FORMEX • ENAMEL
STRIPPED CLEAN IN SECONDS
with X-VAR

X-VAR is non-corrosive, non-creeping — leaves wire ready for soldering. Now in use by leading manufacturers of electrical products. *Write for FREE SAMPLE for testing.*

FIDELITY CHEMICAL PRODUCTS CORP.
472 Frelinghuysen Avenue, Newark 5, New Jersey

—more compact, higher accuracy!



½ WATT INDUCTIVE
MAX. RES: .01 to 7,500 ohm (331 Alloy)
.01 to 4,000 ohm (Nichrome)
.01 to 1,250 ohm (Manganin)
BODY SIZE: ⅝" lg. by 3/16" diam.
TOLERANCE: STANDARD 1%

1 WATT INDUCTIVE
MAX. RES: .01 to 15,000 ohm (331 Alloy)
.01 to 8,000 ohm (Nichrome)
.01 to 2,500 ohm (Manganin)
BODY SIZE: 1" lg. by 3/16" diam.
TOLERANCE: STANDARD 1%

Can be supplied non-inductive with one-half indicated maximum resistance.

IN-RES-CO
APPLICATION-DESIGNED
RESISTORS

Economical in Cost

IN-RES-CO WL series resistors were designed to meet increasing demands for a compact resistor of high accuracy priced for general use. They meet the most critical requirements—close tolerance, ability to withstand overload, long life. Write today for catalog describing the full line of quality IN-RES-CO resistors.

IN-RES-CO

INSTRUMENT RESISTORS CO., 1056 COMMERCE AVE., UNION, N. J.

How to meet a payroll (at a cost of $3.19)

Twenty-four hours before factory payday, another check-writing machine was needed *fast*. At 10 A.M. plant manager ordered one from supplier 400 miles away. He specified Air Express, the service regularly used to keep production rolling. 26-lb. carton delivered same day at 2 P.M.—in time! Shipping cost only $3.19!

$3.19 was total cost – and *included* door-to-door service! Air Express is the most convenient way for you to ship or receive—in addition to being the world's fastest transportation method.

You get round-the-clock service with Air Express. Shipments go on all flights of the Scheduled Airlines. Air Express is service you can *count on* to keep your business rolling in high gear.

Air Express gives you all these advantages

World's fastest transportation method.
Special door-to-door service at no extra cost.
One-carrier responsibility all the way.
1150 cities served direct by air; air-rail to 18,000 off-airline offices.
Experienced Air Express has handled over 25 million shipments.

Because of these advantages, regular use of Air Express pays. It's your best air shipping buy. For fastest shipping action, phone Air Express Division, Railway Express Agency. (Many low commodity rates in effect. Investigate.)

AIR EXPRESS
GETS THERE FIRST

Rates include pick-up and delivery door to door in all principal towns and cities

A service of
Railway Express Agency and the
SCHEDULED AIRLINES of the U.S.

barrier depth around the collector.

The fieldistor applies a high electrostatic field F between the surface of the crystal and a control electrode, as indicated in Fig. 1. If the distance between is small enough (around 10^{-4} to 10^{-5} cm) a small voltage applied will create the high field strengths necessary for obtaining a controlling effect (around 10^{5} volts per cm). The surface charges associated with the field will create free carriers according to Shockley and Pearson[4].

Impurities on the surface have a pronounced influence, possibly by electrochemical processes moving or creating acceptors or donors. The experimental fact is that sufficiently high field strengths of either sign will increase the current through the collector electrode.

Present Day Devices

The transistor, where the controlling electrode or emitter touches the surface and is operated in the forward direction, has necessarily a low input impedance. Its output impedance is close to that of the collector point contact. Representative values are 300 and 20,000 ohms respectively. The signal is applied on top of a bias current of several milliamperes at a few volts. As the current amplification factor is around unity, the transistor can be classified as a voltage amplifier.

The fieldistor has theoretically an infinitely high d-c input impedance like a vacuum triode, if we disregard leakage currents. Its output impedance is that of the contact. It needs only extremely small currents to control the collector current and may thus be considered as a current amplifier. A bias of around 10 volts is required. The voltage amplification is around unity for



FIG. 2—Subminiature fieldistor

good samples and at low frequencies.

As the fieldistor resembles rather closely a vacuum triode, its performance can best be judged by its transconductance, the ratio of collector current change per volt signal. Twenty micromhos is a representative value, which looks very poor compared to vacuum tubes. Much higher values have been observed occasionally.

The noise figure of the two devices is about equally bad, which is to be expected.

The manufacturing of the fieldistor involves some problems, as the control electrode or electrodes have to be very close to the surface.

A subminiature model of the fieldistor is shown in Fig. 2.

For further information on performance and technique the author refers to more detailed publications.[4,5]

REFERENCES

(1) Semiconductor Issue, *B. S. T. J.*; 28 Jul. 1949.
(2) J. Bardean and W. Brattain, *Phys. Rev.* 75, p 1,208, 1949.
(3) W. Shockley and G. L. Pearson, *Phys. Rev.* 74, p 232, 1948.
(4) O. M. Stuetzer, Microspacer Electrode Technique (Submitted for publication in *Proc. IRE*).
(5) O. M. Stuetzer, High Input Impedance Crystal Amplifier (Submitted for publication in *Proc. IRE*).

Linear Sweep Generation

BY DAVID SAYRE
Oxford, England

THE CONSTANT-CURRENT triode circuit can be made the basis of two linear sweep generators, one to generate a negative-going sweep and the other to generate a positive-going sweep. These circuits are accurate, reliable, easy to design and very economical.

Mathematical analysis indicates the desirability of using a high-μ tube. It is also desirable to use a tube with a short grid base, to minimize the effect of tube change on the exact cathode voltage and hence on plate current. The 6SL7 meets both these requirements very well.

Negative-Going Sweeps

If the constant current is made to pass through a capacitance C, as in Fig. 1, a negative-going linear sweep is formed at the plate;

MANUFACTURERS AND DESIGNERS OF
CONTINUOUSLY VARIABLE
REGULATED DC SUPPLIES

SINCE 1943!



✓ MODEL A3 FEATURES

- ✓ Continuously variable, 0 to 350 volts.
- ✓ Ripple voltage less than 10 millivolts.
- ✓ Regulation better than .5%.
- ✓ Maximum current 200 milliamperes.
- ✓ Stabilized variable bias supply.
- ✓ 6.3 volts AC at 5 amperes.
- ✓ Reasonably priced.
- ✓ Request Bulletin 52 for detailed specifications.

87 leading research laboratories use daily hundreds of our "A" series power supplies.

For general laboratory use, the A 3 is worthy of adoption as STANDARD equipment.

*Described in MIT Radiation Laboratory Series Vol. 21, Electronic Instruments.

FOR HIGHER VOLTAGE AND HIGHER CURRENT OR DUAL UNITS REQUEST BULLETIN 53.

Oregon ELECTRONICS MFG. CO
206 S.W. WASHINGTON ST., PORTLAND 4, ORE., U.S.A.

Want to catch a customer's eye?

Little lamps add new appeal—make your product stand out!

Eyes turn to the product with "light appeal". Tiny jewel lights that flash a warning or an "O.K.". Lights that say "here I am" in the dark. Lights that simplify operation, add novelty and give extra safety and convenience!

Whether you're making electronic equipment for industrial use or household products, you'll find General Electric miniature lamps that fit right into your design—give it new appeal at low cost! Complete line of types and voltages—filament or neon glow. And you know you can always depend on G-E lamps for quality and long service.

For assistance in selecting the proper type, consult your nearest G-E lamp district office. Or write General Electric, Nela Park, Cleveland 12, Ohio.

MINIATURE LAMPS

You can put your confidence in—

GENERAL ELECTRIC



FIG. 1—Basic negative-going linear sweep generator

as long as the switch is closed the plate will be at E_{bb} volts and i_p will flow through the switch. When the switch is opened i_p must flow through C. The rate of change of voltage at the plate is $-i_p/C = -E_{bb}/RC$ volts per second. For the values of Fig. 1 the sweep thus falls at the rate of 1 volt per microsecond. By proper choice of these values sweep speeds much faster or much slower than this can be obtained. The sweep will continue until it has dropped to about 50 volts, or until the switch is closed again. At the end it will be falling about 2 percent slower than at the start.

Electronic Switch

For most applications the chief difficulty of this circuit is the switch. If the sweep is to run continuously the simple arrangement of Fig. 2 may be used. Here V_2, which acts as the switch, is turned on very hard momentarily by the incoming pulses and each time rapidly raises the output voltage to 300 volts. Since under such circumstances a section of a 6SN7 can conduct 100 ma or more, the duration of the pulses need be only $i_p/100$ (i_p in ma) of the duration of the sweep. For $i_p = 1$ ma a duty



FIG. 2—Practical continuously-running negative-going linear sweep generator, using pulse input to actuate electronic switch

NATIONAL

• Proven
• Dependable
• Quality



PRECISION-WOUND IF TRANSFORMERS

For years, National's precision-wound IF transformers have more than met the most exacting government specifications and have proved exceptionally stable and dependable under the severest operating conditions.

National IF transformers can be produced in quantity for special commercial applications. Send your specifications.

Address export inquiries to Exp. Div., Dept. E-650

National
NATIONAL COMPANY, Inc.
MALDEN, MASSACHUSETTS

WIRE *Made to Your Order*

• Here are (1) Engineering and research facilities to work on your particular wire problems; (2) Production geared to any quality and quantity desired; (3) Unsurpassed craftsmanship; and (4) Wire that's made right
• Let us quote!

YOUR PRODUCT

HUDSON WIRE

Partial List of Products . . .

Bare Wire (Hudson Wire Division):
Copper. Brass. Bronze. Zinc. Silver-plated. Tin. Phosphor-bronze. Nickel. Silver. Cadmium. Specialty Wires.

Insulated Wire (Winsted Division):
Enameled. Litz. Cement-coated. Enameled. Cotton. Silk. Celanese. Glass-fibre. Enameled Aluminum. Formvar. Loop Wire. Etc.

Winco
TRADE HUDCO MARK

One of the Oldest Fine Wire Companies in America

HUDSON WIRE COMPANY

GENERAL OFFICES: OSSINING, N.Y. • WINSTED DIVISION: WINSTED, CONN.

New Type 2A TAP SWITCHES
HAVE A CONSTANT CONTACT RESISTANCE OF
ONLY 1 or 2 MILLIOHMS!

These high quality switches with up to 24 contacts were specifically developed to meet the need for rugged precision instrument switches that have longer operating life and are economical components in competitively priced electronic instruments and military equipment.

•

Write for Technical Bulletin No. 28.



TECH LABORATORIES PALISADES PARK NEW JERSEY

A Complete Line of PRODUCTION TEST EQUIPMENT for TV Manufacturers

Tel-Instrument has designed and provided the production test equipment for many of the major TV manufacturers. A complete line of instruments designed to be unusually critical in the testing of TV receivers is available. They are the result of the wide practical experience of Tel-Instrument engineers plus a complete understanding of the production problems of TV manufacturing.



TYPE 2120
R.F. PICTURE SIGNAL GENERATOR

Provides picture and sound carrier. Modulated by standard R.M.A. composite picture signal. Sound carrier stability suitable for testing Inter Carrier type receivers. Internal 400 cycle FM and External audio with 75 microsecond pre-emphasis. Output max. 0.1v p-p across 75 ohm line. Available channels 2-13.



TYPE 1200 A
12 CHANNEL
R.F. SWEEP GENERATOR

Intended for precise adjustment of R.F. head oscillator coils and R.F. band pass circuits. Pulse type markers at picture and sound carrier frequencies extend to zero signal reference base line. Accuracy of markers 0.02% of carrier frequency. 12 to 15 MC. sweep on all channels. Max. 1.V peak output across a 75 ohm line. Provisions for balanced input receivers. Instant selection by push button.

TYPE 1900
CRYSTAL CONTROLLED
MULTI-FREQUENCY GENERATOR

A 10 frequency, 400 cps. modulated crystal controlled oscillator, ideal for production line adjustment of stagger tuned I.F. amplifiers. Available with crystals ranging from 4.5 to 40 M.C. Output frequency accurate to 0.02% Immediate push button selection of frequency. Output attenuator range 5V to 500 microvolts. Self contained regulated power supply

TYPE 1500 A
I.F. WOBBULATOR

A two band sweeping generator covering the range of 4.5 to 50 M.C. Capable of a band width of approximately ±25% on either band. Five pulse type crystal generated markers to specified frequencies available for each band. Accuracy of markers .05% Zero signal reference base line with markers extending to base line. I.V. output max. into 75 ohms A saw sweep available for "X" axis of scope.

Write for Detailed Engineering Data Sheets.

Tel-Instrument Co. Inc.
52 PATERSON AVENUE • EAST RUTHERFORD, N. J.

cycle of 99 percent is easy to obtain.

During the sweep run-down, V_1 is cut off by grid-current bias accumulated across the grid RC network. Transformer T can be any pulse transformer. Usually there will be a blocking oscillator elsewhere in the circuit, in which case V_1 can simply be driven from the third winding on the blocking oscillator pulse transformer.

Positive Going Sweep

To obtain a positive-going sweep one must put C in the cathode circuit of the constant-current triode as in Fig. 3. This, however, causes the sweep to appear on the cathode; to keep the current constant, the sweep must be placed on the grid also. This is accomplished by C'. No current can be allowed to pass through C', however, for any such current would alter the current through C itself. For this reason the grid is returned to ground not by a resistor but by diode V_3, which is cut off all during the sweep.

As long as the switch is closed current i_p flows through it. When it is opened the current is diverted into C and the sweep rises at a rate of $i_p/C = E_{cc}/RC$ volts per second. The sweep will continue until the cathode of V_1 has risen to within about 50 volts of E_{bb} or until electronic switch V_2 is closed again by an input pulse.

With the values indicated, the positive-going circuit is suitable for generating a 250-volt linear sweep with a slope of 1 volt per microsecond. If the sweep is to run continuously the grid of switch tube V_2 should simply be supplied with short positive pulses. If single sweeps are required a negative gate of the desired duration must be supplied.

Comparison with Other Circuits

The positive-going circuit contrasts favorably with the ordinary bootstrap linear sweep generator. However, in the bootstrap circuit the charging current for C must flow through C' and both must be recharged after each cycle. Higher duty cycles are therefore easily obtained with the positive-going circuit. For the same reasons C' in the bootstrap version must be



FIG. 3—Practical positive-going linear sweep with switch tube

larger than C by a factor of 10 or more, whereas in the circuit of Fig. 3 it can be as small as 0.001 μf.

The two linear sweep generators described may properly be termed precision circuits. They are suitable for such applications as linear time-modulation, the measurement of short time-intervals as in radar ranging, and the generation of linear functions in electronic computers. Their accuracy is intermediate to those of the two principal methods now employed, the bootstrap and the Miller feedback circuits, being slightly better than the former and slightly poorer than the latter.

It is a characteristic of both these circuits that their output impedance is almost purely capacitive. Consequently the circuit which they are intended to drive may present an input admittance which is capacitive with no harmful effects other than a decrease in the slope of the sweep, but may not present a resistance without some differentiation of the sweep occurring. In this respect these generators resemble the bootstrap circuit but are inferior to the Miller feedback circuit, which has a low output impedance and can drive any type of load.

Surface Wave Transmission Line

A SINGLE wire, coated with a special insulation and terminated in funnel-shaped impedance-matching devices, as shown on the next page is a high-efficiency transmission device for microwaves. Signal Corps engineers at Fort Monmouth predict this sort of surface wave transmission line will replace coaxial cable and waveguide for many ap-

MOSINEE

"More than Paper"

If you have a fabricating or processing problem involving paper . . . if you require definite technical characteristics and, above all, *dependable uniformity*, it may be worthwhile for you and MOSINEE technicians to get together. MOSINEE is not interested so much in terms of volume production as in our ability to render helpful service to manufacturers in the field of electronics and in the electrical goods industry. Our "paperologists" are at your service for consultation. Please write Dept. E.

MOSINEE PAPER MILLS COMPANY • MOSINEE, WIS.
Essential Paper Manufacturers

MODERN ELECTRONIC DESIGN MEANS PLUG-IN UNIT CONSTRUCTION

With basic elements as units—that plug-in, slide-in, lock-in, break away *easily*—so that electronic equipment is *instantly accessible*—ready for rapid checks, servicing, and unit replacement.



More and more engineers are finding that *plug-in unit construction* is the type of design that makes many of the new complex electronic projects feasible to operate and maintain. It's also recognized that *plug-in, unit principles* make present electronic equipment much more practical for wider general use.

Up to now there has been no one place where components *specifically designed* for *plug-in, unit construction* were available. To get this type of construction—it has been necessary for engineers to design and have parts custom made or improvise with standard components to make shift arrangements.

Here at Alden's we are designing and manufacturing components for *plug-in unit construction*. We are setting up to work with manufacturers on as many of these problems as possible. Very frankly, much of our work is still in the pilot run stage—but, in every instance—proven in use. If you don't see the answer to your problems here—let us work it out with you.



Rack connected chassis—become instantly accessible. Half twist of handles brings chassis into place or ejects—no matter how heavy. Built for racks or as separate units—miniature and standard sizes.



Rugged color coded rack connectors—make and break circuits—provide rapid circuit checks. Wide mating tolerances compensate for any chassis misalignment. Miniature and heavy duty sizes.

Top operated clamps for tubes and plug-in units. Take minimum of space. Can be operated in cramped locations. Free floating—orients unit to socket without straining or bending pins.

Alden Cap Captive Convenience Screws—Hold miniature chassis, heavy plug-in cans or detachable mechanical units securely. Assemble easily in production by power tools—yet any tool or coin services in field.

At last—a base specifically designed for plug-in units.
No more broken bosses, bent pins, "shorted" circuits.



More and more engineers have been unitizing the basic elements of their circuits into compact, easily replaceable plug-in units. Since the conventional octal and tube socket bases have been the only component readily available, they have been constantly plagued by the broken bosses, bent pins, and "shorted" circuits caused by these bases.

This suggested an entirely new approach was necessary, so we went to work with some of these engineers. Out of this work the *Alden-Noninterchangeable plug-in base* was developed.

Pins have been made strong and stubby—for long, rugged use. The boss is eliminated entirely. Slight lead of center pins and locating rings with marker in the socket allow quick lining up of plug-in units. Further, this base is supplied with 2 to 11 contacts—in variable pin patterns—so that even where the same number of contacts are used, the pin layout may be varied so only the correct unit will mount in its proper socket. Pin patterns can even be selected to isolate critical voltages or signals.



Write today for literature and samples. Let Alden work with you on your components for *plug-in, unit construction*.

Write for new booklet on "Components for Plug-in Unit Construction"

ALDEN PRODUCTS CO. 117 NORTH MAIN ST. BROCKTON 64, MASS.

plications. Experimental models of the transmission line show its efficiency to be ten times that of com-

parable types presently in use. The device has been named, "The G-String"—after its inventor, George Goubau of the Signal Corps Engineering Laboratories.

SURVEY OF NEW TECHNIQUES

TO PRODUCE a stereoscopic effect, two television cameras are mounted side-by-side to view the object from slightly different angles. The tv signals corresponding to the two offset scenes are then transmitted to two kinescopes. The separate images are combined and viewed through special filters to give the three-dimensional pictures.

MAGNETIC FIELDS around magnetized recording wire can be viewed and photographed by stretching the wire across a clean glass plate, dropping on it a suspension of carbonyl iron particles (approximately 0.0001 inch diameter) in light oil



and using a standard contour-measuring projector with lenses and mirrors to project the resulting pattern onto a screen at a magnification of 150 diameters. The technique is described in NBS Technical Report 1316.

COSSOR for QUALITY

Oscilloscope Recording
simplified with the
COSSOR MODEL 1428 CAMERA

CHECK THESE FACILITIES
25 ft. of film or paper
Standard 35 mm. stock
Guillotine for removing any length of exposed film.
Ground glass focussing screen.
Shutter lock for time exposures.
Shutter-operated beam triggering switch.
Trap door for aligning traces.



COSSOR MODEL 1429
MOTOR DRIVE ATTACHMENT

for use with 1428 Camera—uses capacitor motor for high starting torque, worm-coupled to 3-speed gearbox. Three speed ranges available.
Type F .4", 12", 36"/sec.
Type M. .4", 1.2", 3.6"/sec.
Type S. .04", .12", .36"/sec.

DESIGNED FOR USE WITH COSSOR TWIN BEAM SCOPES.

Model 1428 $220 fob New York
Model 1429 $137 fob Halifax $198 fob Halifax $115

STOP PRESS
Alternative Model 1428C with 100' film capacity now available ..... $320 New York.

COSSOR (CANADA) LIMITED
Windsor St., Halifax, Nova Scotia
★
BEAM INSTRUMENTS CORP.
Room 907, 511 Fifth Ave.,
New York 17, N. Y.

DO YOU KNOW?

—that a PILOT LIGHT CAN IMPROVE YOUR PRODUCT
. . . . add attraction — safety — service?

Ask DIALCO
—what lamp to use
—how to use it
—what it will do
—what it will cost

THIS MAY BE THE ONE
Designed for low cost NE-51 Neon
• Built-in Resistor • Patented
• U/L Listed • Rugged
Catalogue Number 521308 — 997
for 110 or 220 volts.

SAMPLES
for design purpose
NO CHARGE

NEW! Write for the "HANDBOOK OF PILOT LIGHTS."
Write us on your design problems.

The DIAL LIGHT COMPANY of AMERICA
Foremost Manufacturer of Pilot Lights.
900 BROADWAY, NEW YORK 3, N. Y. TELEPHONE SPRING 7-1300

See the New Precision Coil Bobbins

—*with* Anchored Flanges
that can't come loose!

Flanges are securely locked in place on a plastic-coated core to assure coils wound to closer tolerances and fewer rejects. Flange cannot slide to allow crowding of turns, and wire cannot slip off coil form. Insulation is improved. Bobbins made any shape—round, square, rectangular—any size, of finest dielectric Kraft, fish paper, cellulose acetate, or combinations. Low die costs cut unit prices surprisingly

Let us make up a free sample for you! Write today for full information.

PRECISION PAPER TUBE CO.
2041 W. Charleston St. Chicago 47, Ill.
PLANT #2: 79 Chapel St., Hartford, Conn.
Also mfrs. of dielectric paper tubes



Recent additions to the Victoreen series of G.M. counter tubes

1 • The *1B102* is available for operating voltages of 700 or 900 volts, mica window 2 mg/cm², halogen quenching gas, life unlimited by use, standard four-pin base.

2 • The *1B106* is available for operating voltages of 700 or 900 volts, mica window 2 mg/cm², halogen quenching gas, life unlimited by use, standard coaxial base.

3 • The *1B126* needle probe counter, operating voltage 900 volts, wall thickness 200 mg/cm², active length 10 mm, coaxial base.

4 • The *1B124* gamma ray counter, operating voltage 900 volts, wall thickness 800 mg/cm², active length, 12.5 inches, coaxial base.

5 • The *1B125* cosmic ray counter, operating voltage 900 volts, wall thickness 500 mg/cm², active length 16 inches, coaxial base.

The 1B85—possibly the most universally used G.M. tube today

A precision counter tube with .005 inch aluminum wall, rib reinforced to provide added strength to its inherent stability and accuracy. Active length 2.75 inches, absorption 30 mg/cm², operating voltage 900 volts, plateau length 200 volts, slope 3% per 100 volts.

Victoreen G.M. counter tubes, sub-miniature electrometer tubes, and vacuum sealed hi-megohm resistors are available to manufacturers and laboratories for all types of precision instruments.

Write for detailed data sheets.

THE VICTOREEN INSTRUMENT CO.
5806 HOUGH AVE., CLEVELAND, OHIO

NEW PRODUCTS

(continued from page 126)

1×10^{-15} amperes. In the single-stage circuit the tube has sufficient reserve emission to provide operation for several thousand hours. In multistage circuits the filament power may be reduced to 5 mw or approximately 6 ma at 0.85 volt with stable, long-life operation.

Mobile Transmitter-Receiver

GENERAL ELECTRIC CO., Syracuse, N. Y. Type ES-12-A mobile radio transmitter-receiver is a 10-watt unit designed to improve performance in the crowded r-f spectrum. Features include triple-tuned transformers for extra-high selectivity, peak audio output of 2 watts, adjustable i-f gain control, and built-in low-pass harmonic filter that reduces interference to other services, including television.

TV Antennas

LA POINTE-PLASCOMOLD CORP., Unionville, Conn. The J series of Yagi antennas feature high-gain and pinpoint directivity for fringe-area reception. Available in 3, 4 and 5 elements, the antennas incorporate clamp-type construction and are shipped completely assembled. Use of newly developed laboratory measuring equipment has made possible the construction of precision match-

ing transformers (driven elements) insuring a perfect match to a standard 300-ohm transmission line.



Signal Generator

APPROVED ELECTRONIC INSTRUMENT CORP., 142 Liberty St., New York 6, N. Y. Model A-200 signal generator's external appearance features nonglare multicolor frequency dial scales and controls in one convenient line. Controls from left to right are band selector, selector modulation, attenuator and multiplier. The unit covers eight r-f bands; 100 to 250 kc; 190 to 500 kc; 420 to 1,000 kc; 1,000 to 3,000 kc; 3.0 to 9.0 mc; 9.0 to 25 mc; 18 to 50 mc and 27 to 75 mc.

Dynamic Microphones

AMERICAN MICROPHONE CO., 370 South Fair Oaks Ave., Pasadena 1, Calif., announces two new type dynamic microphones. Model D33 is designed for all audio pickup in tv, a-m and f-m broadcasting and recording; and the D22 is designed for less critical public address and recording. The D33 has two impedances (33-50 and 250 ohms)

meeting these "Bugs" in designing new equipment?

Fight them with LINDE Synthetic Sapphire!

LINDE synthetic sapphire is characterized by a low coefficient of friction, high melting point and hardness, and unusual chemical resistance. Applied in many diverse problems, it has paved the way for a longer trouble-free life, for both small and large parts.

Economical to fabricate, valuable uses for this material are constantly being developed. A few of the many applications to new equipment include: precision balls, sleeve bearings, rods, and orifices.

Call or write any LINDE office for detailed information on your specific design problems.



Chemical Composition	Al_2O_3
Hardness, Knoop's	1525-1660
Melting Point	2030°C.
Dielectric Constant	7.5-10
Coefficient of Friction	0.140
(Steel pivot on sapphire ring)	(0.160 graphite)
Chemical Resistance	Inert to common acids, 30% NaOH at 80°C., and HF at 300°C.

THE LINDE AIR PRODUCTS COMPANY
Unit of Union Carbide and Carbon Corporation
30 E. 42nd St., New York 17, N. Y. UCC Offices in Other Principal Cities
In Canada: DOMINION OXYGEN COMPANY, LIMITED, Toronto

The term "Linde" is a trade-mark of The Linde Air Products Company.

Designed for

Application

The No. 10030

INSTRUMENT DIAL

An extremely sturdy instrument type indicator. Control shaft has 1 to 1 ratio. Veeder type counter is direct reading in 99 revolutions and vernier scale permits readings to 1 part in 100 of a single revolution. Has built-in dial lock and ¼" drive shaft coupling. May be used with multi-revolution transmitter controls, etc. or through gear reduction mechanism for control of fractional revolution capacitors, etc. in receivers or laboratory instruments.

JAMES MILLEN MFG. CO., INC.

MAIN OFFICE AND FACTORY

MALDEN

MASSACHUSETTS

with an adjustable jumper for changing from 30-50 to 250 ohms. The D22 has two impedances: low (30-50 ohms) and high (40,000 ohms) with jumper for convenient changing. Both models have omnidirectional pickup, high output levels, minus 52 db. No preamplifier is required.



Audio Sweep Oscillator

THE CLOUGH BRENGLE CO., 6014 Broadway, Chicago, Ill. Model 282-A Audiomatic generator functions as an audio sweeper and a beat-frequency-type audio oscillator with less than 0.5-percent distortion. A continuously adjustable swept segment width between 500 and 10,000 cycles can be selected to start at any frequency between 50 and 32,000 cycles. Thus discontinuities in a response curve may be spread out and examined in great detail.



Coax Splicing Clamp

BRACH MFG. CORP., 200 Central Ave., Newark, N. J., has produced a new copper clamp for splicing coaxial cable. The accessory will prove very convenient when a householder wishes to remove a receiver to another portion of the room beyond the range of existing cable length. Illustrated are (1) two ends of coax cable joined and

POLARAD TELEVISION *Equipment*

for studio • laboratory • manufacturer

SYNCHRONIZING GENERATOR

Model PT 101—Television



$2,680

FEATURES

- Built-in 5" oscilloscope with synchronized sweeps for viewing Timing and Video output pulse wave forms.
- Synchronized marker system for checking pulse width and rise time.
- Extreme stability, insured by deriving all pulses from leading edge of master oscillator pulse.
- Means for checking synchronizing pulses in odd and even fields.

SPECIFICATIONS

525 line, interlaced, 60 fields, 30 frames, RMA Synchronizing pulses held to tolerance specified in the SMPTE report of 1945. Output Pulses: Synchronizing, Video Blanking, Camera Blanking, Horizontal Driving, Vertical Driving Pulses. 5 volts across 100 ohm termination. Dual output jacks. 115 volts 50/60 cps. Complete with tubes.



TELEVISION MONOSCOPE SIGNAL SOURCE

Model PT 102

- Composite Video Signal
- Wide Band Video Amplifier, 6 DB down at 10MC
- Dual outputs for feeding two 75 or 100 lines
- Black positive or Black negative output
- Resolution greater than 600 lines

INPUT: Vertical and Horizontal Driving pulses, Camera and Kinescope Blanking Pulses.

OUTPUT: Composite Video Signal, 3 Volts, 100 ohm line 115 volts 50/60 cps. Complete with tubes and including high and low voltage power units.

$1,440

100 METROPOLITAN AVE.
BROOKLYN 11, NEW YORK

Polarad *Electronics Corporation*

Television engineers and consultants to the nation's great television stations.

Gold Plated

TUNGSTEN *and* MOLYBDENUM GRID WIRE

Made to meet your specifications . . . for gold content, diameter and other requirements.

Write for details and list of products

SINCE 1901

SIGMUND COHN CORP.
44 GOLD ST. NEW YORK

EACH SOLVED A SPECIAL PROBLEM

HEADED AND FORMED WIRE CONTACTS



YET these are "STANDARD" NEY PRECIOUS METAL COMPONENTS

Chart shows form and overall dimensions of a few of the many types of contacts made from Ney Precious Metal Alloys for brush or wiping contact applications. Full technical and test data are available on request. Other Ney Precious Metal Alloys have solved many special industrial application problems. Consult us freely without obligation.

Write or phone (HARTFORD 2-4271) *our Research Department.*

THE J. M. NEY COMPANY
179 ELM STREET • HARTFORD 1, CONN.
SPECIALISTS IN PRECIOUS METAL METALLURGY SINCE 1812

NEY GOLD

Unless the Dry Battery You Need Is Listed in This Free Manual...

BURGESS ENGINEERS WILL DESIGN A NEW BATTERY TO MEET *YOUR* SPECIFICATIONS

It's all part of the Burgess Service! This complete Engineering Manual lists *hundreds* of battery types developed by Burgess Engineers to meet new requirements. If the specific battery you need is not among them, the complete Burgess facilities, design, production, and engineering will be placed at your disposal to build the battery you need in any quantity —large or small!

Write for ENGINEERING MANUAL and CHECK SHEET

No obligation. By return mail you will receive the FREE Engineering Manual listing the complete line of Burgess Batteries together with specifications; also the Burgess "Check Sheet" on which you may outline your requirements in the event that the battery you need has not already been developed. Address:

BURGESS BATTERY COMPANY
(DEPT. E1) FREEPORT, ILLINOIS

THE REED
DIOTRON* POWER LEVEL METER

first instrument based on the new DIOTRON circuit, the most significant advance in power measurement in a quarter of a century . . . . . .

The Reed DIOTRON Power Level Meter is an entirely new device which solves *completely* one of electronics' toughest problems—the measurement of power *regardless of waveform*, from sine wave to random voltage.

Such measurements (hitherto possible only by means of fragile thermocouple devices operated within a few percent of their destruction point) are now made using a robust, all-electronic circuit, which is *completely overload proof.*

SPECIFICATIONS

Ranges—watts	Linear Scales, 1 mw, 10 mw, 100 mw, 1 watt and 10 watt into 600 ohms.
Volts	Corresponding *true* Root Mean Square Voltage Scales.
Voltage accuracy	± 2%—50 cps to 10 mc.
Response time	20 milliseconds for frequencies above 1 kc.
Input impedance	0.5 megohm shunted by 30 mmf. An external 600 ohm input termination is also provided.
Output jack	For oscilloscopic observation.
Case size	6" x 7" x 12".
Power requirements	115 v., 50-60 cps, 100 watts.
Price	$350.00.

This instrument is available either in the laboratory model illustrated or on a standard 19" rack panel 5¼" high. Reed Research is adding to its line other DIOTRON instruments, including: squaring and square-rooting amplifiers; special noise measuring equipment; computer elements.

•

REED RESEARCH, INC.

1048 Potomac St. N. W.
Washington 7, D. C.

** Patent applied for*

held by the clamp, and (2) the Vinyl sleeve fitted over the connection and taped at the ends.

Broadband Noise Source

POLYTECHNIC RESEARCH AND DEVELOPMENT CO. INC., 202 Tillary St., Brooklyn 1, N. Y. Type 904 vhf-uhf noise generator permits direct measurement of the noise factors of r-f amplifiers and receivers operating in the range from 10 to 1,000 mc. A coaxial diode placed in a well-terminated 50-ohm transmission line is used to generate noise power. A front panel control adjusts diode filament voltage, the resulting plate current being indicated on a d-c milliammeter calibrated to read noise factor directly in db.

Heater-Cathode Rectifier

SYLVANIA ELECTRIC PRODUCTS INC., 500 Fifth Ave., New York 18, N. Y. Type 6AX5GT full-wave heater-cathode type rectifier does not require a special filament transformer. This characteristic prevents excessive voltages across filter capacitors that often occur during warmup of filamentary type rectifiers. High d-c

output also makes the tube suitable for rectifier replacement in automobile radio receivers.

Coils and Chokes

SHALLCROSS MFG. CO., 10 Jackson Ave., Collingdale, Pa., has introduced a new line of coils and chokes adaptable to tailor-made specifications. Types include high-Q r-f chokes, progressively-wound slug-tuned broadcast coils and oscillator coils. The r-f chokes may be made up as two separate coils having a specified coupling coefficient. High-permeability iron cores are sometimes used to provide greater inductance in a small unit.



Pressure Transmitter

FREDRIC FLADER, INC., 583 Division St., North Tonawanda, New York. The Teledyne electrical pressure transmitter, for use with corrosive mediums such as red fuming nitric acid, employs four active 300-ohm bonded strain gages arranged in a Wheatstone bridge circuit. It is available in ranges from 100 to 5,000 psi. Powered by a maximum voltage of 18 volts, the instrument produces a full scale output of 50 mv open circuit. Output is linear with pressure and its repeatability is better than 0.25 percent of full scale. The undamped natural fre-

Thousands of America's ENGINEERS must be right!

NEW EICO instruments and KITS give you Laboratory Precision at Lowest Cost!

5" Push-Pull Oscilloscope
Model 425-K, Kit, $39.95
Model 425, factory wired, $69.95

It's smart engineering sense to cut your test equipment costs - without sacrificing quality. That's why more engineers than ever before are building their own precision instruments with EICO Kits.

For top-notch laboratory-precision equipment, EICO gives you the newest efficient designs and circuitry and the finest quality brand-name electronic and mechanical components. Each EICO Kit is complete with pre-punched chassis, cabinet and etched panel. For rock-bottom cost, you do the simple assembly in one easy evening with the EICO simplified instructions.

EICO Kits and Instruments are acclaimed and used by the top-flight universities, schools and original equipment manufacturers from coast to coast. See the complete EICO line of superlatively engineered, handsome VTVM's, scopes, tube testers, signal and sweep generators, etc.—at your favorite jobber TODAY. Ask him about the EICO *Make-Good* Guarantee—the strongest guarantee in the Industry! Write NOW for your free latest Catalog E.

Prices 5% higher on West Coast

Vacuum Tube Voltmeter
Model 221-K, Kit, $23.95
Model 221, factory wired, $49.95

High Voltage Probe,
Model HVP-1, $6.95



Deluxe RF Signal Generator
Model 315-K, Kit, $39.95
Model 315, factory wired, $59.95

EICO

ELECTRONIC INSTRUMENT CO., Inc
276 NEWPORT STREET, BROOKLYN 12, N. Y.

© 1950, Electronic Instrument Co., Inc., Brooklyn, N. Y.



Need help with microwave transmission lines?...call TERPENING

The microwave mixer shown above was designed and produced on special order, in quantity, in our plant. Though made up from a number of different sections brazed together, special jigs, fixtures, and skilled techniques made it possible to hold tolerances between the outer flange center lines to ± .001".

Whether it's a special component, such as the mixer shown, or complete microwave transmission systems, we're set up to produce them with a high degree of precision from blueprints or performance specs. Although our engineering staff, laboratories, and fully equipped shop are usually busy on government contracts, our unusual facilities may permit us to work with you on special components for military or other microwave systems. We shall be happy to talk with you about your present and/or future needs.

L. H. TERPENING COMPANY
DESIGN • RESEARCH • PRODUCTION
Microwave Transmission Lines and Associated Components
16 West 61st St. • New York 23, N. Y. • Circle 6-4760

quency is over 1,500 cps, depending upon the range.

Phase Adapter

VARO MFG. CO., INC., Box 638, Garland, Texas. Model 160 electronic phase adapter changes single-phase, 115-volt 400-cycle current to three-phase, 115-volt at 100 va. Output voltage on all phases is equal to input voltage ± 3 percent over wide ranges of input voltage and frequency, load and power factor, temperature and altitude. It has no moving parts. Weight is 6¼ lb and volume, 168 cu in.



Service-Type Oscilloscope

RADIO CORP. OF AMERICA, Harrison, N. J. Type WO-57A portable oscilloscope, especially suited to television servicing, is an instrument of high sensitivity and wide frequency range which is equally useful in shop, lab or factory, for viewing and measuring square waves, pulses and tv sync signals. Deflection sensitivity of the instrument is better than 30 mv per in. Frequency response of the vertical amplifier is flat within 2.3 db from 0 to 500 kc, down only 6.8 db at 1 mc and useful beyond 2 mc. Featured are a direct-coupled vertical amplifier which is used to provide flat low-frequency response, a high-frequency square-wave response up



e c

Plunger Type MERCURY RELAYS

APPROVED

★ **POSITIVE**—Hermetically sealed mercury - mercury contact assures silent flickerless operation . . . no pitting, no sticking!

★ **DEPENDABLE**—Hermetically sealed . . . no dust, no dirt, no oxidation . . . means no servicing, no cleaning!

They ALWAYS Work

Available in single, double and triple groups operated by one coil. Coil ratings for every application. Contacts rated conservatively at 35 Amp. 115 V. AC; 25 Amp. 220 V. AC. Available normally open or normally closed.

Write for Catalog

EBERT ELECTRONICS CORP.

185-09 Jamaica Avenue, Hollis 7b, L. I., N. Y.

JOB-ENGINEERED



FAIRCHILD PRECISION POTENTIOMETERS

Fairchild Type 748
3-Gang Precision Potentiometer

Here's a custom-built instrument that's typical of Fairchild's job-engineered solutions of difficult potentiometer problems. It's a 3-gang potentiometer with 17 taps per unit, giving 16 sections of equal resistance – 8 each side of center. By using resistors of various sizes between taps, almost an infinite number of non-linear functions can be approximated. For control purposes, each unit can be used as a continuously varying switch to fire tubes such as Thyratrons in sequence.

To help you in analyzing your special applications, Fairchild offers you the services of its Potentiometer Sample Laboratory engineers. Write, giving complete details on your requirements, to Dept. O, 88-06 Van Wyck Boulevard, Jamaica 1, N. Y.

Fairchild
CAMERA AND INSTRUMENT CORPORATION

What Makes a Mailing Click?

Advertising men agree . . . the list is more than half the story. McGraw-Hill Mailing Lists, used by leading manufacturers and industrial service organizations, direct your advertising and sales promotional efforts to key purchasing power.

In view of present day difficulties in maintaining your own mailing lists, this efficient personalized service is particularly important in securing the comprehensive market coverage you need and want. Investigate today.

McGraw-Hill Publishing Co., Inc.
DIRECT MAIL DIVISION
330 West 42nd Street, New York, 18, N. Y.

SMALL
PARTS
Cost less when made by
MULTI-SWAGE
The economy way to get a million small parts similar to these —

Examine the tubular and solid metal parts shown here twice size. If you use anything similar . . . in quantities of over a million . . . important savings can be yours. Send us the part and specs. Our quotation will show why the Bead Chain Company's MULTI-SWAGE Process has long been known as the most economical method of making electronic tube contact pins, terminals, jacks and sleeves. And, why more and more users of mechanical parts (up to ¼" dia. and to 2" length) employ our facilities. WRITE for Data Bulletin.

THE BEAD CHAIN MANUFACTURING CO.,
Tr. Mark 88 MOUNTAIN GROVE ST., BRIDGEPORT 5, CONN.

NOTHELFER
Special TRANSFORMERS



Proven by Past Performance

Over 25 years' experience in the manufacture of special transformers to meet individual requirements. Built in quality proved by years of actual use.



From 10 VA to 300 KVA Dry-Type only. Both Open and Encased. 1, 2, and 3 Phase. 15 to 400 cycles.



Send for NEW 8 page BULLETIN

NWL NOTHELFER WINDING LABORATORIES

9 ALBEMARLE AVE., TRENTON 3, N. J.

Compact
dependable instruments

Heiland DENVER



Portable OSCILLOGRAPH *Recorder*

Designed and developed for applications where a minimum of space and weight are required. Small size...6⅝" x 9⅜" x 12¾". Lightweight...33 lbs. Versatility of operation...for the recording of strain, vibration, displacement, acceleration, pressure and temperature.

Type A 500
12 channel

6¾" x 9⅜" x 12¾"

The Heiland A 500 Portable Oscillograph Recorder has many features found only in larger instruments... easy loading...four quick-change paper speeds...trace identification...simultaneous viewing and recording...zero mirror...film movement indicator...up to 12 channels.

Write for complete detailed information

HEILAND RESEARCH CORPORATION
133 E. Fifth Avenue Denver, Colorado

to 100 kc, a tilt and overshoot of less than 2 percent and a linear sweep range from 15 to 30,000 cps.



Work and Quench Table

LEPEL HIGH FREQUENCY LABORATORIES, INC., 39 W. 6th St., New York 23, N. Y., has designed a combination work table and quench tank that can be easily attached to vacuum-tube or spark-gap converters. With the sink cover on, the combination unit forms a work table 29 in. × 56 in. for mounting work coils and fixtures; with the sink cover off (illustrated lower left) there is a quench tank 24 in. × 24 in. × 18 in. deep, fed by a 1-in. water line, solenoid controlled. Heating and quenching cycles are controlled by a three-circuit timer operated by pushbutton or footswitch.



Reverberation Generator

AUDIO FACILITIES CORP., 608 Fifth Ave., New York 20, N. Y., offers the artificial reverberation generator, a new unit for the addition of reverberation to radio, video and recorded sound channels. It uses a magnetic tape delay system combined with a new re-entrant electronic system. Consisting of two 7-in. rack panels, the basic unit will work in conjunction with most broadcast-type audio consoles. For

EMSCO

FREE-STANDING SQUARE RADIO TOWERS

Engineered for
Maximum Safety
Minimum Maintenance

Emsco square self-supporting towers are conservatively engineered according to RMA standards to provide for wind pressures up to 50 lbs.-per-sq.-ft. Several planes of torque bracing prevent twisting of towers. Square cross section with lacing of all four sides provides an extremely strong, rigid structure. Hot dip galvanizing insures long life, low maintenance and maximum electrical conductivity. Standard square self-supporting towers available in heights to 500 feet with 30, 40 or 50 lb. RMA design. Whether your tower requirements be 40' or 1000', there is an Emsco tower engineered for your needs. Write for new bulletin.

Shown here is an Emsco Type 2RT 120-foot 40# RMA design tower installed for Southwestern Bell Telephone Co. in Dallas, Texas. ➔



EMSCO DERRICK & EQUIPMENT COMPANY
LOS ANGELES, CALIFORNIA
Houston, Texas • Garland, Texas

use in other services the instrument is available with its own microphone preamplifier, isolation amplifier, control panel, vu meter and sound effects filter.



Chain Pulse Amplifier

SPENCER-KENNEDY LABORATORIES, INC., 186 Massachusetts Ave., Cambridge 39, Mass. Model 214 chain pulse amplifier has been specifically designed to amplify very fast pulses and transients. Employing fourteen 6AH6 vacuum tubes in a traveling-wave circuit, it has a bandwidth of 40 kc to 100 mc and a gain of 30 db. The input impedance of 180 ohms is designed to match the output impedance of the series 200 wide-band chain amplifiers for additional gain up to 60 db. The amplifier finds many applications in nuclear physics, radar, high-speed oscillography, television testing and general laboratory measurements.



Fractional H-P Motor

ELECTRIC MOTOR CORP., DIVISION OF HOWARD INDUSTRIES, INC., Racine, Wisc., has announced development of model 1100 fractional h-p motor. The dynamically-balanced single-shaft unit is a brush-type universal motor of 1/20 h-p intermittent duty and 1/25 h-p continuous duty. It can be equipped with any of the company's gear reduction units

2 KW VACUUM TUBE BOMBARDER OR INDUCTION HEATING UNIT



For Only $650.

Never before a value like this new 2-KW bench model "Bombarder" or high frequency induction heater . . . for saving time and money in surface hardening, brazing, soldering, annealing and many other heat treating operations.

Simple . . . Easy to Operate . . . Economical Standardization of Unit Makes This New Low Price Possible

This compact induction heater saves space, yet performs with high efficiency. Operates from 220-volt line. Complete with foot switch and one heating coil made to customer's requirements. Send samples of work wanted. We will advise time cycle required for your particular job. Cost, complete, only $650. Immediate delivery from stock.

Scientific Electric Electronic Heaters are made in the following range of Power: 1-2-3½-5-7½-10-12½-15-18-25-40-60-80-100-250KW.

Scientific Electric

Division of

"S" CORRUGATED QUENCHED GAP CO.

107 Monroe St., Garfield, N. J.

MICRODIAL
TEN TURN-COUNTING DIAL

Microdial is composed of two concentrically mounted dials . . . one for counting increments of each turn and the other for counting turns. The incremental dial has 100 equal divisions and is attached rigidly to the shaft so there is no backlash. Thus the contact position is indicated to an indexed accuracy of 1 part in 1000. Rotation is continuous in either direction. There are no stops on the Microdial assembly.

COMPACT . . . Microdial has same O.D. as Micropot . . . requires no more panel space.

CLEAR READING . . . Forced fast-reading tests showed only 1/20th as many errors with Microdial open window as with next most legible dial. Turn counter distinguishes between 0 and 10 turn readings, and accelerates to avoid confusion on readings near integral turns. Precise readings are made from larger dial with maximum separation of graduations and wide angle visibility.

CONVENIENT . . . delivered completely assembled with dials synchronized. Easily mounted in a few seconds. All dials may be locked.



Microdial . . . turn-counting dial, primarily designed for use on Micropot ten turn linear potentiometers . . . use it on any multiturn device having ten turns or less.

GIBBS DIVISION
THE GEORGE W. BORG CORPORATION
DELAVAN • WISCONSIN

HEAT RESISTANT WIRES FOR EVERY APPLICATION . . .

So—you think this is HOT

Well for you or me it's hot enough, but for Lewis heat resisting insulated wire it isn't even a starter.

Toasters, waffle irons, stoves and on up to include jet engines—that's where Lewis wire is doing its job day after day without complaint. Does your wire problem involve hot spots?

HEATING UNITS
HEATING ELEMENT
RESISTANCE LINE CORD
THERMOCOUPLE WIRE
ASBESTOS LEAD & FIXTURE WIRE
INSULATED RESISTANCE WIRE
FIBERGLAS INSULATED WIRE
WIRE TO ANY SPECIFICATIONS

Send your electronic control, communications or appliance wiring specifications for a recommended solution by our engineers.

FOR A TRIAL ORDER OR A CARLOAD *consult*

THE LEWIS ENGINEERING CO.
Wire Division
NAUGATUCK CONNECTICUT

with hundreds of ratios available for low output speeds.

Broadcast Tuner

APPROVED ELECTRONIC INSTRUMENT CORP., 142 Liberty St., New York, N. Y. Model A-600 AC broadcast tuner is a standard superheterodyne in miniature size. Audio output is adjustable in 10, 5 and 1-volt steps. Power consumption is 25 watts, and total current, 25 ma. The power supply is a standard 117-volt, 60-cycle full-wave rectifier.



D-C Millivoltmeter

INDUSTRIAL CONTROL CO., 1462 Undercliff Ave., New York 52, N. Y. Type 200-A d-c millivoltmeter can detect d-c voltages as low as 5 μv, or with suitable shunts, currents to a level of 10^{-11} ampere. Output is an a-c voltage, the rms magnitude of which is precisely 1,000 times that of the d-c input. There is no drift in the instrument. No zero set or balance controls, or calibration checks during measurement are

How to read with your eyes open for business!

Read the ads! Every issue of this magazine contains ads that offer valuable services and useful products by which your business may be run more profitably.

The time it takes to read all the ads is time well spent. One ad alone can pay off – by informing you of new developments and new sources of supply, by helping you do a more efficient job. For example, you may locate one machine that will cut your production costs, or step up your output. Or you may discover that the equipment you've been waiting for is now available.

This magazine displays more ideas and merchandise than a trade exposition. Make every issue your buyer's guide. Read the ads as well as the articles. That's reading with your eyes open for business.

HEADQUARTERS FOR BUSINESS INFORMATION

McGRAW-HILL publications

F-24

MICROPOT

PRECISION TEN-TURN POTENTIOMETER

1. You get permanent accuracy because the resistance wire is locked in place. It is precision positioned and moulded integrally with the housing.
2. You get permanently accurate settings, smooth action and low uniform torque provided by the stainless steel, precision ground, double thread lead screw guiding the moving contact.
3. You get precise positioning of the moving contact because of the two bearings supporting the rotor assembly.
4. You get good rigid terminals because they are moulded integrally with the housing.
5. Terminals soldered to ends of resistance element before moulding. Entire resistance circuit is an integral part of the housing.
6. You get accurate setting and resetting due to anti-backlash spring in contact guide.
7. You get a fine resolution because of the 43½" length of resistance wire in the spiral element.
8. You get a resistance output directly proportional to shaft rotation within ±0.1% of the total resistance. Every potentiometer is automatically machine tested for linearity at 101 points.

LINEARITY ACCURACY ± 0.1%

Units for immediate shipment:
1,000 to 30,000 ohm range.
Special resistance values made to order.

WRITE TODAY FOR ENGINEERING INFORMATION

GIBBS DIVISION
THE GEORGE W. BORG CORPORATION
DELAVAN • WISCONSIN

Large or Small

SQUARE, ROUND OR RECTANGULAR PAPER TUBES

FOR COIL WINDING

Inside Perimeters from .592" to 19"

With specialized experience and automatic equipment, PARAMOUNT produces a wide range of spiral wound paper tubes to meet every need . . . from ½" to 30" long, from .592" to 19" inside perimeter, including many odd sizes of square and rectangular tubes. Used by leading manufacturers. *Hi-Dielectric, Hi-Strength.* Kraft, Fish Paper, Red Rope, or any combination, wound on automatic machines. Tolerances plus or minus .002". Made to your specifications or engineered for YOU.

Paramount PAPER TUBE CORP.

616 LAFAYETTE ST., FORT WAYNE 2, IND.

Manufacturers of Paper Tubing for the Electrical Industry

PACKAGED
Functional Electronics

SERVO
amplifiers
A MECHA PRODUCT



Plug-in for ease of installation and maintenance

Servomechanisms, Inc. offers a group of functionally packaged Servo Amplifiers and companion Power Supplies designed to fulfill every need in the control and instrument field, providing the system designer with a facility of proven dependability and maximum performance.

60 cycle—400 cycle; open or hermetically sealed construction

DESIGNERS AND PRODUCERS OF PRECISION ELECTRONIC DEVICES

SERVOmechanisms INC.
Old Country & Glen Cove Roads
MINEOLA, N. Y.
Garden City 7-0754-5-6

NEW PRODUCTS (continued)

necessary. A dynamic range of 10,000 to 1 and linearity of the output-input proportion are other advantageous features.



Bidirectional Antenna

THE WORKSHOP ASSOCIATES, INC., 66 Needham St., Newton Highlands 61, Mass., has announced a high-gain bidirectional antenna for straight line communication. Present models cover the frequencies from 30 to 50, 74 and 140 to 174 mc. Each antenna has a 4.5-db gain in each of two opposite directions, a 68-deg horizontal half-power angle, and a front-to-side ratio of over 30 to 1. The antennas are designed for communication to several stations along a straight line. High gain decreases the number of separate installations required, and rugged construction enables maintenance-free operation.

Sharp-Cutoff Pentode

RADIO CORP. OF AMERICA, Harrison, N. J. The 6AS6 sharp-cutoff pentode of the 7-pin miniature type is designed so that grid 1 and grid 3

Specify... GM
D'ARSONVAL PORTABLE
GALVANOMETERS
AND MOVEMENTS...

New!
Series 570-600
Pointer-Type
D-C Galvanometer

Here is a new addition to the line of G-M galvanometers. It is a completely assembled unit featuring an Alnico magnet for greater stability of calibration and a new high in sensitivity. Easily installed and replaced, requires only 2¾" behind the mounting surface. Rugged construction throughout. Three models, with sensitivities per mm. division of .06, 0.10 and 0.20 microamps.

Write for specifications and prices on these and other galvanometers

GM LABORATORIES, Inc.
4336 N. Knox Ave. • Chicago 41, Ill.

Lavite STEATITE CERAMIC

Design engineers and manufacturers in the radio, electrical and electronic fields are finding in LAVITE the precise qualities called for in their specifications . . . high compressive and dielectric strength, low moisture absorption and resistance to rot, fumes, acids, and high heat. The exceedingly low loss-factor of LAVITE plus its excellent workability makes it ideal for all high frequency applications.

Complete details on request

D. M. STEWARD MFG. COMPANY
[illegible] • Chicago • Los Angeles
[illegible] • Philadelphia

can each be used as independent control electrodes. It is especially useful in gated amplifier circuits, delay circuits, gain-controlled amplifiers and mixer circuits. The tube can also be used as an r-f amplifier at frequencies up to about 400 mc.

Crystal Calibrator

MEASUREMENTS CORP., Boonton, N. J. Model 111 crystal calibrator is used for the frequency calibration of equipment in the 250 kc to 1,000-mc range. Frequency accuracy is ± 0.001 percent. A new circuit arrangement utilizes the cross-modulation products of three separate oscillators operating at the fundamental frequencies of 0.25, 1.0 and 10 mc. It contains a receiver with a sensitivity of 2 microwatts.



Frequency-Sensitive Relay

VARO MFG. CO., INC., Box 638, Garland, Texas. The 900 series frequency-sensitive relay, designed to open a 400-cycle supply circuit when the frequency falls below a predetermined safe point, has 5-ampere dpdt contacts. It may be used

Try Remler for Service-Tested "Hard-to-Get" Components



SILASTIC RUBBER SHOCK MOUNTS

① Ideal for sub-panel mounting. Isolates tubes from shock and vibration. Mount retains compliance from *minus* 70° to *plus* 480°F. Invaluable for military and airborne equipment.

Custom Components

Metal-plastic components designed and manufactured to order. Write for quotations specifying electrical and mechanical characteristics. Describe application. No obligation.

MINIATURE TUBE CLAMP

② Corrosion resistant. Holds miniatures in sockets under severe conditions of shock and vibration without restricting air circulation. Easy to insert and withdraw tubes. Three sizes.

Remler Company Ltd.
2101 Bryant St. San Francisco 10, Calif.

Remler

Since 1918 PIONEERS IN ELECTRONICS AND PLASTICS

WIDE BAND DIRECT COUPLED OSCILLOSCOPE

Tektronix Type 514-D



Bandwidth: DC—10 mc

Sensitivity: AC—.03 v/cm
DC—.3 v/cm

Sweep Range: .01 μsec/cm—.01 sec/cm continuously variable

Voltage Calibrator: Square wave, 0—50v in 6 ranges

The advantages of the direct coupled oscilloscope are now available in the region of 10 mc. Not only is it possible to measure the duration and amplitude of a waveform, but also the D.C. level at which it occurs.

- *Distributed type push-pull output amplifiers.*
- *All DC voltages electronically regulated.*
- *Triggered, recurrent or single sweeps.*
- *.25 μsec signal delay network.*
- *Better than 5% accuracy of timing and amplitude.*

Write or wire for complete specifications.

$950.00
f. o. b. Portland, Oregon

TEKTRONIX INC.
713 S. E. HAWTHORNE BLVD. PORTLAND 14, OREGON

Tungsten and Molybdenum Metals

FOR THE ELECTRONICS & ELECTRICAL INDUSTRIES

TUNGSTEN

Wire ● Rod for Contacts
Rod for Valve Seals and Supports
Electrodes for Therapeutic Apparatus
Atomic Hydrogen Arc Welding Rods
Rod and Wire for Metal Volatilization processes ● Hammered Slabs
Sheet, Strip and Foil

MOLYBDENUM

Rod for Contacts ● Valve Stems
Grid and Mandrel Wire
Support Wires and Rods
Wire for Furnace Windings
Hammered Slabs
Sheet, Strip and Foil for all Purposes
Sheet for Furnace Boats

We also supply Tungsten, Molybdenum and Tantalum Metal Powders, Titanium Hydride, Zirconium Hydride and many other metallurgical products.

MUREX LIMITED
RAINHAM · ESSEX
ENGLAND

Sintered Permanent Magnets
ALNICO · ALCOMAX · HYCOMAX



Small physical size and high efficiency. Available in a wide range of sizes and shapes for the Electronics Industry.

on voltages from 75 to 150 at frequencies from 350 to 1,000 cps without injury to the relay circuit.

TV Microsecond Scale

RADIO CORP. OF AMERICA, Harrison, N. J. The Microstick is a transparent ruler for measuring the duration in μsec and determining the frequency of video signals displayed on the kinescope of a tv receiver. It is intended primarily to aid students and technicians in gaining a clearer understanding of time factors in tv. It is also useful in determining picture bandwidth of receivers, calibration of test-pattern wedges, frequency of beat interference and ringing, and other measurements helpful in servicing tv receivers. An illustrated descriptive folder is available.

D-C/A-C Chopper

STEVENS-ARNOLD INC., 22 Elkins St., South Boston 27, Mass. Type 268 d-c/a-c chopper is rated at 10 to 500 cps. It may be used as a modulator to convert pure d-c into pulsating d-c or a-c; and as a demodulator to reconvert to d-c. Contact arrangement is spdt, break-before-make, in air. Nominal ratings are 10 volts, 0.001 ampere d-c, but both values may be exceeded

how would you have this copper stud made?



Transformer stud shown actual size

This transformer stud was made in *one* piece by cold heading at a much lower cost than would be possible by any other method. Cold working of the metal also produces a stronger part.

Perhaps the cold heading process, in the hands of Scovill's engineers, toolmakers and operators, can help *you* get better parts at lower cost. Send your sample or blueprint for further information.

"Guide to the Profitable Use of Cold Heading" —Bulletin No. 2 describes the advantages and limitations of this process for the designer. It's free for the asking.

Recessed Head Screws • Sems
Tapping Screws • Standard
Machine Screws • Special Cold Headed Parts

SCOVILL

SCOVILL FASTENERS AND SPECIAL PARTS

Industrial Fastener Sales, Waterville Division
Scovill Manufacturing Co., Waterville 14, Conn.

Montclair, N. J. • Detroit • Wheaton, Ill.
Los Angeles • Cleveland • San Francisco

The New STAVER
MINI-SHIELD
TRADE MARK REG. AND PAT. PEND.

The shield that fits all Miniature Tubes

A flexible shield that snugly fits all miniature tubes because it compensates for all variations in tube dimensions. Mini-Shields are made for both T5½ and T6½ bulb tubes. Send for catalog sheet.

THE Staver COMPANY INCORPORATED

91 PEARL ST. • BROOKLYN 1, N. Y.
ULSTER 5-6303

TWO NEW
TWIN POWER SUPPLIES

MODEL 610-F

- Precise Electronic Regulation.
- 2 Independent Sources of Power.
- 0-325 V.D.C. at 0-100 Milliamperes. Continuously Adjustable.
- 0-325 V.D.C. at 0-200 Mils if the Sources are Combined.
- Both D.C. Outputs Metered for Voltage or Current.
- 6.3 and 12.6 V.A.C. Outputs Provided.
- A.C. Ripple Less than 10 Millivolts.

MODEL 1210

- Precise Electronic Regulation.
- 2 Independent Sources of Power.
- 0-500 V.D.C. at 0-150 Milliamperes. Continuously Adjustable.
- 0-500 V.D.C. at 0-300 Mils if the 2 Sources are Combined.
- Both D.C. Outputs Metered for Voltage or Current.
- 6.3 or 12.6 V.A.C. Outputs Provided.
- A.C. Ripple Less Than 10 Millivolts.

Also available with regulated bias output.

Furst *Twin* Power Supplies double the usefulness of a single unit at considerable saving in space and cost. Write for complete specifications on these and other Furst *Twin* Power Supply Models.

FURST ELECTRONICS
10 S. Jefferson St., Chicago 6, Ill.

For HIGHEST ELECTRICAL & MECHANICAL EFFICIENCY!
New JONES
SERIES 2400
PLUGS & SOCKETS

- Improved Socket Contacts — 4 individual flexing surfaces. Positive contact over practically their entire length.
- Cadmium plated Plug and Socket, Contacts mounted in recessed pockets, greatly increasing leakage distance, INCREASING VOLTAGE RATING.
- Interchangeable with 400 Series.

P-2406-CCT


S-2406-SB

Send for complete Catalog No. 17. Plugs, Sockets, Terminal Strips.

Howard B. Jones Division

For *Precision* Washers...For *Precision* Stampings...





WHITEHEAD STAMPING CO.

A preferred source of precision-made WASHERS and STAMPINGS. 46 years of experience and up-to-the-minute facilities, assure highest quality and service.

EST. 1903 WHITEHEAD STAMPING CO.

1691 W. Lafayette Blvd. Detroit 16, Michigan

BECO IMPEDANCE BRIDGE

New MODEL 250-C WITH THE LONG PRECISION SLIDEWIRE

Effective length, 59.6 feet; 38,000 turns; 11,000 scale divisions. Accuracy ± (0.05% + 1 scale division)

FOR WIDE RANGE MEASUREMENT OF RESISTANCE, CAPACITANCE AND INDUCTANCE WITH 0.1% PRECISION

$295.00

BROWN ELECTRO-MEASUREMENT CORPORATION

4635-37 S. E. HAWTHORNE BOULEVARD PORTLAND 15, OREGON

STANCOR TRANSFORMERS

Specified as original components by the biggest radio and TV set makers in the industry. They have to be good!



WRITE.
inquiries promptly answered

STANDARD TRANSFORMER CORPORATION
3578 ELSTON AVENUE, CHICAGO 18, ILLINOIS

Simple • Reliable • Economical
Potter decimal counter

Highest quality pretested components, conservative ratings

Four large, easy reading, bulls-eye glow lamps — replaceable socket type

All components turret-lug mounted and accessible . . . all wiring color coded

Special silver plated, self-aligning contact and rigid connectors for positive mechanical mounting

DIRECT DECIMAL READ-OUT — FOUR NEON GLOW LAMPS DESIGNATED 1-2-4-8 PROVIDE DIRECT INDICATION (0-9) AND INSTANTANEOUS LOCATION OF ANY DEFECTIVE TUBE

STABLE OPERATION — WIDE VOLTAGE RANGE

HIGH COUNTING RATES — UP TO 130,000 PER SECOND ABSOLUTE ACCURACY GUARANTEED.

COVERED BY BOTH I.B.M. AND POTTER PATENTS ISSUED AND PENDING

WRITE DEPT 6-T FOR COMPLETE INFORMATION AND QUANTITY DISCOUNTS

A NEW LOW UNIT PRICE OF $45.00 IS ANNOUNCED AS A RESULT OF WIDE ACCEPTANCE AND QUANTITY PRODUCTION

POTTER INSTRUMENT CO.
INCORPORATED
115 CUTTER MILL RD., GREAT NECK, N.Y.

on an intermittent basis, for example, in servomechanism applications.



Two-Way Mobile Radio

MOTOROLA INC., 4545 Augusta Blvd., Chicago 51, Ill., is producing a new f-m two-way mobile radio unit designed specifically for adjacent-channel systems. The Uni-Channel Sensicon Dispatcher is available for operation in the 25 to 50-mc or the 152 to 174-mc land mobile service bands. Outstanding engineering elements are the instantaneous deviation control of the transmitter carrier and the broad-nose steep skirt selectivity characteristic of the receiver. Rated r-f power output is 12 watts in the low band and 10 watts in the high band. Models are available for operation from 6-volt d-c or 117-volt a-c primary power sources.

Standoff Capacitor

ELECTRICAL REACTANCE CORP., Franklinville, N. Y. The MCS metal-clad standoff capacitor has a capacitance of 1,500 $\mu\mu f \pm 500$ $\mu\mu f$ and is a quick-mounting type with a solid axial terminal. The ceramic tube is enclosed in a cadmium-plated metal case with a specially developed end seal for protection against humidity and temperature changes.

TV Receiving Tubes

RAYTHEON MFG. CO., 55 Chapel St., Newton 58, Mass., announces the types 1V2, 6AU5GT and 6CB6 television receiving tubes. Principal application of the 1V2 miniature half-wave rectifier is as a high-voltage rectifier. The 6AU5GT beam power amplifier is intended for use as a horizontal deflection amplifier. The 6CB6 miniature-type sharp-

The new S.S.WHITE 80X HIGH VOLTAGE RESISTOR

(½ Actual Size)

4 watts • 100 to 100,000 megohms

Developed for use as potential dividers in high voltage electrostatic generators, S.S.White 80X Resistors have many characteristics—particularly negative temperature and voltage coefficients—which make them suitable for other high voltage applications.

They are constructed of a mixture of conducting material and binder made by a process which assures adequate mechanical strength and durability. This material is non-hygroscopic and, therefore, moisture - resistant. The resistors are also coated with General Electric Dri-film which further protects them against humidity and also stabilizes the resistors.

WRITE FOR BULLETIN 4906

It gives complete information on S.S.White resistors. A free copy and price list will be sent on request.

S.S.WHITE INDUSTRIAL DIVISION

THE S. S. WHITE DENTAL MFG. CO. — DEPT. R — 10 EAST 40th ST., NEW YORK 16, N. Y.

FLEXIBLE SHAFTS AND ACCESSORIES
MOLDED PLASTICS PRODUCTS—MOLDED RESISTORS

One of America's AAAA Industrial Enterprises



SMALL PARTS

Filaments, anodes, supports, springs, etc. for electronic tubes. Small wire and flat metal formed parts to your prints for your assemblies. Double pointed pins. Wire straightened and cut diameter up to ⅛-inch. Any length up to 12 feet.

LUXON fishing tackle accessories.

Inquiries will receive prompt attention.

ART WIRE AND STAMPING CO.

227 High St. Newark 2, N. J.

Pioneer in Radio Engineering Instruction Since 1927

CAPITOL RADIO ENGINEERING INSTITUTE

An Accredited Technical Institute



ADVANCED HOME STUDY AND RESIDENCE COURSES IN PRACTICAL RADIO-ELECTRONICS AND TELEVISION ENGINEERING

Request your free home study or resident school catalog by writing to:

DEPT. 287B
16th and PARK ROAD, N.W.
WASHINGTON 10, D.C.

Approved for Veteran Training



LET BOWSER MEET YOUR TEST SPECS

Bowser Chambers for testing equipment under simulated environmental conditions meet all Government test specifications. Standard Bowser Units, for example, will perform the tests for High and Low Temperature, Humidity, High Altitude, Mildew Resistance, Sand and Dust, and Explosion Proof tests as required in USAF Spec. No. 41065-B. Special Bowser Units are available to meet other specs such as those set up by A.S.T.M., A.P.I., A.S.A. etc.

Send your testing problems to us. Mail the coupon below NOW!



BOWSER INC.

Refrigeration Division

TERRYVILLE • CONN.

Send me free information on Bowser environmental simulating units.

Name_____ Pos._____

Company_____

Street_____

City_____ Zone____ State_____



MARION RUGGEDIZED METERS

This amazing new family of Marion ruggedized electrical indicating instruments sets new standards of quality and accuracy in electrical measurement. Marion "Ruggedized" instruments give better performance in *any* application. Use them with confidence even where you never before dared use "delicate instruments." They exceed all JAN-1-6 requirements, are *hermetically sealed* and completely interchangeable with existing JAN 2½" and 3½" types.

Marion Ruggedized instruments perform perfectly under critical conditions of shock, vibration, mechanical stress and strain. Hermetic sealing makes them impervious to weather and climate.

When you want the *best* in meters for any application —from bulldozers to Geiger Counters—insist on Marion, the name that means the most in meters.

Send for our booklet on Marion Ruggedized Instruments. Marion Electrical Instrument Company, 401 Canal Street, Manchester, New Hampshire.

MARION MEANS THE MOST IN METERS

Manufacturers of hermetically sealed meters since 1944

marion meters

Trademark
©1950 Marion

E-I HERMETIC SEALING COMPONENTS

NEW! OCTAL PLUG-IN WAFERS

Now available in production quantities, E-I Series OBS Plug-in Wafers feature several important new developments. Hollow keys are form fitting and a new hermetic sealing technique makes the seal practically indestructible, even when the pins are bent. The entire assembly is extremely rigid. For complete data, call or write for the E-I illustrated brochure.

STANDARD SIZES	
MODEL	OUTSIDE DIA.
OBS 146	1.460
OBS 125	1.250
OBS 106	1.060

ELECTRICAL INDUSTRIES
INCORPORATED
44 SUMMER AVENUE • NEWARK 4, N. J.

cutoff pentode is to be used as an i-f amplifier replacing, in many circuits, the 6AG5.

Vibrating Switch

SERVOMECHANISMS, INC., Old Country and Glen Cove Roads, Mineola, N. Y. The Mini-Chopper, type CP-101, is a miniature electromechanical device for converting a d-c signal into an a-c signal. Conversely, it can be employed to translate an a-c signal into a pulsating d-c signal. The unit fits a standard 7-pin miniature tube socket and can be clamped in place using the tube shield. Contacts are spst.

Literature

Geiger-Counter X-Ray Spectrometer. North American Philips Co., Inc., 750 South Fulton Ave., Mt. Vernon, N. Y. A 24-page booklet covers the new Geiger-counter x-ray spectrometer, a high-precision analysis instrument. Technical description, outline of performance, illustrations and charts are included.

High-Fidelity Equipment. University Loudspeakers Inc., 80 South Kensico Ave., White Plains, N. Y. A new six-page illustrated catalog devoted to a line of high-fidelity equipment includes cone speakers, tweeters, tweeter adapters, crossover networks and coaxial speaker systems. The publication gives complete installation instructions for each model and also announces the new 12-in. 30-watt wide-range cone speaker.

Sweep Generators. Manufacturers Engineering & Equipment Corp., Willow Grove, Pa. Two four-page folders describe and illustrate the Sweepmaster I video sweep generator and Sweepmaster II r-f and i-f sweep generator. Chief features, specifications and applications are given, and standard equipment for each is listed.

Connector Bulletin. Cannon Electric Development Co., 3209 Hum-

BIRTCHER

STAINLESS STEEL - LOCKING TYPE

TUBE CLAMPS

Stainless Steel

Corrosion Proof

83 VARIATIONS

Where vibration is a problem, Birtcher Locking TUBE CLAMPS offer a foolproof, practical solution. Recommended for all types of tubes and similar plug-in components.

More than three million of these clamps in use.

FREE CATALOG

Send for samples of Birtcher stainless steel tube clamps and our standard catalog listing tube base types, recommended clamp designs, and price list.

THE BIRTCHER CORPORATION

5087 HUNTINGTON DR. LOS ANGELES 32

Kahle specialists in custom-built, ultra-precision ELECTRON TUBE MACHINERY

KAHLE CUSTOM-BUILDS machines to make the exact tubes you require—from big 20-inchers to tiny sub-miniature—from laboratory types to those for high-speed production. Kahle puts each unit through exhaustive trial runs in our plant to assure trouble-free operation in yours.



#1414 Button Stem Machine
For cathode ray tubes →

Custom-built to individual requirements, turns out 500 TV tubes per hr.—fine adjustment of speed, pressure, heat and sequence of operations—with labor-saving development for automatic tubulation flaring.

We specialize in cost-cutting production-boosting, labor-saving equipment for complete manufacture of cathode ray tubes, standard, miniature and sub-miniature radio tubes, sub-miniature tubes, fluorescent lamps, photocells, x-ray tubes, glass products.

Consultations invited
Send for our new catalog

Kahle ENGINEERING CO.

1309 Seventh Street, North Bergen, New Jersey

ELECTRONICALLY REGULATED

LABORATORY POWER SUPPLIES

BENCH MODEL 25

• STABLE
• DEPENDABLE
• MODERATELY PRICED

WIDTH 14" DEPTH 6" HEIGHT 9" WT. 17 LBS.

- **INPUT:** 105 to 125 VAC. 50-60 cy
- **OUTPUT #1:** 200 to 325 Volts DC at 100 ma regulated
- **OUTPUT #2:** 6.3 Volts AC CT at 3A unregulated
- **RIPPLE OUTPUT:** Less than 10 millivolts rms

For complete information write for Bulletin E

LAMBDA ELECTRONICS

Little-thought-of facts about capacitors

The short time breakdown voltage of a well-made D.C. capacitor is not less than 5 to 8 times the actual working voltage at 20°—

E = 5 × e min
E = Breakdown voltage
e = Rated d.c. working voltage

INDUSTRIAL CAPACITORS are unvaryingly held to this formula.

Designed for maximum safety factor and the smallest possible volume, INDUSTRIAL CAPACITORS are the most widely used capacitor in industrial applications.

WRITE TODAY FOR DETAILED CATALOG

Watch this space for other capacitor facts that will help you.

INDUSTRIAL CONDENSER CORP.

Sales Offices in All Principal Cities
3243 N. California Ave.
Chicago 18, Illinois

EVERY DANO COIL TAILORED TO YOUR REQUIREMENTS

Whether you require an untreated magnetic coil winding or a series of specially treated vacuum impregnated coils—Dano is set up to serve you with custom made coils to your specifications. Send us samples or specifications with quantity requirements for immediate quotations.

Also Transformers Made To Order

- Form Wound
- Paper Section
- Acetate Bobbin
- Molded Coils
- Bakelite Bobbin
- Cotton Interweave
- Coils for High Temperature Applications

THE DANO ELECTRIC CO.
MAIN ST., WINSTED, CONN.

boldt St., Los Angeles 31, Calif., has issued a revised 48-page, two-color engineering bulletin on types K and RK connector series which are widely used in aircraft, radio, radar, phone recorder connectors, Geiger counters, instruments, geophysical and camera equipment, transmitters, control panels, oscillographs, potentiometers, c-r recorders, general electrical and electronic equipment.

Radio Parts. The Ucinite Co., Division of United-Carr Fastener Corp., Newtonville 60, Mass. A 33-page loose-leaf-perforated catalog covers a wide variety of radio parts including anode connectors, sockets, tv components, connectors, stand-off terminals, lamp socket assemblies and shock mounts. Dimensional drawings and descriptions are given.

Sharp-Cutoff Pentode. Radio Corp. of America, Harrison, N. J., has published a four-page technical bulletin on the 5879 sharp-cutoff pentode of the 9-pin miniature type intended for use as an audio amplifier in applications requiring reduced audio noise. The tube described is especially useful in the input stages of medium-gain public-address systems, home sound recorders and general-purpose audio amplifiers.

Motor Starting Capacitor. Cornell-Dubilier Electric Corp., South Plainfield, N. J. Bulletin 511 illustrates and describes type ETW 4190 electrolytic motor-starting capacitor in Bakelite container which is $1\frac{1}{16}$ in. in diameter and $2\frac{1}{4}$ in. long. Capacitance and voltage rating of the unit described are 110 volts a-c, 60 cycles, 124 to 149 μf and maximum ambient temperature, 65 C.

Vibration Isolators and Mounting Bases. The Berry Corp., 177 Sidney St., Cambridge 39, Mass. Catalog 502 illustrates and describes unit-type air-damped mounts and mounting bases used to protect electronic equipment and other sensitive apparatus against shock and vibration in aircraft applications. Photographs and dimensional drawings, plus tables of

WIND more COILS faster

WITH YOUR PRESENT COIL-WINDING MACHINE!



— use PAMARCO Wire DeReeling Tensions for PERFECT COILS

Installation of these inexpensive PAMARCO tensions lowers winding costs because each machine will accommodate more coils at higher winding speeds. In addition to increased production, PAMARCO tensions raise production quality. Free-running action practically eliminates wire breakage and shorted turns. Simple thumb screw setting quickly adjusts for any wire gauge. No tools or special skill are needed for operation. For complete data call or write.

PAPER MACHINERY & RESEARCH, INC.
1014 OAK STREET
ROSELLE NEW JERSEY

Where the Requirements are Extreme...

Use SILVER GRAPHALLOY*

For extraordinary electrical performance

GRAPHALLOY
TRADE MARK REG. U. S. PAT. OFF.

THE SUPREME BRUSH AND CONTACT MATERIAL

IN BRUSHES

- for high current density
- minimum wear
- low contact drop
- low electrical noise
- self-lubrication

IN CONTACTS

- for low resistance
- non-welding character

* SILVER GRAPHALLOY is a special silver-impregnated graphite

Accumulated design experience counts — call on us!

GRAPHITE METALLIZING CORPORATION
1055 NEPPERHAN AVENUE, YONKERS 3, NEW YORK

available load ratings, help the designer in specifying suitable mountings.

Electric Timing Motors. Haydon Mfg. Co., Inc., Torrington, Conn., offers an informational catalog of special interest to users of electric timing motors as components of their products. The 8-page 2-color, file-size booklet gives a comprehensive listing of available electrical timing motors. A full line of standard motors is shown, complete with photographs, dimensional drawings, circuit diagrams and data on standard specifications and ratings of each unit. Ask for catalog No. 322.

Components. Electrical Reactance Corp., Franklinville, N. Y. The Datalog is a 32-page booklet for producers of television and radio equipment and other electronic devices. In addition to complete Hi-Q product information on capacitors, trimmers, resistors and choke coils, it contains a great deal of helpful technical data carefully arranged for convenient, quick reference.

Miniature Tube Guide. Hytron Radio & Electronics Corp., Salem, Mass., recently issued the new 4th edition of the reference guide for miniature electron tubes. It lists all minatures to date, regardless of make, and similar larger prototypes. Included are 132 tubes, 41 of them new, and 70 basing diagrams.

TV Optical Projector. Gray Research and Development Co., Inc., 16 Arbor St., Hartford 1, Conn. A recent 6-page folder illustrates and describes the Telop television optical projector for use with film cameras. The unit described features four optical openings for dual projection of opaque cards, photographs, art work, glass slides, transparencies, strip material and small objects.

Geiger Counter Booklet. National Bureau of Standards, U. S. Dept. of Commerce, Washington 25, D. C. The nature, construction and use of the G-M counter is concisely presented on an elementary level in a new booklet, Circular 490. Included are a number of examples of special

IT'S rpc FOR HIGH VOLTAGE RESISTORS

Stable, dependable resistors made in sizes from one inch to 18½ inches long. Power Rating 1 watt to 90 watts. Resistance values to 100,000 megohms. Designed for easy mounting on a panel or stand-off insulator. Can be assembled to make tapped combinations. Matched pair resistors with 2% accuracy available for high voltage instrumentation. ***rpc High Voltage Resistors*** are used in quantity by leading Manufacturers, Instrument Makers, Universities and Laboratories.

ALSO MANUFACTURERS OF HIGH QUALITY PRECISION WIRE WOUND RESISTORS, HIGH FREQUENCY RESISTORS AND HIGH MEGOHM RESISTORS. WRITE TODAY FOR CATALOG.

rpc RESISTANCE PRODUCTS CO.
714 RACE STREET • HARRISBURG 2, PA.

NEW MODEL DYNAMIC MICROMETER



Accurately Measures Dynamic or Static Displacement, Vibration or Movement of Any Metal Body

Only the Electro Dynamic Micrometer measures static or dynamic displacement due to eccentricity, axial vibration, radial whip, bearing clearance, radial expansion with acceleration and reciprocating movement. Measurements are independent of acceleration or speed of rotation and are made without any mechanical contact between sensing unit and moving object. Not only measures static distance, but amplitude of dynamic movement down to .0001 inch. Sensitivity equal to 1% of total displacement.

UNIQUE FEATURES

Direct reading from conventional mechanical micrometer (no calibration of electronic components necessary). Independent of acceleration or speed of rotation. Easy to operate, (only 5 minutes instruction necessary). Measures movement of any metal body over range up to .075 inch with standard unit. Greater distances can be measured with special adapters.

Send for New Literature Today!

Electro ELECTRONIC EQUIPMENT
Makers of Precision *Electronic Instruments*

ELECTRO PRODUCTS LABORATORIES, Inc., 4513-DM RAVENSWOOD AVE., CHICAGO 40, ILL.

Don't Overlook the

LECTROHM FERRULE TERMINAL RESISTOR

Perhaps the most dependable resistor you can use. *Convenient*—it slips tightly into place with perfect contact. *Trouble-free*—ferrules are of monel metal and therefore non-oxidizing and non-corrosive. Windings are permanently *silver soldered* to ferrules. All parts are integrally embedded in vitreous enamel—a lifetime construction. Tube ends are left open for *thru-ventilation*.

Seven standard sizes, ranging from 13 to 190 Watts, available from stock.

Write for Bulletin #99 illustrating this and many other Lectrohm quality resistors.

LECTROHM

5903 Archer Avenue Chicago 38, Ill.

Division of
The National Lock Washer Co., Newark, N. J.

FOLLOW THE PARADE TO THE *New* Burlington *Hermetically Sealed* INSTRUMENT

JUST PLAIN RUGGED

. . . yet an instrument of highest QUALITY
. . . PRECISION
. . . ACCURACY

The Burlington "Hermetically Sealed" *instrument* was designed and is manufactured to conform to JAN specifications for sealed *instruments*.

- Steel case with heavy copper-cadmium plate and black finish.
- Excellent shielding due to case material and construction.
- Double strength clear glass.
- Black satin anodized aluminum bezel.
- Glass to metal seal under controlled humidity and temperature conditions.
- D'Arsonval permanent magnet type movement for DC applications.
- Designed to enhance panel appearance.
- Available in 2½" and 3½" round case types.
- Guaranteed for one year against workmanship and materials.

Best Buy Burlington

BURLINGTON INSTRUMENT COMPANY
DEPT. F-70, BURLINGTON, IOWA

forms of counters which have been developed and a discussion of some of the electronic circuits commonly used to obtain an indication of the response of the counter to radiation. A bibliography of scientific papers is also presented. The booklet is available from the Supt. of Documents, U. S. Govt. Printing Office, Washington 25, D. C., at 20 cents a copy.

Germanium Diodes. Sylvania Electric Products Inc., 1740 Broadway, New York 19, N. Y., has published a new booklet, profusely illustrated with typical circuits for forty basic germanium diode applications. Text of the booklet is grouped in three sections which describe germanium diode applications in radio and television receivers, radio transmitters and amplifiers, and a wide range of instruments and supervisory circuit devices.

Nuclide Chart. General Electric Co., Schenectady 5, N. Y. Information on more than 1,000 kinds of atoms is given on a new chart being distributed free to scientists in industrial laboratories, colleges and universities. Printed in checkerboard fashion each of the 96 chemical elements which were known at the beginning of the year is given in a horizontal line, in which a square is devoted to each kind of atom or isotope of that element. Position of the square on the chart shows the composition of its atomic nucleus.

Insulation Tester. The Herman H. Sticht Co., Inc., 27 Park Place, New York, N. Y. Bulletin 465 describes the Major Megohmer, a new small, portable, handcrank insulation tester. The instrument treated combines small size and weight with constant pressure d-c generator, and features an extra ohm scale.

Six New Tubes. Eitel-McCullough, Inc., San Bruno, Calif., has issued a small 10-page booklet illustrating and describing six new tubes: the 16AP4 tv picture tube, the 4E27A/5-125B power pentode, the 4X150G power tetrode, the 592/3-200A3 power triode, and the 3×10-000A3 and 3W10000A3 power triodes.

Compare for *results!*
Compare for *price!*
and you'll choose the GREEN ENGRAVER

only $215*

The Green Engraver offers great speed and convenience. Quickly cuts up to four lines of letters from 3/64" to 1" on curved or flat surfaces whether made of metal, plastics or wood . . . operates by merely tracing master copy—*anyone* can do an expert job. Special attachments and engineering service available for production work. Just the thing for radio, electronic apparatus and instrument manufacturers.

For *quality* engraving on
● Panels ● Name Plates ● Scales
● Dials ● Lenses ● Molds ● Instruments

. . . also does routing, profiling and three dimensional modeling.

**Price does not include master type and special work holding fixtures.*

GREEN
GREEN INSTRUMENT CO.
363 Putnam Ave.
Cambridge, Mass.

The *flexibility* of
Waveflex Waveguides

may be the perfect answer to your microwave transmission problems in:
• RADAR
• FM
• TELEVISION

Designers of microwave transmission equipment are now taking full advantage of the flexibility of WAVEFLEX flexible waveguides *without sacrificing any of the advantages of rigid waveguides.* As a result, design problems are greatly simplified. WAVEFLEX waveguides offer lower attenuation loss, excellent impedance match, and extreme flexibility without loss of efficiency.

Standard WAVEFLEX flexible waveguides are made in accordance with joint Army-Navy specifications. We will gladly work with you in developing special Waveguides to serve in special applications.

Literature on request

Titeflex Inc., 410 Frelinghuysen Ave., Newark 5, N. J.

A Titeflex Product

Now COMPLETE TESTING
TO MILITARY SPECIFICATIONS

- ENVIRONMENTAL
- CLIMATIC
- ELECTRONIC
- PNEUMATIC
- HYDRAULIC
- METALLURGICAL
- PHYSICAL
- FATIGUE

INLAND TESTING LABORATORIES INC.
2745 N. JANSSEN AVE.
CHICAGO 14, ILLINOIS

COMPOUNDS

Scientifically compounded for specific applications from waxes, resins, asphalts, pitches, oils, and minerals. Available in wide range of melting points and hardnesses. Special potting compounds are heat conducting and crack resistant at extremely low temperatures. Recommendations, specific data, and samples will be furnished on request.

for

IMPREGNATING
radio coils
transformer coils
ignition coils
wire coverings
paper tubes and forms
porous ceramics

DIPPING
Coils
Transformers
Condensers

SEALING
condensers
batteries
switch base terminals
socket terminals
light fixtures

POTTING
Radio Transformers
Light Units
Loading Coils
Condensers

BIWAX

BIWAX CORPORATION
3443 HOWARD STREET
SKOKIE, ILLINOIS

Quality controlled

SAPPHIRE and GLASS JEWEL BEARINGS

Performance proved for precision and long life by world's leading makers of *electrical, aircraft and timing instruments; compasses; weather recorders; all testing, indicating and recording apparatus.*

Unset or set in screws or bushings to suit requirements. Write for brochure.

Serving industry with fine jewels since 1913

Richard H. Bird & Co., Inc.
3 Spruce Street, Waltham, Mass.

STANDARDIZE ON Standard • STANDARDIZE ON Standard • STANDARDIZE ON Standard • STANDARDIZE ON Standard

FOR FREQUENCY
Stability
IN
Mobile
EQUIPMENT . . . .

make sure your crystals are made by Standard Piezo.

For years, our Crystals have been standard as original equipment with leading manufacturers and for replacement purposes by large operators of mobile equipment.

Precise, accurate, Standard Piezo Crystals are available for *ALL* types of mobile communication equipment.

Request catalog E for complete details.

Standard Piezo COMPANY
CARLISLE, PENNSYLVANIA

Aeracom's new V. H. frequency AM radiotelephone/telegraph transmitter is designed and built to operate amid ice and snow or steaming jungles, and what's more, this fine transmitter will give long trouble free efficient service with low maintenance and operating costs.

MODEL VH-200

The model illustrated (VH-200) operates on one Crystal Controlled frequency (plus one closely spaced frequency) anywhere in the range 118-132 Mcs. or 132-165 Mcs., A-1 or A-3 AM. Nominal carrier power 200 watts up to 132 Mcs., reduced power up to 165 Mcs. Low temperature operation using gas filled rectifiers. Normal temperature operation using mercury vapor rectifiers. Relative humidity up to 95%. Complete technical data on request. Aeracom builds other radiotelegraph/telephone transmitters with accessories, and invites your inquiry if you have a communications problem.

CONSULTANTS, DESIGNERS AND MANUFACTURERS OF STANDARD OR SPECIAL ELECTRONIC, METEOROLOGICAL AND COMMUNICATIONS EQUIPMENT

AER -O- COM

AERONAUTICAL COMMUNICATIONS EQUIPMENT Inc.

DEALERS: Equipelectro Ltda., Caixa Postal 1925, Rio de Janeiro, Brasil • Henry Newman Jr., Apartado Aereo 138, Barranquilla, Colombia • Radiotec, Rosengaista 66, Buenos Aires, Argentina

NEWS OF THE INDUSTRY

(continued from page 130)

try in general. The part of the program relating to the development of a common system of air navigation and traffic control is sponsored by the Air Navigation Development Board.

Flight Radio Operators

A RECENT report from the Civil Aeronautics Board indicates that radiotelephone communication from aircraft in overwater flight is so reliable that a properly licensed navigator-operator will be sufficient in the future. At the same time, CAB indicates that under certain conditions of oversea flight it would be advisable for aircraft to be provided with equipment for contacting surface vessels on the international distress frequency of 500 kc, using radiotelegraphy. At the FCC, however, doubt exists that Atlantic City regulations permit carrying such an operator whose qualifications are less than Second Class Radiotelegraph. The Commission is prohibited from waiving requirements of a licensed operator in the case of a station where an operator is required to be provided for safety purposes. The operator unions oppose complete adoption of radiotelephone on the grounds that only a skilled radio-telegraph operator can successfully establish emergency communications.

New Betatron Installed

ONE of the most powerful atom smashers of its type in the world, a 100,000,000-volt betatron built by the General Electric Co., is now installed and undergoing tests at the University of Chicago. The 160-ton unit is being used for atomic research and x-ray studies by the experimental staff of the University of Chicago's Institute for Nuclear Studies. Effects of powerful radiation on biological organisms will also be studied.

Operation of the betatron involves use of a huge electromagnet to accelerate and maintain electrons in a circular path around a doughnut-shaped acceleration chamber. At a predetermined time, the path of the electrons is changed slightly so they strike a small piece of metal

DISK Recording WITH TAPE Quality

Fairchild Thermo-Stylus Kit

- **For maximum reduction of surface noise**
- **For quality recording at innermost diameters**

WHAT IT IS:

A kit of special styli with miniature heating elements, a cutterhead adaptor and a heat control with calibrated meter.

WHAT IT DOES:

Applies thermoplastic principles to disk recording; eliminates mechanical loading of the cutter by the disk material.

RESULTS:

- **Reduces basic surface noise at least 20 db.**
- **Minimizes frequency discrimination at innermost diameters.**
- **Eliminates most difficulties due to production differences in blank disks.**

Recordings made with the Fairchild Thermo-Stylus Kit retain the esthetic listening appeal of original sound.
Write for illustrated details — specify your cutterhead.

Fairchild
RECORDING EQUIPMENT CORPORATION
154TH STREET & 7TH AVENUE
WHITESTONE, NEW YORK 7R-113

inside the chamber, producing an x-ray beam. These x-rays are many times more penetrating than those produced by conventional x-ray machines and by radioactive substances such as radium.

ELK ELECTRONIC LABORATORIES, specializing in design and development of test equipment for the communications, radar and allied fields, have moved to larger modern quarters at 333 W. 52nd St., New York, N. Y.

GENEVA ELECTRIC & TELEVISION CORP. recently acquired 73 percent of the stock of Continental Electric Co., Geneva, Ill., manufacturer of phototubes and photoconductive cells. Continental Electric, in the reorganization, acquires a new building and will set up facilities for the manufacture of tv picture tubes of all sizes.

TELREX, INC., Asbury Park, N. J., designers and manufacturers of antennas, will supplement existing facilities with a new laboratory now being constructed in Belmar, N. J.

POTTER INSTRUMENT CO., INC., manufacturer of high-speed electronic counters, computers and associated equipments, has moved from Flushing, N. Y., to a new plant at 115 Cutter Mill Road, Great Neck, N. Y.

SPELLMAN TELEVISION CO., INC., manufacturers of high-voltage power supplies, coils and projection tv equipment, recently moved to new and larger quarters at 3029 Webster Ave., Bronx, N. Y.

THE HELIPOT CORP., manufacturers of equipment for precision electronic circuits, recently moved into a modern new home in South Pasadena, Calif.

CLAUDE NEON, INC., New York, N. Y., recently acquired 100 percent of the stock of Standard Electronics Corp. The new Claude Neon subsidiary has taken over Western Electric Co.'s inventories of a-m and f-m transmitting equipment, replacement parts, product designs

One Pickup PLAYS ALL DISKS

New Fairchild Turret-Head 3-Way Transcription Arm Plays Standard Laterals, Microgrooves, and Verticals Without Plug-ins . . .

WHAT IT IS:

A revolutionary new pickup with provision for 3 separate cartridges—All in ONE arm

WHAT IT DOES:

Obsoletes plug-in cartridges. Eliminates extra pickups on turntable. Performs functions of 3 separate pickups.

RESULTS:

- ***Lateral, Vertical, Microgroove in 1 Arm***
- ***Any combination of cartridges in 1 Arm***
- ***Simply turn knob to select cartridge***
- ***Pressure changes automatically***
- ***Optimum performance — separate cartridge for each function***
- ***No arm resonance — new viscous damping***
- ***Fits all transcription turntables.***

Write for Illustrated Details

Fairchild
RECORDING EQUIPMENT CORPORATION
154TH STREET AND 7TH AVENUE
WHITESTONE, N. Y. 7R-113

and drawings, and will service and supply replacement parts for all Western Electric broadcast transmitting equipment in the U. S.

ACCURATE MFG. CO., manufacturer of friction and rubber tapes, has completed expansion of its plant at Garfield, N. J., for the improvement of processing and products.

MARVIN HOBBS, consulting electronics engineer of Chicago, Ill., has been appointed deputy executive director of the Electronics Division of the Munitions Board in the Department of Defense.

M. Hobbs

W. A. Mussen

WILLIAM A. MUSSEN, previously associated with the U. S. Naval Ordnance Laboratory in radio proximity fuze development and instrumentation, was recently appointed supervisor of the electronics laboratory at Southwest Research Institute, San Antonio, Texas.

HORACE E. SLONE, radio engineer for the FCC since 1946, is now electronic engineer for the Commission's new Office of Formal Hearing Assistants.

H. A. MCILVAINE, identified with early crt experiments, has been elected president of Continental Electric Co., Geneva, Ill., manufacturers of thyratrons, rectifiers and other industrial tubes. The company expects to set up facilities soon for the manufacture of all sizes of television picture tubes, cold-cathode 8-foot fluorescent lamps and bactericidal lamps.

S. M. DECKER, formerly assistant chief engineer at Garod Radio Corp., has been appointed assistant chief engineer of the television department of Air King Products Co.,



Which Of These Coil Forms Best Fits YOUR Needs?

Coil Forms Only, Or Coils Wound To Your Specifications . . . Cambridge Thermionic will furnish slug tuned coil forms alone or wound with either single layer or pie type windings to fit your needs, in high, medium or low frequencies . . . and in small or large production quantities.

See table below for physical specifications of coil forms.

SEND COMPLETE SPECIFICATIONS FOR SPECIALLY WOUND COILS

Coil Form	Material	Mounting Stud Thread Size	Form O.D.	Mounted O.A. Height
L57	L-5 Ceramic	8-32	3/8"	11/16"
L56	L-5 Ceramic	10-32*	1/2"	15/16"
L55	L-5 Ceramic	1/4-28*	5/8"	1 1/16"
L5M	Phenolic Paper	8-32	1/2"	15/16"
L53	Phenolic Paper	1/4-28	5/8"	1 1/16"
L541	Phenolic Paper	1/4-28	1 1/2"	2"

*These types only provided with spring locks for slugs. †Fixed lugs. All others have adjustable ring terminals. All ceramic forms are silicone impregnated. Mounting studs of all forms are cadmium plated.



custom or standard the guaranteed components

CAMBRIDGE THERMIONIC CORP.
437 Concord Ave., Cambridge 38, Mass.
West Coast Stock Maintained By: E. V. Roberts, 3014 Venice Blvd., Los Angeles, California

WHITNEY METAL TOOL COMPANY

39 YEARS EXPERIENCE

WHITNEY-JENSEN
No. 5 JR.
HAND PUNCH

A lightweight tool that has found wide acceptance because it is durable, powerful, easy-to-use. The No. 5 Jr. has an adjustable locating stop clearly graduated to permit quick setting to any throat depth up to 5". Furnished complete with seven punches and dies in strong metal carrying case. Capacity — 1/4" hole through 16 ga. mild steel

Overall length — 8 1/4"
Height of gap — 4"
Weight — 2 1/4 lbs.

Write for our latest catalog

WHITNEY METAL TOOL CO.
150 FORBES ST., ROCKFORD, ILL.

SPECIALTY DRY BATTERIES
are *Laboratory Built*

We custom make dry batteries of unusual sizes and capacities to give most effective service in industrial and laboratory work of all kinds. We will specially design batteries to your individual needs.

Promptly Supplied

We are specially equipped to produce and ship even the smallest orders of hard-to-get batteries without delay.

FREE Helpful Catalog

Gives complete description of hard-to-get industrial, laboratory, and radio batteries quickly available from Specialty. Write today.

SPECIALTY BATTERY COMPANY
A RAY-O-VAC SUBSIDIARY
RAY-O-VAC
MADISON 3, WISCONSIN

THIS POINT WILL END YOUR LOOSE SET SCREW PROBLEMS

UNBRAKO

SELF-LOCKING HOLLOW SET SCREW
WITH MONEY-SAVING KNURLED POINT
"WON'T SHAKE LOOSE"

Knurled Head Socket Cap Screws
Flat Head Socket Cap Screws
Self-Locking Socket Set Screws
Knurled Head Shoulder Screws
Precision-Ground Dowel Pins
Fully-Formed Pressure Plugs

SPS STANDARD PRESSED STEEL CO.
JENKINTOWN 17, PENNSYLVANIA

Only with CO-AX

air-spaced articulated
R.F. CABLES

THE LOWEST EVER CAPACITANCE OR ATTENUATION

We are specially organized to handle direct enquiries from overseas and can give

IMMEDIATE DELIVERIES FOR U.S.A.

Billed in Dollars Settlement by your check. Transaction as simple as any local buy.

LOW ATTN TYPES	IMPED OHMS	ATTEN db/100ft at 100 Mc/s	LOADING ft at 100 Mc/s	O.D."
A 1	74	1.7	0.11	0.36
A 2	74	1.3	0.24	0.44
A 34	73	0.6	1.5	0.88
HIGH POWER FLEXIBLE				
LOW CAPAC TYPES	**CAPAC mmf/ft**	**IMPED OHMS**	**ATTEN db/100ft 100Mc/s**	**O.D."**
C 1	7.3	150	2.5	0.36
PC 1	10.2	132	3.1	0.36
C 11	6.3	173	3.2	0.36
C 2	6.3	171	2.15	0.44
C 22	5.5	184	2.8	0.44
C 3	5.4	197	1.9	0.64
C 33	4.8	220	2.4	0.64
C 44	4.1	252	2.1	1.03
PHOTOCELL CABLE				
V.L.C. ★				

★ *Very Low Capacitance cable.*

TRANSRADIO LTD
CONTRACTORS TO H.M. GOVERNMENT
138A CROMWELL ROAD · LONDON SW7 ENGLAND
CABLES TRANSRAD LONDON

ATR

"A" BATTERY ELIMINATORS

Makes it easy to DEMONSTRATE AND TEST D.C. APPARATUS FROM A.C. LINES

for DEMONSTRATING AND TESTING AUTO RADIOS

New Models . . . Designed for testing D. C. Electrical Apparatus on Regular A. C. Lines. Equipped with Full-Wave Dry Disc Type Rectifier, Assuring Noise-less, Interference-Free Operation and Extreme Long Life and Reliability.

✓NEW MODELS ✓NEW DESIGNS ✓NEW LITERATURE

"A" Battery Eliminator, DC-AC Inverters
Auto Radio Vibrators

ATR *See your jobber or write factory*

AMERICAN TELEVISION & RADIO CO.
Quality Products Since 1931
SAINT PAUL 1 MINNESOTA U.S.A.



SCREW MACHINE PRODUCTS

Housings
Assemblies
Metal Trimmings
Electronic Tube Parts

Metal • Fibre **STAMPINGS** *Phenolite • Plastic*

Complete Fabrication Facilities Under One Roof
Exacting Specifications Met—Rigid Inspection System

WM. STEINEN MFG. CO.

Bruen Cor. Hamilton St. Newark 5, New Jersey

WE INVITE STEINEN *YOUR INQUIRY*

a + value for industry

Development and Production of

SPECIAL PURPOSE VACUUM TUBES BY ECLIPSE-PIONEER

TT-1 3000 mc Temperature Limited Noise Diode Tube.

Y-Type Position Convectron—Vertical Sensing Tube.



Chronotron Thermal Time Delay Tube.

We're not in the standard vacuum tube business. But we are definitely in the business of developing and manufacturing special purpose vacuum tubes — tubes that are not generally available. During the past three years, for example, our facilities have produced, such devices as the Chronotron thermal time delay tube, the Convectron® vertical sensing tube, the TT-1 3000 mc temperature limited noise diode tube, counter tubes, glass enclosed spark gaps, and phono pickup tubes. Quantities of all these are now serving many phases of industry in a wide variety of applications. We invite your use of our facilities to develop and produce your requirements of special purpose vacuum tubes. Your inquiries concerning the scope of our facilities or details of any of our tubes will be given immediate attention.

®REG. U.S. PAT. OFF.

Eclipse-Pioneer Division of
TETERBORO, NEW JERSEY
Bendix Aviation Corporation

Export Sales—Bendix International Division, 72 Fifth Avenue, New York 11, N. Y.

Inc., Brooklyn, N. Y., manufacturers of radios, wire recorders and television receivers.

ALFRED ZUCKERMAN, chief engineer in charge of design and development, is now also vice-president of David Bogen Co., Inc., New York, N. Y., manufacturers of sound equipment.

A. Zuckerman

D. B. Sinclair

DONALD B. SINCLAIR has been promoted from assistant chief engineer to chief engineer at General Radio Co., Cambridge, Mass. He succeeds Melville Eastham who retired early this year.

HARRY R. SEELEN, manager of the services group for the past seven years, has been appointed manager of the engineering section of the RCA tube department, Lancaster, Pa.

PHILLIP B. LAESER has been promoted from chief television engineer to manager of radio and television engineering for The Journal Co., Milwaukee, Wisc.

ROBERT W. SANDERS, for the past eleven years chief engineer of the advance development section at Capehart-Farnsworth, Ft. Wayne, Indiana, has been appointed chief radio and television engineer at the Los Angeles plant of the Hoffman Radio Corp.

FREDERIC C. YOUNG, formerly vice-president in charge of research and engineering and a director of Stromberg-Carlson Co., recently became vice-president of Designers for Industry, Inc., Cleveland, Ohio.

DONALD E. STEELE, recently resigned from the engineering specifications department of Raytheon Mfg. Co., Waltham, Mass., has joined Arthur E. Akeroyd, manu-

facturers' representative, Boston, Mass.

LYNN C. HOLMES, senior electrical engineer in the research laboratory since 1943, was recently made associate director of research at Stromberg-Carlson's research laboratory, Rochester, N. Y.

L. C. Holmes

L. T. DeVore

LLOYD T. DEVORE, formerly on the staff of the electrical engineering department at the University of Illinois, was recently named manager of the Electronics Laboratory of General Electric Co., Syracuse, N. Y.

ALBERT C. HALL, director of MIT's dynamic analysis and control laboratory since 1946, has been appointed associate technical director of Bendix Aviation Research Laboratories, Detroit, Michigan.

HAROLD HIGGS, previously chief of electronic service for the Bell Aircraft Corp., has been named chief electronics engineer of Jeffers Electronics Inc., Dubois, Pa., a subsidiary of Speer Carbon Co., St. Marys, Pa.

HAROLD W. SCHAEFER, formerly director of research and engineering on radio and television receivers for Westinghouse, was recently appointed special assistant to the director of research and engineering at Philco Corp., Philadelphia, Pa.

LOUIS KAHN, formerly assistant chief engineer, was recently appointed director of research of Aerovox Corp., New Bedford, Mass.

DAYTON ULREY has retired as chief engineer of the Lancaster, Pa., plant of the RCA tube department, and has been retained as consultant to the company.

PRECISION POTENTIOMETERS

Various types of potentiometers custom wound to specifications are available. They feature extremely close limits in electrical characteristics and mechanical construction, low electrical noise, low torque, and long life.

All types will operate within specified limits of performance at temperatures —55° C. to +55° C., 95% relative humidity at altitudes up to 50,000 feet. Corrosion resistant materials are used throughout and all insulating parts are fungicided. Our potentiometers meet AN-E-19 specifications.

We invite your inquiries and specifications.



A minor modification of the standard RL-11-C (as illustrated) permits operation up to 1800 RPM. After a test of 28 million cycles at 1800 RPM, one of these units showed negligible wear.

Write for Bulletin F-68.

THE GAMEWELL COMPANY

Newton Upper Falls 64, Massachusetts

It's Magic !!!

EAD

NEW PHASE CONVERTER

Single Phase Input

IN



Three Phase Output

OUT

MODEL P31 — 400 cycles

Once again EAD "know-how" provides the right answer to a tough problem. Our P31 rotary phase converter is 2" in diameter, has an overall length of 3 1/32", weighs approximately 16 ounces, and is rated at 60 to 80 volt-amperes output. This newly designed unit features: Balanced Output, Inherent Stability, Long Life, High Efficiency, Minimum Size and Weight.

YOU DESCRIBE IT . . . WE DESIGN IT!

EASTERN AIR DEVICES, INC. 585 DEAN STREET BROOKLYN 17, N.Y.

THE WIDE BAND POCKETSCOPE

BY WATERMAN



MODEL S-14-B

Wt. 14 lbs.
12" x 6" x 7"

Another Waterman POCKETSCOPE confirming the obsolescence of conventional oscilloscopes. Characterized by wide band amplifier fidelity without peaking as well as amazing portability. S-14-B POCKETSCOPE is ideal for laboratory and field investigation of transient signals, aperiodic pulses, or recurrent electrical wave forms.

Vertical channel: 50mv rms/inch, with response within −2DB from DC to 700KC, and pulse rise of 0.35μs. Horizontal channel: 0.3v rms/inch with response within −2DB from DC to 200KC, and pulse rise of 1.8μs. Non-frequency discriminating attenuators and gain controls, with internal calibration of trace amplitude. Repetitive or trigger time base, with linearization, from ½cps to 50KC, with ± sync. or trigger. Trace expansion. Filter graph screen. Mu metal shield. And a host of other features.

WATERMAN PRODUCTS CO., INC.
PHILADELPHIA 25, PA.
CABLE ADDRESS: POKETSCOPE

WATERMAN PRODUCTS INCLUDE:

S-10-B GENERAL	POCKETSCOPE
S-11-A INDUSTRIAL	POCKETSCOPE
S-14-A HI-GAIN	POCKETSCOPE
S-13-A TWIN TUBE	POCKETSCOPE
S-21-A LINEAR TIME BASE	

Also RAMSCOPES, LINEAR AMPLIFIERS, RAYONIC® TUBES and other equipment

WATERMAN PRODUCTS

and also in connection with recent features on computers and related instrumentation in *Time* and the *Saturday Evening Post*. Without going into the argument as to whether these machines can *think*, the egg processing machinery seems to be a perfect answer to those who scoff at Wiener's thesis that a second industrial revolution is upon us.

ROBERT T. NAGLER
Nagler Radio and Electric Service
Prairie Du Sac, Wisconsin

Helical Antennas

DEAR SIRS:

PROBABLY unknown due to lack of publicity during the war, the work on Helical Aerials undertaken by C. S. Franklin of the Marconi Company, England, prior to the war has not received recognition in any of the excellent articles on the subject which have been appearing in ELECTRONICS.

As I feel that you may care to make some reference to this early work, I send you copies of British Patent Specifications No. 573896 and 576159 filed in 1941 and 1942 respectively. Work on helical aerials reached the stage of test on commercial circuits but had to be stopped owing to the then existing circumstances.

J. G. ROBB
Late Director of Research,
Marconi's Wireless Telegraph Co., Ltd.
Chelmsford, England

Audio Oscillations

DEAR SIRS:

YOUR INTEREST in lamp filament oscillation (*Crosstalk*, March, 1950), prompts me to comment that oscillation in the audio-frequency range is a characteristic of the minute filaments of 1.3-volt penlight (flashlight) lamps having integral lenses.

My own observation has shown that these penlight lamps, when energized with a constant, filtered, battery source, will project a modulated light beam with a frequency in the hiss region, probably at 10,000 cycles or more, which may be detected by a high-pass photocell amplifier.

DELMAR L. BROWN
Supt. Testing Department
Portland General Electric Co.
Portland, Oregon

JUST PUBLISHED!
Question and Answers in TELEVISION ENGINEERING

1. This new manual gives you the most recent data on television transmitters, commercial receivers, and all phases of general theory in television engineering. Covers intercarrier sound, dual forms, germanium crystal detectors, and selenium power rectifiers. Answers the problems of the television serviceman, technician and others . . . gives FCC standards and regulations . . . discusses latest design factors in RF section of television transmitter, etc. Includes completely worked-out mathematical problems. By C. V. Ralsted and M. E. Wolbrecht. 300 pages, $4.50

FREQUENCY MODULATED RADAR

2. Explains what is known today about f-m radar, from its background and special characteristics to operational techniques and apparatus used. Covers directive antennas for transmission and reception, oscillators for generating radio frequency power transmitted, frequency modulators controlling these oscillators, etc. The mechanics of simple fire-control is developed. Over 100 diagrams and illustrations. By David G. C. Luck, Research Engineer, N.C.A., 468 pages, $4.00.

ELECTRONICS MANUAL FOR RADIO ENGINEERS

3. Here is practical electronics engineering information of everyday value to the radio engineer or maintenance man. Designed to save you hours of research, these 289 articles supply you with hundreds of formulas, patterns, analyses, equations, tables, calculations, predictions . . . everything arranged and indexed for quick, fingertip reference. Data on microwave, television, circuit theory, antennas, measurements, etc. By Vin Zeluff and John Markus, Editors, Electronics, 879 pages, $9.50.

Handbook of Industrial ELECTRONIC CIRCUITS

4. A ready, practical source of information on the circuits you need for any industrial electronic application. Provides a clearly-drawn diagram for every one of 435 circuits . . . and includes concise descriptions of how the specific circuit works . . . its performance . . . its characteristics . . . its everyday practical application, etc. Valuable cross-referenced index. By John Markus and Vin Zeluff, Editors, Electronics, 272 pages, $6.50.

SEE THEM 10 DAYS FREE

McGRAW-HILL

McGraw-Hill Book Co.
330 W. 42nd St., N.Y.C. 18,

Send me book(s) corresponding to numbers encircled below for 10 days' examination on approval. In 10 days I will remit for book(s) I keep, plus few cents for delivery, and return unwanted book(s) postpaid. (We pay for delivery if you remit with this coupon; same return privilege.)

1 2 3 4

Name .....
Address .....
City ..... Zone .... State .....
Company .....
Position ..... EL 7-50

This offer applies to U.S. only.



F-18A

HERE'S A

Parade

YOU WON'T WANT TO MISS...

Everybody loves a parade but here's one that's particularly interesting to YOU because it's packed with "pocket-book" appeal. It's a never-ending parade of products and services designed to help you do *your* job better, quicker and cheaper. You're in the "reviewing stand" for this parade because it comes to you in the advertising pages of every issue of this magazine. Alert manufacturers use these advertising pages to get the *news* about their products and services to *you* ... quickly and effectively. To be well-informed about the latest developments in *your* industry ... and to stay well-informed ... *read all the ads too.*

McGRAW-HILL PUBLICATIONS

CONTACTS

FOR THE FIELD OF ELECTRONICS

FINE RIBBONS OF TUNGSTEN and Molybdenum

Quality and accuracy in our fabrication of Tungsten & Molybdenum Ribbons have characterized our service to the Electronic industry.

A development of

H. CROSS Co.

3 Bookman St., New York 7, N.Y.

CEMENTS FOR THE RADIO INDUSTRY

NITROCELLULOSE
SYNTHETIC
MOISTURE RESISTANT
THERMO PLASTIC
THERMO SETTING
VINYL IN COLOR
COIL VARNISH

BARRETT VARNISH CO.
1532 South 50th Court
Cicero 50, Ill.

Write Us for Additional Information

MICROMETER FREQUENCY METER

for checking transmitters, from .1 to 175 mc, within 0.0025 per cent.

LAMPKIN LABORATORIES, INC.
Bradenton, Fla., U. S. A.

EL-TRONICS, INC.

Research, development, and manufacture of electronic equipment—a single model to large quantities.

WRITE TODAY FOR FREE RESUME OF OUR PLANT FACILITIES

Specialists in Geiger-Muller equipment

2647-67 N. Howard St. • Phila. 33, Pa. • Garfield 5-3026

EISLER Manufacturers Complete Equipment for:

SPOT WELDERS, Electric for ½ to 250 KVA
TELEVISION TUBE GLASS WORKING EQUIPMENT
TRANSFORMERS, Special and Standard Types
INCANDESCENT LAMP Manufacturing Equipment
FLUORESCENT TUBE Manufacturing Equipment
NEON SIGN MAKERS EQUIPMENT
ELECTRONIC EQUIPMENT, Vacuum Pumps, etc.
WET GRASS SLICING and Cutting machines for Laboratory use

EISLER ENGINEERING CO. 751 So. 13th St., Newark 3, N.J.

high speed *high sensitivity*

SHORTED TURN INDICATOR

The Karton Shorted Turn and Open Circuit Coil Checker — Model 101B — indicates single shorted turns of #44 wire in unmounted coils. Standard mandrel 3/16 x 1/4 for all average size coils. Regulated vacuum tube circuit. Jack for audio indication to supplement 1-ma. meter. Prompt deliveries. Price $150.

KARTRON — Huntington Beach, Calif.

SUB-MINIATURE PRINTED ELECTRONIC CIRCUITS

produced from your schematics or existing electronic equipment. Circuits fired on ceramics or air dried on plastics and paper bases. Confidential service.

PLASTICS & ELECTRONICS CO.
272 Northland Ave., Buffalo 8, New York

SILICONE
DC 4
COMPOUND
THE NON-MELTING WATERPROOFING AND INSULATING SILICONE COMPOUND FOR IGNITION SYSTEMS AND ELECTRONIC EQUIPMENT. MEETS ALL THE REQUIREMENTS OF AN-C-128a.
STABLE AT TEMPERATURES FROM −40° to +400°F.
For more data on DC 4 Silicone compound write Dept. E-4
Dow Corning

DOW CORNING CORPORATION
MIDLAND, MICHIGAN
Atlanta • Chicago • Cleveland • Dallas
Los Angeles • New York
In Canada: Fiberglas Canada, Ltd., Toronto
In England: Albright and Wilson, Ltd., London

ALLEN FLUXES
SODERING
BRAZING & WELDING
6751 Bryn Mawr Ave.



. MPB makes more than 50 different types & sizes

Miniature ball bearings for application in precision mechanisms minimize friction and wear. High load capacity. Least weight and space. Special designs and complete engineering service for your application. Write for catalog E.

MPB MINIATURE Precision BEARINGS
INCORPORATED
KEENE, NEW HAMPSHIRE, U.S.A.

PROFESSIONAL SERVICES

Consulting—Patents—Design—Development—Measurement

in

Radio, Audio, Industrial Electronic Appliances

AMPLIFIER CORP. of AMERICA
Research, Design, Development and Manufacturing Engineers
Specializing since 1936 in All Phases of MAGNETIC TAPE RECORDING FOR ALL APPLICATIONS
Precision Regulated Power Supplies
A. C. Shaner, Chief Engineer
398-7 Broadway New York 13, N. Y.

Eugene Mittelmann, E.E., Ph.D.
Consulting Engineer & Physicist
High Frequency Heating—Industrial Electronics
Applied Physics and Mathematics
549 W. Washington Blvd. Chicago 6, Ill.
State 2-5011

CROSBY LABORATORIES
Murray G. Crosby & Staff
FM, Communications, TV, Industrial Electronics, High-Frequency Heating
Offices, Laboratory & Model Shop at: 136 Herricks Rd., Mineola, N. Y.
Garden City 7-0284

NIAGARA ELECTRON LABORATORIES
CONSULTATION - DESIGN - CONSTRUCTION
MFG. THE THERMOCAP RELAY
Specializing in solution of problems of electronic and electro-physical instrumentation for the research or analytical laboratory. Industrial plant problems also invited.
Andover, New York Cable Address: NIATRONLAB

EDGERTON, GERMESHAUSEN & GRIER, INC.
Consulting Engineers
Research Development and Manufacture of Electronic and Stroboscopic Equipment
Specialists in High-Speed Photography
160 Brookline Avenue, Boston 15, Mass.

PICKARD AND BURNS, INC.
Consulting Electronic Engineers
Analysis and Evaluation of Radio Systems
Research, Development & Design of Special Electronic Equipment
240 Highland Ave., Needham 94, Mass.

ELECTRONIC ENGINEERING CO. of CALIFORNIA
Radio and Electronic Consulting and Designing
180 S. Alvarado Los Angeles
DUnkirk 2-7753 California

ALBERT PREISMAN
Consulting Engineer
Television, Pulse Techniques, Video Amplifiers, Phasing Networks, Industrial Appliances
Affiliated with
MANAGEMENT-TRAINING ASSOCIATES
3308-14th St., N.W. Washington 10, D. C.

ERCO RADIO LABORATORIES, INC.
Radio Communications Equipment
Engineering - Design - Development - Production
Pioneers in Frequency Shift Telegraph
Garden City • Long Island • New York

THE TECHNICAL MATERIEL CORPORATION
Communications Consultants
Systems Engineering
General Offices and Laboratory
121 Spencer Place, Mamaroneck, N. Y.

PAUL GODLEY CO.
Consulting Radio Engineers
GREAT NOTCH, N. J.
Est. 1926 Little Falls 4-1000

ANDREW W. VINCENT
CONSULTANT
Development and Models
Electromagnetic relays & devices Audio and intercommunication equip. Remote control selection circuits. Telephone equipment.
200 W. High Terrace Rochester, N. Y.
Genesee 2645

HANSON-GORRILL-BRIAN INC.
Product & Mfg. Development
ELECTRICAL - ELECTRONIC
HYDRAULIC - MECHANICAL
One Continental Hill Glen Cove, N. Y.
Glen Cove 4-1922

YARDENY LABORATORIES INC.
Research and Development
Remote Controls and Electro Chemical Generators of Energy
105 Chambers Street WO 2-3584, 85
New York, N. Y.

MEASUREMENTS CORPORATION
Research & Manufacturing Engineers
Harry W. Houck Jerry B. Minter
John M. van Beuren
Specialists in the Design and Development of Electronic Test Instruments
Boonton, N. J.

WHEELER LABORATORIES, INC.
Radio and Electronics
Consulting—Research—Development
R-F Circuits—Lines—Antennas
Microwave Components—Test Equipment
Harold A. Wheeler and Engineering Staff
Great Neck, N. Y. Great Neck 2-7800

SEARCHLIGHT SECTION

(CLASSIFIED ADVERTISING)

Continued on pages 211-234

REPLIES (Box No.): Address to office nearest you
NEW YORK: 330 W. 42nd St. (18)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITION VACANT

WANTED: ELECTROSTATIC Capacitor Engineer—Experienced in design, processing and manufacture of paper dielectric capacitors. Knowledge of noise filters, metallized paper capacitors, ceramic capacitors, and mica capacitors desirable. Write full particulars as to experience—confidential. P-6532, Electronics.

EMPLOYMENT SERVICE

SALARIED PERSONNEL $3,000-$25,000. This confidential service, established 1927, is geared to needs of high grade men who seek a change of connection under conditions assuring, if employed, full protection to present position. Send name and address only for details. Personal consultation invited. Jira Thayer Jennings, Dept. L, 241 Orange St., New Haven, Conn.

EMPLOYMENT AGENCY

ELECTRICAL ENGINEERS: Teaching: Power, Electronics. All ranks to Head Department Universities. Atlantic-Pacific. To $8000. Give phone, Photo, Qualif. Cline Teachers Agency, East Lansing, Mich.

POSITIONS WANTED

RADIO-ELECTRONICS Technician: American, age 27, single, desires long term position anywhere in Philippines. Amiable disposition. Speaks some Tagalog and Visayan. 10 years military, amateur and commercial radio experience. PW-6165, Electronics.

PATENT ENGINEER—Attorney now a U. S. Patent Examiner of complex electronic, electrical arts (4 yrs); Electrical Engineer 5 yrs; Member of State Bar 13 yrs; seeks responsible patent connection. PW-6809, Electronics.

ELECTRONICS ENGINEER, graduated M.I.T. 1943 with B.S. and M.S. degrees, specializing in pulse communication systems desires permanent position. PW-6649, Electronics.

AUDIO, TV Field Eng: 10 yrs. practical experience in maintenance of professional audio, TV and radar equip., design and maintenance custom home music systems. Member A.E.S., Asso., A.I.E.E. Good tech. educational background, exc. references, exp. customer relations. Extremely conscientious. Presently mang. TV service lab. and field service tech., electronic organs. Desire field work, H. F. audio or TV. Prefer Wash., D. C. area, consider other. PW-6882, Electronics.

MANUFACTURERS AGENT
Wants line of production items calling on electrical and radio equipment manufacturers. Territory: All of New York State excluding the metropolitan area. Selling the best manufacturers in this area for twenty years.
RA-6720, Electronics
330 W. 42nd St., New York 18, N. Y.

CONTRACT MANUFACTURING
ELECTRONIC DEVICES
per sample or drawings
Fling Electrical Manufacturing Co.
213 E. High St. Ashley, Ohio
Phone 2065

SEARCHLIGHT SECTION

EMPLOYMENT • BUSINESS • **OPPORTUNITIES** • EQUIPMENT—USED or RESALE

UNDISPLAYED RATE:

$1.20 a line, minimum 4 lines to figure advance payment count 5 average words as a line.
INDIVIDUAL EMPLOYMENT WANTED undisplayed advertising rate is one-half of above rate, payable in advance.
PROPOSALS $1.20 a line an insertion.

INFORMATION:

BOX NUMBERS in care of any of our New York, Chicago or San Francisco offices count 1 line additional in undisplayed ads.

DISCOUNT of 10% if full payment is made in advance for four consecutive insertions of undisplayed ads (not including proposals).

DISPLAYED—RATE PER INCH

The advertising rate is $10.25 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

AN ADVERTISING INCH is measured ⅞ inch vertically on one column, 3 columns—30 inches—to a page.

ELECT.

NEW ADVERTISEMENTS received by June 29th will appear in the August issue, subject to limitation of space available.

The publisher cannot accept advertising in the Searchlight Section which lists the names of the manufacturers of resistors, capacitors, rheostats, and potentiometers or other names designed to describe such products.

ELECTRONICS ENGINEERS
FOR
CONSULTING LABORATORY

Unusually suitable openings for engineers who prefer a small company, are interested in specializing in VHF and Microwave antennas and propagation, and who have carried real responsibility in this or a closely related field. Location: Long Island, N. Y.

P-6853, Electronics
330 W. 42nd St., New York 18, N. Y.

REQUIRE KEY MEN FOR RESEARCH LABORATORIES

Outstanding opportunities now available in undertaking highly responsible research and development work in important electro-mechanical instrumentation laboratories. Require section chiefs with MS or PHD degree in E.E., M.E., or Physics with scholastic achievement in upper 10% of class.

Important to have more than 5 years practical experience in developmental work, supervision of projects or group activities to qualify applicant to supervise and direct several diversified projects and administer related activities.

Men with proven ingenuity, imagination, creative ability and with a record of tangible accomplishments can command attractive salaries.

P-6796 (A3), Electronics
520 N. Michigan Ave., Chicago, Ill.

ENGINEER — RADIO AND TELEVISION

Experienced Engineer for research, Design and development of Television Components. Location Summit, New Jersey area. Send complete resume to

P-6696, Electronics
330 W. 42nd St., New York 18, N. Y.

SCIENTISTS AND ENGINEERS

Wanted for interesting and professionally challenging research and advanced development in the fields of microwaves, radar, gyroscopes, servomechanisms, instrumentation, computers and general electronics. Scientific or engineering degree or extensive technical experience required. Salary commensurate with experience and ability. Direct inquiries to Mgr., Engineering Personnel, Bell Aircraft Corporation, P. O. Box 1, Buffalo 5, N. Y.

ELECTRONIC ENGINEER

At least 5 years post college experience in development, D.C. Amplifier, digital computers, pulse and servo-design. Established company, classified work, New York City.

P-6819, Electronics
330 W. 42nd St., New York 18, N. Y.

PROJECT RADIO ENGINEER

To take responsible charge of design of radio communications systems between the Hawaiian islands. Experience in VHF and Microwave links design desirable. College training or equivalent necessary. Live in Honolulu.

MUTUAL TELEPHONE COMPANY
Box 2290, Honolulu, T.H.

RCA VICTOR
Camden, N. J.
Requires Experienced Electronics Engineers

RCA's steady growth in the field of electronics results in attractive opportunities for electrical and mechanical engineers and physicists. Experienced engineers are finding the "right position" in the wide scope of RCA's activities. Equipment is being developed for the following applications: communications and navigational equipment for the aviation industry, mobile transmitters, microwave relay links, radar systems and components, and ultra high frequency test equipment.

These requirements represent permanent expansion in RCA Victor's Engineering Division at Camden, which will provide excellent opportunities for men of high caliber with appropriate training and experience.

If you meet these specifications, and if you are looking for a career which will open wide the door to the complete expression of your talents in the fields of electronics, write, giving full details to:

National Recruiting Division
Box 700, RCA Victor Division
Radio Corporation of America
Camden, New Jersey

RESEARCH ENGINEERS

1—THEORETICAL TUBE DESIGN ENGINEER. Physicist or E. E. with 5-10 years experience in gas and vacuum tube design.

1—RESEARCH AND DEVELOPMENT ENGINEER with experience on crystal diodes and transistors. Good knowledge of physics of solid state and semi conductors required.

1—TUBE QUALITY CONTROL ENGINEER. Knowledge of tubes, circuits and statistical control methods essential.

Work will be in the Eastern Pennsylvania Laboratories of a large, well-established manufacturer. These are permanent positions with excellent opportunities and facilities. Candidates must be U. S. citizens. Send complete details of training, experience, aptitudes and salary.

Our staff is aware of this advertisement.

Write today to:

P-6822, Electronics
330 W. 42nd St., New York 18, N. Y.

RADAR, COMMUNICATIONS *and* SONAR TECHNICIANS
WANTED

For Overseas Assignments

Technical Qualifications:

1. At least 3 years' practical experience in installation and maintenance.
2. Navy veterans ETM 1/c or higher.
3. Army veterans TECH/SGT or higher.

Personal Qualifications:

1. Age, over 22—must pass physical examination.
2. Ability to assume responsibility.
3. Must stand thorough character investigation.
4. Willing to go overseas for 1 year.

Base pay, bonus, living allowance, vacation add up to $7,000.00 per year. Permanent connection with company possible.

Apply by Writing to
A-1, P. O. Box 3414
Philadelphia 22, Pa.

Men qualified in RADAR, COMMUNICATIONS or SONAR give complete history. Interview will be arranged for successful applicants.

SEVERAL ENGINEERS

Needed by contractor for work at Naval Air Missile Test Center, 50 miles northwest of Los Angeles. College Degree and experience essential. Radar, digital computer or general pulse technique experience required.

ELECTRONIC ENGINEERING CO. OF CALIFORNIA
180 South Alvarado Street
Los Angeles 4, California

ELECTRONIC ENGINEERS
AT
DuMONT TELEVISION

SENIOR ENGINEERS (5)
B.S. in E.E.

1—Experienced VHF and UHF Equipment, Design and Propagation Measurement.

2—Experienced in Signal Circuits of AM, FM or TV Receivers.

3—Experienced in TV Deflection Circuits.

4—Experienced in Design of Wide Band IF and RF Amplifier Circuits applicable to VHF Equipment. Must have experience in use of Test Equipment and VHF Spectrum.

5—Experienced in Television or other Electronic Development Work. Special Wave Form Generation, Synchronization and C.R.T. Deflection.

INTERMEDIATE ENGINEERS
B.S. in E.E.

For positions No. 2 & 5 listed above

FOR TRANSMITTER DIVISION

2 years' experience, knowledge of Video Amplifiers, Counter Circuits, Cathode-ray & Indicators, Radar exp.

MECHANICAL ENGINEERS
B.S. in M.E.

SENIOR & INTERMEDIATE

Experience in Mechanical Design and Specification of Radio, TV or Electronic Equipment. Preferably expd in Design of Mass Production.

Apply in person or write:

ALLEN B. DuMONT LABORATORIES, INC.
35 MARKET ST.
EAST PATERSON, N. J.
Att: M. Bruinooge, Personnel Dept.

OUT-OF-TOWN INTERVIEWS MAY BE ARRANGED FOR QUALIFIED APPLICANTS

SENIOR ELECTRONIC CIRCUIT PHYSICISTS
for
Advanced Research and Development

MINIMUM REQUIREMENTS:

1. M.S. or Ph.D. in Physics or E.E.

2. Not less than five years experience in advanced electronic circuit development with a record of accomplishment giving evidence of an unusual degree of ingenuity and ability in the field.

3. Minimum age 28 years.

Hughes Aircraft Company
Attention: Mr. Jack Harwood
CULVER CITY, CALIFORNIA

PHYSICISTS
SR. ELECTRONIC ENGINEERS

Familiar with ultra high frequency and micro wave technique.
Experience with electronic digital and/or analog computer research and development program.
Salaries commensurate with experience and ability. Excellent opportunities for qualified personnel.

Contact:
C. G. Jones, Personnel Department
GOODYEAR AIRCRAFT CORPORATION
Akron 15, Ohio

POSITION OPEN FOR
SENIOR ELECTRONIC ENGINEER

Top Grade Senior Design Engineer—Electronic Circuits. Engineering Degree, 5-10 Years' Good Experience. Wanted for Original Development Work on Industrial Electronic Controls. Permanent Addition to Engineering Staff of Growing New England Concern not Dependent on Military Contracts. Top salary dependent upon ability and experience. Send complete resume to

P-6755, Electronics
330 W. 42nd St., New York 18, N. Y.

POSITION VACANT

Electronic materials development engineer wanted to take charge of development and control laboratory. Man with at least 5 years experience in vacuum tube production, engineering and development, degree in Engineering Physics, Electrical Engineering or Chemistry and some experience in vacuum tube material required. Minimum age 30. Work is primarily with cathode and emission problems. Give details including age, education, experience, marital status, references, availability and salary expected.

P-6943, Electronics
330 W. 42nd St., New York 18, N. Y.

Highest Prices Paid
for manufacturers' over-runs and closeouts of electronic parts.

RAND RADIO CORPORATION
84 Cortlandt St.
New York 7, New York
Telephone: Co 7-7368

WANTED
Inked Tape Recorders
for code reception.
BC-1016 preferred.
write
COMMUNICATION DEVICES CO.
2331 Twelfth Avenue New York 27, N. Y.

WANTED
WESTERN ELECTRIC VACUUM TUBES
Types 101F, 102F, 272A, 274A or B, 310A or B, 311A, 313C, 323A, 328A, 329A, 348A, 349A, 352A, 373A, 374A, 393A, 394A, 121A Ballast Lamps.

W-6863, Electronics
330 W. 42nd St., New York 18, N. Y.

WANTED
Teletypewriters complete, components or parts. Any quantity and condition.

W-6864, Electronics
330 W. 42nd St., New York 18, N. Y.

WANTED
INSULATORS; POLE LINE HARDWARE; GUY STRAND WIRE; COPPERWELD WIRE; WESTERN ELECTRIC TOOLS; SPLICING SLEEVES.

VICTOR-BERNARD INDUSTRIES
NE Cor. 22nd & Lehigh Aves., Phila. 32, Pa.

WILL BUY ALL
BC-348'S WITH DYNAMOTORS
Letters "J", "N" & "Q" ..... $60.00 ea.
All others except "C" ..... $50.00 ea.
Ship via Express C.O.D. subject to Inspection to:
H. FINNEGAN
49 Washington Ave. Little Ferry, N. J.

WANTED
500 RECEIVERS-TRANSMITTERS 4 to 6 Watts
45 SCR-206—45 SCR-503
SURPLUS, COMPLETE, BRAND NEW, UNUSED
Offers FOB New York to be submitted with complete lists of units composing each item to

W-6826, Electronics
330 W. 42nd St., New York 18, N. Y.

FOR SALE
PRODUCTION MATERIALS
(Excepting Bulbs, Flares and Wire) for Tube Type 813. For Specifications and Quantities, write

FS-6839, Electronics
330 W. 42nd St., New York 18, N. Y.

WHOLESALE ONLY
ELECTRONIC COMPONENTS
AIRCRAFT EQUIPMENT
HYDRAULICS
RADIO & ELECTRONIC SURPLUS
13933-9 Brush St. Detroit 3, Mich.
Phone Townsend 9-3403

CONDENSERS

MICA
SOLAR XMB
TAPPED HOLES

Mfd.	Price
2500 V Test	
.00001	$.35
.00025	.35
.0005	.35
.00075	.35
.0001	.35
.0015	.35
.0025	.35
.0003	.35
.0004	.35
.0005	.40
.0075	.40
.00055	.40
.001	.50
.0015	.50
.0016	.50
.0017	.55
.002	.65
.0023	.65
.003	.75
.004	.75
.005	.95
.006	.95
.0063	.95
.0069	.95
.007	.95
.0075	.95
.0076	.95
.01	1.05
.01	1.25
.015	1.25
.02	1.25
.02	1.50
.025	1.50
.027	1.35
.01	1.45
5000 V Test	
.0015	1.75
.002	2.00
Solar XO	
Solder Lugs	
2500 V Test	
.01	1.25
.015	1.30
.02	1.50
.04	1.75
.001	.60
.0015	.60
.002	.75
.0022	.75
.0023	.75
.0024	.75
.0025	.75
.0027	.80
.003	.80
.004	.85
.005	.95
.0056	.95
.006	.95
.0063	.95
.0075	1.00
.0076	1.00
.008	1.05
.0085	1.20
.0065	.60
.00085	.70
.00015	.60

Write For Many Others

ELECTROLYTICS

Prong Mount D Y Type 18c ea. 10 for $1.75	
Mfd.	Volt
40	150
80	150
10	250
8	450
16	450
20-20	25
10-10	150
20-20	150
40-40	150
20-30	250
8x20	150
40	250
30	300
80	350
10	450
15	450
50-50	25
20-10	150
40-20	150
50-30	150
20-1	350
10-1	300
29c ea. 10 for $2.75	
6	400
50	400
40	450
30-20	150
50-50	150
20-20	350-25
20-20	400-25
40-20-10	150
40-30-20	150-25
50-50-20	150-25
60-40-10	150-25
60	300
30	450
32	450
30-30	150
70-30	150
30-20	350-25
10-10	450
40-20-20	150
40-30-20	150
3x50	150
40-10-100	150-10

OIL CONDENSERS

Mfd	Volt	Price
15	220AG	$2.20
5.5	400	.50
1	400	.45
6	600	.90
2	600	1.05
.5	750AC	1.60
7	800	1.20
.5	1K	.60
1.5	1K	.75
2	1K	.90
4	1K	.98
15	1K	2.20
.25	1.5K	1.05
1	1.5K	.90
1.5	1.5K	.95
2	1.5K	1.05
4	1.5K	2.25
1	2K	.98
1	2.5K	1.20
15	4K	2.95
.1-.4	4.8K	2.95
4	5K	2.95
1	6K	2.70
.15-.15	6K	3.95
1.5	6K	9.75
.1-1	7K	3.50
1	7.5K	2.95
1	7.5K	12.95
.15-.15	8K	4.95
1	10K	14.95
.0016	15K	7.95
1	15K	30.95
.015	16K	6.95
.25	20K	16.95
.5	25K	36.95
1	25K	83.95
4	50	.29
1	100	.15
2.5	100	.23
	200VDC	
2x.1	2ST	.15
2x.1	3TT	.15
2x.1	4ST	.16
2	2ST	.20
.5	2TT	.15
.5	2ST	.15
	400VDC	
2x.25	3ST	.21
2x.1	3ST	.21
2x.1	2TT	.20
2x.1	3ST	.25
2x.1	3BT	.25
2x.1	2ST	.20
3x.1	3ST	.25
2x.25	3ST	.25
.25	2TT	.20
1	2ST	.30
2x1	3ST	.35
2	2ST	.40
2	2BT	.39
	1000VDC	
1	2ST	.45

MANY OTHERS

Write for Flyer of 100,000 New Electrolytics in Stock

MINICAPS
PIGTAIL

Mfd	Volt	Price
50	450	$0.49
30	300	.45
30	350	.48
40	450	.50
40	525	.70
16	350	.35
16	525	.45
16	450	.40
16	100	.24
20	25	.20
20	50	.25
20	450	.40
24	350	.30
8	400	.30
8	450	.15
10	150	.20
10	50	.15
4	50	.10
4	150	.14

AC CONDENSERS

75	84	125	1.30
20	28	110	1.00
26	30	110	1.00
31	37	110	1.00
38	42	110	1.00
43	65	110	1.00
45	65	110	1.25
50	75	110	1.25
72	87	110	1.50
86	96	110	1.45
88	106	110	1.50
107	129	110	1.75
124	150	110	1.75
150	150	110	1.75
150	150	110	1.90
161	180	110	1.75
158	191	110	2.00

Write for many others

Line FILTER. GE 100 Amp Filter w/2 x3Mfd 50V oil cond. Operates on 110V AC DC. $1.98

2 KVA: 90 130v input 50-60 cycles, output 115V 2 kva type RM American $7.95

Interphone AMPLIFIER RL-7

Convert to high fidelity phone Amp. or speech Amp. Complete with tubes and dynamotor, for 24 V. DC operation. Used but in good condition. SPECIAL PRICE $2.29

T.V. Transformer, 7" or 9" scope, 3000 v.3MA, 720 vct/200MA, 6.4/8.7A, 6.4/.6A, 5/3A, 1.25/3A. New $4.95

Price

BC-659 Mobile FM TRANSCEIVER — P.O. SCR-610. Includes 10 meter band. Excellent condition with tubes $15.95

PE-120 Power Supply — Less vibrator tubes and Cond. $6.50

Combination BC-620 and PE-120. Both for $20.95

ARR2 HOMING REC

Tunes 234-258 Mc. Contains 1-6AK5, 6-9001, 1 — 12A6. Ideal for 2-6-10 Meter Conv. Less Dyn. As is fair $4.95

RS/ARN 7 Compass Rec.

ADF Rec. 100 to 1750 KC. in 4 Bands 5-Gang Tuning Capacitor w/13 Tubes. 1 — 6K7, 1-6K7, 1-6J5, 2-6B8, 2-6F6, 1-6N7, 1-6SC7, 2-2051, 1-224. Excellent Set $35.00

Good $0.00

EE8SA Telephone Repeater

Used to extend range of field telephones. Simplex Telcg. and 20 cycle ringing possible over lines equipped with unit. Supplied w/305 tube. Phone supplied. (Feather weight). $9.49

EE8SE Telephone Test Set

To locate any kind of trouble on Tel lines; can be used as Telephone. Includes ringing circuit, etc. A valuable unit $17.95

VEEDER Counter

Counts to 9999 and repeats. Many uses 3/8" shaft. Front mtgs. 1" x 1 1/2" 98c

10 for $9.00

SCREW MTG.
Wirebeads D TYPE

Mfd	Volt	Price
4	600	$.35
.5	250	.25
.5	450	.30
10	450	.50
20	450	.60
30	450	.80
40	450	.85
12	250	.50
.5	600	.60
.5	450	.50
16	600	.80
10	150	.50
20	150	.50
30	150	.60
30-30	450	.75

COMMUNICATIONS EQUIPMENT COMPANY for your needs

NAVY ARB RECEIVER

195 KC thru 9 Mc. Includes broadcast band. Can be converted easily to a good ham receiver. 28 V. DC input. Covers 4 bands. This is a deluxe type super-het receiver. Note: The frequency coverage includes the standard broadcast band. Has 4-gang tuning condenser; can be converted to 110 V. AC receiver. Complete with tubes: 12SF7, 12SA7, 3—12SF7 and 12A6. Dial is built on front of chassis. Electric drives on Manual band change switch. Weight 28 lbs. Size 6" x 7" x 15". Complete with tubes and dynamotor. (Fair as is Cond.) $19.95

0-5 MA & 0-5 V Scale w/10V Movement 2" Metal Case Readrite Meter 90c ea. 10 for 9.00

RU-19 or GF-11 or SCR-183 Recv & Xmtrs. Designed for Mobile and Aircraft 2000 to 6050 Kc

for Xmting 157-13950 for Recvg Using T-U. 12-15 watt. Rec Less T-U 3.75

Xmtr Less T-U 3.75



SCR 183 Rec Tuning Units D Range 850-1500 KC. 7.49 ea.

E Range 1350-2040 KC
F Range 2.04-3 MC
G Range 3-4.5 MC
H Range 4-6 MC
K Range 9.05-13.5 MC
Oval Range 300-600 KC 6-9 Mc

SCR 185 XMTR TUNING UNITS

1-1.2 MC
1.2-1.5 MC — 1.49
3.2-4 MC
5-6.2 MC

4-5 MC w/1495 KC XTAL 2.79

BC-733D SUPERHET RECEIVER

w/10 Tubes, 6 Selector-Relays operate on Xtal Controlled Freq. 108.3-110.3 MC. Can easily be converted to 2 Mtr. ham bands ..... $7.95 ea

SCR 522 VHF XMTR-RCVR

10 Tube Xtal Controlled Recv. 7 Tube Xmtr. Makes ideal 2 Mtr. 2 way mobile rig for Cabs, etc. 100-156 MC w/Tubes $34.95

BC 221 Freq Meter Cabinet, wood $2.95

RECTIFIER CAPACITORS

Mfd	Volt	Price
6000	12	5.00
1000	15	.90
3000	15	1.95
2x3000	15	1.75
300	25	.95
500	25	.95
100	30	.79
1000	35	1.39
4000	35	3.49
2000	50	3.00
3x2500	50	2.25
500	50	1.40
125	150	1.40
250	150	1.69
2x1000	6	1.19
75	250	.75

MANY OTHERS.

Large Asst. of Rect. in Stock. Write

AUDIO XFRMRS

707 Plate to Multi Grids output Price 1.49
5119 Plate to line output Price ..... .49
42901 Plate to Voice Coil Price ..... .79
6262 Plate to 8.8 or line Price ..... .69
765 Line to Grid R.C.A. Price 1.10
TPL25 Plate to line ..... .79
8000Ω to 250Ω 1.10
5670 Mike or line to Grid 1.39
4456 807 to Parisl 807s Class C 1.65
7202 input 6V6 pl. to 8Ω Gds. 1.49
839-7 P(1600Ω) to H.S. (4000Ω) ..... .49
8992 P(500Ω) to 672 Line 1.25
445 Line (600Ω) to V.T. (6Ω) ..... .69
649 Line (450Ω) to GRID (750Ω) ..... .79

RELAYS

GE CR 2791

B100-F3	.69
B100-J3	.69
B100-J4	.69
B100-C3	.69
B100-D4	.69
B101-F3	1.10
B106-P36	1.10
G110-F2	.85
C104-B2S	1.49
P100-G3	1.49
B106-J3	1.39
J105-AS3	2.95

MANY OTHERS

ALLIED RJ

DPDT 24V	98
DPDT 28V	98
SPST 12V	98

BOX TYPE

DPST 90MA	98
3PDT 26V	98
SPDT 24V	98

Write for List of Many other Types

TRANSFORMERS ★ SPECIALS ★

- UR369A. 220/440 50 Cy 3.5 960V 600 MA. $24.50
- Amertran 230V 60 Cy In 6.5 KVA 3450 Volts in 2 Gals. of oil $175.00
- Disc Type 115V 60 Cy 17 630V 10.4 KVA 18 Gals. of oil $400.00
- 301171 Amertran Pri 110-220-440. Sec 115V 1 KVA.
- GEKT Type 115V 5.87—5.87 677 KVA 200-2300V 1 KVA $400.00
- GE 67G129 Pri 230V 60 Cy Sec 3850V 1.12 KVA. $59.00
- RA2B 115V 60 Cy Sec 1420V 450 MA. $16.00
- OISC 230V 3.5 32.5 KVA 7250V 3.5 50 Cy 36 Gals. of oil $450.00
- UX9515 Pri 92-138 60 Cy In. Sec 200V 5.5A. Sec 580V 5.25A $59.00
- Volt Stabilizer Pri 190-260V 34 Amp 50 Cy In. Sec 220V 6000 Watt 100% Load ...

Spec Xfrmr 110V 60CY Input

36v/3.5A for Rect. etc. $2.75

24v/15A for Rect. etc. $1.95

2300v/4Ma, 2.5/2A $5.79

1080 Vct/55Ma, 6.3/3.8A, 6.3/2A $4.49

720Vct/220Ma, 6.4/8.7A, 6.4/6, 3v/3A 1.25/3A $5.25

615Vct/50Ma, 3v/2A, 6.3v/1.2A. Tapped Pri $2.25

2.5v/5A, 2.5v/5A, for 866 Tubes 9000 Vt $2.95

330Vct 70 Ma 6.3/.6 6.3v/1.8A $1.75

Special Chokes

10 HY 250 MA $3.25
20 HY 300 MA 6.95
6 HY 150 MA 99
10 HY 90 MA 1.39
8.5 HY 325 MA 3.25
11.5 HY 90 MA 1.39
5 HY 150 MA 1.95
Dual 7 & 11 HY 9 MA 1.39
10 HY 350 MA 11.95
5 HY 200 MA 1.25
10 HY 300 MA 12.45
Many others. Write

GIBSON GIRL

The Emergency Radio Transmitter. Sends S.O.S signals automatically on 500KC. 150-mile range. No batteries required. Hand-driven generator. Tubes, wire. New. It's only $3.49

VIBRATORS

TR 1210, 12 vdc, 5 pin $1.00

OAK V-6675, 24-32 vdc, 7 pin $1.00

Mat. Type G534C, 12 vdc, 5 pin $1.00

Mat. Type G629-C, 12 vdc, 4 pin $1.00

Mfrs. quantities in all types avail. able.

COAX CABLE

RG 8/U. 52 ohm ..... $.25/Ft.
RG 9/U. 52 ohms ..... $.25/Ft.
RG 57/U. Twin Cond. 95 ohms ..... $.55/Ft.
RG 23/U. twin coax. 125 ohm imp. armored ..... $.50/Ft.
RG 28/U. 50 ohm imp. pulse cable Corona min. starting voltage 17 KV ..... $.50/Ft.
RG 35/U. 70 ohm imp. armored ..... $.50/Ft.
Many other Cables & Wire in stock. Write.

BC-605 INTERPHONE AMPLIFIER

Easily converted to an ideal inter-Communications set for office-home-or factory. Original. New w/conversion Diagram $4.49

TU for BC 223 ..... 2.50

TU 17A 3-4.5 Mc 2.50

TU25 3.5-5.2 MC 2.50

Universal Output Transformer

Amertran Silcor. PRI: 20,000/16,000/5000/4000 ohms. Sec: 500/15/7.5/5/3.75/1.25 ohms. 30 db. contin. Flat to 17,000 CY. w/Diag. & Inst. for 6 watt amplifier $4.75

Freq. Mult. Unit for ART13 Xmitter Assy 2-18 Mc for two 1625 tubes No Coils w/Diag. $7.95

YOU'LL SAVE MANY DOLLARS WITH THIS FREE CATALOG

BC 223 XMITR

30 Watt Transmitter with crystal oscillator control on four preselected channels — also master oscillator. Frequency coverage 2000 KC to 3250 KC. by use of three plug in coils. Five tube operation. 801 oscillator, 801 power amplifier, two 46 modulators, and one 46 speech amplifier. Price with TU-17 Tuning Unit, 2000 to 3000 KC 32.95

ARC/5 Xmtrs VFO Drivers 10 Watts Output

3—4 Mc $6.95

Used Fair Cond.



Superhet Recvrs W/Dyn—Used Fair

Can be converted to 110v 60 cy.

190-550 Kc $4.95
3-6 Mc 4.95
6-9 Mc 4.95

Ceramicons

Mmf	
1	25
3	27
5.1	35
4	40
5	47
6	50
7	56
8.5	58
11	60
15	62
16	82
20	90
24	97
29	220
115	240
125	250
150	350
180	1000
200	
100	750

Feed Button	Thru	
40	100	50
180	200	
175	500	470
185	100	950

Birtcher Tube Clamps

926C
926-16
926-B1
926-B2
926-BB
926-CB
926-C-CB
926B
926-C-19
926B-14
926A-14
926A
926C1
926A11
926-B31
926C-25
926-1
926B-10
926B-18
926-K2
Each 18c
10 $1.40
100 $12.00

PRECISION RESISTORS

1.01	128	2250	30000
3	150	4300	33000
5	200	5000	45000
5.05	250	7000	48000
10.1	300	7500	50000
18	430	8500	55000
43.5	468	10000	57000
50	500	12000	75000
75	920	17000	80ip
82	1000	17200	type to
120	1100	20000	stock
125	1450	25000	

Above Ea. 30¢ Ten For $2.50

100000	150000	200000	
120000	170000	220000	500000

Above Ea. 40¢ Ten For $3.50

1,000,000 ohms Each 75¢

AMPHENOL "AN" CONNECTORS



LARGE VARIETY AVAILABLE AT GREAT SAVINGS

Send your specs and let us quote

RL26 Reel unit Gasoline driven wire laying & pick up unit. Reversible engine. Complete $250.00

All merch. guar. Mail orders promptly filled. All prices F.O.B. N.Y.C. Send M.O. or Chk. Only shipping rtgs. sent C.O.D. Rated Concerns send P.O.

COMMUNICATIONS EQUIPMENT CO.

131 Liberty St., New York, N. Y. **Dept. E-7** MR. CHAS. ROSEN **Phone: Digby 9-4124**

COMMUNICATIONS EQUIPMENT COMPANY

RADAR SETS

BCR 883-T3 Sperry searchlight training aircraft, tracking, 10 CM 360° horizontal sweep 90° vert. sweep. Used $450.00

Mark 8 Model 2 Gyro stable element designed for use in stabilizing large caliber naval guns $2,500.00

APS-2	Airborne	10 CM, Major Units	New
APS-3	Airborne	3 CM, Compl.	New
APS-4	Airborne	3 CM, Compl.	Used
APS-15	Airborne	3 CM, Major Units	New
SO-4	Submarine	3000MC, Compl.	New
SE	Shipboard	10 CM, Compl.	New
SF-1	Shipboard	10 CM, Compl.	New
SJ-1	Submarine	10 CM, Compl.	Used
SL-1	Shipboard	10 CM, Compl.	Used
SN	Portable	10 CM, Compl.	Used
SO	Portable	10 CM, Compl.	Used
SO-1 & 2	Shipboard	10 CM, Compl.	Used
SO-6 & 13	Shipboard	10 CM, Compl.	Used
Mark 4	Gunlaying	600MC, Less Ant.	Used
Mark 10	Gunlaying	10 CM, Compl.	New
		Less Rack	New
		Less Rack	Used
CPN-3	Beacon	10 CM, Major Units	Used
CPN-6	Beacon	3 CM, Complete	New
CPN-8	Beacon	10 CM, Complete	New
		Less Ant.	New
SCR-533	IFF/AIR	500MC,	New
Bk	Search Trace		
Airborne Radar Altimeter		500MC, Complete	New

WRITE FOR INFO

TEST EQUIPMENT

TS 268/U to provide a means of rapid checking of crystal diodes 1N21, 1N21A, 1N21B, 1N23, 1N23A, 1N23B. Operates on 1-1½ volt dry cell battery. 3 x 6 x 7, New $35.00

3 cm. wavemeter, Ordnance type micrometer head new: Absorption type $85.00

9000-9500 MCS Transmission type 92.50

BL wavemeter, Type CWR8ABM $125.00

10CM ECHO BOX CABV 14ABA-1 of OBU-3, 2700 MC to 3170 MCs direct reading micrometer head. Ring prediction scale plus 5% to minus 5%. Type "N" input. Resonance indicator meter. New and Comp. w/access. Box and 10CM Directional Coupler $350.00

10 cm horn assembly consisting of two 8" dishes with dipoles feeding single type "N" output. Includes UG28/U type "N" "T" junction and type "N" pickup probe. Mfg. cable. New $15.50

10 cm cavity type wavemeters 6" deep, 8⅛" in diameter. Coax. output. Silver plated ..... $64.50 ea.

10 cm. echo box Part of SFI Radar W/115 volt DC tuning motor Sub Sig 111BAG $47.50

WESTINGHOUSE BRIDGE: Power meter 1-203-A. 10 cm. mfg. WE. Complete with meter, interpolation chart, portable carrying case $72.50

WE I 138, Signal generator, 2700 to 3900 Mc. range. Lighthouse tube oscillator with attenuator & output meter, 115 input req. Pwr. supply. With circuit diagram $150.00

TS 89/AP Voltage Divider. Ranges 100 ½ for 2000 to 2000v, 10:1 for 200 to 2000v. Input Z 2000 ohms. Output Z 4 meg ohms flat response 150 cy to 5 meg cy $42.50

AB-14A/AP—10 cm Pick up Dipole with "N" Cables $4.50

TS 235 UP Dummy Load "L" Band $87.50

10 cm Wavemeter, WE type B 435490 Transmission type, Type N fittings. Veeder Root Micrometer dial. Gold Plated W/Calib. Chart P/o Freq. Meter K65404A. New $95.50

TS 62/AP 3cm Echo Box $245

3 cm Echo Box, meter Drive, "N" input $35

TS-3C/AP Power Measuring Bridge 3 cm $190

"C" Band Slotted Line complete w/ADJ. Probe $490

CG-176/AP Directional coupler X Band, 20 DB nominal, type "N" take off, choke to choke, silver plated $17.50

X Band 1¼" x ½" absorption type wavemeter, micrometer head, 3000 to 3300 mc, Demornay-Budd #158 ..... $185.00

C Band "T" gold-plated at $97.00

C Band Flap attenuator Demornay-Budd type, #335, gold-plated $100.00

X Band 1¼" x ½" Klystron mount with tunable termination gold-plated $75.00

X Band 1¼" x ½" low power load, gold-plated $45.00

X Band 1¼ x ½ waveguide to type "N" adapter, gold plated $7.50

X Band 1¼ x ½ "T" Section, gold-plated $55.00

Dehydrator Unit CPD 10137 Automatic cycling, Compressor to 50 lbs. Compl. for Radar XSW2. Like New $425.00

SO-3 RECEIVER—30 mc. 10, 6 stages 6AC7, 10 mc. Band width input. 5.1 mc B.W. per stg., 9.6 volt gain per stage as desc. in ch. 13 vol. 23 M.I.T. Rad. Lab. Series $89.50

NEW TEST EQUIP. IN STOCK

1-185A Oscillator
1-138 Range Calibrator
1-238—Range Calibrator
DC 438 Freq. Meter
RF Preamp
G.R. Capacity Brdg #216
G.R. Uni Galvo Shunt #229
G.R. 10K() Aud. Osc. #213
TS 226A/AP Pwr. Mtr. 0-1000w
Sig Gen #504 & 330 MC

WRITE OR PHONE FOR DATA & PRICE

24,000 MC BAND

APS-34 Rotating Joint $49.50
Right Angle Bend E or H plane; specify combination of couplings desired $12.00
45° Bend E or H Plane, choke to cover $12.00
Directional coupler CU103/APS 32 ..... $48.50
Mitered Elbow, cover to cover $4.00
TR-ATR Section, choke to cover $4.00
Flexible Section 1" choke to choke $5.00
"S" Curve choke to cover $4.50
Adapter, round to square cover $5.00
Feedback to Parabola Horn with pressurized window $27.50
Low power Load, less cards $18.50
K Band Mixer Block $45.00
Waveguide ½ x ¼" ..... $1.00 per ft.
Circular Flanges ..... $ .50
Flange Coupling Nuts ..... $ .50
Slotted line, Demornay-Budd #397, new $450.00
90° Twist $10.00
"K" Band Directional Coupler CU 104/APS-34 20 DB ..... $49.50 ea.

1⅝" RIGID COAX

Right Angle Bend $35.00
T Section $50.00
T Section with Adapter to ⅞" in rigid coax $65.00
Straight Sections 15' APX ..... $2.50/Ft.

DE MORNAY BUDD — ALL FORMER STOCK AVAILABLE Through COMMUNICATION EQUIPMENT CO.

High Voltage Power Supply

15 KV at 30 Ma DC. Bridge Rectifier, Western Electric ..... $125.

THE MUST of the month

Complete 3 CM Radar System equipment 40 KW peak transmitter, pulse modulator, receiver, using 725AB, power supply operating from 115V 800 Cycle, antenna system. Complete radar set neatly packaged in less than 16 cubic feet, all tubes, in used but excellent condition—$300.00. This price for laboratories, schools, and experimental purposes only.

9,000 MC BAND

Cross gd. Directional coupler 20db Mounted on 90° bend $14.50
90° H Plane 4" Radius Cover to Cover $8.00
Directional coupler, UG-40/U take off, 20 DB $17.50
Directional coupler, APS-6, Type "N" take off, 20 DB, calibrated 17.50
Broad Band Directional coupler type "N" take off, choke to cover, 10 DB calibrated 18.50
Directional coupler, APS-31, type "N" take off, 28 DB 17.50
Bi-directional coupler, type "N" take off 22.50
Flexible Section 10" long 12.00
Straight Section 2½ ft. long choke to cover, silver plated 6.50
Pressure Test Section with 15 lb. gauge and pressurizing nipple 10.00
Bulk Head Feed Through, choke to cover 12.00
Mitered Elbow, choke to cover or choke to choke 12.00
Right Angle Bend 2½" Radius, choke to cover 12.00
90° Twist, 6" long 7.50
45° Twist, 6" long 7.50
90° Twist, 5" long with pressurizing nipple 7.50
15° Bend 10", choke to cover 4.50
5 ft. Sections UG-39 to UG-40, silver plated 9.50
180° Bend, 26" choke to cover 2½" radius 5.00
SWR Measuring Section 4" long, 2 type "N" probes mounted full wave apart 1¼ x ⅝ guide 8.50
WE attenuator 0 to 20 DB, less cards, bell size guide 12.50
90° Bend E Plane 18" 4.00
Rotary Joint, choke to choke 10.00
Rotary Joint, choke to choke with deck mounting 10.00
TR-ATR Duplexer Section for 1B24 and 724B 12.50
Wavemeter-Thermistor MTG Section 6.00
2K25/723 AB Receiver, Local Oscillator Klystron Mount, complete with Crystal Mount, Iris Coupling and Choke Coupling to TR 22.50
TR-ATR Duplexer Section 1B24 above 8.50
723AB Mixer—Beacon Dual Oscillator Mount with Crystal Holder. Used 12.00
721AB Mixer—Beacon Dual Oscillator Mount with Matching Slugs and tunable termination, new 24.50
BI-Directional Coupler, type "N" termination, 26 DB, calibrated, 1¼ x ⅝" guide 24.50
12" Flexible Section 1¼ x ⅝" guide 10.00
Crystal Mount in Waveguide 17.50
SO-3 Echo Box, Transmission type cavity with bellows 28.50
180° Bend with pressurizing nipple 5.00
"S" Curve 18" long 5.00
"S" Curve 6" long 3.25
APS-31 Mixer Section for mounting two 2K25s, Beacon Reference Cavity, 1B24 TR Tube 42.50
Transition 1 x ½ to 1¼ x ⅝, 14" long 8.00
Receiver Front End, complete, C.O Dual 723AB Klystron mount, TR-ATR Duplexer Section, 2 stage 30 MC Preamplifier, now with ALL tubes 59.50
Random Lengths of Waveguide 6 to 18" long ..... 1.00 per ft.

THERMISTORS		VARISTORS	
D-167332 (tube)	$.95	D-170225	$1.25
D-170396 (bead)	$.95	D-167176	$.95
D-167613 (button)	$.95	D-168687	$.95
D-164080 for MTG in "X" band Guide	$2.50	D-171812	$.95
		D-171528	$.95
D-167918 (tube)	$.95	D-171528	$.95
		D-168442	$3.00
		D-165503	$1.25
		D-98836	$2.00
WRITE FOR C.E.C. MICRO-WAVE CATALOG NOW AVAILABLE		D-161871A	$2.85
		D-171121	$.95
		D-98836	$1.50
		D-162356 (308A)	
		D-163357	$2.00
		D-99948	$2.95

3,000 MC BAND

90° Twist, circular cover to circular cover $25.00
Magnetron to Waveguide Coupler with 721A Duplexer Cavity, gold-plated $45.00
Waveguide Switch—Transposer, one input to any of three outputs. Standard 1½" x 3" square flanges. Complete with 115V drive motor. Raytheon CRT24AAB, new $150.00
721A TR Box complete with tube and tuning plungers $12.50
McNally Klystron Cavities for 707B or 2K28. Three types available $4.00
Right Angle Bend 5½ ft. over-all with 8" slotted section $21.00
Pick-up Dipole in Lucite Ball with Sperry Fitting $4.50
F-28/SPR-2 Filters, Type "N", input and output $12.50
726 Klystron Mount, Tunable output, to type "N", complete with socket and mounting bracket $12.50
WAVEGUIDE TO ⅞" RIGID COAX "DOORKNOB" ADAPTER, CHOKE FLANGE, SILVER PLATED BROAD BAND $32.50
WAVEGUIDE DIRECTIONAL COUPLER, 27 db, Navy type CABV -47AAN, with 4 in. slotted section $32.50
SQ. FLANGE to rd choke adapter, 18 in. long OA 1½ in. x 3 in. guide type "N" output and sampling probe $27.50
Crystal Mixer with tunable output TR pick up loop, Type "N" connections. Type 82ABH $14.50
Slotted line probe. Probe depth adjustable. Sperry connector, type CBR 14AAO $9.50
Coaxial slotted section, ⅞" rigid coax with carriage and probe $25.00
Right Angle Bend 6" radius E or H plain $27.50
Right Angle Bend 3" radius E or H plain—Circular flanges $7.50
AN/APR5A 10 cm antenna equipment consisting of two 10 CM waveguide sections, each polarized, 45 degree ..... $75.00 per set
PICKUP LOOP, Type "N" Output $2.75
TR BOX Pick-up Loop $1.25
POWER SPLITTER: 726 Klystron input dual "N" output $5.00
"S" BAND Mixer Assembly with crystal mount, pick-up loop, tunable output $3.00
721-A TR CAVITY WITH TUBE. Complete with tuning plungers $12.50
10 CM OSC. PICKUP LOOP, with male Hemedoll output $2.00
10 CM FEEDBACK DIPOLE ANTENNA, in lucite ball, for use with parabola ⅞" Rigid Coax input $4.00
PHASE SHIFTER, 10 CM WAVEGUIDE, WE TYPE FS-683816, E PLANE TO H PLANE, MATCHING SLUGS, MARK 2 ..... $95.00
721A TR cavities. Heavy silver plated ..... $2.50 ea.
Coax Xtal Mount for Type "N" tunable $15.00
10 CM Mixer $3.00

⅞" RIGID COAX—3000 MC

Directional Coupler, Type "N" take off $22.50
Magnetron Coupling with T Loop, gold-plated $7.50
Flexible Section Male to Female $4.50
Right angle bend 15° over-all $3.50
Sperry Rotating Bend, pressurized $22.50
FL Lengths Stub Supported, gold-plated, per length $7.50
Short Right Angle Bends (for above) $2.50
Rigid Coax to Type "N" Adapters $18.50
Test Block CU-80/AP $8.00
CG-54/U—4 foot flexible section ⅞" IC pressurized $15.00
⅞ Rigid COAX, Bead Supported ⅛" I. C. $1.20
SHORT RIGHT ANGLE BEND ⅛" I.C. $2.50
Rotating Joint, with deck mounting ⅛" I. C. $15.00

COUPLINGS—UG—CONNECTORS

UG/15U	$.75	UG 118 Cover & Coupling Ring	$1.95
UG206U	.90	UG 117 Choke	2.50
UG87U	1.25	UG 51 Cover	1.00
UG27U	1.69	UG 52 Choke	1.35
UG21U	.89	UG 210 Cover	1.85
UG167U	2.25	UG 212 Choke	2.40
UG29U	.90	UG 40U Special for Duplexer	.20
UG254U	1.69	⅞ Coax Female Ring Thd or unthd	.50
UG86U	1.40	⅞ Coax Male Fitting thd or unthd	.95
UG342U	3.25	X Band Circ. Choke Flange	.50
UG85U	1.45	X Band Flat Contact Flange Thk	.25
UG58U	.60	Contact Ring ¼" Thk 1⅛ dia. hole	.25
UG9U	.89	UG 53/U, Cover	$4.00
UG102U	.45	UG 54/U, Choke	4.75
UG103U	.45	UG 55/U, Cover	4.00
UG255U	1.65	UG 56/U, Choke	4.75
UG 40/U Spacl. for Mixer Assy.	.75	UG 65/U, Contact	6.50
		UG 149/U, Cover	3.00
UG 40A	1.10	UG 148/U, Choke	4.00
UG 343 Cover	2.35	UG 150/U, Contact	3.00
UG 344 Choke	3.00	UG 39/U, Cover	.60
UG 425 Contact	2.00	UG 40/U, Choke	.80

Various other types available.
Write us your needs.

All merch. guar. Mail orders promptly filled. All prices F.O.B. N. Y. C. Send MO or Chk. Only shipping chgs sent C.O.D. Rated Concerns send P.O.

COMMUNICATIONS EQUIPMENT CO.

131 Liberty St., New York, N. Y. **Dept. E-7** P. J. PLISHNER **Phone: Digby 9-4124**

COMMUNICATIONS EQUIPMENT COMPANY

PULSE NETWORKS

15A—1-400-50: 15 KV, "A" CKT, 1 microsec., 400 PPS, 50 ohms imp. $42.50
G.E. #6E3-5-2000-50P2T, 6KV, "E" circuit, 3 sections, .3 microsecond, 2000 PPS, 50 ohms impedance $6.50
G.E. #3E (3-84-81C; 8-2-24-400) 30P47; 3KV, "E" CKT Dual Unit: Unit 1, 3 Sections, .84 Microsec, 810 PPS, 50 ohms imp.; Unit 2, 8 Sections, 2.24 microsec, 405 PPS, 50 ohms imp. $8.50
7.5E3-1-200-67P 7.5 KV, "E" Circuit, 1 microsec, 200 PPS, 67 ohms impedance, 3 sections $7.50
7.5E4-16-80.67P, 7.5 KV, "E" circuit, 4 sections, 16 microsec, 80 PPS, 67 ohms impedance $13.00
7.5E3-200-6PT, 7.5 KV, "E" Circuit, 3 microsec, 200 PPS, 67 ohms imp., 3 sections $12.50

PULSE TRANSFORMERS

G.E.K.-2745 ..... $39.50
G.E.K.-2744-A. 11.5 KV High Voltage, 3.2 K.V. Low Voltage @ 200 KW oper. (270 KW max.) 1 microsec. or ¼ microsec. @ 600 PPS $15.00
W.E. #D166173 Hi-Volt Input transformer, W.E. Impedance ratio 50 ohms to 900 ohms. Freq range: 10 kc to 2 mc. 2 sections parallel connected, potted in oil $50.00
W.E. KS 8800 Input transformer. Winding ratio between terminals 3-5 and 1-2 is 1.1:1, and between terminals 6-7 and 1-2 is 2:1. Frequency range: 380-520 c.p.s. Permalloy core $6.00
G.E. #K2731 Repetition Rate: 635 PPS. Pri. Imp: 50 Ohms Sec. Imp: 450 Ohms. Pulse Width: 1 Microsec. Pri. Input: 9.5 KV PK. Sec. Output: 28 KV PK. Peak Output: 800 KW. Rifar 2.75 Amp. $64.50
W.E. #D169271 Hi Volt Input pulse Transformer $27.50
G.E. K2450A. Will receive 13KV.4 micro-second pulse on pri., secondary delivers 14KV. Peak power out 100KW G.E. $34.50
G.E. #K2748A. Pulse input, line to magnetron $36.00
#9282 Utah Pulse or Blocking Oscillator XFMR Freq. limits 780-810 cy-3 windings turns ratio 1:1:1 Dimensions 1 13/16 x 1½" 19/32 ..... $1.50
Pulse 131-AWP L-421435 ..... $6.00
Pulse 134-BW-2F L-440895 ..... $2.25
RAY—WX1298F $18.50
G.E.—K6324730 ..... $50.00
G.E.—K9216945 ..... $80.00

PULSE EQUIPMENT

MIT MOD. 3 HARD TUBE PULSER: Output Pulse Power 144 KW (12 KV at 12 Amp). Duty Ratio: .001 max. pulse duration: 5, 1.0, 2.0 microsec. Input voltage: 115v, 400 to 2400 cps. Uses 1-715B, 4-829-B, 3-72's, 1-173. New w/Tubes $110.00
APD-13 PULSE MODULATION. Pulse Width .5 to 1.1 Micro Sec. Rep. rate 624 to 1348 Pps. Pk pwr. out 35 KW Energy 0.018 Joules $49.00
TPS-3 PULSE MODULATOR. Pk power 50 amp. 24 KW (1200 KW pk): pulse rate 200 PPS 1.5 microsec. pulse line impedance 50 ohms. Circuit series charging version of DC Resonance type. Uses two 705-A's as rectifiers. 115 v. 400 cycle input. New with all tubes $49.50
APS-10 MODULATOR DECK. Complete, less tubes $75.00
APS-10 Low voltage power supply less tubes $18.50
BC 1203B Loran pulse modulator $125.00
BC 756A Pulse modulator $395.00
725A magnetron pulse transformers ..... $18.50 ea.

DELAY LINES

D-163109 Delay Line Small quantity available $50.00
D-168184: .5 microsec. up to 2000 PPS, 1000 ohm term. $4.00
D-170409: .25/.50/.75 microsec. 8 KV. 50 ohms imp. $16.50
D-165997: 1½ microsec. $7.50

INDICATORS—SCOPES

BC 931B 420-50-100 mile range 5" scope w/mtg. rack, indicator amplifier, BC 932B, visor. New w/tubes $24.50
BC 704A 9-36-90 mile range 5" scope $17.50
BC 937A & BC 938A 12" PPI & "A" scope. Complete desk Rack assy w/osc. control unit, rec., pwr. supls, in unused cond. but shelf worn $300.00
Radar Indicator RW 281 mfg. by Research Enterprise Ltd. 5" scope $30.00

PRECISION CAPACITORS

D-163707: 0.4 mfd @ 1500-vdc. —80 to plus 85 deg C $4.50
D-163035: 0.1 mfd @ 600 vdc, 0 to plus 85 deg C $2.00
D-170803: 0.152 mfd, 300 v, 400 cy, —30 to plus 85 deg. C $2.00
D-164960: 2.04 mfd @ 200 vdc, 0 to plus 55 deg C $2.50
D-163344: 2.16 mfd @ 200 vdc, 0 to plus 55 deg C $3.00
D-161555: .5 mfd @ 400 vdc, —30 to plus 85 deg C $3.00
D-161270: 1 mfd @ 200 vdc, temp comp —40 to plus 65 deg C $4.50

30 US ARMY SIGNAL CORPS RADIO MASTS

Complete set for erection of a full flat top antenna. Of rugged plymold construction telescoping into 3 ten-foot sections for easy stowage and transportation. A perfect set-up for getting out. Supplied complete: 2 complete masts, hardware, shipping crate. Shipping wt. approx. 300 lbs. Sig Corps #2A289-233-A. New ..... $39.50 per set

MAGNETRONS

Ask for Qty. Price

Tube	Frq. Range	Pk. Pwr. Output	
2J27	2965-2982 mc.	275 KW.	WRITE
2J31	3220-3260 mc.	250 KW.	
2J21 A	9345-9405 mc.	80 KW.	FOR
2J22	3257-3333 mc.	264 KW.	
2J26	2982-3019 mc.	275 KW.	SURPLUS
2J27	2965-2982 mc.	275 KW.	
2J32	2780-2820 mc.	288 KW.	PRICES
2J37			
2J38 Pkg.	3248-3253 mc.	8 KW.	ALL
2J39 Pkg.	3267-3333 mc.	87 KW.	
2J40	9305-9325 mc.	10 KW.	BRAND
2J49	9060-9160 mc.	58 KW.	
2J34			NEW
2J61	3000-3100 mc.	33 KW.	
2J62	2914-3010 mc.	35 KW.	ORIG.
3J31	24,000 mc.	80 KW.	
6J30			PACKED
714AY			
718DY	2720-2880 mc.	250 KW.	
720BY	2800 mc.	1000 KW.	
720CY	2880 mc.	1000 KW.	
725-A	9345-9405 mc.	80 KW.	
730-A	9345-9405 mc.	80 KW.	

720 AY, BY, CY, DY, EY, FY, GY
700 A, B, C, D
710 AY, BY, DY, EY, FY, GY
Klystrons. 723A/B $12.50; 707B

W/Cavity	
417A $25.00	2K41

MAGNETRON MAGNETS

Gauss	Pole Diam.	Spacing	Price
4850	¾ in.	⅝ in.	$8.90
8200	⅞ in.	¾ in.	$17.50
1300	1⅝ in.	1⅛ in.	$12.50
1893	1⅝ in.	1½ in.	$14.90

Electromagnets for magnetrons ..... $24.50 ea.

GE Magneto type M7765118, GI Distance Between pole faces variable. 2½" (1900 Gauss) to 1½" (2200 Gauss) Pole Dia. 1¼" New Part of SCR 584 $34.50



"CW" MAGNETRONS

QK 62	3150-3376 mc.
QK 59	2675-2900 mc.
QK 61	2875-3200 mc.
QK 60	2800-3025 mc.

New, Guaranteed Each $65.00
QK 915 Raytheon $150.00

FILAMENT TRANSFORMER

for above 115V/60 cy Pri; four 6.3V/4A Sec. 5000VT $27.50
Magnetron Kit of four QK's 2675-3375 inc. w/transformer $250.00

R. F. EQUIPMENT

APS-3I RF Head less Receiver Section $400.00
APR-4 Receiver. Compl Less Tu. $400.00
APR-5 Receiver. 1000 to 5000 Mc. Complete $375.00
LHTR. LIGHTHOUSE ASSEMBLY. Part of MT-39/APG 9 & APG 15. Receiver and Trans. Cavities w/ assos. Tr. Cavity and Type N CPLG. To Rcvr. Uses 2040, 2C43, 1B27, Tunable APX 2400-2700 MCS. Silver plated $40.50
APS-2 10CM RF HEAD COMPLETE WITH HARD TUBE (715B) Pulser, 714 Magnetron 417A Mixer all ⅞" rigid coax. Incl. rcvr. front end $210.00
Beacon lighthouse cavity 10 cm with miniature 28 volt DC FM motor. Mfg. Bernard Rico ..... $47.50 ea.
T-128-/APN-15 10 cm. radar Beacon transmitter package. Used, less tubes ..... $49.50 ea.
Pre-Amplifier cavities type "M" 741059GL, to use 446A lighthouse tube. Completely tunable. Heavy silver plated construction ..... $37.50 ea.
RT/32APS 6A RF HEAD. Compl. with 725A Magnetron magnet pulse xfmr. TRA-ATR 723 A/B local osc. and beacon mount, pre amplifier. Used but Good cond. $97.50
AN/APS-15A "X" Band compl. RF head and mod. incl. 725-A mag and magnet, two 723A/B klystrons (local osc. & beacon) 1B24, TR, rcvr and ampl. duplexer, HV supply blower, pulse xfmr. Peak Pwr. Out: 45 KW aux. input: 115, 400 cy. Modulator pulse duration .5-2 microsec., aux. 13KV. PK. Pulse, with all tubes incl. 715B, 829B, BKR 73, two 72's. Complete pkg. $350.00
S BAND AN/APS2. Complete RF head and modulator, including magnetron and magnet, 417A mixer, TR receiver duplexer, blower, etc., and complete pulser. With tubes, used, fair condition $75.00
ASB-500 Megacycles, Radar Receiver with two GI 446 lighthouse cavities, new less tubes $37.50
10 CM Rec Assy. Less Local OSC. Tube. Consists of mixer stabilizer cavity 30 MC preamp AFC. Ing. Amp. plugs & cables p/o APS2 ..... $37.50
#SCR-520 RF Head Compl. with Hard Tube Pulser c/o 2 Aluminum Drums MTD.
In Tandem. Compl. W/Tubes $350.00
Mark 4 Radar Console (FD) Compl "L" Band RF Pkg. c/o Magnetron CSC, Pulser, Rcvr. H.V. Power Supply. Complete $850.00

30 MC IF STRIP

P/O APS-15 Radar using 6AC7's 2-3 Mc BW 20DB Gain. New & Complete IF Amplifier Video Sect. Less Tubes $17.50

YD-2 MARKER BEACON EQUIP. Compl. Installation in Trailer w/Gas Generator—WRITE.

MICROWAVE ANTENNAS

APS-4 3 cm. antenna. Complete. 14½ dish. Cutler feed dipole directional coupler, all standard 1" x ½" waveguide. Drive motor and gear mechanisms for horizontal and vertical scan. New, complete $65.00
AN-122 Dipole Assy. $22.50
LP-21-A ADF Loop W-Selsyn and Housing, New $8.00
DAK Beltline Tool DF Loops $125.00
Adcock DF Arrays. Complete $65.00
SA Radar 200 Mc Bed Springs. Complete with Pedestal. Less Drive $600.00
APS-15 Antennas. New $99.50
AN MPG-1 Antenna. Rotary feed type high speed scanner antenna assembly including horn parabolic reflector. Less internal mechanisms. 10 deg. conical scan. Approx. 12'L x 4'W x 3'H. Unused. (Gov't Cost—$4500.00) $250.00
AN/TPS3. Parabolic dish type reflector approx. 10' diam. Extremely lightweight construction. New in carrying cases $200.00
RELAY SYSTEM PARABOLIC REFLECTORS: approx. range: 2000 to 6000 mc. Dimensions: 4' x 5' rectangle, new $35.00
TDY "JAM" RADAR ROTATING ANTENNA. 10 cm. 30 deg. beam, 115 v.a.c. drive. New $100.00
DBM ANTENNA. Dual, back-to-back parabolas with dipoles. Freq. coverage 1,000-4,500 mc. No drive mechanism $65.00
AS125/APR Cone type receiving antenna. 1030 to 3200 megacycles. New $4.50
140-600 MC. CONE type antenna, complete with 25 sectional steel mast, guys, cables, carrying case, etc. New $40.50
ASD 3 cm. antenna, used, ex. cond. $40.50
YAGI ANTENNA AS-48A.
APS-4, 5 elements $4.50
Dish for Parabola 30" $4.85
AS17/APS 10 CM Antenna. APS-2 30 inch Dish with ⅞ Coax Dipole and fittings. New and Compl. with 24 V DC Drive motor, selsyn, 360 Deg. Rotation and Vertical Tilt $94.50
RC-224 Antenna, 10 CM, 36" Dish P/O SCR-717 Radar, New and Complete $94.50



WRITE FOR LATEST FLYER OF MICROWAVE EQUIPMENT AND PARTS.

SONAR

QCU Magneto striction head RCA type CR 270225—New $90.00
Stainless Steel streamlining housings for above $18.50
QBG Driver Amplifier. New $200.00
QCU Magneto striction head, coil plate assembly, new $14.50
QCQ-2/QCB Magneto striction head coil plate assembly $14.50
QCQ2 Sonar complete set—Write for details.
QC-RCA magneto striction head assy. consists of coil, plate, nickle diaphragm plate, milled steel body unassembled $65.00
Supersonic Oscillator RCA 17-27 Kc. Rec. Driver, Cos. 115 v 60 cy. AC. Designed for use w/200 watt driver. New tone tubes. $35.50
WEA-1 Console. Consists of Rec. Ind. Osc. Remote training control 200 watt driver amp. 17-27 kc range $450.00
QCQ 2 Console Sub. Mfg. Co. $450.00
QBF Sonar mfg. WE complete console consists of 10-40 kc rec. driver osc. ind. & control unit, and driver amplifier 22-28 kc. Write
QJA Sonar QBF w/QJA adaptor kits w/cathode ray tube indication. Write
QCQ-2 Sonar Compl. Less Hoist—Write

I.F.F. 1 KW Pulsed Output Pkg. Tunable 154-188 mc. adj. modulating pulses 4-10 micro sec. comp. 115v 60cy ac pwr. supply. Video output receiver. New w/tubes $350.00
Wavemeter for above $75.00
Dipole Array for above $65.00
BC 800 XMTR. RCVR. Unit New $55.00
BC 929 Indicator New $35.00

All merch. guar. Mail orders promptly filled. All prices, F.O.B. N.Y.C. Send M.O. or Chk. Only shipping chgs. sent C.O.D. Rated Concerns send P.O.

COMMUNICATIONS EQUIPMENT CO.

131 Liberty St., New York, N. Y. **Dept. E-7** P. J. PLISHNER **Phone: Digby 9-4124**

FULLY GUARANTEED

BRAND NEW SURPLUS OFFERED BY A LEADING

A.C. MOTORS

5071930, Delco, 115 V., 60 Cycle, 7000 r.p.m. **Price $4.50 each net.**

36938-2, Haydon Timing Motor, 110 V., 60 cycle, 2.2 w., 4/5 r.p.m. **Price $3.00 ea. net.**

Type 1600 Haydon Timing Motor—110 V., 60 cycle, 3.2 w., 4 r.p.m., with brake. **Price $4.00 each net.**

Type 1600 Haydon Timing Motor—110 V., 60 cycle, 2.2 w., 1/240 r.p.m. **Price $3.00 each net.**

Type 1600 Haydon Timing Motor 110 V., 60 cycle, 2.3 w., 1 r.p.m. **Price $2.70 each net.**

Type 1600 Haydon Timing Motor, 110 V., 60 cycle, 2.2 w., 1 1/5 r.p.m. **Price $2.70 each net.**

Type 1600 Haydon Timing Motor 110 V., 60 cycle, 3.5 w., 1 r.p.m. With shift unit for automatic engaging and disengaging of gears. **Price $3.30 each net.**

Type 1600 Haydon Timing Motor, 110 V., 60 cycle, 2.2 w., 1/60 r.p.m. **Price $3.00 each net.**

Eastern Air Devices Type J33 Synchronous Motor 115 V., 400 cycle, 3 phase, 8,000 r.p.m. **Price $8.50 each net**

Telechron Synchronous Motor, Type B3, 115 V., 60 cycle, 2 r.p.m., 4 w. **Price $5.00 each net.**

Barber-Colman Control Motor, Type AYLC 5091, reversible 24 volts D.C. 1.7 amps 1 R.P.M., Torque 500 in. lbs. Contains 2 adjustable limit switches with contacts for position indication. Ideal for use as a remote positioner or to beam or television antenna rotator, will operate on A.C. 60 cycle. **Price $6.50 each net.**

SERVO MOTORS

CK 1, Pioneer, 2 phase, 400 cycle. **Price $10.00 each net.**

CK 2 Pioneer, 2 phase, 400 cycle. **Price $4.25 each net.**

10047-2-A Pioneer 2 phase, 400 cycle, with 40:1 reduction gear. **Price $7.25 each net.**

FPE-49-6 Diehl, Low-Inertia, 115 V., 60 cycle, 2 phase, 3 amps., 10 watt, output. **Price $34.50 each net.**

FPE-25-16 Diehl Low-Inertia 20 V., 60 cycle, 2 phase, 1600 r.p.m., 85 amps. **Price $10.00 each net.**

CK 2, Pioneer, 2 phase, 400 cycle, with 40:1 reduction gear. **Price $6.50 each net.**

CK5 Pioneer, 2 phase, 400 cycle **Price $20.00 ea. net**

MINNEAPOLIS-HONEYWELL TYPE B Part No. G303AY, 115 V., 400 cycle, 2 phase, built-in gear reduction, 50 lbs. in torque. **Price $8.50 each net.**

Kollsman Type 776-01 400 cycle 2 phase drag-cup type, fix phase voltage 29, variable phase 35V. maximum, frequency 400 cycle. **Price $10.50 each net.**

REMOTE INDICATING MAGNESYN COMPASS SET

Pioneer Type AN5730-2 Indicator and AN5730-3 Transmitter 26 V., 400 cycle. **Price $40.00 per set new sealed boxes.**

Kollsman Remote Indicating Compass Set Transmitter part No. 679-01, indicator part No. 680k-03, 26 V., 400 cycle. **Price $12.50 each net.**

GYROS

Schwein Free & Rate Gyro type 45600. Consists of two 28 V. D.C. constant speed gyros. Size 8" x 4.25" x 4.25". **Price $10.00 ea. net.**

Sperry A5 Directional Gyro, Part No. 656029, 115 volts, 400 cycle, 3 phase. **Price $17.50 each net.**

Sperry A5 Vertical Gyro, Part No. 644841, 115 V., 400 cycle, 3 phase. **Price $20.00 each net.**

Sperry A5 Amplifier Rack Part No. 644890. Contains Weston Frequency Meter. 350 to 450 cycle and 400 cycle, 0 to 130 voltmeter. **Price $10.00 each net.**

Sperry A5 Control Unit Part No. 644836. **Price $7.50 each net.**

Sperry A5 Azimuth Follow-Up Amplifier Part No. 656030. With tube. **Price $5.50 each net.**

Sperry A5 Autopilot Indicator, contains Pioneer AY20 autosyn 26 V., 400 cycle. **Price $9.50 ea. net**

Pioneer Type 12800-1-D Gyro Servo Unit. 115 V., 400 cycle, 3 phase. **Price $10.00 each net.**

Norden Type M7 Vertical Gyro. 26 V., D.C. **Price $19.00 each net.**

Allen Calculator, Type C1 Bank and Turn Indicator, Part No. 21500, 28 V. D.C. Contains 28 V. D.C. constant speed gyro. **Price $10.00 each net.**

Type C1 auto-pilot formation stick, part No. G1880A3. **Price $15.00 each net.**

C.A.A. approved instrument repair dept. No. 3564.

D.C. MOTORS

5069625, Delco Constant Speed, 27 V., 120 r.p.m. Built-in reduction gears and governor. **Price $3.90 each net.**

A-7155, Delco Constant Speed Shunt Motor, 27 V., 2.4 amps., 3600 r.p.m., 1/30 h.p. Built-in governor. **Price $6.25 each net.**

C-28P-1A, John Oster Series Motor, 27 V., 0.7 amps., 7000 r.p.m., 1/100 h.p. **Price $3.75 each net.**

Jaeger Watch Co. Type 44-K-2 Contactor Motor, Operates on 3 to 4.5 volts D.C. Makes one contact per second. **Price $2.00 each net.**

General Electric Type 5BA10AJ52C, 27 V. D. C., 0.65 amps., 14 oz. in. torque, 145 r.p.m. Shunt Wound, 4 lead reversible. **Price $5.00 each net.**

General Electric Type 5BA10AJ37C, 27 V. D. C., 0.5 amps., 8 oz., in. torque, 250 r.p.m. Shunt Wound, 4 leads reversible. **Price $6.50 each net.**

General Electric Type 5BA10J18D, 27 V. 0.7 amps. 110 R.P.M. 1 oz. ft. **Price $4.75 ea. net**

D.C. ALNICO FIELD MOTORS

S. S. FD6-16, Diehl, 27 V., 10,000 r.p.m. **Price $4.50 each net.**

S. S. FD6-18, Diehl, 27 V., 10,000 r.p.m. **Price $4.50 each net.**

S. S. FD6-21, Diehl, 27 V., 10,000 r.p.m. **Price $4.50 each net.**

5069600 Delco 27.5 V. 250 R.P.M. **Price $9.75 ea. net**

706343 Delco 27.5 V. 10,000 R.P.M. Shaft 0.5 in. long. **Price $7.50 ea. net**

5068571 Delco 27.5 V. 10,000 R.P.M. with blower assembly. **Price $10.00 ea. net**

5071895 Delco 27.5 V. 250 R.P.M. **Price $8.50 ea. net**

5072400 Delco 27.5 V. 10,000 R.P.M. Shaft 0.5 in. long with worm gear. **Price $6.75 ea. net**

GENERAL ELECTRIC D. C. SELSYNS

8TJ9-PDN Transmitter, 24 V. **Price $3.75 each net.**

8TJ9-PAB Transmitter 24V. **Price $3.75 each net.**

8DJ11-PCY Indicator, 24 V. Dial marked—10° to +65°. **Price $4.50 each net.**

8DJ11-PCY Indicator, 24 V. Dial Marked 0 to 360°. **Price $7.50 each net.**

AMPLIFIER

Pioneer Gyro Flux Gate Amplifier, Type 12076-1-A. **Price $17.50 ea. net, with tubes.**

G. E. Servo Amplifier Type 2CV1C1, 115 V. 400 cycle. **Price $9.00 ea. net**

Minneapolis Honeywell Amplifier Type G403, 115 V. 400 cycle. **Price $8.00**

INSTRUMENT ASSOCIATES

37 EAST BAYVIEW AVE., GREAT NECK, N. Y.
Telephone IMperial 7-1147

Write for Catalog NE100

U. S. Export License-2140

SUPPLIER OF ELECTRONIC & AIRCRAFT EQUIPMENT

IMMEDIATE DELIVERY

INVERTERS

Wincharger Corp. Dynamotor Unit. PE 101-C. Input 13, V.D.C. or 26 V.D.C. D.C. AT, 12.6 or 6.3 amps. Output 400 V.D.C. AT. .135 amps., 800 V.D.C. AT. .02 amps., 9 V.A.C. 80 cycle at 1.12 amps.
Price $10.00 each net.

153F, Holtzer Cabot, Input, 24 V.D.C. Output 115 V., 400 cycle, 3 phase, 750 V.A. and 26 V., 400 cycle, 1 phase, 250 V.A. Voltage and frequency regulated also built in radio filter.
Price $115.00 each net.

149H, Holtzer Cabot. Input 28 V. at 44 amps. Output 26 V. at 250 V.A., 400 cycle and 115 V. at 500 V.A., 400 cycle. **Price $40.00 each net.**

149F, Holtzer Cabot. Input 28 V. at 36 amps. Output 26 V. at 250 V.A., 400 cycle and 115 V. at 500 V.A., 400 cycle. **Price $40.00 each net.**

12117, Pioneer. Input 12 V.D.C. Output 26 V., 400 cycle, 6 V.A.
Price $22.50 each net.

12117-2 Pioneer. Input 24 V.D.C. Output 26 V. 400 cycle, 6 V.A.
Price $20.00 each net.

12116-2-A Pioneer. Input 24 volts D.C., 5 amps. Output 115 volts 400 cycle single phase 45 watts.
Price $100.00 each net.

5D21NJ3A General Electric. Input 24 V.D.C. Output 115 V., 400 cycle at 485 V.A. **Price $12.00 each net.**

PE218, Ballentine. Input 28 V.D.C. at 90 amps. Output 115 V., 400 cycle at 1.5 K.V.A. **Price $50.00 each net.**

METERS

Weston Frequency Meter. Model 637, 350 to 450 cycles, 115 volts.
Price $10.00 each net.

Weston Voltmeter. Model 833, 0 to 130 volts, 400 cycle. **Price $4.00 each net.**

Weston Voltmeter. Model 606, Type 204 P, 0 to 30 volts D. C.
Price $4.25 each net.

Weston Ammeter. Model 506, Type S-61209, 20-0-100 amps. D. C.
Price $7.50 each net with ext. shunt.

Weston Ammeter. Type F1, Dwg. No. 116465, 0 to 150 amps. D. C.
Price $6.00 each net.
With ext. shunt $9.00 each net.

Westinghouse Ammeter. Type 1090-D120, 120-0-120 amp. D. C.
Price $4.50 each net.

Weston Model 545. Type 82PE Indicator. Calibrated 0 to 3000 RPM. 2¾" size. Has built-in rectifier, 270° meter movement.
Price $15.00 each net.

RECTIFIER POWER SUPPLY

General Electric, input 230 V. 60 cycle 3 phase. Output 130 amps. at 28 V. D.C. Continuous duty, fan cooled, has adjustable input taps. G.E. model No. 6RC146F3. Size: Height 46", width 28", depth 17½". **Price $200.00 each net.** New

PIONEER AUTOSYNS

AY1, 26 V., 400 cycle.
Price $5.50 each net.

AY14D, 26 V., 400 cycle, new with calibration curve.
Price $15.00 each net.

AY20, 26 V., 400 cycle.
Price $7.50 each net.

AY5, 26V., 400 cycle. Has hollow shaft.
Price $7.50 ea. net

PRECISION AUTOSYNS

AY101D, new with calibration curve.

PRICE—WRITE OR CALL FOR SPECIAL QUANTITY PRICES

AY131D, new with calibration curve.
Price $35.00 each net.

AY130D, new. **Price $35.00 each net.**

PIONEER AUTOSYN POSITION INDICATORS

Type 5907-17. Dial graduated 0 to 360°, 26 V., 400 cycle.
Price $15.50 each net.

Type 6007-39, Dual, Dial graduated 0 to 360°, 26 V., 400 cycle.
Price $30.00 each net.

PIONEER TORQUE UNIT

Type 12602-1-A. Price $40.00 each net.



Type 12606-1-A. Price $40.00 each net.
Type 12627-1-A. Price $80.00 each net.

MAGNETIC AMPLIFIER ASSEMBLY

Pioneer Magnetic Amplifier Assembly Saturable Reactor type output transformer. Designed to supply one phase of 400 cycle servo motor.
Price $8.50 each net.

PIONEER TORQUE UNIT AMPLIFIER

Type 12073-1-A, 5 tube amplifier, Magnesyn input, 115 V., 400 cycle.
Price $17.50 each net with tubes

BLOWER ASSEMBLY MX-215/APG

John Oster, 28 V.D.C., 7000 r.p.m. 1/100 h.p. **Price $4.50 each net.**

Westinghouse Type FL Blower, 115 V., 400 cycle, 6700 r.p.m., Airflow 17 C.F.M. **Price $3.70 each net.**

RATE GENERATORS

PM2, Electric Indicator Co., .0175 V. per r.p.m. **Price $8.25 each net.**

F16, Electric Indicator Co., two-phase, 22 V. per phase at 1800 r.p.m.
Price $12.00 each net.

J36A, Eastern Air Devices, .02 V. per r.p.m. **Price $9.00 each net.**

B-6B, Electric Indicator Co., Rotation Indicator, 110 V., 60 cycle, 1 phase.
Price $14.00 each net.

PM-1-M Electric Indicator Co. Same as type B3S. 2 V. per 100 R.P.M. Max. speed 5,000 R.P.M. Can be used as D.C. motor, 1/77 H.P. 115 V. D.C.
Price $9.75 ea. net

SINE-COSINE GENERATORS (Resolvers)

FPE 43-1, Diehl, 115 V., 400 cycle.
Price $20.00 each net.

SYNCHROS

1F Special Repeater, 115 V., 400 cycle. Will operate on 60 cycle at reduced voltage.

Price $15.00 each net.

7G Generator, 115 V., 60 cycle.
Price $30.00 each net.

2J1F3 Selsyn Generator 115 volts, 400 cycle. **Price $5.50 each net.**

2J1M1 Control Transformer 105/63 V., 60 cycle. **Price $20.00 each net.**

2J1G1 Control Transformer, 57.5/57.5 V., 400 cycle. **Price $1.90 each net.**

2J1H1 Selsyn Differential Generator, 57.5/57.5 V., 400 cycle.
Price $3.25 each net.

W. E. KS-5950-L2, Size 5 Generator, 115 V., 400 cycle.
Price $4.50 each net.

5G Generator 115 volts, 60 cycle.
Price $50.00 each net.

5G Special, Generator 115/90 V., 400 cycle. **Price $15.50 each net.**

5SF Repeater, 115/90 V., 400 cycle.
Price $19.00 each net.

2J1F1 Selsyn Generator, 115 V., 400 cycle. **Price $3.50 each net.**

5SDG Differential Generator 90/90 V., 400 cycle. **Price $12.00 each net.**

1CT Control Transformer. 90/55 volts, 60 cycle. **Price $40.00 each net.**

POSITION TRANSMITTER

Pioneer Type 4550-2-A Position Transmitter, 26 volts 400 cycle, gear ratio 2:1. **Price $15.00 each net.**

ALL PRICES, F. O. B. GREAT NECK, N. Y.

INSTRUMENT ASSOCIATES

37 EAST BAYVIEW AVE., GREAT NECK, N. Y.
Telephone IMperial 7-1147

Write for Catalog NE100

Western Union address: WUX Great Neck, N. Y.

TEST EQUIPMENT

I 135 Test Set
BC 771 Frequency Meter
BC1287 Scope
TS 62/AP
TS 13/AP
TS 102A/AP
TS 251
BC 221 Freq. Meter
I 222 Signal Generator
LM Frequency Meters

RC 150 EQUIPMENT

Receiver BC 1161 A
Transmitter BC 1160 A
Control Unit BC 1162A
Signal Generator I-199A

Miscellaneous Specials

1D6/APN4 - Scope
R 78/A PS 15 - Scope
R7/APS 2 Receiver and Scope
ASB7 Scope
SCR 522 Receiver-Transmitter
MN26 C- or Y Receiver
RA 10 Receiver
BC 639 Receiver
RA 42 Rectifier
TA2J24 Transmitter
SCR 269 G Compass Installation
ARN7 Compass Installation
MN 26 Compass Installation
ILS Installation (BC733 & R89)
SCR 584 components
R 132/TPS10 Radar Receiver
MD22 - URA/T1 Modulator
AN/APR1 Receiver and Tuning units
ASB 7 Complete Radar Installation
BD 71—6 position Field Switchboard
EE8 Field Phones
RM 29 Remote Phone Control
SCR 193 complete
ARC/1 Transceiver
ART 13 Transmitter
BC348 Receiver
RTA1B Transceiver
Model 15 Radar Trainer

PRICES OF ABOVE UPON REQUEST

T-85/APT5 UHF TRANSMITTER

Operating over a frequency range of 300 to 1400 MCPC with a nominal output of from 10 to 30 watts. Unit is equipped with 110 V 60 CPS filament transformer; blower; locher wire test frequency set, and 8 tubes —1-931A; 2-6AC7; 2-6AG7; 1-6L6G; 2-829B; 1-3C22 (GL522) (oscillator).

New in original box with operating Instruction Manual..... **$69.50**

Portable VHF Communication Unit

Two-way radio telephone equipment designed for operation between 152 and 162 megacycles. Adaptable for many uses, a complete unit including the rechargeable storage battery weighs but fifteen pounds, and is housed in a sturdy case 11½" x 9" x 4¼", provided with shoulder straps.

This brand new set of big name manufacture comes complete with battery, battery tray, and handset but less crystal $89.50.

Battery charger is extra at $19.95.

Mobile VHF Communication Unit

Adaptable for many mobile uses, this is a compact unit 3½" x 8" x 15½" operating on 152 to 162 megacycles. It is six volt powered direct from storage battery, and is complete with the tone filter and crystal; handset, control box, antenna and installation kit.

Brand new, ready to go. **$129.50**

Extra 18" stub type antennae are available. **$2.95**

Extra handsets (cradle type) **$5.95.**

Extra control units which house a PM speaker and provide mounting for handset **$4.95.**

A combination of both the handset and control box **$9.95.**

ARROW has the VALUES!

RADIO EQUIPMENT R. C.-100-B



This equipment made by General Electric, was designed for ground use as an identification of friendly aircraft.

Radio equipment RC-100-B consists of Cabinet CH-118 in which are mounted Transmitter BC-769, Keying unit BC-770, Radio Receiver BC-788, Rectifier RA-52, Wave Trap FL-25, wiring and Blower. Additional equipment consists of Antenna unit AN-82B; Transmission line MC-377, air compressor M-349, Oven M-348, control box BC-773, Amplifier BC-783B and associated cords and hardware.

Primary requirements are 110 to 120 volts, 50 to 60 cycle for the entire unit and accessories.

Cabinet CH-118 is of the Standard 19 inch rack type structural steel frame with runner angles for each of the units. A full length access door with safety interlocks forms the rear of the cabinet.

Transmitter BC-769 is designed to transmit RF pulsed signals at 470 megacycles with the use of two type 15E Tubes operating in push-pull with resonant grid, plate and filament lines.

Keying unit BC-770 furnishes the pulse of the Transmitter.

Receiver BC-788 was used to detect the 493.5 megacycle reply pulses from the interrogated station and to sufficiently amplify these signals for oscilloscope observation.

Rectifier RA-52 produces the high voltage. An 0-15 kilovolt DC Meter is connected across the output of the filter to measure the voltage fed to transmitter BC-769, while an 0-20 milliammeter is connected to the ground return to measure the average current drawn.

Antenna AN-82B consists of 24 vertically polarized, half wave radiating elements, a reflecting screen, open-wire transmission line sections and a concentric-line terminating section or elevator.

Wave trap FL-25 is used to separate received and transmitted signals.

Transmission line MC-377 is of ⅞ inch air-dielectric, 70 ohm concentric line type and is assembled by means of solderless air tight connectors.

Control Box BC-773 contains necessary controls for operation.

Amplifier BC-783-B is used to amplify the output of Receiver BC-788 for suitable oscilloscope presentation.

Air Compressor M-349



together with 12 feet of ¼ inch soft copper tubing and necessary hardware is used to fill and maintain transmission lines with dry air under pressure. Operation is direct from 110 V AC 60 Cycles.

Oven M-348

is furnished for removal of moisture from the dehydrating cylinders of the compressor. It too operates from 110V AC 60 cycles.

Frequency Meter BC-771



Frequency Meter BC-771 is used for frequency checking and for tuning operations on Radio Transmitter BC-769 and Radio Receiver BC-788. It is a separate unit mechanically and has its own power supply, which requires a 110 to 120 Volt, 50 to 60 cycle source.

The circuits consist of an r-f oscillator, a crystal oscillator, a 30,000 cycle oscillator and associated mixer, multiplier, and amplifier tubes. The crystal oscillator is used to set the r-f oscillator to exactly 94 or 98.7 megacycles.

For tuning Radio Transmitter BC-769 to 470 megacycles, the signal from the radio transmitter is mixed with the fifth harmonic of the r-f oscillator, operating at 94 megacycles, to produce an audio-beat frequency. For tuning Radio Receiver BC-788 to 493.5 megacycles, the fifth harmonic r-f oscillator, operating at 98.7 megacycles and modulated by the output of the 30,000 cycle oscillator, is fed into the radio receiver.

The entire RC 100 as described above—all brand new—complete— **$595.00** F.O.B. Warehouse

Technical Manual TM11-1113B is furnished with the complete set.

Prices on individual components will be furnished on request.

ARROW SALES, Inc.
Dept. IX
1712-14 S. Michigan Ave., Chicago 16, Ill.
PHONE: HArrison 7-9374

All items FOB warehouse. 20% Deposit required on all orders. Minimum order accepted—$5.00. Illinois residents, please add regular sales tax to your remittance.



ASB YAGI ANTENNA

5 ELEMENT ROTATABLE ARRAY—450 TO 500 MC **$7.00**

SAME EXCEPT DOUBLE STACKED 5 ELEMENT 450 TO 500 MC **$12.70**

Same Except Double Stacked 9 Element 370 to 430 MC **$29.40**

Double stacked antennas can be supplied with hydraulic remote controls at $29.50 per set additional.

PULSE TRANSFORMERS

UTAH 9262	$1.50
UTAH 9278	$1.50
G. E. 69G-627	$3.75
AN/APN-9 (90176A-501)	$1.25
AN/APN-9 (90176A-502)	$1.25
AN/APN-4 Block, Osc	.88

CAPACITORS

MOLDED OIL-IMPREGNATED PAPER

.02 MFD	200VDC	.04½ Ea.	$3.00 per 100
.05	200	.04½	3.00
.1	200	.04½	3.00
.25	200	.06	3.00
.1	400	.09	4.00
.005	600	.04½	3.00
.01	600	.07	4.75
.05	600	.08	5.50

OIL-FILLED CAPACITORS

50 MFD	220 VAC	$2.95
40 MFD	330 VAC	$4.89
32 MFD	2500 VDC	$10.88
7 MFD	660 VAC	$2.95
3.8-.5 MFD	1000 VDC	.77
.1 MFD	7000 VDC	$1.75
.045 MFD	16 KVDC	$4.70

SPECIAL

2 MFD 12,500 VDC INERTEEN TYPE FP

$23.95

KOLLSMAN INSTRUMENT

LOW INERTIA SERVO MOTORS

Type 937-0240—85/68 Volts—100 Cycles 2 Phase—3 Watts—2650 RPM Will Operate Satisfactorily at 60 Cycles Original Price $34.50—Our Price—$8.22 ea.

$7.50 EACH—Lots of 10

COAXIAL CONNECTORS

83-1AC	.42	UG-12/U	.63	UG-86/U	1.22
83-1AP	.15	UG-21/U	.67	UG-87/U	.65
83-1F	1.12	UG-22/U	.86	UG-171/U	1.33
83-1H	.10	UG-23/U	.63	UG-179/U	.15
83-1J	.90	UG-24/U	.67	UG-176/U	.15
83-1R	.28	UG-27/U	.68	UG-178A/U	3.82
83-1SP	.28	UG-29/U	.83	UG-191/AP	.57
83-1SPN	.28	UG-30/U	.94	MX-195/U	.41
83-1T	1.12	UG-34U	12.88	UG-197/U	1.33
83-22AP	1.10	UG-36/U	12.88	UG-206/U	.88
83-22F	1.45	UG-37/U	13.88	UG-255/U	.82
83-22R	.68	UG-88/U	.57	UG-264/U	1.74
83-22SP	.60	UG-85/U	.42	MX-367/U	.15

FULL LINE OF JAN APPROVED COAXIAL CONNECTORS IN STOCK

GENERAL ELECTRIC FG-172 THYRATRONS

$14.50

$10.00 EA.

IN LOTS OF 10 BRAND NEW ORIGINAL CARTONS FULLY GUARANTEED

GENERAL ELECTRIC FG-32 TUBES

$4.25

$3.75 Ea. - Lots of 10 Brand New Original Cartons

IGNITRONS

GL-413/5550	$22.00
WL-681/5550	$22.00
WL-682/5651	$38.00

SELENIUM RECTIFIER STACKS

FULL WAVE BRIDGE

MAXIMUM RATINGS AC VOLTS INPUT	18	MAXIMUM RATINGS AC VOLTS INPUT	40
DC VOLTS OUTPUT	14.5	DC VOLTS OUTPUT	34
1.2 Amps	$2.64	0.6 Amps	$3.00
2.4	3.07	1.2	3.44
6.4	4.09	3.2	5.15
13.0	6.14	6.0	9.32
17.5	8.69	9.0	10.05
26	15.33	12	18.64
39	23.00	18	29.12
52	30.67	24	35.96
65	38.33	36	41.24

All voltage and current ratings based on continuous operation in 35°C. (95°F.) ambient, self-cooled. Current ratings can be increased up to 2½ times normal ratings by intermittent operation or forced cooling.

GENERATORS

- Eclipse-Pioneer type 710-3A (Navy Model MEA-3A) Output—AC 115V 10.4A 800 to 1400 cy 1 ø DC 30 Volts 60 Amps. Brand New — Original Packing $32.50
- Eclipse-Pioneer type 1235-1A. Output—30 Volts 15 Amps. Brand New—Original Packing..... $9.50

NAVY MODEL AIA ANTENNAS

3 CM Conical Scan Aircraft Intercept Antenna Assys. Brand New $120.00

TEST EQUIPMENT

- Alfred W. Barber Labs. Mod. VM-25 VTVM ..... * $80.00
- General Radio Model P-500A Standard Signal Generator (Same as G. R. 805A except covers 5KC to 32 MC) ..... * $450.00
- Galvin Model CES-1 Standard Crystal Test Set ..... * $45.00
- TS-10A/APN Delay Line Test Set..... $25.00
- TS-19/APQ-5 Calibrator $75.00
- AT-48/UP "X" Band Horn $3.00
- REL W-1158 Frequency Meter 100-220 MC. $32.50
- CWI-60AAG Range Calibrator for ASB, ASE, ASV and ASVC Radars $30.00
- CRV-14AAG Phantom Antenna for Transmitters up to 400 MC..... $11.75
- Raytheon VR-5 Constant Voltage Transformer Input 95/130 V 60 cy—Output 115 V 500 W * $38.50
- Sola Constant Voltage Transformer Input 95/125 V 60 cy.—Output 115 V 200 VA $24.70
- Federal Constant Voltage Transformer Input 95/135 V 50/60 cy—Output 115 V 210 W..... $34.00
- Sola Constant Voltage Transformer—Input 95/125 V 60 cy.—Output 115 V 90 VA—Price on request.
- TS-146/AP X-Band Test Set. Price on request.
- TS-186/AP ..... Price on request.
- CPR-60AAJ and CPR-60AAK—IFF Test Sets. (pair) $16.95
- Navy Model LD-3 Combined Heterodyne Freq. Meter and Crystal Controlled Calibrator Equip. Mfd. by General Radio—100 KC to 5000 KC—Input 115 V 60 cy ..... * $370.00
- C-D Quietone Filter Type IF-10 110/220 V AC/DC 20 Amps $9.50

All Items New Except Where Noted * (Exs. Used Condition)

TYPE "J" POTENTIOMETERS

38c each

Resis.	Shaft	Resis.	Shaft	Resis.	Shaft
100	SS	10K	SS	50K	SS
200	SS	10K	SS	50K	SS
500	½"	15K	½"	100K	5/8"
650	SS	15K	SS	100K	SS
1000	SS	20K	SS	150K	½"
5000	3/8"	25K	1½"	200K	SS
6500	SS	25K	SS	250K	SS
10K	3/8"	30K	1 7/8"	1 MEG	SS

Triple 100K - 3/8" Shaft - 1.47

All shaft lengths beyond bushing - SS (screw slot)

STANDARD BRANDS ONLY — TUBE SPECIALS — BRAND NEW FIRST QUALITY

RECEIVING TUBES				CATHODE RAY		THYRATRONS AND IGNITRONS		TRANSMITTING & SPECIAL PURPOSE TUBES							
0Z4G	.59	6F6	.69							4B22/EL-5R	5.20	FG-190	12.15	561	1.45	813	7.25
1A3	.45	6H6	.49									203A	6.40	575B	5.85	814	3.79
1AB5	.73	6J5	.49	2AP1	3.65	OA4G	.95	OA3	1.52	4B25/EL-6CF	8.70	203B	4.33	HY615	.29	815	1.72
1B3GT	1.18	6J6	.89	2AP5	5.95	EL-C1A	3.35	OB2	1.75			204A	27.90	WL-6670A	8.70	816	.97
1L4	.66	6J7	.72	3AP1	6.63	2A4G	1.15	1B22	3.87	4C28	21.65	CE-206	3.15	700B	16.90	826	.97
1N5	.73	6K6GT	.52	3AP4/-7		2D21	1.99	1B23	8.95	4E27	12.75	211	.62	700C	16.90	828	12.48
1R4	.29	6L6	1.22	906P4	5.94	3C23	3.20	1B24	4.90	5D21	20.50	211-215A	.62	700D	16.90	829	4.91
1R5	.69	6L6G	1.11	3BP1	2.89	3C31/EL-C1B	3.35	1B26	6.24	5J23	14.20	221A	1.95	701A	3.67	830B	3.35
1S4	.86	6L6GA	.87	3CP1	1.87	4C35	21.00	1B29	2.90	5J29	14.20	227A	2.40	702A	2.95	832	4.91
1S5	.64	6S7Y	.79	3DP1	2.92	EL-C3B	8.95	1B31	3.15	6C21	19.88	WE-231D	1.25	702B	3.87	832A	5.50
1T4	.64	6SC7	.66	3DP1A	5.75	C6J	4.44	1B42	9.80	RK-25	2.11	RK-233A	1.95	703A	3.95	837	.69
2X2/879	.69	6SF7	.72	3HP7	4.91	4AP10	5.35	1H29	.58	7-7-11	.89	WE-244A	4.20	704A	2.75	837	1.38
2X2A	.79	6SG7	.69	5AP1	3.75	FG-17	2.89	1H30	.58	10T1	.58	WE-245A	1.35	705A	1.17	838	2.93
3A4	.61	6SH7	.44	5AP4	4.75	FG-33	11.95	2B22	1.41	15R	.75	WE-249C	1.60	706AY	45.00	841	.49
3A5	.56	6SJ7	.59	5BP1	2.40	FG-47/-1904	8.85	2C22	1.41	REL-21	3.25	WE-254A	6.90	706BY	45.00	843	.99
3A8GT	1.76	6SL7GT	.69	5CP1	2.87	FG-81A	4.95	2C26	.27	25G	.44	WE-257A	2.77	706CY	17.95	851	27.90
3B7/1291	.29	6SN7GT	.79	5CP7	3.76	91	5.85	2C34	.26	RK-25	2.11	WE-271A	6.75	706PY	45.00	852	6.60
3D6/1299	.29	6SN7W	1.45	5CP7	3.76	FG-95	20.60	2C43	.79	FG-32	4.25	WE-283A	1.27	706QY	45.00	860	6.60
3Q5GT	.79	6V6	1.07	5FP7	1.85	FG-105	9.95	2C44	.79	RK-34	.28	WE-304B	7.50	707A	5.22	861	17.50
3S4	.61	6V6GT	.59	5HP4	3.35	FG-172	14.50	2E22	1.25	REL-36	.78	304TH	3.86	707B	6.95	864	.19
5R4GY	1.30	6W4GT	.65	5JP2	9.55	GL-415/-5550	22.00	2J21A	8.95	RK-47	4.92	304TL	1.25	708A	4.85	865	.88
5T4	.89	6X4	.59	5LP1	13.95	KU-610	6.35	2J22	8.95	EF50	.45	307A	3.50	708A	4.87	866A	1.15
5U4G	.59	6X5GT	.59	5MP1	10.65	KU-628	16.90	2J26	7.88	VT-52	.36	WE310A	7.50	710A	2.25	869B	27.90
5V4G	.84	7F7	.79	7BP1	12.87	KU-634	17.20	2J27	13.70	53A	3.82	WE-313C	3.15	713A	1.45	872A	1.88
5Z3	.65	7N7	.79	7BP7	4.95	WE-388A	14.15	2J31	9.60	RK-59	2.44	318A	.66	714AY	6.95	874	1.65
6AB7/1853	.99	10Y	.19	7BP14	14.95	393A	5.77	2J32	14.45	RK-60/1641	.59	350A	2.80	715A	6.75	876	.39
6AC7/1852	.79	12A6	.24	9GP7	9.85	394A	3.77	2J33	19.98	RK-72	.92	350B	1.95	715B	9.95	878	1.85
6AC7W	1.45	12AH7GT	.87	9LP7	3.88	GL-415/-5550	22.00	2J34	19.90	RK-73	.92	354C	19.50	717A	.97	954	.39
6AG5	.89	12AT6	.59	10BP4	21.95	KU-610	6.35	2J37	13.70	VR-75/-6AA3	1.10	WE-354B	4.45	721A	2.95	955	.39
6AG7	1.19	12AT7	.99	10FP4	28.35	KU-634	17.20	2J38	12.70	75T	3.80	361A	6.75	723A	6.95	956	.49
6AJ5	.89	12AU6	.72	12DP7	12.85	WL-652/-5550	22.00	2J41	132.50	75T	3.80	371B	.92	723A/B	11.95	957	.49
6AK5	1.20	12AU7	.86	12GP7	12.85	5551	38.00	2J48	14.95	VR-78	.34	388A	2.95	724A	3.22	958A	.49
6AK6	.82	12AV7	.86	902P1	3.95	WL-672	13.25	2J61	36.20	VR-90/OB3	.81	417A	19.65	724B	3.22	959	.49
6AL5	.69	12BA6	.64	905	4.47	WL-677	24.00	2K23	23.95	VT-90(BR)29,90		434A	3.65	725A	8.95	991	.29
6AQ5	.72	12BA7	.86	913	4.99	WL-681/-5550	22.00	2K25	19.95	C100E	2.30	446A	.79	726A	14.50	1005	.24
6AQ6	.65	12BE6	.64	PHOTO CELLS		722A	3.75	2K28	19.95	100R	2.90	446B	1.95	730A	10.95	1201/7E5	.29
6AS7G	4.22	12C8	.59			872/873	6.95	2X2A	.79	100TH	10.25	450TH	19.70	731A	2.45	1203/7C4	.29
6AT6	.54	12SG7	.69	1P24	.29	884	1.35	3B22/EL-1C	1.65	WE-101D	1.65	450TL	32.50	WL-787	9.80	1294/1R4	.29
6AU6	.72	12SH7	.49	918	.88	885	1.20	3B23	4.75	WE-101F	3.62	451	1.75	800	1.88	1299/3D6	.29
6AV6	.55	12SJ7	.49	919	1.79	1665	.97	3B24	1.25	VR-105/-OC3	.72	471A	1.75	801A	.65	1823	.68
6BA6	.65	12SJ7	.49	921	.97	1904	8.85	3B27	1.29	WE-113A	1.32	SS-501	11.50	802	4.25	1613	.61
6BA7	.86	12SK7	.59	927	1.67	2050	.83	3C24	.44	WE-124A	3.80	503AX	1.47	803	4.87	1616	.97
6BE6	.65	12SL7GT	.69	931A	3.22	2051	.49	4-125A	24.95	VT-127A	2.40	504AX	1.47	804	8.95	1619	.19
6BG6G	1.72	12SN7GT	.79	1645	1.67	4-250A	24.75	VR-150/-0D3	.65	507AX	1.47	805	4.75	1624	.49
6BH6	.72	12SR7	.69			4A1	.58			527	9.75	807	1.40	1625	.19
6BJ6	.72	12SR7	.69							530	17.20	808	2.19	1626	.29
6C4	.21	28D7	.61							531	17.80	809	2.60	1629	.29
										532A	3.15	810	7.95		
										559	1.41	811	2.11		

SEND FOR OUR COMPLETE TUBE LISTING

MONTHLY BULLETINS

SEND IN YOUR NAME AND ADDRESS TO GET ON OUR MAILING LIST

All material brand new and fully guaranteed. Terms 20% cash with order, balance C. O. D. unless rated. All prices F.O.B. our warehouse, Phila., Penna.

LECTRONIC RESEARCH LABORATORIES

1021-A CALLOWHILL ST. PHILA. 23, PA

Telephones - MARKET 7-6590 and 6591

OUR JULY SPECIAL
2" Sun 0-50 milliamp meter. Square Bakelite case. 0-100 scale $1.69 ea.

PEAK ELECTRONICS CO.
188 Washington St., New York 7, N.Y.

GUARANTEED SURPLUS

HIGH WATTAGE ANTENNA RELAY
110/220 volt 60 cycle coil. D.P.D.T. rated at 5000 V. 15A. Heavy duty paralleled contacts. Sturdy construction. Isolantite insulation. Base 6" x 10½". Made by Monitor Controller $18.50

ANTENNA RELAY
Same Specs. as above but D.P.S.T. Base size 4½" x 10½" $12.95

PANEL METERS
BRAND NEW
Govt Surplus

2" Simpson 75-0-75 Microamps $5.95
2" Gruen 0-500 Microamps (Volt Scale) 3.25
2" GE 0-5 MA (Amp Scale) 1.95
2" Simpson 0-5 MA, Basic, Square 2.25
2" Westinghouse 0-10 MA 2.25
2" Simpson 0-20 MA (Amp Scale) 1.95
2" Sun 0-25 MA (0-100 Scale) 1.95
2" GE 0-50 MA 2.45
2" Gruen 0-50 MA 1.95
2" GE 0-1 Amp RF 1.95
2" Simpson 0-2 Amp RF (Square) 1.95
2" GE 0-4 Amp RF 1.95
2" GE 0-250 MA AC 3.50
2" Sun 0-20 Volts DC 1.75
2" Weston 0-20 Volts DC 2.45
2" GE 0-50 Volts DC (1000 ohms/volt) 2.95
2" Triplett 0-300 Volts AC 2.95
2" GE 0-30 Amps DC 1.95
2" GE 0-25 Volts AC, Linear (0-100 Scale) 3.50
2" Westinghouse 0-2 MA 3.75
2" Westinghouse 0-15 MA (Square) 3.75
2" Westinghouse 0-20 MA 3.75
2" Western Electric 0-50 MA 2.75
2" GE 0-200 MA DC 1.75
2" Triplett 0-75 Amps AC 2.95
2" GE 0-15 Volts AC 3.95
2" GE 0-1 Amp DC 3.95
2" Westinghouse 0-2 Amps DC 1.95
2" Westinghouse 0-1 MA (Basic) KV Scale 3.95
2" Westinghouse 0-750 Volts DC (1000 Ohms/Volt) 4.50
3" Weston 0-1 Volt DC 3.95

FILAMENT TRANSFORMERS
110 V 60 CY Pri. Cased.
2.5 Volt 10 Amp 3.49
2.5 Volt CT 21 Amps 4.75
5 Volt 6A, 6.3V 3A 2.49
2.5V CT 20A, 2.5V CT 20A 6.95

CHOKE BARGAINS
6 Henry 50 ma 300 ohms ..... 3 for $0.99
8 Henry 150 ma 140 ohms ..... .99
15 Henry 250 ma 72 ohms ..... .59
6 Henry 400 MA 97 Ohms 1.95

HEAVY DUTY RHEOSTAT
25 Ohms, 675 Watts Max. with Knob and Hardware $3.95
10 for $29.50

FILAMENT TRANSFORMER
6.3 volts at 12 amps. Primary 110 volts 60 cy. Size 3¼"H x 2⅞"W x 1"D. WT. 3½ lbs. As Illustrated.
$1.59 ea.

SENSITIVE RELAY
Breaks at 3 MA. Beautifully Constructed and delicately pivoted. Approx. 2000 ohms resistance. Housed in dustproof aluminum can. Plugs into 5 prong socket. Only ..... 99 ea.

500 MICROAMP RELAY
Delicately balanced, S.P.D.T., 10,000 ohm coil. Trips at .4 to .5 MA. 2⅝" x 2⅝" x 1⅞" high $2.95



General Electric Overload Relay. Electrical Reset 110 Volts 60 Cycle
Breaks at 640 Milliamps but easily adjustable for other currents. Ter-rific values at only $2.95
10 for 25.00

CERAMICONS
MMF: 1.5, 2, 3, 8, 10, 20, 22, 120, 500 ..... .05 ea.

LINK TEST SET
Type 21419. Contains two 3½" meters—a 75-0-75 microamp Galvanometer and a 0-1 MA multi-scale meter. Has tap switch for changing ranges. Ranges are as follows: 75-0-75 microamps, 1 MA, 2.5 MA, 50 MA, 25 volts, 500 volts. Ideal for balancing discriminators and general lab use. Housed in hard wood case with hinged cover. 10" x 8" x 4½". Only ..... $14.95 ea.

RESONANT RELAY
Available in frequencies of 240 cps and 442 cps. Enclosed in octal metal tube cover. Will control thyratron or slow acting relay $1.69

HIGH CURRENT MICAS
Type G4 Ceramic Case 3¾" High, 5" Diameter Tolerance 5% or Better.

CAP MFD	Amps 1 Mc	Amps 500 Kc	KV DC	Price Each
.05	60	42	4	$27.50
.1	70	50	4	29.50
.05	60	42	5	24.50
.037	45	35	6	26.50
.02	40	30	9	29.50
.02	55	38	10	29.50
.0117	40	27	14	24.50
.0075	39	27	15	24.50
.009	40	25	15	29.50
.00978	40	25	15	29.50
.01	43	28	15	29.50
.0025	23	15	20	29.50
.00315	26	18	20	29.50
.004	30	20	22	33.50
.0033	25	16	25	35.50

TYPE G3 4" HIGH, 5" DIAMETER

.0013	15	9	15	14.50

TYPE G2 3" HIGH 3½" DIAMETER

.00057	8	4	10	4.95
.01	25	17	7	6.95

TYPE G1 1½" High 2/16 DIAMETERS

.00024	4	2	6	3.95
.0047			6	5.95

SILVER MICA CAPACITORS
MMF: 10, 47, 50, 60, 340, 750, 780, 1000 ..... .09 ea.

Precision 15 Meg. 10% Accuracy Resistor, Non-inductive, 1 watt, hermetically sealed in glass .25 ea. 10 for $1.90

Thermal Time Delay Relay. 15 to 3 seconds, plugs into 4 prong Tube Socket Glass Enclosed 250 V ..... .75

PRECISION 1% W.W. RESISTORS
Ohms: 2K, 2500, 5K, 6500, 95K, 750K ..... .25 ea.

PLUG IN CAPACITOR
8 x 8 Mfd 600 volts DC, Oil filled. Plugs into standard 4 prong socket. 3¼ h x 3⅛ w x 1⅞ d $1.39

GENERAL ELECTRIC Type PBC Instantaneous Overcurrent Relay. Adjustable from 100 to 200 MA. Electrical and Manual Reset, 4 PDT, Reset 110 Volts 60 Cycles $7.95

BAKELITE CASED MICAS

MMF	VDC	Price	MMF	VDC	Price
D .001	600	$ .18	C .001	3 KV	$ .90
E .01	600	.26	C .002	3 KV	.95
D .02	600	.26	D .005	3 KV	.70
E .027	600	.26	C .005	3 KV	1.24
C .01	1 KV	.45	C .006	3 KV	1.50
C .017	1 KV	.55	D .002	5 KV	.70
D .02	1200	.35	C .0001	5 KV	.70
C .024	1500	.65	C .0005	5 KV	.85
C .033	1500	.75	C .0015	5 KV	1.60
C .015	2 KV	.90	C .003	5 KV	1.90
C .02	2 KV	.90	C .005	5 KV	2.50
D .002	2500	.45	C .002	6 KV	2.90
E .005	2500	.55	B .0017	5 KV	2.75
C .025	2500	1.25	B .0015	8 KV	2.90
			B .002	8 KV	6.50

MOSSMAN SWITCHES
4 Pole Single Throw $1.10
1 PDT, plus 6 PST 1.75

WESTINGHOUSE SELENIUM RECTIFIER
Hermetically sealed, Oil Immersed Full Wave Bridge. 30 Volts AC Input. 24 Volts at 2 Amps Output.
Size ..... $3.75 ea.

GUARDIAN LATCHING RELAY
Type RC 100. 110 volt 60 cycle coil. S.P.D.T. each impulse reverses the position of the contacts. Locks automatically. Contacts rated 1500 watts at 110V 60 cycles. Size 3" long, 2⅛" wide, 1½" high. Only ..... $1.95 ea.

MINIATURE HEADPHONES
250 ohms imp. Can be used for sound power Telephones, etc.
Type HS 30 ..... .69 ea.
HS 30 with Trans. ..... .89 ea.
Hi Imp. Transf. ..... .45

THORDARSON PLATE TRANS.
Pri 115-230 V, 60 cy, 625 Watts. Sec 2000, 2500, 3000, 3500 Volts Center Tapped. Type T15P22 $22.50

30 WATT WIRE WOUND RESISTORS
Ohms: 100-2500-3k-4k-4500-5k-5500
12k-18k ..... .15 ea. 8 for ..... .99

SCOPE AND FIL. TRANSFORMER

Pri. 115 volts, 60 cycles. Sec. 4400 volts RMS 4.5 MA., 5 volts, CT 3 amps. Fil. Ins. 15 KV. RMS test. Hermetically sealed. Has insulated plate cap for rectifier. Made by Raytheon, 4½ x 5 x 5½ ..... Only $3.95

MIDGET VARIABLE CONDENSERS
Steatite Insulation
15 MMF (HF 15) ..... .39
Dual 15 MMF (HF 15 D) ..... .69
250 MMF (MC 250 S) ..... .69

50 megohm 15 watt Resistor with mount. $1.49 each; 10 for $9.90
10 Meg 10 Watts ..... .49; 2 Meg 5 Watt ..... .35

OIL CONDENSERS

2	mfd 600 vdc	.39	10	mfd 2000 vdc	5.95
4	mfd 600 vdc	.59	2	mfd 4000 vdc	4.95
6	mfd 600 vdc	.79	1	mfd 5000 vdc	4.50
3.3	mfd 600 vdc	.79	1.1	mfd 7000 vdc	2.25
10	mfd 600 vdc	.89	2	mfd 6000 vdc	9.95
4	mfd 1000 vdc	.95	1	mfd 7500 vdc	6.50
10	mfd 1000 vdc	1.99	.01	.01 mfd 12 kv	
2	mfd 1500 vdc	1.25		dc	5.75
6	mfd 1500 vdc	2.95	.65	mfd 12,500 vdc	12.95
1	mfd 2000 vdc	1.45	2	mfd 15 kv dc	49.50
2	mfd 2000 vdc	2.25	.61	mfd 15 kv dc	15.95
8	mfd 2000 vdc	4.95			

WIRE WOUND RESISTORS
5 Watt type AA, 20-25-50-200-470-2500-4000 ohms ..... $.09 ea.
10 watt type AB, 25-40-84-400-470-1325-1000-2000-4000 ohms ..... .15 ea.
20 watt type DG, 50-70-100-150-300-750-1000-1500-2500-2700-5000-7500 10000-16000-20000-30000 ohms ..... .20 ea.

ADJUSTABLE RESISTORS
20 Watt: 1, 5, 50 Ohms ..... .25
50 Watt: 80, 100, 500 Ohms ..... .35
75 Watt: 40, 80, 100, 150, 200 Ohms ..... .39
100 Watt: 20, 50, 75, 120, 180 Ohms ..... .49
150 Watt: 50, 100 Ohms ..... .59

W. W. POWER RHEOSTATS
25 Ohms 25 Watt ..... .39
250 Ohms 50 Watt ..... .59
300 Ohms 50 Watt ..... .59
Dual 200 Ohms 50 Watt ..... .79
100 ohm 100 watt ..... .99
200 ohm 100 watt ..... .99

MISCELLANEOUS BARGAINS

.02 400 volt dc tubulars	15 for	.99
2mfd 250 volts ac oil cond	6 for	.99
10 meg 10 watt resistor	2 for	.99
Heineman 25 amp 110 volt ac ckt breaker		1.19
Ceramicon .0005 mfd	20 for	.99
.01 600 volt dc pigtail micas	10 for	.99
.001 600 volt dc pigtail micas	15 for	.99
.006 600 volt, pigtail micas	12 for	.99
Butterfly cond. 2 to 11 mmf ball brngs	3 for	.99
CD type 4 micas .001 600vdc	10 for	.99
250 mmf variable cond. (mc250a)		.59
10,000 ohm potentiometers	6 for	.99
500 ohm 100 watt non-induct. Resistor		.99
250 ohm 100 watt non-induct. Resistor		.99
16 mfd 450 volt electrolytic (EB9160)	3 for	.99
Var. cond. 150 mmf .07 spacing	2 for	.99
Variable ceramicon 20 to 125 mmf type 823	5 for	.99
Western Electric silver varble .5 to 2.5 mmf	8 for	.99
50 K 1% W. W. Resistors, Precision		.14
.55 at 16 KV plus .25 at 8 KV Oil Cond		3.95
.1 MFD 7500 VDC Oil Cond		.89
.05 MFD 7500 VDC Oil Cond		.75
2 MFD 330 VAC Oil Cond		.69
Meter Multiplier 2 MEG. 1/2 of 1% 2KV		1.49

Tremendous stocks on hand. Please send requests for quotes. Special quantity discounts. Price f.o.b. N.Y. 20% with order unless rated, balance C.O.D. Minimum order $3.00

PEAK ELECTRONICS CO.
188 Washington St., New York 7, N.Y.

Phone Co 7—6486 —6443
DEPARTMENT EA

Reliance Specials

CAPACITORS

POSTAGE STAMP MICAS

MMF	MMF	MMF	MMF	MFD
8.2	62	370	800	.0047
10	68	390	910	.005
15	75	400		.006
20	72	430	MFD	.007
22	90	500	.001	.0068
24	100	510	.0012	.0075
25	110	560	.0013	.0082
39	150	600	.00136	.009
40	160	620	.0015	.01
47	200	650	.002	
50	240	680	.0026	
51	250	700	.0027	
56	300	750	.003	
60	330	820	.0033	

Price Schedule

8.2	MMF to .001 MFD	5¢
.0012	MFD to .002 MFD	7¢
.0026	MFD to .009 MFD	14¢
.01	MFD	18¢

SILVER MICA

MMF	MMF	MMF	MMF	MFD
10	85	260	488	.0023
24	100	270	500	.0024
30	110	300	510	.0027
39	115	325	525	.003
40	120	330	560	.0033
45	125	360	680	.0039
50	150	370	700	.004
51	180	390	750	.0047
60	200	400	820	.005
62	208	430	MFD	.0051
66	225	450	.001	.006
68	240	466	.0013	.0082
75	250	470	.0022	.01

Price Schedule

10	MMF to .001 MFD	10¢
.0012	MFD to .0027 MFD	20¢
.003	MFD to .0082 MFD	50¢
.01	MFD	65¢

OIL FILLED

MFD	V.D.C.	Price
.25	20,000	$16.75
.4	10,000	4.75
.03	16,000	1.95
.1	7,500	1.55
1-1	7,000	1.55
.02-.02	7,000	1.25
1	6,000	5.25
.3	4,000	4.35
.2	4,000	2.25
.25	3,000	1.10
.8	2,000	5.75
4	2,000	3.95
1	2,000	.95
.3	1,000	.80
.2	1,000	.65
.10	600	1.00
.4	600	.60
.2	600	.39

WW PRECISION RESISTORS, 1% OR BETTER

¼ WATT—25c

6.68Ω	12.32Ω	16.37Ω	123.8Ω	414.3Ω
10.48	13.02	62.54	147.5	705
10.84	13.52	79.81	220.4	2193
11.25	13.89	105.8	301.8	10,000
11.74	14.98		366.6	59,148

½ WATT—25c

250Ω	3.53Ω	75Ω	270Ω	4,000Ω	8,000Ω
334	3.04	97.8	295.3	4,451	8,500
502	11.1	125	400	5,000	14,825
537	13.15	180	723.1	5,900	15,000
627	46	210	2,500	6,500	15,750
76	52	235	2,850	7,000	17,000
1.01	55.1	260	3,427	7,500	30,000
					100,000

1 WATT—30c

1.01Ω	5.21Ω	1.2302	9.0002	65.0002
2.58	10.9	3,300	18,000	70,000
3.39	270	7,000	55,000	

1 WATT—40c

120,000	128,0002	320,000	522,0002
125,000	130,000	470,000	680,000
	160,000		700,000

1 Megohm—1 Watt 1%—65c; 5%—40c

100 pieces—10% off; 1,000 pieces—20% off

SELSYNS

115 V., 60 Cyc.
#C78248
3⅛" dia. x 5⅛" long
$7.95 pair

Mounting Brackets — (Bakelite) for selsyns, and differentials shown above..... 35c pair



DIFFERENTIAL

115 V., 60 Cyc.
#C78249
3⅛" dia. x 5⅛" long
$2.25 ea.

Used between two #C78248's as dampener. Can be converted to 3600 RPM Motor in 10 minutes. Conversion sheet supplied. (Converted..... $3.00)



TAIL END RADAR

APS-13—like new, complete with tubes..... $14.95

CERAMICONS

2 MMF	38 MMF
5.6	39
10	45
12	82
15	150
20	680

$4.50 per hundred

CHOKE

400 MA
12 Hy.
90 OHM
HIGH VOLT TEST



$3.85
10 for $34.00

ALLEN SET SCREWS

4-40 x 1/16 — 8-32 x 1/8 — 8-32 x 1/4
4-40 x 1/8 — 8-32 x 1/4 — 8-32 x 3/8
ALL SIZES..... $1.50 per 100

GLYPTAL CEMENT 1 qt..... 75c

SELENIUM RECTIFIERS HALF WAVE

117 V.A.C. IN. 110 V.D.C. OUT @ 75 Ma..... $ .49
117 V.A.C. IN. 110 V.D.C. OUT @ 100 Ma..... .72
117 V.A.C. IN. 110 V.D.C. OUT @ 400 Ma..... 1.51

TIME DELAY RELAY

Raytheon CPX 24166 KS 16193-60 Sec.
• 115 V., 60 Cycle • Adj. 50-70 Seconds • 2½ second receiving time—spring return • Micro-switch contact, 10A. • Holds ON as long as power is applied • Fully cased •
ONLY..... $4.50

DELAY NETWORK—ALL 1400Ω

T 113—Approx. 1.2 micro sec. delay..... 85¢
T 114—Approx. 2.2 micro sec. delay..... 85¢
T 115—Similar to T 114 with tap brought out..... 85¢

3AG FUSES

AMP	Per 100	AMP	Per 100	AMP	Per 100
1/16	$4.00	1½	$2.50	5	$2.50
⅛	4.00	2	2.50	10	3.00
¼	4.00	2½	2.50	15	3.00
½	2.50	3	2.50		

Fuse Holder—for 3AG Fuse..... 18¢

4AG FUSES

AMP	Per 100	AMP	Per 100	AMP	Per 100
1/10	$4.00	2	$2.00	10	$2.50
1/4	3.50	3	2.00	15	2.50
1/2	3.50	3.2	2.00	20	2.50
1	2.00	5	2.00	25	2.50
				30	2.50

Fuse Holder—Little fuse for 4AG Fuse..... 18¢

MICRO AMMETER 0-500

2" round Basic move. 500 micro-amps. NEW—Guaranteed. Original box..... $3.85 ea.—10 for $35

Wrapped—BALL BEARINGS—New

Mfg.	ID	OD	Width	Price
Fafnir 33K5	3/16"	1/2"	5/32"	.25
N.D.38	5/16	7/8"	9/32"	.45
Fafnir K8A	1/2"	1 1/8"	5/16"	.60
N.D. 5202L13M	1/2"	1 3/8"	1/2"	1.00
Fafnir 7308W	1 37/64"	3 9/16"	5/16"	2.00
SKF466430	6"	8"	1"	5.00
SKF170645	3 11/32"	4 1/8"	7/16"	1.50
Fafnir 545	2 1/16"	2 5/8"	15/32"	1.00

NEEDLE BEARINGS

B108	1/2" wide	5/8"	13/16"	30¢
GB34X	1/4" wide	3/16	11/32"	25¢

SOUND POWERED HANDSET

Brand New! TS-10
Includes 6 ft. cord & spring clips
$8.92 ea. — $17.60

POWER RHEOSTATS

STANDARD BRANDS

25 WATT		25 WATT		123Ω	½"	79¢
Resist.	Shaft	5,000	½"*	1,250	½"	89
10Ω	¼" 49¢		88¢	2,000	½"	89
145	¼" 49	50 WATT		150 WATT		
	with switch	8Ω	½"*	79	8Ω	½" $1.99
250	½" 59	20	½"	79	*S.D. Screw Driver Slot	
370	½" 59	90	½"	79		

2J1G1 SELSYNS (Brand New)

400 Cyc. Use on 24V. or 110 VAC..... $1.65 each

FILAMENT TRANSFORMER

Pri., 115 V., 60 Cyc.—Sec. 5V., 115 A. 6000 volt insulation..... $9.95 each

FILAMENT TRANSFORMER

Amertran Type WS
For High Voltage Rectifiers. PRI. 115V., 50/60 Cycle.
SEC. 5V., C/T @ 10 Amp.
35 KV R.M.S. Test 12 KV D.C. Operating. Uses 872A Tube or other tubes.
NEW OVERSEAS PACKED
872-A Tube.....
$10.95
$1.88

CARBON RESISTORS

Large stock on hand. Send list of your requirements.
Write for Monthly Bulletin

COAXIAL CABLE

RG 8/U 52 OHM

$55.00 per 1,000 feet

	Ohm	Price per 1,000 ft.		Ohm	Price per 1,000 ft.
RG 5 U	53.5	$70.00	RG 27 U	48	$290.00
RG 7 U	97.5	60.00	RG 29 U	53.5	50.00
RG 8 U	52	55.00	RG 34 U	71	175.00
RG 9 U	51	135.00	RG 39 U	72.5	150.00
RG 10 U	52	125.00	RG 41 U	67.5	575.00
RG 11 U	75	100.00	RG 54 U	58	65.00
RG 12 U	75	190.00	RG 54 AU	58	75.00
RG 13 U	74	125.00	RG 55 AU	53.5	60.00
RG 18 U	52	450.00	RG 57 U	95	100.00
RG 20 U	52	450.00	RG 58 U	53.5	50.00
RG 22 U	95	110.00	RG 59 U	73	60.00
RG 24 U	125	240.00	RG 62 U	93	50.00
RG 25 U	48	575.00	RG 74 U	52	250.00
			RG 77 U	48	100.00

Less than 1,000 ft. add 25%

COAXIAL CABLE CONNECTORS

Angle Adapter	Plug	Hood	Socket
15¢	28¢	9¢	28¢
M-359	PL-259A	83-1H	SO-239
83-1AP	83-1SPN		83-1R

Adapter for PL-259 A for use on small coax, 12¢ each..... $10.00 per 100

83-1SP	$.28	83-22R	.48	UG27 U	.60
83-1J	.80	83-22SP	.60	UG59 U	.60
83-1RTY	.45	UG13 U	.60	UG61 U	.60
83-1T	1.12	UG21 U	.60	UG85 U	.62
83-1F	1.12	UG22 U	.60	UG87 U	.68
83-22AP	.85	UG24 U	.60	UG167 U	3.00
83-22F	.88	UG25 U	.60	UG281 U	.60

HAYLON TIMING MOTOR

4 R.P.M., 115V., 60 Cycle..... $1.79

VOLTMETER—0—300 VDC

2" Round; basic movement, 1 ma. New. Guaranteed. Original Box..... $3.50 ea.—10 for $32.50

#18 SHIELDED WIRE—STRANDED

Single Conductor—100 ft..... $1.95 1,000 ft..... $12.50
Two Conductor—100 ft..... $2.95 1,000 ft..... $19.50

PULSE TRANSFORMERS

X 124 T2, UTAH, marked 9262, 9340, small gray can..... $1.50

D161310, 50 Ma. to 4 Ma. 1½" dia. x 1⅝" high. 120 to 2350 ohms..... $1.50

332-7178. Spec. 10, 111 Chicago Trans. equivalent to 9262 (above)..... $1.00

D-166638 W. E. Permalloy core, Semi-toridal windings..... $4.25

KS9800, Ratio, 1:1:1, 2:1, Freq. range 380 to 520 CPS..... $3.50

D106173, W.E. Freq. resp. 10KC to 2 MC..... $9.00

800 KVA G.E. K2731, 28000 Volt pk. output..... $28.50

Riflin', one microsecond pulse width..... $4.00

CARBON MIKE

T-17. Slightly used, guaranteed, 5 ft. cord & PL 68..... 60¢

JONES BARRIER STRIPS

Type	Price	Type	Price	Type	Price
2-140Y	$.05	5-141	$.20	15-141Y	$.77
2-140¼ W	.10	5-141Y	.27	17-141Y	.87
3-140¼ W	.15	5-141⅛ W	.27	3-142	.15
4-140	.13	6-141⅛ W	.32	5-142	.24
8-140W	.33	7-141	.27	5-142⅛ W	.34
10-140⅛ W	.40	7-141⅛ W	.37	6-142	.26
13-140	.37	7-141Y	.37	6-142⅛ W	.40
2-141	.60	8-141⅛ W	.42	6-142½ W	.60
3-141⅛ W	.17	9-141⅛ W	.47	8-142⅛ W	.64
3-141W	.17	9-141Y	.47	10-142⅛ W	.64
4-141W	.22	10-141Y	.83	2-150	.26
4-141⅛ W	.22	13-141	.67	5-150	.49
4-141Y	.22	13-141⅛ W	.67	6-150	.52
				6-150	.75

Gear Assortment..... $6.50
Experimenters dream, 100 pieces, many stainless steel.

PRECISION CONTROLS

6 WATT

20,000	Muter	314A	*1.70
20,000Ω	GR	314A	2.50
6,000	De Jur	260	1.70
6,000	Muter	314A	1.70
5,000	Muter	314A	2.80
5,000	GR	214A	1.40
2,000	De Jur	260	1.70

25 WATT

100K	GR	433A $4.95

4 WATT

500Ω	Centralab	48-501	$.90
50	De Jur	292	.75
50	GR	301	1.10
25	GR	301	1.10
20	De Jur	292	.75
12	GR	301	1.10

12 WATT

10,000	Muter	471A	$2.00
10,000Ω	De Jur	271T	2.00
5,000	De Jur	271T	2.00

7 Terminal Bakelite tie point..... 35 for $1.00

VERNIER DIAL (From BC-221)

2 ⅝" Dia. 0-100 in 360°. Black with silver marks. Has thumblock..... 85¢

Minimum Orders $3..... All orders f.o.b. PHILA., PA.

RELIANCE MERCHANDIZING CO.

Arch St. Cor. Croskey Phila. 3, Pa. *Telephone Rittenhouse 6-4927*

IMMEDIATE DELIVERY • LOW PRICES • FULLY GUARANTEED

BROWN TELEPLOTTER RECEIVER



Model 791X1R

115 volt 60 cycles

Contains a pen driven by two balancing motors which writes on rear of a translucent chart. Pen arm position is in terms of two co-ordinates supplied balancing motors thru two amplifiers. Originally intended for recording plotted or written data from central plotting board. Writes at one half scale on 18 in. chart. Discriminator input circuit designed to operate unit as function of two varying R.F. frequencies varying about mean of approx. 450 KC. Further data on request. (Shipping weight 435 lbs.)

Price $375.00

LP-21-LM Compass Loops

Motor driven loop enclosed in graphitted zeppelin housing includes Autosyn transmitter. Stock #SA-99.

$14.50 each

G.E. Servo Amplifier—2CV1C1. Aircraft amplidyne control amplifier, 115 volt 400 cycles. Two channel. Uses 2 6BN7GT and 4 6V6GT tubes. Supplied less tubes. Stock #SA-168. **Price $9.50 each.**

D.C. MOTORS

Universal Electric

W.E. KS-5603-1-02,-28 v. d-c 0.6 amps. 1/100 hp. 4 lead shunt. Stock #SA-233..... **Price $3.75 each**

12 V.D.C. Motor

John Oster B-9-2

1.4 amps.

5400 rpm.

1⅛" Diam. x 3¾" Lg. Spline shaft. C.W. rotation. Stock #SA-46. **Price $1.95 each**

DELCO CONSTANT SPEED MOTOR A-7155

1/30 hp. 27.5 v d-c 3600 rpm. Cont. duty. 3¼" diam. x 5⅛" lg. ⅜" shaft extension. 5/32" diam. 4 hole base mounting. Stock #SA-94. **Price $4.75.**



Delco 5009235 Constant Speed DC Motor, 27 v. d-c 120 rpm. Governor controlled. Stock #SA-249. **Price $3.95 each.**

General Electric 2 RPM Motor. Type 5BA19FJ221. 27 v. d-c @ 0.6 amps. 10 lb/in torque at 2 rpm. Shunt wound. D-C noise filter. Stock #SA-274. **Price $6.75 each.**

Synchron 10 RPM D.C. Timing Motor—24 V. Hanson Mfg. Co. Stock #SA-110. **Price $3.75 each.**

General Electric Type 5BA10AJ52C 145 rpm. 27.5 volt D-C motor. 0.68 amps. 14 oz./in. torque. Shunt wound four lead reversible. Stock #SA-318. **Price $4.75 each.**

D-C ALNICO FIELD MOTORS

Delco 5069456. 27.5 volts, 10,000 rpm. 1" x 1" x 2" lg. Stock #SA-236. **Price $6.75 each.**

Other models also available

MICROWAVE ANTENNA

AS-217-APG 15B, 12 Cm. dipole and 12 inch Parabola housed in weatherproof Radome 16" dia. 24 v. DC spinner motor for conic scan. Stock #SA-95. Shipping wt. 70 lbs.

Price $6.95 ea.

INVERTER SPECIALS 400 Cycles

Pioneer Type 12128-1-B. 27.5 volts D-C input. 26 volts 400 cycle 1 phase out. 6.0 V.A. (Current manufacture) Prices on Request

General Electric 5D21NJ3A — Input 28 volts DC at 35 amps. Output 110 volts 400 cycles. 485 V.A. at 0.90 P.F. Weight 15 lbs. Stock #SA-41. **Price $12.50 each**

General Electric 5AS131NJ3 — Input 26 volts DC at 100 amps. Output 115 volts 400 cycles. 1500 V.A. 0.8 PF. Stock #SA-246. **Price $19.50 each**

SYNCHROS

Navy Types

1G, 1F, 1CT, 5G, 5F, 5CT, 5DG, 5HCT, 5SF, 5HSF, 5SDG, 6DG, 6G, 6DG, 7G, etc.

Prices on Request

SERVO AMPLIFIER

Minneapolis Honeywell 115 v. 400 cycle unit. For use with SA-268. Model G403ATCA3. Designed for use with A-C error signal from bridge circuit. Stock #SA-269A. **Price $8.50.**

MOTOR SPECIALS

G.E. 5BA25AJ31A and 32A. Dual field reversible gear head shunt wound. 24 v. @ 2.9 amps. 9 rpm. 10 min. time rating. Aircraft type. Magnetic brake. Stock #SA-295. **Special Price $19.50 each.**

G.E. 5PS56HC18 — Split field series reversible motor. 60 v. d-c at 1.4 amperes. 5500 rpm. 3" diam. x 5" lg. Ideal for servo applications. Stock #SA-273. **Price $8.75 each.**

OSTER PM MOTOR

Alnico Field

27.5 v. d-c. Can also be used as rate generator. #SA-281. **$3.75 each**

Gyro and Housing Mirror Assembly. For K-14A sighting head. Gyro stabilized mirror assembly. Stock #SA-294. **Price $9.75 each.**

AC-SERVO MOTORS

Pioneer Type CK-3. 26 v. 400 cycles fixed phase, var. phase 45 v. max. 40:1 gear reduction. Stock #SA-97A. **Price $6.50 each.** Also available less gear train. **Price $4.25 each.** Stock #SA-97.

PIONEER CK-17

400 cycle 2 phase, 26 v. fixed phase, 45 v. max. variable phase. Built in gear reduction. Output shaft speed approx. 4 rpm. Stock #SA-287. **Price $12.50.**

FORD SERVO MOTOR

115 volt 60 cycle two phase low inertia motor. 15 watts output. BuOrd. 207927. Stock #SA-291. **Price $49.50 each.**

MINNEAPOLIS-HONEYWELL

Type G303AY2CA4 Servo Motor

115 v. 400 cycles. Built in gear reduction. 50 in/lb. torque. Stock #SA-248. **Price $6.75 each.**

SAWTOOTH POTENTIOMETER

W.E. KS-15138



Type RL-B-R. 100 ohm element. Non linear ring gives linear output with CRT deflection coil load. Cont. rotation. 2 brushes 180 degrees opposed. 2 taps 180 degrees opposed. Stock #SA-248. **Price $5.50 each.**

400 Cycle Generators

Homelite 18A120D28-1 400 cycle out at 1 phase 115 v. 39 amps. Also a d-c output of 28 v. and 17.9 amps. **Special at $175.00 each.**



G. E. 5ASB21JJ3. 400 cycles out at 115 volts 7.3 amps. Ideal for lab. 6" lg. x 6" diam. 8000 rpm. Stock #SA-292. **Price $79.50 ea.**

PRECISION AUTOSYN



Pioneer Type AY-150 Control Autosyn. Precision type. 26 v. 400 cycle. Stock #SA-297. **Special low price $14.50 each.**



A-5 Autopilot Indicator

Autosyn Type Pilot Indicator for A-5 Autopilot. 26 v. 400 cycles. Stock #SA-299. **Price $12.50 each.**

ANTENNA TILT INDICATOR

D-C Selsyn type tilt indicator. G.E. 8DJ29AAK. 24 volt. Stock #SA-296. **Price $2.75 each.**

Prices F.O.B. Paterson
Phone ARmory 4-3366
Teletype PAT. 199
WRITE FOR LISTING

Servo-Tek products co.
4 Godwin Ave. Paterson, N. J.

SPECIALISTS IN FRACTIONAL HORSE POWER MOTOR SPEED CONTROL

OUTSTANDING VALUES NOW AVAILABLE

- AMPLIFIERS
- AN CONNECTORS
- CABLE
- CAPACITORS
- CHOKES
- CIRCUIT-BREAKERS
- COAX-CONNECTORS
- COILS
- CORDS
- CRYSTALS
- DELAY LINES
- FILTERS
- FUSES
- HANDSETS
- INVERTERS
- JACKS
- KLYSTRONS
- KNOBS
- MAGNETRONS
- MAGNETS
- MICROPHONES
- METERS
- MOTORS
- POTENTIOMETERS
- POWER PLANTS
- POWER SUPPLIES
- PROJECTION LAMPS
- RECORDERS
- RESISTORS
- SELSYNS
- SCOPE ACCES.
- SHOCK MOUNTS
- SOCKETS
- SWITCHES
- TELEPHONE EQUIP.
- TEST EQUIPMENT
- TRANSFORMERS
- TRANSMITTERS
- TUBES
- WAVEGUIDE
- WAVEMETERS
- WIRE

RADIO HAM SHACK broadcasts its sincere thanks to all its old friends and a hearty welcome to new ones.

TO OUR OLD FRIENDS. It is not news that **RADIO HAM SHACK** is the house of value. They know that our mass purchasing policy of vast quantities of surplus equipment and the maintenance of one of the largest stocks of radio tubes and electronic components in the United States enables us to offer them low, low prices that are difficult to beat anywhere in the world.

TO THE NEW FRIENDS we should like to meet, we extend our services and facilities to bring them the best of equipment at the lowest prices. Deal with us in confidence, secure in the knowledge that our tubes, components and equipment are of standard manufacture, rigidly inspected and securely packed to insure that only first **QUALITY, BRAND NEW MERCHANDISE** reaches you.

Send for our monthly value packed flyer. Your requirements for immediate quotation will receive a prompt reply.

REMINDER—RADIO HAM SHACK is a **BIG BUYER** of tubes, components and equipment. Submit your surplus stock inventory to us for fast action. No lot too large—none too small.

WIRE! WRITE! today for latest prices. **SPECIAL DISCOUNTS** for large quantity purchases.

OVERSEAS BROADCAST!! WE SHIP ALL OVER THE WORLD!! SPECIAL HANDLING BY OUR EXPORT DIVISION INSURES SWIFT, CHEAP DELIVERIES TO ALL DESTINATIONS. CORRESPONDENCE IN ALL LANGUAGES. CABLE ADDRESS: HAMSHACK—NEW YORK.

TUBES!! BRAND NEW! STANDARD BRANDS! NO SECONDS! COMPARE! TUBES!!

OA2/VR75	$1.05	2C22	$39.50	227A/8C27	$2.69	816	.99	9006	.18	6B3	$1.47	6Z4	.77	6SN8GT	.97	12BR7	.69
OB2/VR90	.65	2C23	2.19	249C	1.49	826	.39	C1JA	9.95	6E4	.87	6A8	.77	6SN7GT	.84	1223	.69
OC2/VR105	.69	2C24/24G	.35	250R	8.95	828	10.95	C5B	6.95	6J4	.39	6A4LA	1.00	6SQ7	.65	14A4	.79
OD2/VR150	.65	2C30/809	1.89	250TH	18.95	829	7.65	C8A	7.95	1A3	.69	6A6	.79	6SL7GT	.52	14A7	.83
1B21/	2.95	2C31/C1B	2.98	250TL	18.95	830B	3.19	C9J	3.65	1A4	1.49	6A7	.69	6SK7	.69	14B8	.67
1 GL471A	2.87	2C45	12.95	274B	2.69	832A	6.89	C100D	.98	1A4P	.97	6A8	.75	6ST7	.72	14F7	.66
1B22	2.87	3CP1	1.39	298A	2.98	833A	33.95	CK502AX	2.25	1A6GT	.49	6AB7	.79	6SU7GTY	1.25	14F8	.79
1B23	8.75	3DP1	3.79	304A	2.95	836A	1.97	CK503AX	1.95	1A6	.79	6AC7	.74	6SV7	.77	14H7	.83
1B24	4.59	3DP1-82A	2.79	300B	9.95	837	1.19	CK505AX	2.25	1A7GT	.67	6AD7G	1.00	6TT0	.89	14J7	.87
1B26	2.79	3D21A	.98	304TH	3.49	838	1.98	CK506AX	1.95	1AB5	.89	6AF6G	.79	6U8G	.65	14N7	.65
1B27	7.95	3EP1	2.89	304TL	1.29	841	.29	CK507AX	1.98	1B2/8016	1.19	6AQ5	.69	6U8GT	.65	14Q7	.83
1B29	.79	3EP9	8.95	305A	24.95	843	.29	CK512AX	2.25	1B4	1.19	6AQ7	.69	6U7G	.69	14R7	.67
1B32	1.89	3FP7	.97	307A	3.69	845	4.25	CK571AX	8.45	1B5/25S	.89	6AH6	1.29	6V6	.89	19	.69
1B36	3.95	3GP1	5.95	310A	.29	851	12.95	CK605	.89	1C5GT	.89	6AJ5	.79	6V6GT	.87	24A	.69
1B38	34.50	3HP7	3.95	327A/8C27	2.75	860	14.95	CK1006	.98	1C6	.89	6AK5	.85	6W4GT	.63	25L6GT	.83
1D21	2.75	4-65A	14.21	331A	12.95	861	9.95	CK1007	.89	1C7G	.89	6AL5	.79	6W7G	.77	25Z5	.64
1N21	.49	4-125A	26.95	350A	1.98	864	.29	E1148	.29	1D5GP	.97	6AL5	.59	6X4	.57	25Z6GT	.63
1N21A	.89	4-250A	34.25	350B	1.39	865	.79	EF50	.39	1D7G	.85	6AQ5	.69	6X5GT	.67	26	.69
1N23B	1.39	4AP10	1.98	368A/N	4.95	866A	1.05	F123A	7.95	1D8GT	.95	6AQ6	.89	6Y6G	.87	27	.63
1N22	.98	4B22	9.98	371B	.49	866JR	1.05	F127A	15.95	1F4	.75	6AR5	.85	6C7G	.98	28D7	.85
1N23	.79	4B24	1.98	388A	.47	869B	26.50	F128A	69.50	1F5G	.75	6AT6	.64	6ZY5G	.89	30	.87
1N23A	.79	4B26	7.95	393A	3.49	872A	1.12	F606	27.50	1G4GT	.69	6AU6	.59	7A4/XXL	.49	31	.84
1N23B	1.89	4B28	4.49	394A	3.65	874	.39	F660	49.50	1G6GT	.65	6AV6	.69	7A5	.99	32	.88
1N27	1.29	4B28	2.47	417A	9.95	876	.79	F862A	397.50	1H7G	1.15	6B4G	.89	7A7	.83	32L7GT	.99
1N34	.82	4B32	9.95	446A	1.25	878	1.98	FG17	2.49	1H4G	.58	6B6G	.79	7AG7	.72	83	.69
1P23	2.49	4C35	19.28	446B	1.79	884	1.19	FG32	4.95	1H5GT	.54	6B7	.87	7B4	.83	807	.87
1P24	.59	4D22	9.95	450TH	19.95	885	1.19	FG32	4.95	1H6GT	.87	6B8G	.87	7B6	.67	35/51	.87
1P26	2.85	4D32	9.95	450TL	44.50	902	3.39	FG33	7.95	1J6G	.75	6BA6	.55	7B6	.54	35A5	.88
1R21	2.95	4E27/		527	8.95	905	2.49	FG57	12.95	1L4	.49	6BE6	.52	7B7	.89	35B5	.88
2AP1	3.89	257B	12.45	559	.98	906	4.98	FG81A	3.29	1LA4	.79	6BF6	.87	7C4	.54	35C5	.89
2C21/RK33	.26	5AP1	2.95	575A	11.95	918	1.49	FG105A	8.95	1LA6	.89	6BG6G	1.47	7C5	.48	35L6	.82
2C22/7193	.15	5AP4	2.95	631P1	3.75	919	1.95	FG172	13.95	1LB4	.89	6BH6	.59	7C7	.89	35W4	.39
2C26A	.15	5BP1	2.29	700A	19.95	923	.79	FG180	13.95	1LC5	.89	6BJ6	.97	7E5	.67	35Y4	.87
2C34/RK34	.22	5BP4	2.39	700B	19.95	927	1.25	GL146	4.95	1LC6	.79	6C4	.57	7E6	.54	35Z3	.87
2C39	17.95	5CP1	1.29	700C	19.95	930	.98	GL434A	2.69	1LD5	.79	6C5	.67	7E7	.62	35Z4	.44
2C40	6.95	5CP7	2.95	700D	19.95	931A	2.98	GL471A	2.85	1LE3	.69	6C6	.57	7F7	.89	35Z5	.89
2C43	7.95	5D21	24.45	701A	3.95	954	.16	GL861	89.50	1LE	.79	6C8G	.64	7H7	.89	36	.87
2C44	.98	5FP7	1.19	702A	2.69	955	.25	GL867	69.50	1LH4	.79	6D6	.44	7K7	.89	37	.85
2C46	6.95	5GP1	2.98	703A	1.89	956	.25	HF100	6.95	1LN5	.67	6D8G	.79	7L7	.69	38	.87
2C51	8.95	5JP1	39.50	704A	1.49	957	.22	HF115A	14.95	1N5GT	.58	6E5	.69	7N7	.67	39/44	.77
2D21	.89	5JP2	8.95	705A	.49	958	.22	HF200	14.95	1P5GT	.67	6F5	.57	7Q7	.59	41	.69
2D29	1.39	5JP4	39.50	706B	18.95	959	.38	HF300	17.45	1Q5GT	.67	6F6	.57	7R7	.69	42	.69
2E22	1.19	5J23	12.95	706CY	18.75	991/NE16	.24	HY114B	.69	1R4	.59	6F8GT	.57	7V7	.87	43	.69
2E25	3.29	5J29	12.95	706PY	47.50	1613	.49	HY115	.89	1R5	.69	6F7	.69	7W7	.79	45	.83
2E30	2.39	5J30	47.50	706GY	47.50	1614	1.35	HY615	.19	1S4	.59	6F8G	.87	7X7	.79	45Z3	.87
2J21A	7.95	5LP1	12.95	707B	14.95	1616	.49	KU610	6.95	1S5	.49	6G6G	.69	7Y4	.67	45Z5	.85
2J22	7.95	5MP1	9.98	708A	3.89	1619	.17	KU627	6.95	1T4	.59	6H6	.39	7Z4	.57	46	.62
2J26	6.95	5NP1	6.98	715A	.79	1624	.67			1T5GT	.49	6H6GT	.39	12A	.57	47	.69
2J27	12.75	5C21	19.69	714AY	3.89	1625	.19	ML100	27.50	1U4	.59	6J5	.47	12A6	.57	49	.85
2J30	49.50	6P4	8.59	715A	5.49	1626	.25	ML101	49.50	1V	.57	6J5GT	.39	12A7	.69	50	1.39
2J31	8.49	6J4	6.49	715B	6.95	1629	.19	NX408U	.39	2A3	.87	6J6	.77	12AH7GT	.69	50A5	.69
2J32	12.95	7BP7	9.95	715C	19.95	1630	.49	REL21	.98	2A4G	1.07	6J7	.67	12AT7GT	.80	50B5	.69
2J33	18.75	9GP7	8.95	717A	.49	1631	.98	RK59	1.49	2A5	.69	6J7GT	.65	12AT6	.64	50L6GT	.83
2J34	18.95	9JP1	6.95	721A	1.98	1632	.69	RK60	.42	2A6	.79	6K5GT	.79	12AT7	.79	50Y6	.87
2J35	97.50	9LP1	19.95	723A/B	12.95	1633	.79	RK61	24.50	2A7	.79	6K6GT	.64	12AU6	.57	53	.87
2J37	12.95	9LP7	1.98	724A/B	2.98	1634	.98	RK72	.59	2V3G	.69	6K7	.49	12AU7	.67	56	.48
2J38	11.95	10BP4	19.69	725A	6.45	1635	1.09	RK73	.89	2X2	.57	6K8	.79	12AV6	.54	57	.48
2J39	19.95	10Y	.19	726A	6.75	1636	1.98	RK92	2.89	2X2A	.65	6L6GT	.79	12BA6	.55	58	.48
2J40	24.50	12DP7	14.95	726B	29.50	1638	.45	RX120	8.95	3A4	.54	6L6	1.08	12BE6	.55	59	.48
2J46	49.50	12GP7	12.75	726C	49.50	1644	.98	V70D	7.35	3A5	.79	6L6G	.99	12C8	.34	70L7	.99
2J48	12.75	12HP7	13.95	730A	9.95	1654	2.48	VCR138	8.95	3A8	1.39	6L6GA	.85	12F5GT	.58	71A	.89
2J49	29.50	12LP4	24.95	730TL	69.50	1655	1.10	VR53	.19	3B7/1291	.59	6L7	.87	12H6	.27	75	.83
2J50	22.50	15E	1.19	800	1.49	1851	.69	VR78	.29	3D6/1299	.39	6L7G	.87	12J5GT	.34	76	.84
2J54B	22.50	15R	.49	801A	.19	1990	.89	VT127A	2.19	3LF4	.79	6N7	.75	12J7GT	.67	77	.43
2J55	69.50	16AP4	49.50	802	4.19	2050	1.19	VT136A	14.95	3Q4	.67	6Q7	.64	12K7GT	.52	78	.44
2J61	34.50	19T8	.89	803	2.95	2051	.89	VT171	.49	3Q5GT	.67	6R7	.79	12K8	.59	80	.87
2J62	34.50	23D4	.29	804	7.95	8005	4.75	WL468	5.95	3S4	.57	6S7G	.79	12Q7	.49	81	1.25
2K25	22.50	28D7	.29	805	3.65	8011	.25	WL530	12.75	3V4	.67	6S8GT	.77	12SA7	.57	82	.84
2K26	24.95	30SP	1.19	807	1.69	8012	1.39	WL531	14.75	5R4GY	1.09	6S8T	.44	12SC7	.54	83	.78
2K29	24.50	35TG	5.95	808	.99	8013	1.39	WL532	1.89	5T4	.87	6S7	.44	12SF5	.59	83V	.89
2AP1	4.59	456P	.19	809/3C30	1.89	8014	22.50	WL616	37.50	5U4G	.49	6S7GT	.54	12SF7	.54	84/6Z4	.84
3B22	1.98	53A	5.95	810	7.95	8020	.89	WL619	18.95	5V4G	.87	6SF5	.49	12SH7	.58	85	.69
3B24	1.49	76PL	5.95	811	1.98	8026	3.49	WL677	34.50	6W4	.67	6SF7	.59	12SJ7	.47	117L7/M7	1.19
3B25	4.87	100R	.97	812	2.45	9001	.32	WL681/		6X4G	.57	6SH7	.87	12SK7	.87	117N7	1.19
3B26	1.49	100TH	9.98	812H	4.86	9002	.25	686	22.50	6X5GT	.39	6SJ7	.47	12SL7	.89	117P7	1.19
3B27	1.95	100TS	2.25	813	6.85	9003	.33	WL710A	.25	6Y3GT	.49	6SK7GT	.44	12SN7	.52	117Z3	.69
3B28	7.95	211	.25	814	1.98	9004	.24	OA2	1.29	6Y4G	.53	6SL7GT	.89	12SQ7	.49	117Z6	.69
3BP1	2.39	217C	9.98	815	1.89	9005	1.35	OA4G	.89	6Z3							

RADIO HAM SHACK Inc.
189 GREENWICH STREET . NEW YORK, N. Y.

PHONE DIGBY 9-0347
WRITE FOR QUANTITY PRICES
Prices Subject to Change Without Notice
All Merchandise Guaranteed
F.O.B. N.Y.C.

RELAYS for every purpose

OVER A MILLION IN STOCK!

STANDARD DC TELEPHONE RELAYS

Stock No.	Operating Voltage	Coil Resistance	Contacts	Net Each
R-153	12V	200	SPDT-SPST (NO)	$1.25
R-154	12V	200	SPST (NO)	1.20
R-155	12V	100	SPST (NO)+NC	1.15
R-156	6V	50	4PST (NO)	1.10
R-159	6V	50	DPST (NO)	1.10
R-160	6V	12	4PDT-4PST (NO)	1.05
R-161	6V	10	3PST (2NO-1NC)	1.00
R-121	150V	6000	SPST (NO) SPDT	1.65
R-517	12V	250	DPST (NO)	1.20
R-520	250V	14000	DPDT	2.10
R-166	24V	Dual 200	DPDT-SPST (NO)	1.95
R-168	24V	Dual 200	4PST (NO)	1.20
R-725	100-300V DC	6500	3PST (2NC-2NO)	1.95
R-726	115AC		5PDT	2.25
R-743	48V DC	600	4PDT	1.10
R-777	12-24 VDC	70	DPST (1NO-1NC)	1.20

TYPE 18 DC TELEPHONE RELAYS

R-109	24-48V	4000	SPDT	1.50
R-110	24-32V	2500	SPDT	1.50
R-114	24V	500	4PST (NO)	1.30
R-115	24V DC	500	SPDT	1.35
R-740	24V DC	850	4PST (NO)	1.50
R-764	48V DC	1000	DPDT DPST (NO)	1.50
R-770	24V DC	150	DPST (NO) 10 amp.	1.15
R-771	24V DC	200	4PST (NO) 10 amp.	1.15
R-799	24V DC	500	None	.75
R-800	12V DC	150	DPDT-SPST (NO)	1.25
R-801	115AC		None	1.15
R-238	24V	150	DPDT-SPST (NC)	1.25
R-239	24V	180	DPST (NO)	1.25

SEALED DC TELEPHONE RELAYS

R-125	24V	300	DPDT	$2.75

E TYPE DC TELEPHONE RELAYS

R-154	24-32V	1080	SPST (NO)	1.20
R-526	6V	35	DPDT-SPST (1NC-1NO)	1.05

AC—STANDARD TELEPHONE RELAYS

R-213	5-8V		DPST (NO)	1.50
R-605	24V		3PST (NO)	.95
R-606	24V		DPST (1NO-1NC)	.95
R-607	24V		SPST (NO)	.95

DIRECT CURRENT MIDGET RELAYS

R-132	24V	300	DPDT	$1.20
R-133	24V	800	None	.60
R-135	24V	300	SPST (NC)	1.15
R-137	24V	300	SPDT	1.15
R-138	24V	300	4PST (NO)	1.15
R-139	24V	200	4PDT	1.15
R-140	24V	280	SPDT	1.15
R-141	24V	280	3PST (NO)	1.15
R-142	24V	400	DPDT	1.20
R-143	24V	280	SPST (NO)	1.15
R-144	24V	250	SPST (NO)	1.15
R-145	24V	300	DPST (NO)	1.15
R-146	12V	120	DPST (1 NO) (1NC)	1.10
R-148	12V	100	SPST DPDT-(NC)	1.10
R-149	6-8V	45	SPST (NC)	1.00
R-150	6V	30	SPST (NO)	.95
R-623	90-125V	6500	DPDT	1.90
R-722	12V	100	DPST (NO)	.95
R-696	24V DC	200	SPST (NO) 8 amp.	1.50
R-730	24V DC	30	SPST (NO)	1.00
R-731	24V DC	300	DPDT	1.25
R-733	12V DC	120	DPDT	1.00
R-734	12V DC	60	3PST (NO)	.95
R-743	110V DC	5000	4PST (1NO) (3NC)	1.65
R-755	24V DC	300	SPST (NO)	1.15
R-761	24V DC	230	DPST (1NO-1NC)	1.20
R-762	100V DC	6500	4PDT-6PST (NO)	1.95
R-732	12V DC	120	SPST (NO)	1.15
R-763	100V DC	6500	SPDT Mercury	1.85
R-765	60V DC	1300	DPDT	1.50
R-768	24V DC	280	DPDT-10 amp	1.50
R-242	24-32V	300	DPDT	1.20
R-243	24-32V	300	4PDT	1.20

SENSITIVE DC RELAYS

R-177	24V	300	4PDT	$1.65
R-218	4-6V	1800	SPDT	1.95
R-220	75V	3000	SPDT	1.20
R-221	18-24V	3000	SPST (NO)	1.15

Stock No.	Operating Voltage	Coil Resistance	Contacts	Net Each
R-600	8-12V	5000	SPDT	$2.10
R-716	24V	70	DPST (NO) 5 amp.	1.45
R-778	8V DC	4500	SPDT 5 amp.	2.10
R-798	24V DC	Dual 500	Each SPDT-5 amp.	1.95
R-693	2-6V DC	125	SPDT-3 amp.	.95
R-692	-6 to 24V DC	1250	SPDT-3 amp.	1.10
R-695	12V DC	70	DPDT-3 amp.	1.05
R-694	24V DC	260	SPST (NO) 5 amp.	1.20
R-706	24V DC	150	4PDT 10 amp.	1.95
R-705	12-24V DC	70	SPST (NO) 10 amp.	1.25

TYPE BO DC RELAYS

R-169	24V	250	SPST (NO)	1.95
R-171	24V	230	DPDT	2.15
R-173	2-6V	5	SPST (NO)	1.25
R-529	24-48V	1000	DPDT	2.00

TYPE BJ DC RELAYS

R-204	12V	65	DPST	1.15
R-205	24V	260	DPDT	1.25
R-224	12V	75	SPST (NO)	1.15
R-237	27V	230	DPDT	1.25

HEAVY DUTY KEYING RELAYS

R-248	28V DC	150	SPST (NO) 10 amp.	1.05
R-244	75V AC	265	SPST (NO) 20 amp.	1.75
R-206	24V DC	150	3PDT-3 amp.	1.20
R-207	24V DC	210	4PDT-3 amp.	1.10
R-219	50V DC	1500	DPST (NO) 15 amp.	1.25
R-508	110 AC	600	SPDT-6 amp.	1.95
R-506	24V DC	300	DPST (NO) 6 amp.	.95
R-604	24V DC	200	SPST (NO) 30 amp.	1.25
R-223	28V DC	150	SPST (NO) 40 amp.	1.35
R-230	12-24V DC	50	DPDT (NO) 10 amp.	1.20
R-231	24V	230	DPST (NO) 5 amp.	1.15

DC-TYPE 76 ROTARY RELAYS

R-197	9-16V	70	DPDT	1.65
R-198	9-16V	125	6PST (3 NO) (3NC) 8PDT	1.65
R-200	24-32V	275	SPDT-SPST (NC)	1.65
R-201	24-32V	230	DPST (NO) SPDT (NC) DPDT	1.65

KEYING RELAYS

R-191	28V DC	125	DPDT 10 amp.	$1.20
R-192	12V DC	44	3PDT 10 amp.	1.35
R-193	5-8V DC	11	DPDT 10 amp. SPST (NO)	1.05
R-196	12V DC	50	DPDT 10 amp. SPST (NC)	1.15
R-242	24V DC	170	SPDT 2 amp.	1.25
R-734	24V DC	150	3PDT-10 amp.	1.05
R-752	24V DC	150	DPDT-3 amp.	1.15
R-757	12V DC	44	DPDT SPST (NO)	1.15
R-758	24V DC	160	DPDT-10 amp.	1.25
R-744	24V DC	265	SPST (NO) 20 amp.	1.20
R-720	24V DC	50	DPDT-Ceramic	1.35
R-724	75V DC	2200	DPST (NC) 3 amp.	1.85
R-715	24V AC		DPDT-Ceramic	2.95
R-503	24V DC	Dual 50	MCALEX INS. 5PST (3NO) (2NC)	2.25
R-508	110 AC		SPDT 6 amps.	2.25
R-768	24V DC	175	DPST (NO) 5 amps.	1.15
R-772	12V DC	70	8PST (NO) 15 amps.	1.15
R-773	24V DC	280	3PDT-10 amp.	1.30
R-775	28V DC	180	DPDT	1.25
R-776	28V DC	265	DPST (NO) 8PST (NC) 10 amp.	1.35
R-779	12V AC		DPDT-10 amp.	1.25
R-791	24V DC	375	DPDT-10 amp.	1.25
R-792	24V DC	Dual 200	8PST (NO) 15 amp.	1.05
R-793	12V DC	42	DPDT-10 amp.	1.25
R-794	3 coils 12V DC	3 coils 16 Ea.	8PST (NO) 15 amp. 8PST (NC) 15 amp.	2.65
R-795	24V DC	160	DPST (NO) 10 amp.	1.25
R-796	24V DC	160 Dual	DPST (NO) 15 amp.	2.25
R-797	24V DC	160	8PST (NO) 8 amp.	2.25
R-698	24V DC	200	3PDT-5 amp.	1.25
R-697	12-24V DC	100	8PST-10 amp.	1.15
R-708	6-12V DC	15	5PDT-5 amp.	1.00
R-700	24V DC	200	DPDT-8 amp.	1.25
R-691	12V DC	50	DPDT-6 amp.	1.10
R-701	22-28V DC	425	DPST (NC) 10 amp.	1.35

HEAVY DUTY CONTACTORS

R-178	24V DC	100	SPST (NO) 100 amp	$3.85
R-179	6V DC	6.5	SPST (NO) 50 amp.	3.00
R-180	12V DC	25	SPST (NO) 50 amp.	3.25
R-739	24V DC	200	SPST	1.10
R-742	26V AC, DC	70	SPST (NO) 25 amp.	2.45
R-748	24V DC	60	SPST (NO) 30 amp.	1.95
R-762	115V AC		DPST (NO) 30 amp.	3.45
R-719	24V DC	10	SPST (NO) 200 amp.	3.95
R-717	24V DC	200	SPST (NO) 50 amp.	2.75
R-727	10V DC	20	SPST (NO) 20 amp.	1.50
R-767	24V AC	20	DPST (NO) 10 amp.	2.95
R-788	110 AC		3PST (3NC-2NO) 10A	4.35
R-703	12V DC	20	DPST (NO) 25 amp.	2.25
R-232	24V	55	SPST (NO) 50 amp.	3.25
R-235	24V	70	SPST (NO) 100 amp.	3.85

DIRECT CURRENT AIRCRAFT CONTACTORS

R-182	28V	80	SPST (NO) 25 amp.	1.85
R-183	24V	60	SPST (NO) 50 amp.	2.75
R-184	28V	50	SPST (NO) 100 amp.	2.95
R-185	24V	100	SPST (NO) 50 amp.	2.75
R-186	24V	132	SPST (NO) 50 amp.	3.50
R-187	24V	100	SPST (NO) 50 amp.	2.95
R-188	24V	200	SPST (NO) 75 amp.	2.95
H-234	14V	45	SPST (NO) 30 amp.	1.65

ANTENNA CHANGEOVER RELAYS

R-192	6-12V DC	44	2PDT 10 amp.	1.35
R-503	12-32V DC	100	SPDT-SPST	1.95

COMBINATION PUSH BUTTON AND REMOTE RELAY

H-244	12-24V DC	Dual 60	SPDT	1.65

ADJUSTABLE TIME DELAY RELAY

R-246	115 AC		SPST (NO) or (NC) 10 amp.	8.95

DC MECHANICAL ACTION RELAYS

R-245	12V	.25	4° Lever	0.95
R-527	6-12V	200	2° Lever	.95

TYPE C M S RELAYS

R-511	24V DC	200	MICRO-SW SPST (NO)	2.45

DC CURRENT REGULATOR

R-509	6-12V DC	40	SPST (NC)	0.85

LATCH AND RESET RELAY

R-500	12V DC	10	DPDT-10 amp.	2.85

DC-ROTARY STEP RELAY

R-711	24V DC	200	2 position DPDT-SPST (NC)	1.65
R-712	24V DC	200	2 position DPST (NC)	1.65
R-713	9-14V DC	125	2 position SPDT-SPST (NO)	1.65
R-766	24V DC	230	12 position 8 deck	3.95

DC-RACHET RELAY

R-230	5-8V	2	SPDT-DPST (NO)	2.15

VOLTAGE REGULATOR RELAYS

R-745	6V	2	SPST (NO) amp.	.85
R-780	24V DC	350	SPDT-6 amp.	.85

MAGNETIC OVERLOAD RELAY

R-749	600V DC	28 amp.	-Oil Dashpot Type	5.95

DC TIME DELAY

R-525	12-24V DC	200	DPDT 10 amp.	1.25

OVERLOAD CURRENT RELAY

R-250	115 AC 60 Cycle		SPST (NC)	12.95

ORDER DIRECTLY FROM THIS AD OR THROUGH YOUR LOCAL PARTS JOBBER

Manufacturers: Write for Quantity Prices

Distributors: Write For The New Wells Jobber Manual

WELLS SALES, INC.

320 N. LA SALLE ST., DEPT. SL, CHICAGO 10, ILL.

LAVOIE FREQ. METER MICRO-WAVE

375 to 725 MCS

Model TS-127/U is a compact, self-contained, precision ± 1 MC1 frequency meter which provides quick, accurate readings. Requires a standard 1.5V "A" and 45V "B" battery. Has 0-15 minute time switch. Contains sturdily constructed HI-"Q" resonator with average "Q" of 3000 working directly into detector tube. Uses 957, LS6 and 384 Tubes. Complete, new with inst. book, probe and spare kit of tubes. Less batteries. Write for descriptive circular..... **$49.50**

THERMOSTATIC TIME DELAY RELAY

Amperite type 115 No.—45 Heater voltage 115V. Normally open SPST contacts. 45 sec. delay. Contact rating 115V-3A., A.C. (or 440V A.C. 2A) max. voltage on contacts—1000 max. voltage bet. contacts and heater—1500. Size 3 9/32 x 1¼" overall. Made for U. S. Navy..... **$1.10**

High Voltage Capacitors Oil Filled

.25 MFD., 20KV	$15.75
.5 MFD., 25 KV	$23.50
1 MFD., 15KV	$16.50
1 MFD., 7.5KV	$4.95

All brand new. Made by prominent manufacturers.

● TUBE SPECIALS ●

1B24	$3.75	700A	$19.50
2J26	$7.50	705A	$16.50
2J27	$12.50	721A	$3.90
2J49	$19.50	725A	$8.50
2J62	$35.00	7H7T	$4.25
3BP1	$2.00	814	$3.50
3B22	$2.00	826	$ .40
3B24	$1.45	861	$10.00
3CP1	$2.50	8020	$1.25
3C45	$1.00	8025	$3.00
3D21A	$1.00	9LH7	$3.85
4C35	$17.50	WE394A	$3.65
5FP7	$1.25	WL531	$6.75
		OSJ	$2.00



LINEAR SAWTOOTH POTENTIOMETER

No. KS 15138

$5.50 Brand New

Has continuous resistance winding to which 24 volts D.C. is fed to two fixed taps 180° apart. Two rotating brushes 180° apart take off linear sawtooth wave voltage at output. Size approximately 3⅜" dia. x 2" deep x 4⅞" long. Enclosed in die cast alum. frame with AN connector socket.

U. S. NAVY SOUND POWERED BATTLE PHONES

Western Electric No. D173312. Type Combination headset and chest microphone as illustrated. Brand new including 20 ft. of rubber covered cable..... **$17.50**

Automatic Elec. Co. No. GL84AO. Similar to above but including Throat microphone in addition to chest microphone. Brand new with 20 ft. rubber covered cable **$13.50**

SYNCHRO GENERATORS

Brand new—Gov't. sealed and inspected—Packed in overseas cans. Synchro Transmitters 115 V., 60 cy. operation. Precision accuracy made for gun fire control. Cost Gov't $90.00 each. Wgt. 5 lbs. Dimensions: 4⅝"L x 3⅜".

Brand New Per Pair **$14.75**

Differential Synchros

90-90 volts, 400 cycles. Brand new in sealed containers. Ford Inst. Co. type 5M16. Brand new... **$12.50**

MICROWAVE RECEIVERS

APR-1, APR-4, APR-5A.

Tuning Units for APR-1 or APR-4, TN-16 (38-95 mc), TN-17 (74-320 mc) TN-18 (300-1000 mc.) These front ends may be used with any 30 mc. IF amplifier or as converters into receivers tuned to 30 mc.)

MODEL AN/APA-10 PANORAMIC ADAPTER

Provides 4 Types of Presentation:

(1) Panoramic (2) Aural

(3) Oscillographic (4) Oscilloscopic

Designed for use with receiving equipment AN/ARR-7, AN/ARR-5, AN/APR-4, SCR-587 or any receiver with I.F. of 455kc, 5.2mc, or 30mc. With 21 tubes including 3" scope tube. Converted for operation on 115 V. 60 cycle source

PRICE **$195.00**

MOTOR GENERATORS DYNAMOTORS, INVERTERS, ETC.

2.5 KVA MG SET. Diehl Elec. Co. 120V DC to 120V AC, 60 cy. 1 Ph. Complete with Magnetic Controller, 2 Field Rheos and Full Set of Spare Parts including Spare Armatures for Generator and Motor. Full specs. on request. New..... $185.00

2 KVA MG SET. O'Keefe and Merritt. 115V DC to 120V AC, 60 cy. Idles as 3 Ph. synch motor on 208V, 50 cy. New. Export crated. $165.00

1.25 KVA MG SET. Allis-Chalmers. 115V DC to 120V AC, 60 cy, 1 Ph. Fully enclosed. Splashproof. Ball Bearings. Centrifugal Starter. New..... $97.50

Same machine but for 230V DC operation.... $110.00

Spare Parts for either machine..... $15.00

MG SET FOR NAVY TBS TRANSMITTER. Type CG-21502. 440V AC, 60 cy, 3 Ph, 1500VA to 875V DC and 300V DC. New..... $45.00

DYNAMOTOR. Navy Type CAJO-211444. 105/130V DC to 13V DC at 40A or 26V DC at 20A. Radio filtered. Complete with Line Switch. New..... $68.50

DYNAMOTOR. Elecr. 32V DC to 110V AC, 60 cy, 1 Ph, 2.04 Amps. New..... $24.50

DYNAMOTOR. Elecr. 32V DC to 110V AC, 60 cy, 1 Ph, 0.43 Amps. New..... $17.50

MISCELLANEOUS SMALL MOTORS INVERTERS, AMPLIDYNES

AMPLIDYNE—G. E. Model 5AM31NJ9A. 550 Watts, 7500 R.P.M. Input: 27V, DC, Output: 60V, DC. Weight—34¾ lbs. New..... $10.50

AMPLIDYNE—G. E. Model 5AM21JJ7. 4000 R.P.M. Motor Compound wound. 150 Watts. Input: 27V, DC. Output: 80V, DC. Stg. Corp. U. S. Army MG-27-B. New..... $16.50

INVERTER—Leland Elec. Co. Model PE206A. Input: 28V, DC, 38 Amps. Output: 80V., 400 cy, 485 VA. New..... $12.50

INVERTER—Gen. Elec. Model 5D-21NJ3A. Input: 24V, DC. Output: 115V, 400 cy, 485 VA. New..... $12.50

INVERTER—Bendix Pioneer Type 12131-A. 24V DC to 115V AC, 400 cy, 3 Ph, 250 VA. New..... $89.50

D.C. MOTOR—G. E. Model 5BA 50JJ2A. 0.5 HP. Armature: 27V, at 8.3 Amps. Field: 60V, at 2.3 Amps. R.P.M. 400. New..... $12.50

DYNAMOTOR—Type PE94C. For use with SCR522 Transmitter-Receiver. Brand new in export cases..... $9.50

LINE VOLTAGE STABILIZERS

RAYTHEON—Navy Type, CRP-391407 Input: 92-138V, 57-63 CPS., 1 PH Output: 115V, 0.82 KVA., 1% Reg., 0.96 PF. Weight 385 lbs. Overall size—36" high x 20" wide x 12¼" deep. Enclosed in Navy Grey Ventilated Cabinet for Wall Mounting.

Brand New **$49.50**



RAYTHEON Adj. input taps 90-130V., 60 cy., 1 Ph. Output: 115V., 60 Watts. ½ of 1% Reg. Wt. 20 lbs. 6¾" H x 8¾" L x 4⅝" W. Overload protected. Sturdily constructed. Tropicalized.

Special..... **$12.50**

400 CYCLE TRANSFORMERS

AUTO. 400 cy. G.E. Cat. No. 8943184 KVA .0438—.0201. Volts 440/345/230/115. New $3.45

FILAMENT. 400/2600 cy. Input: 0/75/80/85/105/115/125V Output: 5V3A/5V3A/5V3A/5V3A/5V6A/5V6A/6.5V6A/6.3V5A. New..... $1.95

THYRATRON POWER. 400/1600 cy. Raytheon UX-8876. 400/1600 cy. Pri: 115V. Sec: 50-0-50V at 0.5A, 6.3V at 1.2A. Test r.m.s. 1780. New..... $2.75

PLATE. WECO K89560. 400/800 cy. Pri: 115V. Sec: 1350-0-1350 at .037A (2700V Total). Electat shilded. Wt. 2.3 lbs. New..... $2.95

SCOPE PL. & FIL. WECO 9556. 400/2400 cy. Pri: 115 HV Wdg. 112V at .008A. Fil. Wdgs. 6.4V4A/2.5V1.75A/6.4V 6A. Electat shilded. Wt. 1.4 lbs. New..... $2.75

FILAMENT. 400/2400 cps. WECO K89555. Pri: 115V, Sec: 8.2V1.25A/6.3V1.5A. Electat shilded. Wt. 0.8 lbs. New..... $1.65

PLATE & FIL. 400/2600 cy. Pri: 0/80/115V. Sec#1=1200VDC at 1.5MA, Sec#2=400VDC at 130MA. Fil Secs: 6.4V4.5A/6.3V0.8A (ins.1500V)/5V2A/5V2A $3.95

RETARD. 400cy. WECO K89598. 4 Henry 100MA $1.09

400 CY. SERVO TRANSFORMERS

G.E. #68G665X Pri: 57.5V. Sec:#1=28.75V, Sec#2=28.75V..... $1.50

G.E. #68G666X Pri: 57.5V. Sec: 115V C.T..... $1.50

G.E. #68G667 Pri: 220V C.T. Sec: 220V C.T..... $1.50

G.E. #68G668X Pri: 115V. Sec: 275V/275V/275V/275V/230V/230V/6.3V CT/ 6.3V CT..... $3.50

60 CYCLE TRANSFORMERS

4.5 KVA STEPDOWN. G.E. Cat. No. 7603173. Pri: 115/230V Sec: 23/11.5V. Either high voltage connection may be used with either low voltage connection $23.90

50KVA STEPDOWN. Standard Trans Corp. Oil trans type MD. Pri: 450V111A, Sec: 117V427A. Navy type. Ambient temp. 50 Deg. C..... $125.00

FILAMENT. Raytheon Hyperail Core. Pri: 115V. Sec: 6.3V22A/6.3V2.4A/6.3V2.25A/6.3V0.6A Ins. for 1700V..... $3.98

FILAMENT. Kenyon. For 866 tubes. Pri: 115V Sec: 2.5VCT at 10A. Insulation 10,000V..... $2.98

PULSE TRANSFORMER

PULSE. WECO KS 9563. Supplies voltage peaks of 3500V from 800 ohms. Tested at 2000 Pulses/sec and 5000V peak. Wdg. 1-2=18 ohms. Wdg. 1-3=72 ohms. L of Wdg. 1-3 ..05-.082H at 100 cps..... $5.50



12 and 24 Volt POWER KIT

Consists of Power Trans. and full wave bridge selenium rectifier. Input: 115/230 A.C. Output: 12/24V D.C. at 1.1 amps. Fine for operating relays, small motors, dynamotors, or for low voltage D.C. source in laboratories, etc.

Brand New **$7.95**

SWEEP GENERATOR CAPACITOR



High speed ball bearings. Split stator silver plated coaxial type 5/16 omfd. Brand new.

$1.00

PARABOLOIDS

Spun Magnesium dishes 17½" dia., 4" deep. Mounting brackets for elevation and azimuth control on rear. 1¼" x 1⅝" opening in center for dipole. Brand new per pair..... **$8.75**

All prices indicated are F O B Tuckahoe, New York. Shipments will be made via Railway Express unless other instructions issued.

ELECTRONICRAFT

INC.

5 WAVERLY PLACE TUCKAHOE 7, N. Y.

PHONE: TUCKAHOE 3-0044

All merchandise guaranteed. Immediate delivery, subject to prior sale.

All Prices Subject to Change Without Notice

SELENIUM RECTIFIERS and ASSOCIATED COMPONENTS

SINGLE PHASE FULL WAVE BRIDGE RECTIFIERS

Input 0-115VAC		Output 0-12 VDC
Type No.	Current	Price
B1-250	250 MA.	$0.98
B1-1	1 AMP.	2.49
B1-1X5	1.5 AMP.	2.98
B1-5X5	5.5 AMP.	4.66
B1-5	5 AMP.	5.95
B1-10	10 AMP.	9.95
B1-20	20 AMP.	15.95
B1-30	30 AMP.	26.95
B1-40	40 AMP.	37.95
B1-60	60 AMP.	52.95

Input 0-36VAC		Output 0-26 VDC
Type No.	Current	Price
B2-160	160 MA.	$0.98
B2-250	250 MA.	1.25
B2-500	500 MA.	1.50
B2-2	2 AMP.	4.95
B2-5X5	5.5 AMP.	6.95
B2-5	5 AMP.	9.95
B2-10	10 AMP.	15.95
B2-20	20 AMP.	27.95
B2-30	30 AMP.	36.95
B2-60	60 AMP.	64.95

Input 0-115VAC		Output 0-90 VDC
Type No.	Current	Price
B6-250	250 MA.	$2.95
B6-500	500 MA.	3.95
B6-750	750 MA.	6.95
B6-1X5	1.5 AMP.	10.95
B6-5X5	5.5 AMP.	15.95
B6-5	5 AMP.	24.95
B6-10	10 AMP.	34.95
B6-15	15 AMP.	54.95

THREE PHASE FULL WAVE BRIDGE RECTIFIERS

Input 0-234VAC		Output 0-250 VDC
Type No	Current	Price
3B13-1	1 AMP.	$22.00
3B13-2	2 AMP.	32.00
3B13-4	4 AMP.	56.00
3B13-6	6 AMP.	81.50
3B13-10	10 AMP.	105.00
3B13-15	15 AMP.	120.00

CENTER TAPPED RECTIFIERS SINGLE PHASE FULL WAVE

Input 10-0-10VAC		Output 0-8 VDC
Type No.	Current	Price
C1-10	10 AMP.	$6.95
C1-20	20 AMP.	10.95
C1-30	30 AMP.	14.95
C1-40	40 AMP.	17.95
C1-60	60 AMP.	20.95

RECTIFIER MOUNTING BRACKETS

For Types B1 through B6, and
Type C1 ..... $ .25 per set
For Types 3B ..... 1.95 per set

Selenium Rectifier Catalog

Write for our Catalog No. 719 which lists Selenium Rectifiers, associated transformers, condensers and filter chokes.

Minimum order $5.00

No C.O.D.'s. Orders shipped via Ruy. Exp. Charges collect unless accompanied by additional 10% for Parcel Post and handling—15% west of Rockies. Add 10% for Prepaid Parcel Post and Handling. Terms: Net 10 days in the presence of approved credit.

All prices subject to change without notice. *Prices and Delivery F.O.B. our NYC Warehouse. All merchandise subject to prior sale.*

POWER SUPPLY KITS

24 to 28 VDC Filtered

Designed for continuous duty ground operation and bench testing of aircraft equipment, these kits provide a reliable means of obtaining a source of low ripple 24 VDC, from a 115 VAC 60 cycle line. Full wave bridge Selenium Rectifiers insure instantaneous and efficient operation. Adjustment of the DC output voltage is accomplished by transformer primary taps. Ripple is limited to within 1% of the average DC output by choke-input filters.

Kit No.	Amperes DC	Net Price
242	2.0	$16.39
245	5.0	22.39
2410	10.0	47.44
2420	20.0	79.44

Write for descriptive Bulletin No. 201

RECTIFIER CAPACITORS

CF-16	3000 MFD	12VDC	$1.49
CF-1	1000 MFD	18VDC	.98
CF-2	2000 MFD	18VDC	1.49
CF-20	2500 MFD	18VDC	1.95
CF-3	1000 MFD	25VDC	1.25
CF-4	2X3500 MFD	25VDC	3.45
CF-6	4000 MFD	30VDC	3.25
CF-7	3000 MFD	35VDC	3.25
CF-8	100 MFD	50VDC	.98
CF-19	500 MFD	50VDC	1.95
CF-16	2000 MFD	50VDC	3.25
CF-21	1200 MFD	90VDC	3.25
CF-9	200 MFD	150VDC	1.49
CF-10	500 MFD	200VDC	3.25

Mounting clamps for above capacitors ..15c ea.

RECTIFIER TRANSFORMERS

All Primaries 115VAC 50/60 Cycles

Type No.	Volts	Amps.	Shpg. Wt.	Price
XF15-12	15	12	7 lbs.	$3.95
TXF36-2	36	2	6 lbs.	3.95
TXF36-5	36	5	8 lbs.	4.95
TXF36-10	36	10	12 lbs.	7.95
TXF36-15	36	15	20 lbs.	11.95
TXF36-20	36	20	30 lbs.	17.95
XFC18-14	18VCT	14	10 lbs.	8.95

All TXF Types are Tapped to Deliver 32, 34, 36 Volts. XFC Type is Tapped to Deliver 16, 17, 18 Volts Center Tapped.

RECTIFIER CHOKES

Type No.	Hy.	Amps.	Dc Res.	Price
HY5A	.028	5	.20	$3.95
HY10	.02	10	.38	9.95
HY10A	.014	10	.04	7.95
HY20A	.007	20	.02	12.95

Type "A" low resistance chokes are specially suited to circuits requiring excellent voltage regulation.

D-C PANEL METERS

Attractive, rugged, and reasonably priced. Moving vane solenoid type with accuracy within 5%. Square case.

0 - 6 Amperes D-C
0-12 Amperes D-C
0-15 Volts D-C

Any range $2.49 each

Opad-Green COMPANY
71-2 Warren St. New York 7, N. Y.
Phone: BEekman 3-7385-6

synchros
SINE/COSINE RESOLVERS

2 phase stator and rotor 60 cycle and higher, suitable any-both waveforms, length 6-3/4" diameter 3-3/4" Guaranteed, $11.50 each post free. Snooperscope Infrared Image converters $3.60 ea. 12 for $36.00 post free.

HOPTON RADIO 1, HOPTON PARADE
Streatham High Rd., London S. W. 16

#104 Universal Coil Winders

FOR SALE

Two 1946, Unused - Complete with Motors and Accessories

MILLER ELECTRIC CO.
32 River St. Pawtucket, R. I.

FOR SALE
INFRARED TELESCOPES

2—only Navy Type US/C-3, complete

Cunningham Engineering Company
Beaumont, Texas

Select SURPLUS ELECTRONIC *Equipment*



AIRCRAFT RADIO TRANSMITTERS

Type BC-375-E

100 watt output. Frequency range 200-500 and 1500-12kc., complete, new, with all tuning units, dynamotor, tubes, plugs, etc. Brand new in original packing. Not removed from aircraft. Original cost $1800. **$97.50** ea.

Navy Model TDE Radio Transmitters

Frequency range 300 to 18,000 kc., 125 watt output on C. W., 25 watts on phone, for operation on 230 volts D.C. power supply, complete with tubes and ready for operation.

Our information indicates that these units cost the U. S. Navy $9,000 ea. We offer them to you at a mere fraction of the original price. **$675.00** ea.

BD-72 Field Telephone Switchboards

These sets are sold individually packed in strong, steel-strapped, wooden cases, and they are ready to set up and operate. **$37.50** ea.

Radiomarine Corporation
Telegraph Transmitter Model ET-8023 D1

Power output 200 watts master-oscillator or crystal controlled in operation. Frequency range 2,000 to 24,000 kc., in nine overlapping bands. New, in original export packing. Complete with tubes and typewriter table.

Does not include motor generator power supply. **$375.00** ea.

Generating Plants Type PE-197, 5 KW

Gasoline-engine driven. 120 volts, 60 cycles AC, manufactured by Hobart with Hercules 4-cylinder engine, water cooled, including cable, set of tools, automatic starting. **$675.00** ea.

Navy Model TCS Transmitters-Receivers

Covering 1.5 to 12 mcs. Output 25 watts. Complete with remote control, power supply, antenna tuning unit, cables, key and microphone. Available for 110-220 volts AC and 12 or 24 volt operation. Ask for special leaflet and prices.

ALL ITEMS ARE OFFERED F.O.B. OUR WAREHOUSE, AND ARE SUBJECT TO PRIOR SALE. ALL ITEMS ARE NEW, UNUSED SURPLUS UNLESS OTHERWISE INDICATED. ASK FOR COMPLETE LISTING ON OTHER DESIRABLE EQUIPMENT. SEPARATE TECHNICAL BULLETINS ON ALL EQUIPMENT AVAILABLE UPON REQUEST.

FRENCH-VAN BREEMS, Inc.

405 Lexington Avenue, New York 17, N. Y.

A MULTI-PURPOSE RADAR SEARCH RECEIVER ARD-2

Will measure RF signals from 80 to 3000 MCS and pulse rates from 50 to 8000 cycles. It can also locate transmitted signal sources by visual and aural indicators.

EQUIPMENT: Consists of the following: 1 ANTENNA-DETECTOR (CMD-60AFH) has variable length antennas (2), diode detector, and silver plated tuning stub with calibrated scale; 1 AMPLIFIER (CMD-50ADG) has three stage pulse amplifier, a trigger circuit, a pulse rate counter circuit and audio amplifier, a visual signal indicator, and a rectifier power supply which is operative on 115 Volts AC, single phase, at 60 to 2400 cycle current, regulated; 1 TEST OSCILLATOR (CMD-60ABG) has carrier frequency of 400 cycles with selection of four pulse repetition rates. With the above are included all cables with fittings, accessories, and shock mounted rack, a steel chest with complete spare parts and 200% additional tubes and 2 technical manuals. Gross weight 113 pounds.

BRAND NEW! ORIGINAL PACKING! COMPLETE!

Price, each.....$175.00

RADIOTELEPHONES

5 WATT, Model JT-52 by Jefferson-Travis, 2 channel, crystal controlled recvr-transmitter, built-in speaker, hand microphone, 6 Volt DC power supply. Freq: 2000-3000 KCS, in compact steel cabinet, complete less xtals. New in original cartons. In dealer quantities.

50 WATT, MTR-5032 by Harvey-Wells, SIX channel xtal controlled recvr-transmitter, 2000-3000 Kcs, with built-in speaker, telephone hand set, (provisions for selector-ringer and external deck calling system) in handsome steel cabinet, for 32 Volt DC input. Complete, less crystals. NEW.

50 WATT, MTR-5011, as above, but for 115V DC.

75 WATT, MTR-7532, similar to above, with same features, for 32 Volts DC Input.

75 WATT, MTF-7511, as above, but for 115 V. DC.

RECEIVER-TRANSMITTER COMBINATIONS

SCR-508/528 FM at 25 Watts output: 20.0-27.9 Mcs., complete with receiver and transmitter, dynamotors, control boxes, crystals, antennas.

SCR-608/628 as above, except for frequency of 27.0-38.9 Mcs.

TCS Mfgd by Collins 40/20 W. Phone & CW for 12 V. DC, 1.5 to 12.0 Mcs. with all accessories.

AVT/B/A Mged by RCA, 6-10 Watts phone and CW 2300 to 6700 Kcs. Small compact for 6 & 12 V.D.C. NEW & COMPLETE with power supply, mike, key & antenna.

TRANSMITTERS

BC-610 Hallicrafter, 2.0-18.0 mcs. 450 watts CW 350 watts phone. Antenna tuner & speech amplifier, cables, manuals, complete. Wt: 446 lbs. net.

BC-365 Federal Tel. & Tel. 150 to 550 Kcs. 250 watts CW. for Radio Range or carrier communication. Complete. Wt: 629 lbs. net.

BC-325 Federal Tel. & Tel., 1.5-18.0 Mcs. 400 W. phone 100 W. CW. complete with remote control. Wt: 900 lbs. net.

TDE Westinghouse Mfg. 300 to 18,100 Kcs., 125 W. A1; 25 W. A2 A3; for naval or shore use. Complete in several input voltages. Wt: 672 lbs. net.

WALKIE-TALKIES
HANDY TALKIES

Many types to choose from in new and complete condition and guaranteed. Bulletins on request.

PORTABLE RADAR

LORAN
MOBILE EQUIPMENT

TAPE FACSIMILE EQUIPMENT

DESCRIPTIVE LITERATURE ON REQUEST

Communication Devices Co.
2331 TWELFTH AVENUE
NEW YORK 27, N. Y.

Cable: COMMUNIDEV Tel: AD-4-6174, 5

TEST EQUIPMENT



X Band Spectrum Analyzer 8500-9600 Mc., calibrated linear below cut-off attenuator, calibrated frequency meter, tuned mixer, 4 i.f. stages, 3 video stages overall gain 125 db., regulated power supply.

S Band Spectrum Analyzer 2700-3900 Mc., similar to above.

The above Spectrum Analyzer also available with S and X band tuning units.

K Band Test Load low power.....**$20.00**

X Band Power, Frequency and SWR Measuring Equipment complete with R.F. source, A.S.D. equipment.

X Band Below Cut-Off Wave Guide Attenuator, with calibrated dial, type N input connector, output connects to ½" x 1" wave guide **$55.00**

X Band Test Load, low power....**$15.00**

TS-62 X Band Echo Box with r.f. cable and pick-up antenna.

TS-33 X Band Frequency Meter, 8500-9600 Mcs. Crystal detector and 50 micro-amp. meter. Indicates Resonance. Connection for scope available.

APR-1 or APR-4 Radar Search Receiver, 30 mc I.F., 2 mc wide.

Tuning Units For APR-1 or APR-4 Receivers (can be used with any 30 mc amplifier):

TN-19, range 1000-2000 mc, tuned mixer cavity **$150.00**

TN-54, range 2000-4000 mc, tuned mixer cavity **$150.00**

30 Mc I.F. Strip and 110 Volt 60 cps Power Supply, bandwidth 10 mc, complete, new (part of APR-5 Receiver) **$65.00**

TS-45A/APM-3 Signal Generator, 9200-9600 mc, 110 V, 60-800 cps.

TS-35/AP X Band Signal Generator, pulsed, calibrated power meter, frequency meter, 8700-9500 mc.

X Band VSWR Test Set TS-12/AP, complete with linear amplifier, direct reading VSWR meter, slotted waveguide with gear driven traveling probe, matched termination and various adapters, with carrying case, NEW UNITS I and II are available separately or together as a test set.

High Pass Filter F-29/SPR-2, cuts off at 1000 mc and below; used for receivers above 1000 mc.....**$12.00**

S Band Test Load TPS-SSP/BT, 50 ohms **$8.00**

X Band Test Load, 50 Watts.....$35.00

250 Watt X Band Test Load, VSWR less than 1.15 between 7 and 10 KMC **$150.00**

Standard Signal Generator Measurements 65B, 100 kc to 30 mc, 1-2,000,000 micro-volts, good working order.**$400.00**



S Band Crystal Mixer (illustrated), Variable Oscillator Injection.....**$12.50**

S Band Mixer, tunable by means of slider type N connector for the R.F. and local oscillator input, U.H.F., connector for the I.F. output, variable oscillator injection **$30.00**

Fixed Attenuator Pads, 20 db + 0 — 2 db, DC-1200 mc, 50 ohms, VSWR 1.3 or less, 2 watts average power....**$30.00**

Waveguide Below Cut-Off Attenuator, type N connectors, rack and pinion drive, attenuation variable 120 decibels, calibrated 20-120 db. frequency range 300-2000 mc **$32.00**

Waveguide Below Cut-Off Attenuator, similar to above except upper frequency limit is 3300 mc.....**$32.00**

Waveguide Below Cut-Off Attenuator, same as above except input is matched in range of 2200-3300 mc. VSWR less than 1-2 .....**$54.00**

Electro Impulse LABORATORY
P. O. Box 250 *Eatontown* **3-0768** **Red Bank, N. J.**

BRAND NEW U. S. GOV'T. SURPLUS GUARANTEED

POWER RHEOSTATS

Ohms	watt	ea.	Ohms	watt	ea.
2	225	$4.95	150	150	$3.50
3	50	2.90	200	25	.98
3	225	4.95	200	150	3.50
4	225	4.95	225	50	1.24
5	50	1.24	250	25	.98
5	100	2.90	250	35	.98
5	150	3.50	350	100	2.90
6	25	.98	375	150	3.50
6	50	1.24	400	25	.98
7	25	.98	500	25	.98
8	50	1.24	500	75	2.49
10	25	.98	585	150	3.50
10	100	2.90	750	25	.98
12	25	.98	750	150	3.50
15	25	.98	1000	25	.98
15	50	1.24	1200	225	6.95
22	50	1.24	1250	50	1.24
25	25	.98	1250	150	3.50
25	250	5.25	1500	50	1.24
30	25	.98	2000	25	.98
50	50	1.24	2000	50	1.24
50	750	14.95	2500	100	2.90
60	25	.98	3000	25	.98
75	150	3.50	3000	100	2.90
80	50	1.24	4500	50	1.24
90	500	7.60	5000	25	.98
100	25	.98	5000	50	1.49
100	50	1.24	7500	50	1.63
100	225	4.95	7500	100	3.50
125	25	.98	10000	50	1.63
125	500	7.60	10000	100	3.50
150	50	1.24	20000	150	5.26

Specify whether shaft required is KNOB or SCREWDRIVER type. Discount to Quantities Users.

SELECTOR SWITCHES

Pole	Pos.	Deck	Type	Each
1	6	1	bak-shtg	$1.1
1	11	1	bak-n.-shtg	58
1	12	1	cer-n.-shtg	58
1	23	3	bak-n.-shtg	69
1	24	2	bak-n.-shtg	79
2	2	1	cer-shtg	39
2	6	2	bak-n.-shtg	49
2	6	2	bak-shtg	54
2	11	2	bak-shtg	66
2	6	2	cer-n.-shtg	54
3	4	1	bak-shtg	1.28
3	11	2	cer-n.-shtg	56
3	11	2	bak-n.-shtg	1.98
3	12	3	cer-shtg	1.49
3	3	3	bak-shtg	.75
6	2	4	bak-n.-shtg	.98

"AN" CONNECTORS

LARGE VARIETY AVAILABLE AT GREAT SAVINGS

Send your specs and let us quote

OIL CONDENSERS

Mfd	VDCW	Each
1	3000	.75
1	6000	1.89
1	20-000	18.95
.25	3000	1.10
.5	1500	.89
1	600	.35
1	2000	1.95
2	400	.35
2	600	.39
2	1000	.79
4	600	.67
6	400	.75
6	600	.79
10	600	.98
14	600	1.75
15	600	1.98
15	1000	3.25
2 x 1	7000	3.95
2 x .5	9000	14.95

BATHTUBS

mfd	vdcw	each
.033	400	.12
.05	200	.17
.05	400	.19
.05	600	.21
1	400	.20
1	600	.22
1	1000	.32
.15	600	.22
.25	200	.19
.25	600	.23
.35	400	.22
.5	400	.23
.5	600	.25
.5	1000	.35
1	200	.29
1	400	.35
1	600	.59
2	50	.25
4	500	.59
.25	50	.28
.25	75	.30
.50	25	.28
.100	12	.35
.500	6	.39
.05-.05	600	.29
.05-.05	1500	.45
1-1	400	.26
1-1	600	.28
.25-.25	600	.30
.5-.5	600	.35
1.0-1	300	.29
200-200	9	.49
5 x .05	600	.60
5x 1	100	.42
5x 1	600	.45
5x 25	600	.50
5x1.0	100	.40

Specify Top, Side or Bottom Lugs.

TYPE "J" POTENTIOMETERS

TYPE "J" 50c			TYPE "JJ"	
ohms	ohms	ohms	$1.25 ohms	$1.50 ohms
60	1000	25K		
100	1,000	30K	100-100	100K-100K
150	2000	50K	200-200	150K-150K
200	4000	75K	500-500	250K-250K
300	5000	100K	2000-2000	350K-5000
400	10K	200K	2200-24K	350K-25K
500	15K	250K	20K-2000	500K-500K
600	20K	1 meg	25K-10K	500K-75K
			35K-5000	1meg-1meg
			50K-50K	2meg-2meg
				4meg-4meg

Specify type shaft needed — 5meg-5meg
For n.D. or knob

TYPE "JJJ" $2.25

ohms	ohms
20K-200K-20K	750K-750K-750K
45K-27K-250Ω	500K-500K-500K
700K-700K-700K	1meg-1meg-1meg

TRANSMITTING MICAS

mfd	vdcw	type	ea.	mfd	vdcw	type	ea.
.00001	600	4	.18	.0016	600	4	.18
.00003	600	4	.18	.002	600	4	.20
.00005	600	4	.18	.002	1200	4	.45
.00005	2500	9	.31	.0022	2500	9	.78
.0001	600	4	.19	.0025	600	4	.23
.0001	2500	9	.31	.003	600	4	.25
.00015	2 600	4	.18	.0039	600	4	.25
.0002	600	4	.18	.005	600	4	.25
.00025	600	4	.18	.005	1200	9	.60
.0005	600	4	.18	.005	2500	9	1.18
.00051	2500	4	.43	.0062	600	4	.30
.0007	600	4	.18	.01	600	4	.40
.0008	600	4	.18	.01	600	9	.49
.0009	600	4	.18	.01	1200	9	.98
.001	600	4	.18	.0142	600	4	.45
.001	1200	4	.31	.02	600	4	.55
.001	2500	9	.31	.02	1250	9	1.36
.0013	600	4	.18	.027	600	4	.66
.0015	600	4	.18	.043	600	4	.99

Other sizes available

"UHF" CONNECTORS

Cat. No.	Army No.	Each	Per C
SS-1AC		.42	.39
SS-1AP	M-359	.35	.28
SS-1D	PL-271	1.25	1.00
SS-1F	PL-274	1.10	.98
SS-1R	SO-239	.35	.28
SS-1SPN	PL-259A	.35	.28
SS-22R	SO-264	.50	.40
SS-22SP	UG-102/U	.68	.60

Open Accounts to Rated Concerns
Prices net FOB our whse NYC.
Send for our catalog

ALEXANDER MOGULL CO., INC.

161 Washington St., N. Y. 6, N. Y. WOrth 4-0865

TELEVISION TUBE MACHINERY

8 HEAD MACHINE, for button stems.

TUBE STEM MACHINES Mfd. by Kahle Eng. Co. 4-5-6-7-8 positions with Geneva movements.

HYDROGEN FURNACES Complete with automatic controls, 20" x 7" x 4". Brick-lined, with two Bristol automatic controllers, Brown pyrometers.

EXHAUST MACHINE 32 head, capacity 60 tubes per hour, 60 W. type B174 Sealtex chassis.

VACUUM FIRING EQUIPMENT Mfg. by GE.

SEALING & STEM MACHINE 16 head, mfd. by GE.

EXHAUST MACHINE 16 head, mfd. by GE, can be converted to standard tube production.

Many other items of good, used glass working equipment. Please write for details:

HAYDU BROTHERS

Plainfield, New Jersey

ELECTRONIC TUBE-MAKING MACHINERY

For manufacturing radio tubes, electronic tubes, cathode-ray tubes, lamps. New and used. Reasonably priced, satisfaction guaranteed.

AMERICAN ELECTRICAL SALES CO.
67 E. 8th St. New York, N. Y.

D.C. MICROAMMETERS

0-200 ua 3" sq. G.E. DO 50 ..... $ 8.00
0-100 ua 3" sq. G.E. DO 50 ..... 10.00
0-50 ua 3" sq. G.E. DO 50 ..... 12.00

R.F. MILLIAMMETERS

0-115 Ma 2½" Weston 425 ..... $12.00
0-100 Ma 2½" Weston 425 ..... 12.00

PRECISION PORTABLE INSTRUMENTS

Single or multi-range

D.C. Microammeters, from 5 ua full scale. Thermo-couple Milliammeters, from 1 Ma. Thermo-couple voltmeters.

Precision Electrical Instrument Co.
146 Grand Street New York 13, N. Y.

STEPPING SWITCHES

EXCESS INVENTORY LIQUIDATION

This Low Price in Effect Only As Long as This Excess Stock Lasts!

Class Type SD-14
20 Steps, 6 Levels, 120 Contacts Total. Coil 12V. D.C.

CLEARANCE PRICE $13.00
(Immediate Delivery)

Original Price $40.26 List

Satisfaction Guaranteed or Money Refunded

NEOMATIC INC.
879 Wellesley Ave. Los Angeles, 49, Cal.
Phone—ARizona 34897

EDUCATIONAL FREQUENCY MODULATION TRANSMITTER

GENERAL ELECTRIC TYPE BT-10-B MODEL 4BT10B1

SPECIFICATIONS

Carrier power output—2½ watts.

Carrier frequency range—88 to 108 M.C. Tuned to 100 M.C.

Carrier frequency stability—±1000 cycles.

F.M. carrier noise level—65 db below ± 75 kc swing, unweighted.

R.F. load—51.5 ohm line.

Modulation capability—±100 kc. swing, 50 to 15000 cycles with less than 3% distortion.

A.F. input level—10 db ±2 db for 100% modulation at 400 cycles.

600 or 150 ohm input impedance balanced or unbalanced.

A.F. response—± db from FCC pre-emphasis standard 50—15000 cycles.

Power supply—115 to 2300 V. 50, to 60 cycles single phase.

The G.E. transmitter is completely self contained in a modern Hammerlin grey lacquered steel cabinet with stainless steel trim. The cabinet provides radio frequency shielding as well as protection to station personnel. Access to the front is through two doors. There is no power or high voltage accessible from the front and all tuning controls, on-off switches and metering facilities are located there; also all tubes may be replaced from the front. The cabinet is 42½" high, 30" wide and 18" deep and is furnished with an enclosed stand to raise it to rack height (67½") if desired. Access to the rear for service is through a removable panel which has an interlock to remove power when panel is removed.

For further information write:

BENDIX RADIO DIVISION
BENDIX AVIATION CORPORATION
BALTIMORE 4, MARYLAND
Attention: Mr. R. L. Grotefend

ACORN

SERVES SCHOOLS, LABS, INDUSTRIALS— SAME DAY SERVICE

TYPE J POTENTIOMETERS

Singles — 50c each

Ohms	Shaft	Bush	Ohms	Shaft	Bush
50	¾	¾	10K	¾	¾
60	¾	⅜	10K	2½	¼
100	⅜ sw	⅜	10K	⅜ sw	⅜
150	¼	¾	10K	¾ sw	¼
400	¼ sw	⅜	15K	¼ sw	¼
500	¾	¼	20K	¼	¼
500	1¾	¼	20K	¼ sw	⅜
500	⅛ sw	⅜	25K	⅛	⅜
500	⅜	¼	25K	⅛ sw	⅜
500	⅜	¼	30K	⅛ sw	¼
1K	¾ sw	⅜	40K	⅛ sw	⅜
1K	2½	⅜	50K	⅛ sw	¼
1K	⅛ sw	⅜	50K	⅛ sw	⅜
1.2K	⅛ sw	¼	50K	2½	⅜
1.5K	⅛ sw	⅜	60K	⅛	¼
2K	⅛ sw	¼	75K	⅛	⅜
2K	⅛ sw	⅜	100K	⅛ sw	¼
2.5K	⅛ sw	⅜	100K	⅜	¼
5K	⅛ sw	⅜	100K	⅛ sw	¼
5K	1⅛	¼	100K	⅛	⅜
5K	2¼	⅜	250K	⅛ sw	¼
6K	⅛ sw	⅜	1 meg	⅛ sw	⅛
6.5K	⅛ sw	¼	3 meg	1¼	⅜

ATLAS PAGING AND TALK-BACK SPEAKER MODEL HU-15V

Alnico V Magnet. Complete with unbreakable super-efficient driver unit. Power 12 watts, impedance 8 ohms. Length 11", diameter 2¼" air column 15". List $29.75

OUR PRICE **$13.95**

6V6 OUTPUT TRANSFORMER

8000 ohm plate-to-plate 15 w. output. Universal v.c. 4, 8, 15, 250 & 500 ohms.

Upr. mt. Shielded **$1.99**

OIL CONDENSERS

Standard Brands

MFD	Volts D. C.	Prices Ea.
16	400	$1.49
4	600	.69
5	600	.79
6	600	.84
7	600	.89
8	600	1.39
10	600	.99
2	1000	.79
10	330 AC 1000v DC	1.49
12	330 AC 1000v DC	1.49
8+1	1000	1.49
.5	2000	1.79
1	2000	1.44
.25	3000	1.89
.5	3000	2.79
1	3000	2.89
1.5	4000	1.95
.25	4000	2.39
.5	5000	3.39
.25	6000	3.49
1	7500	1.95
.03	10,000	6.95

BEACON RECEIVER

BC-1206-CM—

Made by Stotchell-Carlson

Frequency range—195 KC to 420 KC, IF Frequency — 455 KC. Power supply 24-28 volts. Comes complete with 5 tubes. Includes instruction book. Brand New

$6.45

JANETTE ROTARY CONVERTER

115 v. D.C., 110 v. A.C., .225 KVA 60 cy. 1 ph. Brand New

$19.95

ERIE TRIMMERS

Type 554

5-25 MMF

8-50 MMF

15c each; $10.00 per 100

BIG BUYS IN CHOKES

Mt.	Hy.	Ma.	Ohms DC	Price Ea.
Channel	10	75	200	$0.79
Channel	10	55	330	.69
Channel	2½	235	60	1.39
Channel	8	150	130	1.19
Channel	2½	200	60	1.29
Upright	10	300	55	2.79
Herm. Sealed	15	70	420	.79
Herm. Sealed	10	60	400	.69

APC AIR TRIMMERS

	Each	Per 100
15 MMFD. screwdriver	.20	$15.00
25 MMFD. with shafts	.30	25.00
25 MMFD. screwdriver	.25	15.00
50 MMFD. with shafts	.45	35.00
50 MMFD. screwdriver	.25	20.00
60 MMFD. with shafts	.50	45.00
60 MMFD. screwdriver	.39	35.00
75 MMFD. with shafts	.50	40.00
75 MMFD. screwdriver	.40	30.00
100 MMFD. with shafts	.60	45.00
100 MMFD. screwdriver	.40	30.00
140 MMFD. with shafts	.75	60.00
140 MMFD. screwdriver	.50	45.00

WESTON METER 506

2½" 0 to 500 microamp basic. Scale 0 to 15 v., and 0 to 600 v.

Reduced to **$3.19**

G. E. DC VOLTMETER Type DO-41

2½". 0 to 300 v. 1,000 ohms per volt. only **$3.89**

UTAH POWER TRANSFORMER Y-250

Pri. 150 v., 50-60 cy. Sec. #1, 600 v., c.t. @ 400 mils. #2, 5 v. @ 2 amps. #3, 2½ v. @ 4 amps.

each $ 1.69
10 for 15.00
100 for 35.00

UTAH AUDIO TRANSFORMER—VAT-3

Universal

1:1 S. plate to S. Grid
1:1½ S. plate to S. Grid
1:2 S. plate to S. Grid
1:1 P. P. plates to P. P. Grids
1:2 P. P. plates to P. P. Grids

each $1.19
10 for 10.90
100 for 90.00

ISOLATION TRANSFORMERS

Pri. 115 v., 50-60 cy. Sec. #1, 115 v. @ 90 mils. #2, 12.6 v. c.t. @ 6.3 v. @ 2½ amps.

each $ 1.89
10 for 17.00
100 for 150.00

POWER TRANSFORMER

Pri. 115 v., 50-60 cy. Sec. #1, 450 v. c.t. @ 100 mils. #2, 6.3 v. @ 6 amps. #3, 5 v. @ 3 amps.

each $ 2.79
10 for 25.00
100 for 225.00

TV FLY BACK TRANSFORMERS 211T-5

For Voltage Doubler. 13.5 KV.

$3.45 each
10 for $32.50

MICA TYPE F CONDENSERS—CM 65 & CM 70—Very Special Low Price

Quantities of 25 or more, deduct 10% *Quantities of 100 or more, deduct 20%*

Cap.	Volt	Each	Cap.	Volt.	Each	Cap.	Volt.	Each
.1	1000	$1.26	.00025	3000	$ .73	.0004	5000	$ .77
.05	1500	1.32	.0004	3000	.73	.0005	5000	.84
.075	1500	1.36	.00075	3000	.77	.0008	5000	.84
.00008	2000	.50	.001	3000	.79	.0008	5000	.84
.01	2000	1.08	.0035	3000	1.08	.001	5000	.94
.00033	3000	.58	.0001	5000	.77	.0012	5000	.94
.000075	3000	.58	.0002	5000	.77	.0015	5000	.94
.0001	3000	.58	.00025	5000	.77	.00034	6000	1.11
.0002	3000	.73	.00032	5000	.77			

PHONE WORTH 4-3270

ACORN ELECTRONICS CORP.

76 Vesey St. Dept. E-7 New York 7, N. Y.

TERMS: 20% cash with order. Balance C.O.D. unless rated. All prices F.O.B. our warehouse in New York City. No orders under $2.50

UNIVERSAL SAVES U 50%

Actual Size

H-F TIE POST

LOW-LOSS BAKELITE INSULATION

$7.50/C $67.00 M

LARGE STOCKS OF

AN Connectors	Coils	Resistors
APC's	Controls	Shock-Mounts
Binding Posts	Crystals	Sockets
Cable	Filters	Spaghetti
Capacitors	Fuses	Switches
Ceramicons	Hardware	Servo Xfmrs
Ceramics	Knobs	Wire Xfmrs
Chokes	Potentiometers	Transformers
Circuit Breakers	(Standard-Custom) Relays	Tubes

Write Us Your Needs for Immediate Quote

Min. Order $2.50

Note Our New Address

Universal general corp

324 Canal St. N.Y.C. Walker 5-9642

ONLY 12 AVAILABLE

Brand New—Original Crate & Cartons

$1500.00 G. E. No. 910 Projection T. V. Receiver

with FM-AM and short wave radio

43 Tubes:—540-1620 KC Standard
9.4-12.1 MC. S.W.—2 bands
42-108 MC. F.M.—2 bands

- Screen Size: 18"x24"
- Schmidt Optical System
- 5TP4 Picture Tube
- Complete with AM & FM Antenna, & Connecting Cables
- Includes 2 G.E. 12" P.M. Speakers
- 25 Watts Max. Audio Output

Just the Thing for Custom Installation

Price only **$395.00**

Express prepaid Anywhere in U. S. A.

FS-6838, Electronics
330 W. 42nd St., New York 18, N. Y.

METER MULTIPLIER
Westinghouse RA, 1 meg., w.w., noninductive ½% tol. $.90 each, 10 for $7.50 or 10 multipliers plus 5 Weston or Westinghouse 0-1 ma. meter $10.00

RECTIFIER
Copper Sulphide, F.W.R., 3.6 v., a-c in, 1.8 v. d-c @ 1 amp out. (Fine for 1.5 v. d-c filaments). New, boxed. $.60 each, 10 for $5.00, 100 for $40.00.

TUBES:

Discount 20% on orders over $50.00

1B23	$4.25	714AY	3.75
1N21	.60	715A	7.50
1N23	.60	715B	6.50
2J32	27.50	721A	7.75
3B22	3.50	723A	7.50
3BPTL	15.50	724B	3.50
310A	.35	725A	9.50
800A	2.75	800	15.50
700A	5.75	846	47.50
701A	9.50	872A	1.75
703A	3.75	C6B	2.75
708A	3.75	C6A	5.25
709A	1.00	C6J	4.75
709EY	12.50	FG81A	5.75
707A	12.50	WE-	
707B	7.00	203A	8.75
708A	3.75	VT95	
718A	.75	(Br.)	12.99

SPECIAL: Rectigon, Westinghouse Battery Charger Tube, 4 amp. 65 v., Cat. #B9414/2AN42B2M. New, orig. box. $1.50 each, 4 for $5.50.

Immersion heater, Westinghouse, low surface, 3 heat, oil type, 115 v. 300, 400, and 600 watt, 1¼" male pipe connection with coiled elements projecting 9". List $17.20. Our price $8.50 each, 2 for $16.00.

NEW!
- low prices
- values
- equipment
- components

Note: All merchandise not designated as new is guaranteed to be in excellent to new condition

EPCO
1527 E. 7th St.
Los Angeles 21, Calif.

VACUUM CAPACITOR: 50 mmfd. 12,000 v. d-c. New, original carton. $4.50 each, 4 for $16.00.

TRANSTAT, 115-230 v., 50/60 c., 0-260 v. 2½ amp. cont. 5 amp. max. output. New. Original packing. List $43.00. $17.50 each, 2 for $30.00.

NEW RA-38 RECTIFIERS
..15 v., 60 cy., 1 phase input, output 0-15,000 v. d-c @ 500 ma. Write for detailed information.



CIRCUIT BREAKERS Westinghouse Type "AB" De-Ion, Thermal Trip Without Enclosure, 3 pole, 50 amp frame size. Specify 15 amp, 25 amp, or 50 amp rating. New, $9.75 each, 3 for $10.00.

Filament Transformer
HIGH VOLTAGE FILAMENT TRANSFORMERS: American Type W-8, .650 KVA, 50/60 c., 1 phase; 24 KV test, 12 KV d-c operating; one 5 v c-t @ 10 amps. Has socket that takes 872A, 250T, 371, 5563 etc., rectifiers. Net Wt. 16 lbs. $12.50 each, 2 for $22.50, 4 for $40.00.

MIRROR — front surface aluminized on optical glass 1 3/16" diameter 3/32" thick ..... $.50

PRECISION LEVEL — interior ground tube level with 4 adjusting screws. Overall length 1¾". diam. 15/32". One end with shoulder ¾" diam. $.85

DELCO BLOWER — sirocco type D.C. Flange diameter 3¾" blade 3-3/16" RPM @ 12 volts 3400 RPM @ 6 volts 1400 ..... $2.95

SELENIUM RECTIFIERS — G.E. model 6RS 8FB3 maximum A.C. volts 54 D.C. amps. 0.150 ..... $1.35

CIRCUIT BREAKER — 10 amp 30 volt D.C. C-H. Cat. #2751K4 ... $1.10

GLASS VIAL — to use as a permanent level on equipment $1.00

Miniature lamp T1¾. 1 volt .19 amp. Airplane Indicator, Amb. Ctd.
10 for ..... .85
100 for $7.50

Lamp Assembly C202 Genl. 1 Made by Eastman Kodak with Iris Diaphragm 12 volt lamp ..... each $1.95

WATTHOUR METER SINGLE PHASE— G.E. type 1-16 two wire 5 amp. 115 volt 60 cycle $5.75

SEND FOR FREE BULLETIN

TELEPHONE BEEKMAN 3-0929
A. Cottone & Company
ELECTRONIC MECHANICAL & OPTICAL COMPONENTS
220-240 CANAL ST., NEW YORK 13, N.Y.

ALL PRICES F.O.B. N. Y. CITY

NEW HOLTZER-CABOT TOTALLY ENCLOSED MOTORS



50 R.P.M. Reversible Single Phase Capacitor-Run type. 115 Volts AC 60 cycle 0.3 Amp. Torque 100 oz. inches. 4¾" shaft ¾" dia. 250 left. $16.50 ea. SAMPLE $17.50

GRAIN OF WHEAT LAMPS

Used for illuminating meters, compass, dials, airplane instruments, etc. Soldering iron removes lamp from base to use in models, doll houses, miniature trains, Xmas trees, etc.
Mazda G.E. 323 Mazda G.E. 328
3V..19 A 6V..2A
Either type, doz. **$1.50**

MARKTIME 5 HOUR SWITCH
A 10 amp. timing device. Pointer moves back to zero after time elapses. Ideal for shutting off radios and TV sets when you go to bed. Limited supply at this special PRICE **$3.90**
Also available in 30 min. and 1 hr. at $6.90

ISOLATION TRANSFORMER $1.95
Nat. known Mfgr. 50 watt 2 windings, 115 V. to 115 V. 60 cy. Ideal to prevent shocks from small radios and medical and electronic devices. Shipping Weight 5 lbs.
Other sizes and 220-110 in stock.

Rilewatt Demand Meter Totalizer containing heavy duty TELECHRON D-7, 1 RPM motor and hundreds of watch size gears, clutches, springs, etc. Shipping weight 2 lbs. **$2.50**
5 for $10.00

Fractional H.P. Motor Brushes & Springs. Assorted Sizes will fit any motor ..... 20 for $1.00
150 for $5.00—500 for $10.00

RUSSELL 110V AC MOTOR $1.95
3 for $5.00

RCA 100A
Free Floating Cone Type Magnetic Loud Speaker. Removed from rooms of a large N. Y. Hotel. Original cost $32.00 ..... $1.85
3 for $5.00

GONIOMETER CFT—47243 CFT—47372
We are Authorized Wholesalers for Micro Switch Corp. and carry the largest stock of Allen-Bradley Solenoids, Potter & Brumfield Relays, Guardian Electric Co. Solenoids and Relays and Haydon Clock Motors in all speeds. Electric Counters.

EST. 1923 **BLAN** EST. 1923
Experimenters and Inventors Supplies
64 Dey St., New York 7, N. Y.

MID SUMMER CLEARANCE SALE

Transtat 103-126v, 250va, 60cy. $3.95
Auto-Xfmr. 425v-117v, 2½a. can use for 117 to 33v. full cased 1.95
60 Amp. Xfmr. 6dv in, 15v-60a out 1.95
Use two in series for 30v-110v, two for... 3.95
PULSE TRANSFORMERS. 9262 ..... 1.49
D161310 (50kc-4mc) 100-2000 ohms 1.49
Ux 7250 plug-in, to .05 ms pulses 2.49
L406824, 250v-a out 500v-3a. 6 ft ohm dc... 1.49
K346SB, 250kva@¼ma, 50 ohm in. 17KV out 13.50
C-12A, 1216, 50 to 10 milliheavy 1.95
Mod. Xfmr. 720 ohm to 2600, 70 ma ..... .39
IF Xfmr. 455KC K-Tran or 4Mc rd. RCA ..... .39
Choke, 1.7H tapped .85H, 1¼" x 2" cased .... .39
Choke, 5H-165ma small strap mtg 80c/30 or .93 ea.
Choke, 10H-110ma cased Wemco ..... .95
Variable Choke 100-400micro henry ..... .18
Var. Choke ceramic, ten turns, iron slug ..... .23
RELAYS, Allied 3J dpdt, ceramic 110ac..... 2.98
3J dpdt, 24vdc ..... .49
10XBX102 6D dpdt, 24dc has shaded pole so that two in series work on 110ac ..... .89
Sigma 2000 ohm plug-in, 3ma spdt 3a. ..... .90
RBM 110 vac spec. no bounce contact dpdt.. 1.35
Cook 1200 ohm 4½ma sp n.o. ..... .59
Stepping relay, 4 pole 25 pos. 24vdc..... 12.50
Delay Adj. 1 to 50 minute sec. motor spdt.. 5.95
Five Minute delay w motor n.o. 10a.. ..... 3.00
Wafer Switch, 5pole 8pos. adj. stop..... .75
Mercury Switch ⅝"x¼" w leads..... .29
Toggle spdt center off 5A 125 vac ..... .19
Mom. Sw, bush. mtg. 3A-250, dpst n.o..... .28
Clock Meters 15, 1, 1/60 RPM 115 vac..... 2.49
Marktime switch set up to 4½ hrs 10a..... 3.95
Variable Speed Drive, GE, ¼HP 7500 RPM motor, differential drive giving continuously var. speed out: 60-0-60 rpm. Terrific Steal..... 14.95
20 Cond. Cable, 500' long... $4.50, 1000'... 11.00
COAX CONNECTORS PL 258 (83-1J) — 60c.
PL 274 95
Type N: UG21U, UG22U—60c. BN: UG87, UG87 60
BNC: UG88 $1.15, UG220—85c. UG89 ..... 1.15
TEES: UG 107, UG 28..... 1.98
Sperry Tee: 5657707 DR #2-201..... .75
PL 259, SO239, PL 259A ..... .32
M359 (83-1AP) 15c, UG 167 pulse to N 1.50
49482 special 83-1SPN with small hole, RG58 .45
Tubular Condensers, 1, .5, .25, .1mfd ..... .10
.05, .025, .02, .01, .007, .005, .001mfd ..... .09
Capacitors 3mfd 12KV $35, 5mfd 10KV $35, 1mfd 20KV—$17, 8—4mfd6KV—$20, .25mfd 32KV $20
1KVA Transformer 7KV 1¼a many taps.. $235
Pots WW, CTS, 4w. Extra high quality: 6, 50, 100 400, 500, 1K, 2K, 3K, 4K, 5K, 7.5K, 10K, 15K, 20K ohms & most in 2 watt, reg. $2 value, ea. 45c
Complete Stocks Turret Sockets, AN connectors Closeouts, etc. Recoil and Service, ALL NEW ITEMS

HAROLD H. POWELL
632 Arch Street Philadelphia 6, Pa.

SHEET METAL MACHINERY
NEW and Used—Brakes—Shears
Forming Rolls — Folders — Punches — Di-Acro, Pexto, Niagara & Whitney Equipment.
B. D. BROOKS CO., INC.
HAncock 6-5200
361 Atlantic Ave., Boston 10, Mass.

STOP HERE!

YOU CAN'T BEAT THESE PRICES TRANSMITTING

TUBES

BY NATIONALLY KNOWN TUBE MANUFACTURER
NEW, BOXED, FACTORY PRE-TESTED & GUARANTEED
IMMEDIATE DELIVERY
10% Discount on Orders over $500

TRANSMITTING TUBES

24G	$ .25	332	$14.50
HF60	2.65	332A	14.50
HF100	3.25	333	16.25
111H	5.45	343A	115.00
ZB120	4.50	446	8.50
HF120	6.25	520MT	67.50
HF140	8.50	520B	67.50
HF150	6.25	562A	85.00
HF175	7.25	805	2.25
HF200	9.00	810	5.00
HF201A	9.00	813	4.50
204A	40.00	830	2.75
212E	32.50	838	1.75
217C	7.25	845	3.25
220C	115.00	846	100.00
220K	115.00	849	15.00
228A	100.00	849A	17.50
232CH	100.00	849H	45.00
242C	4.50	858	100.00
249B	1.75	859	175.00
249C	1.35	869B	17.95
HF250	10.00	889A	67.50
258B	3.65	891	80.00
264B	.25	891R	115.00
267B	8.95	1652	115.00
270A	45.00	4125A	20.00
284D	5.50	5809	4.50
304B	4.50	5905	3.75
308	32.50	5948	3.50
331	4.50	6011	.85

Get Solo's Prices on Other Tubes Before Buying
All Prices F.O.B. N.Y. Minimum Order $5
5% Deposit (Check or Money Order) Bal. Sent C.O.D.
Rated Companies—Send Purchase Order
Cash For Your Surplus Inventories

SOLO Electronics Sales Corp.
168 Washington Street
New York 6, New York
Phone—WOrth 2-1042-3

VU VOLUME LEVEL INDICATOR, Weston 642 type 30 Scale B, reads in % voltage and in VU 3-15/16 x 4-1/4" semi-flush mounted bakelite case, with external illumination feature. Designed for monitoring purposes for broadcasting, recording, and sound studios. A Real Buy at

Only $22.50

DECIBEL METER, HIGH SPEED TYPE, multirange, Weston 301 type 61, minus 10 to plus 6 DB, 6 MW in 600 Ohms, zero DB equals 1.9 volts, 5000 ohms. Complete with 3 external wire wound precision resistors to extend the ranges of 16, 30 and 50 DB at zero scale. 3⅛" round flush bakelite case

Only $11.50

SOCKET SELECTOR SET—A must for all who have occasion to check tube circuits, etc. Weston 666—type 1C.

Designed for purpose of taking readings of currents, voltages and resistance and other electrical measurements in a vacuum tube circuit. It can be used with any Analyzer or multirange volt-milliammeter. To test a tube circuit the tube is plugged into the appropriate adapter and the test plug inserted in the tube socket. This brings all currents and voltages out through a cable where they may be measured with an analyzer.

Complete with Tube Base Data Connections and Chart, 15 adapters, pin leads and test block.

Ideal for checking television and complicated circuits as it REDUCES SERVICING TIME TO A MINIMUM. List Price $30.00

Only $9.50

PORTABLE OHMMETER Weston 564 type 21, 60 ohms full scale, 7 ohms center scale (basic movement is 400 microampere 2.2 MV movement)

Only $12.00

PORTABLE MICROAMMETER, Weston model 440, 0-15 microampere approximately 154 ohms resistance, CAN BE USED WHEREVER MEASUREMENTS MUST BE MADE IN LOW ENERGY CIRCUITS, as in thermocouple and photo cell applications. Accurate within 1½%. Dimensions approximately 6⅝" x 4¼" x 2⅝", with leather carrying case and straps.

Current Total List Price $106.50

Only $35.00

SENSITIVE RELAY, WESTON MODEL 20 Permanent magnet moving coil type, for use for regulating currents within narrow limits. IDEAL FOR USE IN VACUUM TUBE AND PHOTOCELL CIRCUITS. Has a high and low sensitivity range of 50-0-50 Microamperes (50 microamperes value to close contacts) and is used to control non-inductive circuits up to 6 volts. Furnished in a surface type case approximately 3⅛"L x 3⅛"W x 3½"D with 5 binding posts.

Only $14.50

SENSITIVE D.C. VOLTAGE RELAY same as above except sensitivity of 32 volts low and 33 volts high, at approximately 400 ohms.

At $11.50

SENSITIVE D.C. VOLTAGE RELAY same as above except sensitivity of 20 volts low and 21 volts high, approximately 550 ohms.

At $11.50

D.C. DIFFERENTIAL VOLTAGE RELAY same as above except effective on 2.5 volts unbalance with maximum line voltage of 125, approximately 400 ohms.

At $11.50

VOLTAGE RELAY—20% to 0 to ∅ 20%

A suppressed zero instrument, with 2 Adjustable Pointers to control operating limits. There is a potential difference of 80 M.V. from —20% to end scale (∅ 20%) with zero (center scale) equal to 150 M.V. at 150 M.A. Roller Smith type CMR-2. Measures 5"L x 3¼"W x 3¼"D, projection mounted case.

At $4.95

PORTABLE A.C.—D.C. MULTIRANGE WATTMETER, Westinghouse PY-5, Accuracy within ¼ of 1%. Range 1250, 2500 & 5000 Watts. Normal 5/10 amps and 250/500 volts. Electrodynamometer type. Dimensions approximately 7-1/4 x 8-1/16 x 4".

Only $65.00

PORTABLE A.C. VOLT-AMMETER, FOUR METERS IN ONE, Westinghouse PA-5, Accuracy with ¼ of 1%. Ranges of 5 and 10 amps, and 300/600 volts. Dimensions approximately 7¼ x 8-1/16 x 4". Push button for voltage readings.

Only $55.00

PORTABLE A.C. VOLT-AMMETER same as above except ranges of 5 and 25 amps, and 300 and 600 volts.

Only $55.00

NOTE: ANY OF THE ABOVE INSTRUMENTS CAN BE EXTENDED TO COVER HIGHER AMPERE RANGES BY USE OF THE

CURRENT TRANSFORMER, WESTON 461 TYPE 4. This unit when connected to the 5 amp. binding posts will extend the ranges of these meters to 50, 100, 200, 250, 500 or 1000 amperes A.C. ¼ of 1% accuracy.

List Price $50.00

Only $35.00

Weston 433 PORTABLE A.C. VOLTMETER FREQUENCY RANGE 25 to 2400 CYCLES 0-150 Volts, Weston 433, Accuracy within ¼ of 1% on A.C. from 25 to 1000 Cycles and within 1¼% up to 2400 Cycles. Knife edge pointer; hand calibrated mirror scale; shielded moving iron vane movements; Resistance approximately 2200 Ohms. Scale length 4.04", in case 5" x 6" x 3¼". Similar to illustration.

Only $35.00

ALL ITEMS ARE BRAND NEW-SURPLUS-GUARANTEED. All materials shipped from stock same day as order received, subject to prior sale.

MARITIME SWITCHBOARD
338 Canal St., N. Y. 13, N. Y.
Worth 4-8217

Orders accepted from rated concerns, public institutions and agencies on open account, others please send 25% deposit, balance C.O.D. or check with order. All prices FOB our warehouse, N.Y.C.

LOOK

AIRCRAFT RADIOS ACCESSORIES

274-N Command Equipment (Brand Spanking New)

BC-453B Receiver 190-550 KC	$18.00
BC-696 Transmitter 3-4 MC	24.50
BC-458 Transmitter 5.3-7 MC	7.50
FILTER FL-8B, new	1.25
FL-5, new	.75
HEADSETS HS-33, Mfg. W. E., less headband (Factory Cartons)	$ 1.25
Extension Cord CD-307A for HS-33, new	.40
THROAT MIKE T-30V, with CD-318 Cord. Press to talk Switch and PL-68 plug, new	$ 1.00
MN-20E (Loop Type), new	7.50
RL-42B Antenna Reel, reversible motor, ideal for Rotating Antenna, new	$ 3.50
SPECIAL METER (Vibrating Type) 100-130 volts, 380-420 Cycles, new	$ 4.25
INVERTER FOR ADF, Mfg. G. E., new	7.50

COAXIAL CONNECTORS

83-1AP M359	$ .15	UG 21/U	$ .60
83-1SP PL259	.25	UG 22/U	.80
83-1T M358	1.00	UG 27/U	.80
PL-55 new	.35	PL-68 new	.20

PL-293 rt. angle adaptor for Twinax $ .75
Adaptor, fits PL-259 for small Coax .10
Clamp, M297 for PL-259 .08

IN STOCK ARC-1, ARC-3, ARC-5 VHF, BC348-O, R5A/ARN-7, SCR-522-C, RA-1B, RA-2, RTA-1B, R89B, TA2-1B24, R-28/ARC-5, T-23/ARC-5, RA10-DB, R8/ARN-8, T47A/ART-13, above subject to prior sale.

WHAT ELSE DO YOU NEED?

SOUTHERN SKYWAYS
R-20 Love Field Terminal
Dallas 9, Texas

MILLIONS OF
RESISTORS

½-1-2 Watts

FOR THOSE IMMEDIATE REQUIREMENTS

LIFE ELECTRONIC SALES

91 Gold St. **DI 9-4154** **N. Y. 7, N. Y.**

HETERODYNE FREQUENCY METER LM-14

- 125 — 20,000 KC
- Internal Modulation
- Orig. Calibration Book & All Cables
- With Orig. Rectifier Power Supply For 115V-60CY. Operation

$110.00 Complete

FS-6000, Electronics
230 W. 42nd St., New York 18, N. Y.

SELENIUM PHOTO ELECTRIC CELLS

Manufactured by Selenium Corp. of America

Generates current without batteries. Build your own photoelectric equipment. Use to make photographic exposure meters, colorimeters, photometers. Operate sensitive relays to open doors, start machines, turn on lights, 1001 uses.

A Precision Item — Worth $5.00

$1.00 POSTPAID U.S.A.

WARREN INDUSTRIAL CO.
56 Warren St., Dept. B, New York 7, N. Y.

WESTINGHOUSE HIPERSIL CORES

OVER 40,000 UNITS IN 20 DIMENSIONS, SEVERAL GAUGES; UP TO 16,000 UNITS IN SOME SIZES. AVAILABLE FOR IMMEDIATE DELIVERY. SEND FOR LIST WITH COMPLETE DESCRIPTIONS.

RAYTHEON MFG. CO.
Surplus Sales Dept., Waltham, Mass.
Tel. Waltham 5-5860—Ext. 2

GIANT VALUES



HAYDON synchronous motor—110 Volt 1/2 RPM Brand new $1.47 each

Electrolytic Condensers Standard Brand.

NEW Black Bakelite Screw

Type 40mfd 600 v.p. 79¢

Vacuum Capacitors GL-1 L24 100 mmfd 20000 v. $4.95

VC 50 50 mmfd 3000 V.P. $3.95

VC 25 25 mmfd 30000 V.P. $3.95

SOCKET 4 prong Westinghouse for KU627 Tube, or similar type. 3 inch hole 15¢

OIL CONDENSER 4 mfd 600 volts DC Standard Brand Type 609X 55¢

MULTI SWITCHES

Arkiee Type 2JR15—3 amps @ 125 V DC, 10 Amps @ 125 V AC $3.67

A-H-H Type JR 501P, 5 Amps @ 125 V DC, 10 Amps @ 125 V DC $2.15

SWITCHES Arrow H.H. D.P.S.T. 20 Amps @ 250 V 1½ H.P. @ 250 V $1.75

RELAYS

110 V AC. Allied Type B015A115 D.P.D.T. $1.45

1 15V AC. Guardian Elec. 1 Side Open 1 Side Closed 75¢

POTENTIOMETERS W. W. Tree Z Mfg. 2000 Ohm. 50,000. Ohm Screw Driver Shaft 38¢

THORANSON TRANSFORMERS

Pri. Voltage	Sec. Voltage	Fit.	
115V 60C T19P65	6000 V CT 4840 CT	300MA	$24.50
115V 60C T19P62	4800 V CT 4200 V CT	300MA	22.50
115 V 60C T19P61	4250 V CT 3750 V CT	300MA	17.50
115V 230 V 60 C T 13P12	650-500 V CT	200MA	8.95

U T C TRANSFORMERS

S43 115 V 60 C 525-525 V 40-40 5V-3A 5V-6A 6.3VCT 2A 6.3V CT5A 450 MA 200 MA $12.50

PA 301 115 V 60 C Plate Trans $14.25

Germanium Diodes 1N34 $0.69

UG Connectors Ask for quotation on Quantities

UG 9 U	$ 0.75 each
UG 36 U	10.00 each
UG 234 U	10.00 each
UG 250 U	10.00 each
UG 58 A U	1.45 each

Turner Microphones Type 9DH1 NEW $8.75

Tubes in original boxes Nationally Advertised Brands

26	40¢	721	$2.95
56	52¢	575A	$11.95
27	40¢	CRP-72	$1.25
6X5 GT	48¢	WL 872 A	$2.25
24A	46¢	3 B 24	$1.45
12Q7	46¢	4B31	$10.45
75	50¢	1B51	$9.75
6J4	$4.50	FG 104	$12.75
2050	99¢	FG 105	$9.95
4C35	$18.75	Rectifier Tube EL 1C	
6N7 BN	70¢		$1.71

NO RISK TO YOU

ALL MATERIAL OFFERED BRAND NEW! ONLY A PARTIAL LIST

LEONARD GREENE

360 Tremont St., Boston, Mass.

Phone: HAncock 6-4794

SOUNDTRONICS SPECIALS

JULY SPECIAL

New Army **MINE DETECTOR** AN/PRS-1. Will detect metallic and non-metallic objects, buried cables, etc. Uses 3-45 V. & 1-6 V. Batteries. Complete w/spare rods, tubes, etc. Less Batteries. In original overseas packing $16.95

TRANSFORMER POWER SUPPLY — 115 V. 60 Cy. 300 V. @ 55 MA., 6.3 V. @ 2 Amps. Has—5Y3, 2—8 HY. Chokes, 3—30 MFD Filters, Pilot, Term. Strip. Meas. 5" x 5" x 8". Completely wired $6.85

6 V. 12 Amp. **TRANSFORMER** 115 V. @ 60 Cy. Inp., Open Frame 2½"x3"x3½" $1.65

Weston Model 425 R.F. Amp. Meters

0-2 Amps	$5.49	0-5 Amps	$6.95
0-3 Amps	5.95	0-10 Amps	7.49
0-4 Amps	6.49	0-15 Amps	7.95

Accurate within 2% up to 60 meg.

Glass Insulated Wire #22 Stranded Various Lengths 100' 59¢; 1000' $4.50

SELENIUM RECTIFIERS

Single Phase Full Wave Bridge

Input 0-18 Volts	Output 0-14 Volts
2.4 Amps	$3.07
6.4 Amps	4.00
18 Amps	7.67
17.5 Amps	8.69

SPRAGUE NOISE FILTER

7 Amps. 150 V. A.C. 400 V. D.C. #JN65 $2.49

9 **COAX CABLE RG11U** with PL 259 on each end 69¢ ea. 10 for $5.00

U.T.C. CHOKES P. A. STYLE

10 Hy. @ 66 MA.	400 ohm DC. R.	$ .97
10 HY. @ 110 MA.	80 ohm DC. R.	1.40
10 Hy. @ 150 MA.	126 ohm DC. R.	2.25
5 Hy. @ 150 MA.	120 ohm DC. R.	1.85

W110B TWISTED PAIR TEL. FIELD WIRE

Stranded 4 Steel, 3 Copper, Weatherproof

½ MI. Reel	$4.95
1 MI. Reel	9.25

FOLLOWING EQUIP. USED BUT LIKE NEW

U.H.F. Signal Generator. Similar to RCA Type 710A. 470 to 560 Meg. Output, 1 Microvolt to .08 V. 400 Cy. Int. Mod. Dial Cal. Directly in Meg. Cavity Tuner. Cal. Piston Atten. Ideal for Citizens Band $145.00

TRANSTATS—3.9 KVA 1 Phase 50/60 cy. fixed winding 115/230 V. output 0-260 V. Max amps 15 $42.00

5.85 KVA 1 phase 50/60 cy. fixed winding 115/230 V. output 0-260 V. Max amps 25.5 $52.00

SOUND LEVEL METER. Type RA 142A. Made by Electrical Research Products Co. $125.00

SA3 & SL RADAR UNITS

SOUNDTRONICS LABS.

632 Arch St., Phila. 6, Pa. MA 7-2775

FREE Bulletin of World's Biggest Bargains in Surplus and Closeout Stocks of...

NEW ELECTRICAL WIRE & CABLE

Send Request on Your Letterhead to:

STANDARD WIRE & CABLE CO.

9608 Venice Street

Culver City, California

Brand New BLOWERS

115 Volt 60 cycle, approx. 100 Cubic Ft. Min. 3¼" Intake, 2" outlet. Motor size 2⅛" x 3". 1525 RPM. Complete with mounting bracket. Gov't surplus. Brand new and Boxed.

Order No. E-3084 **$7.95**

SELENIUM RECTIFIER UNITS

HEAVY DUTY—30 VOLT DC OUTPUT:

115/230 V. Three Phase 400 Cycle Input:

TYPE 143 w Transformer & VR 100 amp. $89.50

TYPE 3FS-5 w Trans., VR, & Blower 200 amp. $99.50

TYPE 52A-11 Rectifier only, Cased 200 amp. $49.50

TYPE A1 Rectifier only, Cased 300 amp. $59.50

TYPE RE-60 Rectifier only, Cased 400 amp. $69.50

WRITE TODAY FOR QUOTATION ON YOUR DYNAMOTOR OR INVERTER NEEDS!

WHIP ANTENNA EQUIPMENT:

MAST BASES—INSULATED

MP-132—1" heavy coil spring, 2" insulator. Overall length: 11½". Weight: 2½ lbs. Price $3.95

MP-22 Spring action direction of bracket. 4" x 6" mounting. Price $2.95

MAST SECTIONS FOR ABOVE BASES:

Tubular steel, copper coated, painted, 3 foot sections, screw in type. MS-53 can be used to make any length, with MS-52 51-50-49 for taper. Price, per section 50¢

SECTIONS MS-54—55 Larger than MS-53 75¢ ea.

BAG BG-56 for carrying 3 mast sections 50¢ ea.

METERS:

0-150 Volt AC 3" Round	$3.95
0-150 Volt 400 Cycle 2½ Round	2.95
0-5 Amp. AC 3" Rd. 0-100 A. Scale	3.95
0-5 Amp. AC 3" Rd. 0-75 A. Scale	3.95
0-5 Milliamp AC 2½" Square	2.95
0-500 Microamp 2½" Rd. w/0-15 & 0-600 DC Volt Scale	3.95

GENERATOR—12 Volts 4 Amps. and 240 Volts DC 100 MA. 3450 RPM. 3-16 HP. Shaft size: ½" x 1⅛". Price $6.95

PI AIRCRAFT GENERATOR—24 Volts 200 Amps. Prices: NEW $30.00 REBUSE $18.95

Address Dept. E • • • All Prices Are F.O.B. Lima, O. • 25% Deposit on C.O.D. Orders

FAIR RADIO SALES

132 S. Main St. LIMA, OHIO

LARGE QUANTITY AIRCRAFT RADIOS

RT-18/ARC-1 VHF SETS

Famous VHF airline communications transceiver, beautifully reconditioned. Available for delivery from stock 10 or 20-channel. Price on request.

BENDIX RTA-1B SETS

Famous MF and HF airline communications transceiver, in stock for 24-volt operation or dual 12-24-volt. Brand new and reconditioned. Price on request.

MG-149-H 400 CYC. INVERTERS

Brand new in original cans. Input: 28 v.d.c. output 115-v 1 ϕ 500 va and 26V 1 ϕ 250VA $35.00 ea.

PE-109-D 400 CYC. INVERTERS

These are the scarce 12-V input models. Brand new in original cartons. Input 12-V D.C. Output: 115-V 1 ϕ 175 VA. $50.00 ea.

ARC-1 ANTENNA RELAY

Antenna Change-over Relay K-101 of Transceiver RT-18 ARC-1 Brand new. Deliveries begin July 30th quantities will be limited. ORDER NOW. Quantity prices on request. $30.00 ea.

Write for 8 page catalogue

AIRCRAFT RADIO INDUSTRIES, INC.

274 Madison Ave. State & Eld

N.Y.C. LE 2-6254 New Haven, Conn.

★ ★ ★ ★ ★ ★ ★ ★ ★ ★

AAF
SURPLUS VALUES!

SPECIAL PURCHASE!
Air Force Field Clearance
All items available NOW!

★ ★ ★ ★ ★ ★ ★ ★ ★ ★

AAF
SURPLUS VALUES!

TEST EQUIPMENT • TEST EQUIPMENT • TEST EQUIPMENT • TEST EQUIPMENT • TEST EQU

TEST OSCILLATOR
TS47/APR.

A real precision instrument! Complete with self contained power supply and power cord. Tunes 40-500 MC with usable harmonics up to 3000 MC. Used, top condition. Priced at a fraction of its original cost..... $125.00

1—100 TEST SET

For ARN7 or SCR-269. Indispensable for doing the right job on aircraft or marine radio-compass work. Contains BC-733-A and BC-714A. With cables. Just like new! A sensational buy at..... $395.00 Dealers: Write for quantity discount!

TS-170/ARN-5 GLIDE PATH TEST SET

Battery oper. portable oscillator; provides xtal controlled signal at 332.6, 333.8 or 335 MC. May be modulated internally at 90, 150, 1000 cps., or unmodulated, for glide path channels GX, GY and GZ..... $95.00

FREQUENCY METERS

TS 164/AR. Airborne version of BC-221. With original calibration book..... $75.00
TS 174/U. 20-250 Mc..... $200.00
TS 175/U. 80-1000 Mc..... $250.00

ELECTRONIC LABORATORY SPECIALS!

- TS-14 FIELD RADIATION TEST SET
- TS-35/AP X BAND SIGNAL GENERATOR 8700-9500 MC. Complete with all cables!
- TS-36 POWER OUTPUT TEST SET..... $75.00
- TS-45A/APM-3 SIGNAL GENERATOR 9200-9600 MC 110v. 60-800 cycle; NEW $175.00
- TS-126/AP RANGE CALIBRATOR OSCILLOSCOPE Manufactured by Galvin..... $125.00
- TS-143/CPM-1 SYNCHROSCOPES Outstanding precision instruments, manufactured by Galvin..... $175.00

ORDER DIRECT FROM THIS AD!

Cash with order. 25% deposit on all COD orders. All orders shipped by truck or RR Express collect. California buyers please add sales tax. Prices subject to change. All merchandise subject to prior sale.

Unless otherwise stated all equipment is used, in good condition

ALVARADIO SUPPLY CO.

- DEPARTMENT L-5
- 341 S. VERMONT
- LOS ANGELES 5, CALIF.

GENERAL RADIO COUNTING RATE METER. Type 1500A.

GENERAL RADIO MICROVOLTER. UHF Generator 8-330 MC..... $177.00

WESTERN ELECTRIC COMPUTER POTENTIOMETERS D170545, 6, 7 and D170561 each $8.50

BC-376 MARKER BEACON TEST UNIT. Crystal controlled portable 75 Mc Transmitter. Output may be tone modulated at 400, 1300 or 3000 cycles per second. Top value at... $85.00

IE-19 TEST SET

for SCR-522. Complete; good cond. A real bargain..... only $125.00

•

1.8 KW DYNAMOTOR TEST SETS. $49.00

BC-797 VHF AIRPORT CONTROL TRANSMITTER

Mfd. by Radio Receptor Co. Freq. 116-126 MC. 115v. 60 cycle power supply. Complete with all tubes. Excellent condition. A real buy!

AN/ARM-1 Test set for ARC-3..... $125.00
AN/CRM-3 Localizer Test Set..... $200.00

A. C. POWER ANYWHERE
with Katolight Plants and Generators



Lighting Plants

Three 10 KW, 1200 RPM Generators powered with Minneapolis – Moline Engines complete with 6 Volt starter and generator, each..... $99.00



Motor Generator Sets

One 1000 Watt, 400 cycle Generator driven by a 2 H.P., single phase Motor..... $240.00
One 1000 Watt, 110 Volt A.C. Generator, driven by a 110 Volt, D.C. Motor..... $220.00

Lighting Plants

One 2500 Watt, 115 Volt, 60 cycle, A.C. $250.00



All offered subject to prior sale.

KATO ENGINEERING COMPANY
105 Maxfield Avenue
Mankato, Minnesota

BANISH FOREVER HOT *DAYS! NIGHTS!*

FIRST TIME ANYWHERE AT THIS LOW PRICE!



- USES NO WATER
- COOLS
- Shuts Out Noises
- Filters Out Dust, Dirt and Pollen
- Patented Filter
- CONTINUOUS VARIABLE CONTROL

NO WIRING OR ALTERATIONS

PLUGS IN LIKE A RADIO—NO INSTALLATION REQUIRED

HOMES • OFFICES • HOTELS • HOSPITALS • SHOWROOMS

PERFECT VENTILATION. Air filtration is assured by use of PATENTED FILTER for ELIMINATING DUST, DIRT and POLLEN from outdoors.

Ventilates your room with CLEAN, COOL, FILTERED AIR — SUMMER or WINTER. Enables you to SUBDUE outside NOISES by keeping windows closed and to get the amount of air you want, whether calm or stormy.

Easily ADAPTED TO ANY WINDOW without cutting or marring; mounted flush with inside of window for pleasing appearance.

Cabinet is made of HEAVY STEEL with "BAKED ON" BRONZE HAMMERTONE FINISH. Will blend with all home, office, or showroom surroundings.

References: Marine Midland Trust Co. of N. Y., 143 Liberty St., New York, N. Y.

Regular Price $85.00

YOUR COST 110 V. 60 Cycle AC **$44.95***

Regular Price		$120.00
YOUR COST	110 V. D.C.	$59.95*
	220-230 V. A.C.	59.95*
	220-250 V. D.C.	59.95*

TERMS: 20% Deposit Balance C.O.D., F.O.B., N.Y.C.
* Plus 10% U. S. Excise Tax
N. Y. C. Residents: Add 2% City Sales Tax

MANUEL KLEIN, 74-76 Cortlandt St., New York 7, N. Y.
REctor 2-6460

"TAB" THAT'S A BUY TUBES

Tested-Guaranteed

0	.59	2A6	.75	5W6	.66	6J6	6.45	7F8	1.25	723A	6.95	5516	5.85	K49A	.36
0A2	5.20	2A6	.75	5X4	.66	6J6GT		7F8/7GT		723A/B	7.98	5646	18.98	K55B	.36
0A2/VR75	.98	2A7	.75	5X4G	.66	6J6GT/1232	.98	7F7/7F7/1232	.98	724A/B	2.49	5654	4.23	M35B	.36
0A4G	.94	2B7	.78	5Y3GT	.38	6J6	.70	7H7	.88	724A	6.39	5817/CK		L62A	.49
0B2	1.54	2B22/GL559	.75	5Y4	.45	6J7	.65	7J7	.98	726A	5.95	1613	1.89	K90B	.36
0B2/VR90	.74	2C21/1613	.85	5Z3	.51	6J7GT	.50	7K7	.65	726C	29.98	CK5702	8.89	WL121A	2.61
0C2/VR105	.78	2C22/7193	.98	5Z4	.54	6J8GT	.95	7L7	.67	730A	9.95	CK5724	9.95	C37A	2.95
0D3/VR150	.67	2C26	.18	C6A	7.85	6K8GT	.79	7N7	.65	801A	.29	CK5734	5.59	ZB583	5.98
0Z4	.56	2C34/RK34	.21	6A3	.90	6K6GT	.42	7Q7	.57	802	4.65	5612	2.98		
0Y4	4.50	2F2	.89	6A4	1.00	6K7	.48	7R7	.67	803	2.85	UX5653	2.49	Meade Pilots	
1A	.45	2G40	4.90	6A6	.75	6K8	.78	7S7	.89	805	2.85	6F12A	1.35	44, Box 10	.50
1A3	.62	2G43/464A	7.95	6A7	.66	6L5	.78	7T7	1.03	807	2.49	6H12A	7.98	49, Box 10	.60
1A4	1.00	2G44	.98	6A8GT	.72	6L6	.98	7V7	.77	809	5.89	6H13A	7.98	55, Box 10	.60
1A5GT	.68	2G45	.79	6A8G	.79	6L6G	.82	7W7	.77	810	1.19	6Q9P	.87	85, Box 10	.87
1A6	.78	2C51	6.98	6AB5/6N8	.58	6L6GA	.82	7X7/XXFM	.77	811	.65	9001	.31	87, Box 10	.97
1A7GT	.63	2C52	5.06	6AB7/1853	.77	6L7	.77	7Y4	.44	812	.65	9002	.23	56,74,3W	.15
1B3/9016	.65	2D21	.98	6AC5	.65	6N4	1.00	7Z4	.45	813	4.50	9003	.30	100W 20V	.25
1B4	1.10	2E5	.89	6AC7	.78	6N6G	1.49	10Y	.29	814	2.98	9004	.24	211, Box 10	.45
1B5/25S	.84	2E22	1.15	6AC7W	1.30	6N7GT	.75	12A6	.39	815	2.98	9005	.24	311/28V	.15
1B7GT	.98	2E24	2.50	6AD4	.98	6P5G	.81	12A7	.42	826	1.19	9006	.24	323/28V	.10
1B21/671A	2.98	2E26/HY68	6.89	6AD5	.57	6P5GT	.88	12A8GT	.48	829	6.49	3GP1	4.89	Sylvania 6s/	
1B22	4.50	2E36	3.38	6AD7	1.00	6R7	.77	12AH7GT	.58	832	1.15	3HP7	4.50	6W/120V	.15
1B23	8.25	2E50	2.50	6AE5	.89	6R8	.79	12AL5	.72	833	1.15	3HP14	9.98	Wstghs C7/	
1B24	6.32	2E51	.98	6AE6	.89	6S4	.79	12AT6	.43	834	2.75	4AP10	6.75	7W/120V	.09
1B26	4.69	2J31	11.39	6AF6G	.77	6S7	.85	12AT7	.79	32	.39	5AP1	3.75	Med Scr Base	
1B27	7.83	2J31A	11.45	6AG5	.89	6S8GT	.75	12AU6	.32	FG32	4.89	5BP1	2.25	Bulb Eye Pilot	
1B35	.84	2J32	9.79	6AG7	.97	6SA7GT	.43	12AU7	.52	32L7GT	4.85	10DP7	1.25	Dialco Type	
1B3/852A	1.71	2J39	6.98	6AH7GT	.98	6SB7Y	.43	12AV6	.39	33	12.98	10BP4	5.79	Chromed, Less	
1B37	.85	2J47	12.69	6AJ8	.73	6SC7	.57	12AV7	1.89	FG33	7.89	5CP1	1.75	Bulb 59¢;	
1B38	34.00	2J51	8.39	6AK5	.98	6SD7GT	.43	12AW6	.58	34	.53	5CP7	3.70	for	.98
1B40	2.98	2J52	2.50	6AK6	.75	6SF5	.48	12AX7	.81	35/51	.58	5FP4	6.49	Tel-Slide Lamps	
1B41	49.95	2J53	18.45	6AL5	.35	6SF7	.56	12BA6	.54	35A5	.51	5FP7	1.19	6/12,24/45/	
1B42	7.50	2J54	12.19	6AL7	1.00	6SG7	.57	12BA7	.75	35B5	.54	5FP14	10.95	55V ea	.15
1B43	6.49	2J57	12.80	6AN5	2.49	6SH7	.38	12BD6	.39	35C5	.56	5GP1	6.95		
1B44	49.95	2J58	4.75	AQ5	.67	6SJ7GT	.48	12BE6	.45	35L6GT	.51	5HP1	4.85	XTAL DIODES	
1B64	49.95	2J59	19.63	6AQ6	.54	6SK7GT	.40	12BF6	.46	35W4	.38	5HP4	6.75	IN21	.49
1B65	49.95	2J48	12.70	6AQ7GT	.88	6SL7GT	.58	12BH7	1.11	35Y4	.48	5JP2	11.75	IN21A	1.00
1B66	12.95	2J49	12.70	6AR5	.98	6SN7GT	.38	12C8	.32	35Z4GT	.43	5JP4	11.89	IN21B	1.98
2.5	.65	2J50	39.98	6AS5	.50	6SN7WGT	.99	12E5	.98	35Z5GT	.39	5LP1	11.89	IN22	1.39
2A	.87	2J85	92.50	6AS6	2.89	6SQ7GT	.43	12F5	.88	36	.39	5MP1	4.75	IN23	1.98
2C5	.87	2J86	81.00	6AS7G	6.29	6SR7	.51	12H6	.27	REL36/6J4	.39	5RP4	1.43	IN23A	1.75
2D4GP	.98	2J87	68.00	6AT6	.48	6ST7	.58	12J5GT	.51	36	.39	5BP4	7.89	IN23B	2.49
2D7G	.84	2J63	14.98	6AU6GT	1.19	6ST7	.70	12J7GT	.52	37	.34	6CP7	2.70	IN25	2.49
2D8GT	.94	2K28	19.95	6AU8	.52	6SU7GTY	.98	12K7GT	.86	38	.27	6FP4	9.98	IN26	2.98
2E5	1.00	2K38	19.95	6AV6GT	1.49	6SV7	.75	12K8	.98	39/44	.39	6FP7	1.19	IN27	1.75
2E7G	2.00	2K45	24.95	6AV6	.44	6T7G	.84	12L8GT	1.39	CRC40	.34	WL414	63.95	IN28	1.75
2F4G	.74	2V3G	.49	6AX5GT	.69	6T8	.89	12Q7GT	.48	41	.49	417A	9.49	IN29	1.75
2F7GT	1.35	2W3GT	.98	6AW6	.89	6U4GT	1.35	12S8GT	.79	42	.47	GL434	2.49	IN34	.97
2G4GT	.68	2X2	.98	6AW6G	.84	6U5/6G5	1.49	12SA7GT	.43	43	.44	446A/2C40	2.98	IN35	1.95
2G6G	.98	3A4	.32	6B8	1.49	6U6GT	.60	12SC7	.38	45S/VT52	.18	446B	1.75	IN48	.78
2G6GT	.63	3A8	.75	6B6	.75	6U7G	.48	12SF5GT	.54	45Z3	.84	450TH	19.75	IN54	.78
2G6G	.68	3ABGT	1.89	6B7	.85	6V6GT	.52	12SF7GT	.54	45Z5	.84	450TL	24.95	IN55	.98
2H4G	.84	3B4	1.89	6B8GT	.98	6V6GTY	.98	12SG7	.32	46	.51	GL451	1.90	IN83	.98
2H6G	.86	3B5	.98	6BA4	1.00	6V6M	.98	12SH7	.34	47	.68	469	.958		
2J6G	.98	3B7/1291	.79	6BA6	.49	6V7G	1.18	12SJ7GT	.46	49	.75	HF200	13.95	Thermistors	
2J7	1.00	3B22	29.95	6BA7	.79	6W4GT	1.37	WL465	5.89	50	1.37	WL465	5.89	D107019 Vol.	
2J8	.65	3B24	1.75	6BC5	1.10	6W7G	.78	12SK7GT	.52	50A5	.97	CK5654AX	1.79	Limiter	2.98
2J42	.78	3B25	6.85	6BD6	.69	6X4	.52	12SK7GT	.54	50A5	.67	RH507	9.98	D168391 Ther-	
2J43	.88	3B26	7.84	6BE6	.69	6X5GT	.42	12SN7GT	.67	50B5	.81	527	5.95	mal comp	.98
2J44	.88	3B28	2.84	6BF6	.52	6X8	.89	12SQ7GT	.48	50C5	.89	530	12.69	D168392 Ther-	
2J45	.64	3C31/C1B	2.95	6BG6G	1.30	6Y6G	.65	12SR7	.58	56C6	1.18	WL531	3.75	mal Comp	2.00
2J46	.75	3C45	12.85	6BH6	.52	6Y7G	.98	12X3	.90	50L6GT	.81	CK533AX	1.49	D173096 HF	
2J47	.79	3D6/1299	.49	6BJ6	.54	6Z4/12Z5	.51	12Z3	.98	50Y6	.98	GL534	2.49	Pwr Meas	.90
2J48	.79	3D21	1.10	6BQ6GT	.89	6Z7G	1.08	14A4	.99	50Y6	.55	1521	3.89	IC Bulb Timer	
2J49	.78	3E29	16.98	6C4	.35	6ZY5G	.67	14A7/12B7	.81	50Y7GT	1.98	544	4.98	Delay	.98
2J50	.62	3LF4	.76	6C5	.68	7A6/XXL	.68	14AF7	.80		.84	GL546	4.98	Varistor	.88c
2J51	.89	3Q4	.76	6C6	.85	7A7	.65	14B6	.56		.43	550P1	19.95	CW20259	2.95
2N6GT	.68	3Q5GT	.85	6C8G	.88	7A8	.58	14B8	.77		.57	CK551AX	1.69	WE41A	1.98
2N6G	.98	3Q6GT	.66	6C6G	.85	7A6	.58	14C5	.87		.47	575A/975	12.68	1613/6F6X	.65
2S6GT	.84	3S4	.84	6C7	1.26	7A7	.82	14C7	.58		.44	603	29.50	2PX472	1.39
2S7	.84	3V4	.97	6C8G	1.20	7A8	.69	14E6	.71	RK61	1.98	HY615	.15	1616	.75
2W3GT	.66	4C33	81.00	6C21	19.62	7B7	.79	14E8	.71	RK65	24.95	WL619	18.98	1619	.16
2Y6	69.00	4C35	19.30	6CD6	.79	7AG7	.69	14E7	.87	RK68	24.95	WL619	18.98	1619	.16
4A4/1294	.57	4E27/287	12.39	6CD6G	2.49	7AH7	.87	14F7	.69	HY69	6.95	KU627	6.85	1620	4.95
4B4	2.98	4E31	24.95	6CH6	2.75	7B5	.87	14F8	.52	1.49	631P1/SN4	6.85	1620	4.95	
4B6	.78	4J42/700	29.95	6D6	.43	7B6	.65	14H7	.87	70L7GT	.97	WL632A	8.98	1624	1.05
4B7	.48	4J47	99.00	6D7	.98	7B6	.55	14J7	.89	71	.48	791A	2.98	1625	.19
4C6	.81	4T4/2	9.95	6D8	.75	7B7	.87	14N7	.83	72	.53	792A/792B	2.98	PM3	.25
4D4GT	.76	5C22	4.98	6E5	.69	7B8	.87	14Q7	.51	CRP72	1.37	793A	1.89	4A1	1.29
4E/5910	.49	5C30/C8B	8.49	6E7	1.20	7C4/1203A	.33	14R7	.65	73	1.67	794A	1.48	6-11	.49
4J8	.69	5D21	24.50	6F5	.47	7C5	.44	14S7	1.05	NR74	.79	795A/3021	.99	PM5	.98
4J9	.69	5D22	24.50	6F6	.58	7C6	.52	14T7	.81	75	.52	797	7.95	PM6	.98
4J2	.69	5J29	12.98	6F6GT	.52	7C7	.87	14X7	.98	HY75A	6.50	810A/3011	.65	PM7	.98
4J3	.78	5J32	99.00	6F7	.68	7C25	69.00	14Y4	1.05	76	.38	713A	1.19	1641/RK64	.68
4J4	3.98	5R4GY	1.00	6F8	.84	7EA/1201	.65	15E	1.17	77	.38	715B	6.49	PM8	.98
4J5	.84	5T4	.64	6G6	.65	7E6	.49	17A	.49	78	.49	717A	.61	2051	.98
4J6G	1.04	5U4G	.47	6H6	.38	7E7	.89	FG17	2.98	79	.84	721A	1.89	RA340	36.00
4J8	.65	5V4G	.88	C6J	2.00	7F7	.98	RK18	.98	80	.36	722A/287A	9.98	5514	6.85

19	.59	41	1.23	723A	6.95	5516	5.85	K49A	.36						
19BG6G	1.98	FG81A	6.45	723A/B	7.98	5646	18.98	K55B	.36						
1Y34	1.89	82	.95	724A/B	2.49	5654	4.23	M35B	.36						
1YT8	.89	82V	.95	725A	6.39	5817/CK		L62A	.49						
20	1.17	83	.69	726A	5.95	1613	1.89	K90B	.36						
RK20A	6.98	83V	.87	726C	29.98	CK5702	8.89	WL121A	2.61						
FJ21	6.95	84/6Z4	.37	801A	9.95	CK5724	9.95	C37A	2.95						
REL21	4.85	85	.87	801A	.29	CK5734	5.59	ZB583	5.98						
RK21	2.35	89	.32	802	4.65	5612	2.98								
FJ22/CE1C	1.49	VR92	.78	803	2.85	UX5653	2.49	Meade Pilots							
23	.45	PG104	14.75	804	2.85	6F12A	1.35	44, Box 10	.50						
24A	.45	PG105	8.89	805	5.89	6H12A	7.98	49, Box 10	.60						
24G/3C24	.45	VU111	.49	807	1.49	6Q9P	.87	55, Box 10	.60						
25A6	1.04	HY114B	.49	808	2.85	9001	.31	85, Box 10	.87						
25A7	2.98	HY115/145	.87	809	2.45	9002	.23	87, Box 10	.97						
25AC5GT	1.66	117L7	1.17	810	11.96	9003	.30	56,74,3W	.15						
25B5	1.39	117N7GT	1.17	811	2.98	9004	.24	100W 20V	.25						
25B6	1.39	117P7GT	1.17	812	2.98	9005	.24	211, Box 10	.45						
25BQ6GT	.89	117Z3	.49	813	13.20	C'RAY TUBES		311/28V	.15						
25C5	1.18	117Z4GT	1.18	814	2.98	2AP1	3.85	323/28V	.10						
25L6GT	.49	117Z6GT	.94	815	1.18	3AP1	4.63	Sylvania 6s/							
25N6	1.69	117Z7GT	1.49	816	1.39	3BP1	2.39	6W/120V	.15						
25W4GT	.79	FJ27A	15.89	826	1.98	3BP1A	7.98	Wstghs C7/							
25Y5	1.06	CV140	4.98	SD828	1.98	3BP1-81	4.49	7W/120V	.09						
25Z5	.42	158	.29	829	14.98	3DP1	3.75	Med Scr Base							
25Z4GT	.42	FG166	49.00	829B	14.98	3DP1-81	4.49	25W/125V	.08						
26	.42	FG172	19.80	832	7.98	3EP1	2.66	25W/125V	.09						
27	.41	FG190	12.50	832A	10.00	3FP7	2.98								
FJ27A	6.50	205B/VT2	6.49	836	1.49	3GP1	4.89	NEON BULBS							
28D7	.25	211/VT4C	.24	837	1.15	3HP7	4.50	NE16, 991	.22						
28	.35	RK215	9.98	838	2.21	3HP14	9.98	1993	.35						
HY31Z	4.89	WE218A	.35	852	2.75	4AP10	6.75	NE45/NW	.27						
32	.85	227A	2.65	843	.39	5AP1	3.75	NE51/NE2H	.07						
FG32	4.89	231	1.20	845	3.95	5BP1	2.25	Bulb Eye Pilot							
32L7GT	.82	250TH	17.95	851	12.98	5BP4	4.85	Dialco Type							
33	.53	250TL	17.98	860	8.79	5CP1	1.75	Chromed, Less							
FG33	7.89	252B	8.49	861	9.89	5CP7	3.70	Bulb 59¢;							
34	.53	304TH	3.45	864	.79	5FP4	6.49	for	.98						
35/51	.58	304TL	3.45	865	1.19	5FP7	1.25	Tel-Slide Lamps							
35A5	.51	307A/RK75	3.40	866A	.98	5FP14	10.95	6/12,24/45/							
35B5	.54	310A	6.98	866Jr	1.04	5GP1	6.95	55V ea	.15						
35C5	.56	310A	.79	866Sr/FJ23	1.04	5HP1	4.85								
35L6GT	.51	327A	2.50	869	25.98	5HP4	6.75	XTAL DIODES							
35W4	.38	350	1.23	872A	1.29	5JP2	11.75	IN21	.49						
35Y4	.48	350B	1.69	GE872A	2.98	5LP1	11.89	IN21A	1.00						
35Z4GT	.43	368AS	3.75	876	.29	7BP7	4.65	IN21B	1.98						
35Z5GT	.39	371B	.49	878	1.95	7CP1	12.95	IN22	1.39						
REL36/6J4	.39	388A	1.79	884/6Q8G	1.43	7JP4	16.49	IN23	1.75						
36	.39	389A	.45	885	.29	9CP7	3.89	IN23A	1.75						
37	.34	393A	3.68	922	2.70	9LP7	18.00	IN23B	2.49						
38	.27	394A	3.45	923	1.19	10BP4	19.49	IN25	2.49						
39/44	.28	395A	3.45	923	.27	10BP14	19.49	IN26	2.98						
CRC40	.34	WL414	63.95	927/CE2S	1.26	12DP7	12.45	IN27	1.75						
41	.49	417A	9.49	929	1.33	12GP1	49.98	IN34	.97						
42	.47	GL434	2.49	930	.90	12GP7	12.78	IN35	1.95						
43	.44	446A/2C40	2.98	931A	2.89	12JP7	12.78	IN48	.78						
45S/VT52	.18	446B	1.75	954	.16	12KP4	34.00	IN54	.78						
45Z3	.84	450TH	19.75	955	.24	12LP4	24.35	IN55	.98						
45Z5	.84	450TL	24.95	956	.24	12QP4	24.35	IN83	.98						
GL451	1.90	957	.20	12RP4	26.00										
469	.958	.29	15DP4	86.00	Thermistors										
HF200	13.95	SD968	1.98	16AP4	49.00	D167019 Vol.									
WL465	5.89	991	.22	16BP4	49.00	Limiter	2.98								
CK506AX	1.79	FM1000	.98	16FP4	87.50	D168391 Ther-									
RH507	9.98	CK1005	.99	16RP4	49.98	mal comp	.98								
508B	5.89	CK1006	.99	16TP4	49.98	D168392 Ther-									
530	12.69	CK1009	2.98	19AP4	86.00	mal Comp	2.00								
WL531	3.75	CK1090	2.69	19CP4	85.00	D173096 HF									
CK533AX	1.49	R1100	2.00	902	.15	Pwr Meas	.90								
GL534	.98	GL538	1.98	910	3.95	IC Bulb Timer									
1521	3.89	HY1231Z	8.39	910/3AP1	4.63	Delay	.98								
544	4.98	HY1269	5.39	913	89.98	Varistor	.88c								
GL546	4.98	HY1289	1.19	914	45.00	CW20259	2.95								
550P1	19.95	1230	1.19	TUNGAR		WE41A	1.98								
CK551AX	1.69	1609	5.98	BULBS											
575A/975	12.68	1613/6F6X	.65	16X897	2.49										
603	29.50	1616	.75	2PX472	1.39	Xtal Freq									
HY615	.15	1616	.75	189046GE	3.49	Standards									
WL619	18.98	1619	.16	199698	2.95	100Kc	7.98								
KU627	6.85	1620	4.95	289881	2.98	200Kc	3.95								
631P1/SN4	6.85	1620	4.95	1000Kc	2.95										
WL632A	8.98	1624	1.05	BALLAST		4700Kc	.98								
791A	2.98	1625	.19	1P1	.49	Htr Oven'Xtals									
792A/792B	2.98	1629	.25	PM3	.49	5010 5025/5055									
793A	1.89	1629	1.29	4A1	.49	Kc, Ea.	14.98								
794A	1.48	1632	.69	6-11	.49										
795A/3021	.99	1633	.77	PM5	.98										
797	7.95	1634	.77	PM6	.98	Tubes Grd Exc									
810A/3011	.65	1635	1.49	PM7	.98	Open Fil &									
713A	1.19	1641/RK64	.68	PM8	.98	B'kage									
715B	6.49	2050	.98	9-3	.49	Via R'Exp Only									
717A	.61	2051	.98	10-4B	.49										
721A	1.89	RA340	36.00	13-4	.49	Min Tube									
722A/287A	9.98	5514	6.85	20-4	.49	Order $5									

"Williamson" 10-Watt Hi-Fi Kit

10cps to 30kc with case! Internationally Famous. Simplicity of design. Extraordinary linearity. A lack of distortion. To 1 Mc. for experimenters. BCA Chassis. Less Output Xformer $19.95. Same with PreAmp-ToneControl Kit 29.95

"Wmson" 32 page brochure ..... 20¢

Super Wide-Range Hi-Fi Amp Kit

20cps to 20kc, 10W Max harmonic distortion 1% at full output: 0.5% 5W output. PreAmp, Tone Cont, BCA chassis. Less Output Xfmr $24.95

Hi-Fi Bionorian Concentric Duplex 10" Speaker 50 to 14000 cps 6 watts. Write for data $14.95

UTC Hi-Fi Output Xfmr 30Watts PP5k/6P1 $a3.6A5G Pri4000ohmseCT; SecStaps2 5 to 250 ohms 8.90

With 1201D G-E Hi-Fi Speaker ... 21.15

"TAB" Hi-Fi Pickup Assemblies "TAB" Pickup Arm & G-E VarReluctCartridge w/Replaceable Stylus: Standard,RPX040 or "LP", RPX41 (Specify) $7.29

Amc w/G-E Triple-Play Cartridge RPX050 (33,45&78RPM)&Stylus .. 9.49

G-E VarReluctCartridge(PermNeedle) 1.98

PFLASH CONDENSERS—For Photoflash

13mfd/330vac,1800vdc .. 9.49

25mfd/330vac,1800vdc .. 9.49

16 mfd,600vac,2800vdc 8.98

16mm PAN film (DBA)* camera, 24 rolls 4.98

16ExpCartridges,35mm Supersnap ..... 5 for $1

16ExpCartridges,35mmMicrodisk 5 for $1

PRECISION RESISTORS

Almost ANY Value—We Ship Types In Stock 0.1 to 950K, Ea. 36¢; 10 for $2.98 1 to 13 Megohms, Ea. 70¢; 10 for 9.98

MV Resistors—High Voltage

Megs.	Type	Watts	Peak Each	10 for
.2	MVP	10	15Kv	$1.98
.5	MVO	4	5Kv	1.29
.75	MVO	4	8Kv	1.29
.8	MVP	10	15Kv	9.98
1	MVP	10	15Kv	1.69
1	MVO	10	15Kv	13.49
1	MVZ	20	25Kv	1.98
2.5	MVA	20	20Kv	16.98
2.5	MVT	5	7.5Kv	1.79
5	MVP	10	15Kv	1.69
10	MVO	4	5Kv	1.29
10	MVO	10	15Kv	13.49
15	MVA	20	25Kv	1.98
20	MVP	10	15Kv	1.69
30	MVA	20	25Kv	1.98
50	MVE	25	40Kv	1.98

MP Resistors—High Freq. High Voltage

.005	MPD	10	1.5Kv	1.98
1	MPA	25	2.75Kv	2.49
1	MPB	25	2.75Kv	2.49
.5	MPA	25	2.75Kv	2.49
1	MPA	25	40Kv	2.49
1	MPB	25	40Kv	2.49
10	MP	10	10Kv	1.98

MF Types (1Ma.)—Sealed Precision WW (±1%) JAN-R-25

Megs.	Type	Kv	Each	10 for
1	MFC105	1	$2.49	$19.98
1.5	MFB155	1.5	2.98	24.98
2.5	MFB255	2.5	3.98	34.98
5.5	MFA	5.5	4.98	44.98
20	M5	20	34.98	Write

$1500 BANK-CLIMB Gyro Control For MK-4 AutoPilot. Mfr for SPERRY $1,800GovtCost. BRAND NEW 82.98

$1600 GYRO SERVO UNIT Bendix 13800-1D. Horiz Stabilizer 6.98

CONSTANT VOLTAGE REGULATORS

60 Watts RAYTHEON Input 95-130V/60 cyc: Output 115V/.58 A/5% $14.98

300 Watts GEN ELEC Input 115-220V/ 60 cyc: Output 115V/380Watts 39.95

500 Watts RAYTHEON Input 198-248V/ 50-60 cyc: Output 220V/500W/.95PF/1% Reg. 98.00

2000 Watt SOLA Input 95-130V/50-60 cyc: Output 115V/2KW/17.4A 1% Reg. Like New $130. Same New $369USmet. Your Cost ..... $162.

W E CO 188A Step Capacitor NEW $1.69

115Volts/400Cycle Xformers

5V/10Amp/5K+lns/Freed Csd $2.98

2.5VCT/10A/Amp/Freed Csd 2.98

115Volts/60Cycle Xformers

15000 Volt Dbler or7500V/30ma $18.95

1500VCT/360Ma, Csd HiV Ins 6.98

5800VorVct/1A,/17Kv/208-251Vin $59.50

2400orVCT/1A/17Kv/104-126Vin. $59.50

2V/60Amps $7.95; 5V/115Amps. $12.95

CHOKE:1.5Hy/1A420ohm/17Kv Ins $49.00

15Hy/400Ma or 20Hy/300Ma/12Kv $7.95

Snooperscope Infrared

Hi-Sensitivity Image Converter Tube, 2" diam. Complete data & tube ..... $4.95; Two for $9.49

IN34 CRYSTAL DIODE, 67¢; 10

INDEX TO ADVERTISERS

Accurate Spring Mfg. Co. ... 169
Aeronautical Communications Equipment, Inc. ... 202
Aircraft Radio Corp ... 42
Alden Products Co. ... 176
Allen-Bradley Co. ... 34
Allen Co., Inc., L. B. ... 200
Allied Control Co., Inc. ... 40
American Gas Accumulator Co. ... 165
American Lava Corp. ... 30
American Screw Co. ... 36
American Television & Radio Co. ... 205
American Time Products, Inc. ... 52
Ampex Electric Corp. ... 140
Andrew Corporation ... 144
Arma Corporation ... 26
Art Wire & Stamping Co. ... 195
Audak Company ... 236
Audio Devices, Inc. ... 127

Ballantine Laboratories, Inc. ... 150
Barrett Varnish Co. ... 200
Barry Corporation ... 62
Bead Chain Mfg. Co. ... 186
Beaver Gear Works, Inc. ... 128
Belden Mfg. Co. ... 43
Bell Telephone Laboratories ... 147
Bendix Aviation Corp. Eclipse-Pioneer Div. ... 206
Berkeley Scientific Co. ... 163
Bird & Co., Inc., Richard H. ... 201
Birtcher Corporation ... 197
Biwax Corporation ... 201
Boonton Radio Corp. ... 121
Borg Corp., George W. ... 188, 189
Bowser, Inc. ... 195
Bradley Laboratories, Inc. ... 46
Bridgeport Brass Co. ... 20
Brown Electro-Measurement Corp. ... 193
Burgess Battery Co. ... 181
Burlington Instrument Co. ... 200
Burnell & Co. ... 31

Cambridge Thermionic Corp. ... 204
Cannon Electric Development Co. ... 134
Capitol Radio Engineering Institute ... 195
Carboloy Company ... 50
Carnegie-Illinois Steel Corp. ... 43
Centralab, Div. Globe-Union, Inc. ... 11, 12, 13, 14
Cinch Mfg. Corp. ... 113
Cleveland Container Co. ... 141
Cohn Corp., Sigmund ... 181
Communication Accessories Co. ... 162
Cornell-Dubilier Electric Corp. ... 37
Corning Glass Works ... 38
Cornish Wire Co., Inc. ... 166
Cossor (Canada) Ltd. ... 177
Coto-Coil Co., Inc. ... 148
Cross Company, H. ... 200

Dano Electric Co. ... 197
Daven Company ... Third Cover
Dial Light Co. of America ... 177
Distillation Products, Inc. ... 135
Dow Corning Corp. ... 200
Driver-Harris Co. ... 19
du Pont de Nemours & Co., E. I. ... 55

Eastern Air Devices, Inc. ... 207
Eastman Kodak Co., Industrial Photographic Div. ... 123
Ebert Electronics Corp. ... 135
Elsler Engineering Co., Inc. ... 161, 209
Eitel-McCullough, Inc. ... 39
Electric Indicator Co. ... 140
Electrical Industries, Inc. ... 198
Electrical Reactance Corp. ... 21
Electro Motive Mfg. Co., Inc. ... 2
Electro Products Laboratories ... 199
Electro-Voice, Inc. ... 154
El-Tronics, Inc. ... 209
Electronic Instrument Co., Inc. ... 183
Emsco Derrick & Equipment Co. ... 187
Enthoven & Sons Ltd., H. J. ... 165
Erie Resistor Corp. ... 27

Fairchild Camera & Instrument Corp. ... 185
Fairchild Recording Equipment Corp. ... 203
Federal Telecommunications Laboratories, Inc. ... 7
Federal Telephone & Radio Corp. ... 15
Fidelity Chemical Products Corp. ... 169
Furst Electronics ... 193

G-M Laboratories, Inc. ... 190
Gamewell Company ... 207
General Ceramics & Steatite Corp. ... 161
General Electric Co
Apparatus Dept. ... 24, 25, 139
Electronics Dept. ... 33, 41
Lamp Dept. ... 172
General Industries Co. ... 9
General Radio Co. ... 137
Graphite Metallizing Corp. ... 198
Green Instrument Co. ... 201

Hathaway Instrument Co. ... 157
Haydon Mfg. Co., Inc. ... 155
Heath Company ... 164
Heiland Research Corp. ... 186
Hudson Wire Co. ... 173
Hytron Radio & Electronics Corp. ... 23

Industrial Condenser Corp. ... 197
Inland Testing Laboratories, Inc. ... 201
Instrument Resistors Co. ... 169
International Nickel Co., Inc. ... 54
International Resistance Co. ... 4, 5
I-T-E Circuit Breaker Co. ... 17

Johnson Co., E. F. ... 159
Jones Div., Howard B., Cinch Mfg. Corp. ... 193

Kahle Engineering Co. ... 197
Karp Metal Products Co., Inc. ... 29
Kartron ... 209
Kay Electric Co. ... 133
Kenyon Transformer Co., Inc. ... 161
Kester Solder Co. ... 117
Kollsman Instrument Div., Square D Co. ... 18

Lambda Electronics Corp. ... 197
Lampkin Laboratories, Inc. ... 209
Lavoie Laboratories ... 129
Leach Relay Co. ... 144
Lectrohm, Inc. ... 200
Lewis Engineering Co. ... 188
Lewis Spring & Mfg. Co. ... 160
Linde Air Products Co., Unit of Union Carbide & Carbon Corp. ... 179
Littelfuse, Inc. ... 140
Lord Mfg. Co. ... 158

Machlett Laboratories, Inc. ... 10
Mallory & Co., Inc., P. R. ... 64, 115
Marion Electrical Instrument Co. ... 196
McGraw-Hill Book Co. ... 165, 208
Millen Mfg. Co., Inc., James ... 180
Miniature Precision Bearings, Inc. ... 200
Minneapolis-Honeywell Regulator Co., Industrial Div. ... 61

20 Millivolts
Vertical Sensitivity
PRECISION
SERIES ES-500
5" OSCILLOSCOPE



NET PRICE $149.50

Complete with light shield, calibrating screen and operating manual. Size 8¼ x 14½ x 18".

• • IMPORTANT FEATURES • •

★ Wide Range High Sensitivity Vert. Amplifier
Response to 1 Megacycle
2 Megohms input resistance
★ Vertical Input Step Attenuator, x1, x10, x100.
Additional continuous vernier control
Cathode follower input circuit
★ Extended Range Horizontal Amplifier
Response to .5MC. ½ meg. input resistance
★ Linear Multi-Vibrator Sweep Circuit
10 cycles to 30 KC. Improved circuits assure unusual linearity thruout range
★ Amplitude Controlled Synch. Selection
★ "Z" Axis Modulation terminals
★ Phasing Control
★ Audio Monitoring phone jacks plus direct access to Hor. and Vert. plates
★ Light Shield and Calibrating Screen
Removable and rotable
★ Tube Complement 1 each type 6J5, 6AK5, 7H7, 6X5, 2X2. 2 each type 7W7, 5CP1/A CR tube.
★ Fully Licensed under patents of A.T.&T. & W.E.
★ PLUS many "Precision" refinements that must be seen to be appreciated.

See the new Precision 5" Oscilloscope and Series E-400 Sweep Signal Generator on display at leading radio equipment distributors. Write for catalog fully describing the complete line of selected test instruments for all phases of AM, FM, and TV.

Precision Apparatus Co., Inc.
92-27 HORACE HARDING BLVD.
ELMHURST 10, N. Y.

Export: 458 B'way, N.Y.C., U.S.A. Cables: MORHANEX
In Canada: Atlas Radio Corp. Ltd., Toronto, Ontario

when you use the **Audax** POLYPHASE... ONE single unit plays ALL your records SUPERBLY... and at less than the cost of ordinary magnetic pick-ups.

"The Standard by which Others Are Judged and Valued"

Microgroove, 78, r.p.m., etc.

- Response 20 to over 10,000 cps.
- Jewel styli replaceable individually.
- Needle talk practically nil.
- Tracking remarkable.

See it at your local distributor or write us

Send for editorial reprint on POLYPHASE principles

AUDAK COMPANY

500 5th Ave [redacted] New York 18

PROCEEDINGS
of the
1949 NATIONAL ELECTRONICS CONFERENCE
—CHICAGO—
Now Available

60 Papers on Electronics research and development in this 575-page cloth-bound volume just off the press.

Mail Your Coupon Now To Obtain Your Copy of This Limited Edition.

National Electronics Conference, Inc.
852 East 83rd St.
Chicago 19, Illinois

I inclose $4.00 (check or money order) for which please send me one (1) copy of the Proceedings of the 1949 National Electronics Conference.

Name .....

Street Address .....

City ..... Zone ..... State .....

(Proceedings of previous conferences available upon request)

Mitchell-Rand Insulation Co., Inc. 16
Monroe Paper Mills Co. 175
Muirhead & Co., Ltd. 3
Murex Limited 192
Mycalex Tube Socket Corp. 22

National Company, Inc. 173
National Electronics Conference, Inc. 236
National Moldite Co. 167
National Varnished Products Corp. 53
Ney Company, J. M. 181
Nothelfer Winding Laboratories 186

Oregon Electronics Mfg. Co. 171

Paper Machinery & Research, Inc. 198
Paramount Paper Tube Corp. 189
Plastics & Electronics Co. 200
Polarad Electronics Co. 180
Potter Instrument Co., Inc. 194
Precision Apparatus Co., Inc. 235
Precision Paper Tube Co. 177
Premax Products, Div. Chisholm-Ryder Co., Inc. 140
Presto Recording Corp. 136
Pyramid Electric Co. 60

Radio Corp. of America ..... 49, 152, Fourth Cover
Radio Receptor Co., Inc. 145
Railway Express Co., Air Express Div. 170
Raytheon Mfg. Co. 125
Reed Research Corp. 182
Remler Co. Ltd. 191
Resistance Products Co. 199
Revere Copper & Brass, Inc. 8
Richardson Company 30
Rogers Corporation 35
Rola Company, Inc. 47
Rome Cable Corp. 153

Scientific Electric, Div. of "S" Corrugated Quenched Gap Co. 187
Scintilla Magneto Div., Bendix Aviation Corp. 44
Scovill Mfg. Co. 192
Servomechanisms, Inc. 190
Sigma Instruments, Inc. 63
Specialty Battery Co. 204
Sprague Electric Co. 119
Stackpole Carbon Co. 32
Standard Piezo Co. 202
Standard Pressed Steel Co. 205
Standard Transformer Corp. 194
Staver Co., Inc. 193
Steinen Mfg. Co., Wm. 206
Steward Mfg. Co., D. M. 190
Stoddart Aircraft Radio Co. 28
Stupakoff Ceramic & Mfg. Co. 142
Superior Tube Co. 51
Sylvania Electric Products, Inc. 121, 143
Synthane Corporation 56, 57

Tech Laboratories, Inc. 173
Technology Instrument Corp. 168
Tektronix, Inc. 191
TEL-Instrument Co., Inc. 174
Terpening Co., L. H. 181
Thomas & Skinner Steel Products Co. 138
Titeflex, Inc. 201
Transradio Ltd. 205

Union Carbide & Carbon Corp., The Linde Air Products Co., Unit 179
United States Steel Corp. 43
United Transformer Co. ..... Second Cover

Veeder-Root, Inc. 45
Vickers Electric Div., Vickers, Inc. 6
Victoreen Instrument Co. 178

Waterman Products Co., Inc. 208
White Dental Mfg. Co., S. S. 156, 195
Whitehead Stamping Co. 193
Whitney Metal Tool Co. 204

PROFESSIONAL SERVICES 210

SEARCHLIGHT SECTION
(Classified Advertising)

EMPLOYMENT
Positions Vacant 210, 211, 212
Positions Wanted 210
Selling Opportunities Wanted 210
Employment Agencies 210
Employment Services 210

SPECIAL SERVICES
Contract Work 210

EQUIPMENT
(Used or Surplus New)
For Sale 212-234

WANTED
Equipment 212

ADVERTISERS INDEX

Acorn Electronics Corp. 229
Aircraft Radio Industries, Inc. 232
Alvarado Supply Co. 233
American Electrical Sales Co. 228
Arrow Sales, Inc. 218

Bell Aircraft Corp. 211
Bendix Aviation Corp. 228
Blan 230
Brooks Co., Inc., B. D. 230

Communication Devices Co. 212, 226
Communications Equipment Co. ..., 213, 214, 215
Cottone & Co., A. 230
Cunningham Engineering Co. 226

Dumont TV 212

Electro Impulse Laboratory 227
Electronic Engineering Co. of Calif. 211
Electronicraft, Inc. 225
EPCO 230

Fair Radio Sales 232
Fling Electrical Manufacturing Co. 210
Finnegan, H. 212
French-Van Breems, Inc. 226

Goodyear Aircraft Corp. 212
Greene, Leonard 232

Haydu Bros. 228
Hopton Radio 226
Hughes Aircraft Co. 212

Instrument Associates 216, 217

Kato Engineering Co. 233
Klein, Manuel 233

Lectronic Research Laboratories 219
Life Electronics Sales 231

Maritime Switchboard 231
Miller Electric Co. 226
Mogull Co., Inc., Alexander 228
Mutual Telephone Co. 211

Neomatic, Inc. 228

Opad-Green Co. 226

Peak Electronics Co. 220
Powell, Harold H. 230
Precision Electrical Instrument Co. 228

Radio & Electronic Surplus 212
Radio Corporation of America 211
Radio Ham Shack, Inc. 233
Rand Radio Corp. 212
Raytheon Manufacturing Co. 231
Reliance Merchandising Co. 221

Servo-Tek Products Co., Inc. 222
Solo Electronics Sales Corp. 230
Soundtronics Laboratories 212
Southern Skyways 231
Standard Wire & Cable Co. 232

TAB 234

Universal General Corp. 229

Victor-Bernard Industries 212

Warren Industrial Co. 231
Wells Sales, Inc. 224

This index is published as a convenience to the readers. Every care is taken to make it accurate, but ELECTRONICS assumes no responsibility for errors or omissions.

THEY'RE NEW!
THEY'RE SMALL!
30 step "T" networks, T-730 series, 2¼" diameter
30 step ladder, LA-130 series, 1¾" diameter (also available as potentiometer)
45 step "T" networks, T-345 series, 2¼" diameter

3 ADDITIONS to the most complete line of Attenuators in the WORLD!

- Multiple Input & Output Networks
- Potentiometers
- "T" networks
- Balanced "H" Ladder Networks
- R. F. Attenuators
- Fixed Pads
- Impedance matching networks
- Rheostats
- Balanced Ladder Networks
- Video Attenuators
- Dual Potentiometers
- Power Attenuators
- Decade Attenuators

Daven offers a new group of Attenuators which are designed for compactness and light weight. This has been done as an aid to Design Engineers—in line with the growing trend to miniaturization of components.

By combining all the other well-known Daven features, these units are ideal where space and weight are at a premium.

Let Daven fill your needs from over 5,000 types of standard attenuators. Our Engineering Department will be glad to work with you in selecting a unit for your specific requirements.

Write to Dept. E-1 for additional information

"The best equipment deserves the finest attenuators— . . . Always Specify Daven!"

THE DAVEN CO.

191 CENTRAL AVENUE
NEWARK 4, NEW JERSEY



CHARACTERISTICS OF RCA MULTIPLIER PHOTOTUBES

Tube No.	Spectral Response	Maximum Response Wave Length Angstroms	Sensitivity uA/uW	Equivalent Noise Input—Lumens
5819	S-9	4800	4650	2×10^{-11}
931-A	S-4	4000	9300	1×10^{-11}
1P21	S-4	4000	74000	5×10^{-13}
1P22	S-8	4200	370	1×10^{-10}
1P28	S-5	3400	5665	1×10^{-11}
				*1.5×10^{-14}

*Equivalent ultra-violet noise input in watts at 2537 Angstroms

The Fountainhead of Modern Tube Development is RCA

RCA Multiplier Phototubes...

for low-level detection and measurement

The extraordinarily high values of amplification obtainable from RCA Multiplier Phototubes make them particularly applicable to the detection and measurement of low levels of illumination. Coupled with suitable phosphors, these tubes may also be used for detecting and measuring nuclear particle radiation. The secondary-emission multiplier stages employed in these tubes make possible improved signal-to-noise ratio at very low illumination levels.

RCA-5819 with its head-on photocathode of large diameter may be used in scintillation counters for the detection and measurement of nuclear particle radiation, and in other applications involving low-level, large-area light sources.

RCA-931-A is the preferred type for high-volume, low-cost applications.

RCA-1P21 now has a sixfold improvement in noise input. It is especially desirable for photo-electric spectrometers, astronomical telescopes, and scintillation counters using collimated light beams.

RCA-1P22 is especially useful in colorimetry and spectroscopy requiring the advantages of a panchromatic surface.

RCA-1P28 is intended for specialized industrial and scientific applications such as spectrophotometry, where the measurement of low levels of ultraviolet radiation is involved. Its envelope of special glass permits transmission of ultraviolet radiation down to a wavelength of 2000 Angstroms.

RCA Application Engineers are ready to assist you in the adaptation of these or any other RCA tube types to commercial electronic equipment. For further information write RCA, Commercial Engineering, Section G42R, Harrison, N. J.

The world's most modern tube plant...

RCA, LANCASTER, PA.

RADIO CORPORATION of AMERICA

ELECTRON TUBES — **HARRISON, N. J.**